



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA

सन्दर्भ सं:भा.वि.प्रा/वारा/अभियंत्रण/टॉयलेट्स/ डब्लू.ओ-118/469-481/6067-79

दिनांक: 11.08.2025

Ref No.: AAI/VNS/ENGG/Toilets/ WO-118/

Date: 11.08.2025

सेवा में,

मेसर्स पंकज कुमार पटेल
ग्राम - धरमनपुर, पोस्ट-जमालपुर
वाराणसी-221105

M/s Pankaj Kumar Patel
Village-Dharamanpur, Post-Jamalpura
Varanasi-221105

विषय : एल.बी.एस.आई. हवाई अड्डा वाराणसी में शहर की ओर, कर्मचारियों और सार्वजनिक शौचालयों के लिए सैनिटरी फिक्स्चर का नवीनीकरण और प्रतिस्थापन और अन्य विविध कार्य।
Renovation & replacement of sanitary fixtures for the city side staff & public toilets and other miscellaneous works at L.B.S.I Airport Varanasi (Tender ID : 2025_AAI_240910_1)

संदर्भ : ई-निविदा खुलने की तिथि : 31.07.2025

प्रिय महोदय/Dear Sir,

- उपरोक्त कार्य की, कुल निविदा रकम रुपया 26,47,176.00 (रुपया छब्बीस लाख सैतालीस हजार एक सौ छिहत्तर मात्र) (जी.एस.टी. रहित) की मद दर निविदा, जो कि कार्य की अनुमानित लागत रुपया 37.26 लाख (जी.एस.टी. रहित) से 28.95% (अट्टाइस दशमलव नौ पॉच प्रतिशत) कम है, आपके द्वारा निविदा प्रपत्र की अनुसूची 'अ' में दर्शायी गयी मद दरों पर भरी गई है, अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से स्वीकृत की जाती है।
Your tender for the work mentioned above is hereby accepted on behalf of the Chairman, Airports Authority of India at the net tender amount Rs. 26,47,176.00 (Rupees Twenty Six Lakhs Forty Seven Thousand One Hundred Seventy Six only) (excluding GST) which is 28.95% (Twenty Eight point Nine Five percent) below to the estimated cost put to tender of Rs. 37.26 lakhs (excluding GST).
- उपमहाप्रबन्धक (अभि०-सिविल), भा.वि.प्रा., लाल बहादुर शास्त्री अन्तर्राष्ट्रीय विमानपत्तन, वाराणसी इस कार्य के कार्य प्रभारी अभियन्ता होंगे तथा कनिष्ठ कार्यपालक (अभि०-सि०), भा.वि.प्रा., लाल बहादुर शास्त्री अन्तर्राष्ट्रीय विमानपत्तन, वाराणसी उनके प्राधिकृत प्रतिनिधि होंगे। आपसे अनुरोध है कि दिनांक 05.09.2025 तक उपमहाप्रबन्धक (अभि०-सिविल) के कार्यालय में उपस्थित होकर संविदा अनुबन्ध को हस्ताक्षरित कर पूर्ण करें। अनुबन्ध 100/- रुपए के गैर न्यायिक स्टाम्प पेपर पर सम्पादित किया जाएगा, स्टाम्प पेपर की कीमत आपके द्वारा वहन की जाएगी।
The DGM(Engg-Civil), AAI, Lal Bahadur Shastri International Airport, Varanasi shall be the Engineer-in-charge of the work and Jr. Executive (E-C), AAI, Lal Bahadur Shastri International Airport, Varanasi shall be our authorised representative. You are requested to attend the office of the DGM(Engg-Civil) by 05.09.2025 to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs. 100/- and the cost of stamp paper shall be borne by you.
- धरोहर राशि रुपया 1,11,780.00 (रुपया एक लाख ग्यारह हजार सात सौ अस्सी मात्र) संविदा प्रपत्र के अनुच्छेद 1ए पेज 16 के अनुसार प्रतिभूति निक्षेप राशि का हिस्सा मानकर उसमें बदल दिया जाएगा। कृपया शेष प्रतिभूति निक्षेप राशि रुपया 1,52,938.00 (रुपया एक लाख बावन हजार नौ सौ अठ्तीस मात्र) इस पत्र के निर्गत दिनांक से दस दिनों के भीतर जमा करें अन्यथा उक्त धनराशि की कटौती संविदा प्रपत्र की उक्त संदर्भित शर्त के अनुसार चालू लेखा बिलों से की जाएगी।
The earnest money amount of Rs. 1,11,780.00 (Rupees One Lakh Eleven Thousand Seven Hundred Eighty only) received along with your tender will be treated and converted as a part of security deposit. Please deposit Rs.1,52,938.00 (Rupees One Lakhs Fifty Two Thousand Nine Hundred Thirty Eight only), towards balance security deposit within 10 days from the date of issue of this letter, failing which the same will be deducted from the Running Account Bills as per condition GCC 1A on page 16 of the contract document.

शेष पृष्ठ 2 पर....

कार्यालय: निदेशक विमानपत्तन, लाल बहादुर शास्त्री हवाई अड्डा, वाराणसी-221006 टेलीफोन: 2622155, फैक्स नं०. 0542-2622320
O/o Airport Director, Lal Bahadur Shastri Airport, Varanasi-221006 Phone: 2622155, Fax: 0542-2622320

Dr. General Manager (Engg-Civil)
भारतीय विमानपत्तन प्राधिकरण
Airports Authority of India
हवाई अड्डा, वाराणसी

-2-

- 4) आपसे अनुरोध है कि संविदा श्रमिक प्रावधान (विनिमय एवं उन्मूलन) एक्ट 1970, श्रमिक प्रावधान (विनिमय एवं उन्मूलन)-केन्द्रीय नियम 1971, न्यूनतम मजदूरी अधिनियम एवं इस सम्बन्ध में केन्द्र/राज्य सरकार के नियमों का पालन करना सुनिश्चित करें।
You are requested to comply with the provisions of Contract Labour (Regulation & Abolition) Act of 1970 and Contract Labour (Regulation & Abolition) Central rules 1971 and Minimum Wages Act & Rules thereof Central and State Governments with upto date amendments.
- 5) आपको निर्देशित किया जाता है कि आप तुरन्त प्रभाव से कनिष्ठ कार्यपालक (अभि०-सि०), भा.वि.प्रा., लाल बहादुर शास्त्री अन्तर्राष्ट्रीय विमानपत्तन, वाराणसी से सम्पर्क करें जो आपको कार्यस्थल सौंपने की व्यवस्था करेंगे।
You are also directed to contact the Jr. Executive (E-C), AAI, Lal Bahadur Shastri International Airport, Varanasi, immediately who will arrange to hand over the site to you.
- 6) कृपया ध्यान दें कि कार्य पूर्ण करने की अवधि 02(दो) महीने हैं जो कि दिनांक 21.08.2025 से प्रभावी मानी जाएगी।
Please note that time allowed for carrying out the work shall be 02 (Two) months and the same shall be reckoned from 21.08.2025
- 7) संविदा के सन्दर्भ में किसी भी प्रकार का पत्राचार सामान्यतः उपमहाप्रबन्धक (अभि-सिविल), भा.वि.प्रा., लाल बहादुर शास्त्री अन्तर्राष्ट्रीय विमानपत्तन, वाराणसी-221006, को सम्बोधित करें।
Any further correspondence in connection with the contract should normally be addressed to the DGM (Engg-Civil), AAI, Lal Bahadur Shastri International Airport, Varanasi-221006
- 8) कृपया इस पत्र की पावती भेजें एवं पत्र कि अनुलिपि जो कि संलग्न है को हस्ताक्षरित कर अधोहस्ताक्षरी को स्वीकृत चिन्ह के रूप में वापस करें।
Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.
- 9) विषयक कार्य से संबंधित अनुसूची-अ, (कुल प्रष्ठ 15 (सिविल एवं विद्युत कार्य रु. 26,47,176.00) संलग्न है।
Schedule 'A' (total page 15) (Civil & Elect Rs. 26,47,176.00) of the work is enclosed.

उपरोक्त के हिन्दी पाठ में कोई अन्तर या द्विधार्थकता होने की स्थिति में अंग्रेजी पाठ मान्य होगा।

In case of difference or ambiguity in Hindi and English version, the English version will prevail.

धन्यवाद।

भवदीय

संलग्नक- यथोपरि
Encl:- As above

11/08/2025
उ.म.प्र.(अभि.-सिविल),
DGM (Engg-Civil)

अध्यक्ष, भा०वि०प्रा० के लिए व उनकी तरफ से
For and on behalf of the Chairman, AAI

उप महाप्रबन्धक (अभि.-सिविल)
Dy. General Manager (Engg-Civil)



प्रतिलिपि:

मूल प्रति पर नहीं (NOO)

अ. बाहरी-

1. संयुक्त महाप्रबन्धक (अभि)-उ०क्षे०, भाविप्रा, नई दिल्ली-110037 : सूचनार्थ
2. सहायक श्रम आयुक्त (सी), 189-ए/4ए, अलोपी बाग, पोस्ट-दारागंज, प्रयागराज : सूचनार्थ
3. श्रम प्रवर्तन अधिकारी (सी), 189-ए/4ए, अलोपी बाग, पोस्ट-दारागंज, प्रयागराज : सूचनार्थ

ब. आंतरिक-

- | | | |
|---------------------------------|---|------------------------|
| 1. निदेशक विमानपत्तन | : | सूचनार्थ |
| 2. म.प्र. (अभि)-प्रोजेक्ट | : | -तदैव- |
| 3. प्रभारी (वित्त) | : | -तदैव- |
| 4. सं.म.प्र. (अभि-विद्युत) | : | -तदैव- |
| 5. उ.म.प्र. (अभि-सिविल) | : | -तदैव- |
| 6. प्रभारी (सुरक्षा) | : | -तदैव- |
| 7. कनिष्ठ कार्यपालक (अभि-सिविल) | : | आवश्यक कार्यवाही हेतु। |
| 8. कार्यादेश फाईल | : | |
| 9. अनुबन्ध | : | |

11/08/2025

उ.म.प्र.(अभि.-सिविल),
भा.वि.प्रा, लाल बहादुर शास्त्री अन्तर्राष्ट्रीय विमानपत्तन,
वाराणसी

उप महाप्रबन्धक (अभि - सिविल)
Dy. General Manager (Engg-Civil)
भारतीय विमानपत्तन प्राधिकरण
Airports Authority of India
लाल बहादुर शास्त्री हवाई अड्डा, वाराणसी
Lal Bahadur Shastri Airport, Varanasi

Print

Help

Item Rate BoQ

Bidding Authority: Airports Authority of India

Work: Renovation & replacement of sanitary fixtures for the city side staff & public toilets and other miscellaneous works at L.B.S.I Airport Varanasi.

Contract No: 2025_AAI_240910_1

Name of Bidder/
Firm /
Company :


Pankaj Kumar Patel

PRICE SCHEDULE

NUMBER #	TEXT #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Item Code / Make	Quantity	Units	RATE (excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	7	8	10
1.00	Civil Works						
1.01	Demolishing cement concrete including disposal of material within 50 metres lead: 1:3:6 or richer mix	Item1	8.25	cum	1500.00	12375.00	INR Twelve Thousand Three Hundred & Seventy Five Only
1.02	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 metres lead: a) Of area 3 sq. metres and below	Item2	2.00	each	1000.00	2000.00	INR Two Thousand Only
1.03	Dismantling stone slab/tiles flooring laid in cement mortar including stacking of serviceable material and disposal of unserviceable material within 50 metres lead.	Item3	140.45	sqm	800.00	112360.00	INR One Lakh Twelve Thousand Three Hundred & Sixty Only
1.04	Dismantling C.I. pipes including excavation and refilling trenches after taking out the pipes, manually/ by mechanical means breaking lead caulked joints, melting of lead and making into blocks including stacking of pipes & lead at site within 50 metre lead as per direction of Engineer-in-charge: a) Up to 150 mm diameter metre	Item4	30.00	mtr	600.00	18000.00	INR Eighteen Thousand Only
1.05	Dismantling of flushing cistern of all types (C.I./PVC/Vitrious China) including stacking of useful materials near the site and disposal of unserviceable materials within 50 metres lead.	Item5	5.00	each	900.00	4500.00	INR Four Thousand Five Hundred Only
1.06	Dismantling of Sanitary fixtures & fittings including WC, Urinals, Wash Basins etc. including stacking of useful materials near the site and disposal of unserviceable materials within 50 metres lead.	Item6	10.00	each	900.00	9000.00	INR Nine Thousand Only

प्रबंधक (अभि. अभिन.)
Dy. Central Manager, Engg Civil
भारतीय विमानपत्तन प्राधिकरण
Airports Authority of India

Sl. No.	Item Description	Item Code / Make	Quantity	Units	RATE (excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Rs. P	TOTAL AMOUNT in Words
1.07	Dismantling aluminium/ Gypsum partitions, doors, windows, fixed glazing, false ceiling and toilet cubicles including disposal of unserviceable surplus material and stacking of serviceable material with in 50 meters lead as directed by Engineer-in-charge.	Item7	65.30	sqm	150.00	9795.00	INR Nine Thousand Seven Hundred & Ninety Five Only
1.08	Dismantling G.I. pipes (internal work) including chasing wall after taking out the pipes, manually/ by mechanical means and making wall good with 1:3:6 concrete including stacking of pipes lead as per direction and satisfaction of Engineer-in-charge : 15 mm to 75 mm nominal bore	Item8	50.00	mtr	200.00	10000.00	INR Ten Thousand Only
1.09	Dismantling or taking out fixed mirror in toilet including disposal of unserviceable surplus material and stacking of serviceable material at suitable place as direction and satisfaction by Engineer-in-charge.	Item9	3.90	sqm	100.00	390.00	INR Three Hundred & Ninety Only
1.10	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. In cement mortar	Item10	0.30	sqm	1000.00	300.00	INR Three Hundred Only
1.11	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in Cement mortar 1:4 (1 cement : 4 coarse sand)	Item11	1.65	cum	8000.00	13200.00	INR Thirteen Thousand Two Hundred Only
1.12	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level. Cement mortar 1:3 (1 cement :3 coarse sand)	Item12	12.80	sqm	1000.00	12800.00	INR Twelve Thousand Eight Hundred Only
1.13	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : "1:2:4 (1 cement : 2 coarse sand (zone-III) : 4 graded stone aggregate 20 mm nominal size).	Item13	6.15	cum	8000.00	49200.00	INR Forty Nine Thousand Two Hundred Only
1.14	Extra for providing and placing 2 nos. 6 mm dia M.S. bars at every third course of half brick masonry.	Item14	5.60	sqm	500.00	2800.00	INR Two Thousand Eight Hundred Only
1.15	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels. Granite of any colour and shade. Area of slab over 0.50 sqm (Sample of granite is kept in the office of EIC)	Item15	7.20	sqm	3000.00	21600.00	INR Twenty One Thousand Six Hundred Only
1.16	Providing and fixing ISI marked flush door shutters conforming to IS : 2202 (Part I) non-decorative type, core of block board construction with frame of 1st class hard wood and well matched commercial 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters:b) 35 mm thick including ISI marked Stainless Steel butt hinges with necessary screws	Item16	4.20	sqm	2500.00	10500.00	INR Ten Thousand Five Hundred Only
1.17	Extra for providing lipping with 2nd class teak wood battens 25 mm minimum depth on all edges of flush door shutters. (Overall area of shutter to be measured over item no. 21)	Item17	4.20	sqm	2000.00	8400.00	INR Eight Thousand Four Hundred Only


11/08/2025

उप-प्रमुख (अभियंता-सिविल)
Dy. General Manager (Engg-Civil)

भारतीय विमानपत्तन प्राधिकरण
Airports Authority of India

लाल बहादुर शास्त्री हवाई अड्डा, वाराणसी
Lal Bahadur Shastri Airport, Varanasi

	Item Description	Item Code / Make	Quantity	Units	RATE (excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1.18	Providing & fixing Stainless Steel tower bolts of OZONE TBS-10"/6" SS 304 grade or approved equivalent of grade 304 heavy duty with necessary Stainless Steel screws, etc. complete as per directions of Engineer-in- Chargea) 250 x 25 mm	Item18	4.00	each	200.00	800.00	INR Eight Hundred Only
1.19	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position all complete	Item19	112.50	Kg	80.00	9000.00	INR Nine Thousand Only
1.20	Providing and fixing expansion hold fasteners on C.C. /R.C.C./Brick masonry surface backing including drilling necessary holes and the cost of bolt etc complete.(a) Fastener with threaded dia 10 mm	Item20	20.00	each	200.00	4000.00	INR Four Thousand Only
1.21	Providing and fixing 12-15 mm thick moulded Acrylic solid surface counter/ slab tops of Dupont/Samsung Staron/Avonite or approved equivalent for kitchen platforms , vanity counters,window sills, facias and similar location of required size of approved shade, colour and texture fixed over 12 mm thick base ply with seamless joints through thermoforming process including all fixing, sticking, moulding, bending, use of flexible ply (if required) as per requirements of the approved drawings etc. and as per the directions of the Engineer in charge complete at all levels.Solid surface of approved shade & company	Item21	7.75	sqm	2000.00	15500.00	INR Fifteen Thousand Five Hundred Only
1.22	Providing and laying in floors anti skid homogenous premium quality vitrified tiles with water absorption less than 0.08% and conforming to IS:15622 of approved Belgium Grey NITCO/Marbonite -Ash Grey/JOHNSON/ RAK CERAMICS brand/ manufacturer, of size 600 x 1200 mm in combination as per approved drawing without warpage of approved make and colour shades laid on 20 mm bed of cement mortar 1:4 (1 cement : 4 coarse sand) & pasting with polymer based tile adhesive including grouting the joints of thickness 1 to 3 mm with solid epoxy grout of PIDILITE / LATICRETE / BAL ENDURA / FERROUS CRETE or approved equivalent of desired shade etc. complete and as per pattern specified in approved drawings and specifications complete as per directions of Engineer-in-charge. (Note : -Basic price of vitrified Wall tiles shall not be less than Rs 55/Sqft for any size without GST, freight upto destination, loading and unloading etc. Purchase voucher shall have to be submitted for price verification before bill payment of this bill)	Item22	41.15	sqm	2500.00	102875.00	INR One Lakh Two Thousand Eight Hundred & Seventy Five Only


 11/08/2025
 उप महाप्रबंधक (अभि: - सिविल)
 Dy. General Manager (Engg-Civil)
 भारतीय विमानपत्तन प्राधिकरण
 Airports Authority of India
 लाल बहादुर शास्त्री हवाई अड्डा, वाराणसी
 Lal Bahadur Shastri Airport, Varanasi
 लाल बहादुर शास्त्री हवाई अड्डा, वाराणसी

Sl. No.	Item Description	Item Code / Make	Quantity	Units	RATE (excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1.23	Providing and fixing 1st (premium) quality high gloss vetrified glazed wall tiles conforming to IS: 15622 of approved NITCO/Marbonite -Ash Grey/Porselano – Dew Grey JOHNSON/ Fresco Azul RAK brand/ (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size 600x1200 mm as approved by Engineer-in-Charge and as per approved drawing including 30% highlighter of individual toilet, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) & pasting with polymer based tile adhesive including grouting the joints of thickness 1 to 3 mm with solid epoxy grout of PIDILITE / LATICRETE / BAL ENDURA / FERROUS CRETE or approved equivalent of desired shade etc. complete and as per pattern specified in approved drawings and specifications complete as per directions of Engineer-in-charge. (Note : -Basic price of vetrified Wall tiles shall not be less than Rs 55/Sqft for any size without GST, freight upto destination, loading and unloading etc. Purchase voucher shall have to be submitted for price verification before bill payment of this bill)	Item23	120.85	sqm	3000.00	362550.00	INR Three Lakh Sixty Two Thousand Five Hundred & Fifty Only
1.24	Providing and fixing false ceiling at all height including providing and fixing of frame work made of special sections, power pressed from M.S. sheets and galvanized with zinc coating of 120 gms/sqm (both side inclusive) as per IS : 277 and consisting of angle cleats of size 25 mm wide x 1.6 mm thick with flanges of 27 mm and 37mm, at 1200 mm centre to centre, one flange fixed to the ceiling with dash fastener 12.5 mm dia x 50mm long with 6mm dia bolts, other flange of cleat fixed to the angle hangers of 25x10x0.50 mm of required length with nuts & bolts of required size and other end of angle hanger fixed with intermediate G.I. channels 45x15x0.9 mm running at the spacing of 1200 mm centre to centre, to which the ceiling section 0.5 mm thick bottom wedge of 80 mm with tapered flanges of 26 mm each having lips of 10.5 mm, at 450 mm centre to centre, shall be fixed in a direction perpendicular to G.I. intermediate channel with connecting clips made out of 2.64 mm dia x 230 mm long G.I. wire at every junction, including fixing perimeter channels 0.5 mm thick 27 mm high having flanges of 20 mm and 30 mm long, the perimeter of ceiling fixed to wall/ partition with the help of rawl plugs at 450 mm centre, with 25mm long dry wall screws @ 230 mm interval,	Item24	41.15	sqm	2500.00	102875.00	INR One Lakh Two Thousand Eight Hundred & Seventy Five Only
1.25	Providing & fixing of white vitreous China wall mounting cascade type water closet American standard Acacia E double vortex WC 2/4.2 L 3119 WT/ Proguard (sc.seat&cover),KHOLER Vitreous 28778IN-0, ROCA The GAP RS346477460 & RE801472464, JAQUAR O PS-WHT-15951 with CP bolts, nuts, CI chair hanging arrangements, bakelite seat & cover with CP hinges & rubber buffers, CP brass screw, washer with all accessories with WC connector with Rubber Lip / Buffer and side gap filled with silicon sealant wherever required with flush valve American standard /Grohe WC 38987000,Kohler 7702IN-P-NA, Jaquar JCS-WHT-2400 Flushing cistern GD 2 & 38732000 Skate Cosmopolitan Wall plate/Kholer 8857IN-M-MS1 ROCA RE890195001 Jaquar JCP-CHR-392415 approved including brass / SS screws and washer complete including cutting, making good the walls, floors, slab wherever required as per direction of Engineer-Incharge.	Item25	2.00	each	12000.00	24000.00	INR Twenty Four Thousand Only

	Item Description	Item Code / Make	Quantity	Units	RATE (excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Rs. P	TOTAL AMOUNT in Words
1.26	Providing & fixing of white vitreous china under counter wash basin/circular basin 550x450 American standard Activa modle no 600 mm WP-0440.000.04,KHOLER 2215IN-0 LADENA, 2240X-0 VINTAGE, JAQUAR FNS-WHT-40701 ,Hindware Q197150110 with CP brass waste assembly, CP cast brass bottle trap with extension piece (Jaquar ALD-CHR-769L300X190 / Grohe A-8107-D1Y / Kohler 7314IN-CP,Hindware F850004 , or approved equivalent), 450 mm long CP copper connections pipes (Jaquar Cat No. 803B or approved equivalent), wall flanges and rubber adapters for waste connection complete including CI/MS brackets duly painted, nuts, washers, cutting and making good the walls floors wherever required as per direction of Engineer-Incharge.	Item26	6.00	each	12000.00	72000.00	INR Seventy Two Thousand Only
1.27	Providing & fixing Off white vitreous china flat back urinal with automatic flushing systems American Standard CP-6507.322.04\Concept 1.9 L Urinal HE2,KHOLER 16321T-M-0 PATIO TOUCHLESS, ROCA RS35945E000 EURET ,Hindware Q257630210 or approved equivalent) comprising of all plumbing, electronic and electrical items. CP brass flush pipe with CP brass elbow, CP brass spreader, CP wall flange, infrared photo cells, eyes electrically operated solenoid valve, step down transformer / equipment and any other item required to provide satisfactory functioning including necessary wall cutting / chasing and making good, as required for urinal flushing complete as mentioned above as per direction of Engineer-Incharge.	Item27	4.00	each	13000.00	52000.00	INR Fifty Two Thousand Only
1.28	Providing & fixing C.P. hand spray with lever control (health faucet) American Standard TP 405, KHOLER 12925IN-CP, ROCA RF9060A1, JAQUAR ALD-CHR-573 ,Hindware F160187 or approved equivalent) and flexible hose 1 m long connection with C.P. holder for hand spray complete in all respects as per direction of Engineer-Incharge.	Item28	3.00	each	5000.00	15000.00	INR Fifteen Thousand Only
1.29	Providing and fixing C.P. brass long body bib cock of approved quality conforming to IS standards and weighing not less than 690 gms. a) 15 mm dia nominal bore	Item29	6.00	each	3000.00	18000.00	INR Eighteen Thousand Only
1.30	Providing & fixing 15 mm dia C.P. brass angle valve American Standard FLR 5053N A-4400, KHOLER 80155IN-4-CP CUFF, ROCA RF525159700, JAQUAR AQT-CHR-3057 ,HindwareQ123100126 with C.P. brass wall flange with any other items complete including cutting and making good the walls wherever required as per direction of Engineer-Incharge.	Item30	10.00	each	2000.00	20000.00	INR Twenty Thousand Only
1.31	Providing and fixing plasticised PVC connection pipe with brass unions :45 cm length 15 mm nominal bore	Item31	8.00	each	50.00	400.00	INR Four Hundred Only
1.32	Providing & fixing stainless steel jumbo roll toilet tissue dispenser (Bobrick cat no. B2890 or approved equivalent) with stainless steel roller complete with accessories ,including cutting and making good the walls and floors wherever required as per direction of Engineer-Incharge.	Item32	5.00	each	4000.00	20000.00	INR Twenty Thousand Only
1.33	Providing & fixing recessed liquid soap dispenser (Bobrick cat no. B-822 or approved equivalent) as per direction of Engineer-Incharge.	Item33	5.00	each	600.00	3000.00	INR Three Thousand Only
1.34	Providing & fixing recessed paper towel dispenser and waste receptable (Bobrick cat no. B-3944)or approved equivalent) as per direction of Engineer-Incharge.	Item34	2.00	each	500.00	1000.00	INR One Thousand Only

Sl. No.	Item Description	Item Code / Make	Quantity	Units	RATE (excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT In Rs. P	TOTAL AMOUNT In Words
1.35	Providing & fixing of modular toilet cubicles (Titan Standard 12 mm series of Merino/ sturdo classique of greenlam industries or approved equivalent) consisting of high pressure 12 mm thick compact laminate board as per IS 2046 (Indian Standards) and as per fire retardant BS-476/97 standards with phenolic core panels for partitions of intermediate divider, doors and pilasters(. The cubicle shall have dimensions of 1500 mm depth x 900 mm width x 2050 mm height with a door size of minimum head rail on top of panels and panels shall be fixed on the floor with a clearance of maximum 150 mm using stainless steel satin finish adjustable legs screwed to the floor included stainless steel (SS) lock set, SS door knob, SS gravity self closing hinge, SS coat hook with door stopper, SS U channel, SS head rail, SS adjustable foot, SS tabular holder, SS head rail wall bracket, SS head rail corner connection and SS noise reducing tape, etc.(all SS accessories shall be of Grade 304) as per direction of Engineer-Incharge.Note:- The quantity shall be calculated on basis of surface area of compact laminate board	Item35	27.60	sqm	4000.00	110400.00	INR One Lakh Ten Thousand Four Hundred Only
1.36	Providing & fixing Urinal Modesty Panels having standard dimension of 1200 mm Height x 450 -500 mm Width and 12 mm thickness (SS Series of Merino Industries /sturdo classique of greenlam industries or approved equivalent) Panel starts 500-600 mm above ground level, complete with compact Laminate Board: 12 mm thick Compact Laminate (Titan Series of Merino Industries or approved equivalent) made as per IS 2046 (Indian Standard) and as per fire retardant BS-476/97 standard and should be heat, bacteria, water, chemical, scratch and impact resistant 12 mm thick solid compact laminate panels as per approved texture/shade. The product should have Green Guard Certificate. Including all accessories as per approval and direction of Engineer-in-Charge Modesty panels will be fixed with right angle bracket which will provided in stainless steel grade-304. (a) Right Angle Bracket b) Screws & Wall Plugs. Hardware & Fixing : All screws will of 304 Grade in stainless steel with satin finish & panel will be supported by right angle brackets & will be used to hold the panels with a clearance height upto 500-600 mm. The work includes all accessories, machineries, tools etc., complete as per direction of Engineer-in-charge.	Item36	5.00	each	6000.00	30000.00	INR Thirty Thousand Only
1.37	Providing & fixing sanitary napkin dispenser (ELAN FEMININE) or approved equivalent) as per direction of Engineer-Incharge.	Item37	2.00	each	5000.00	10000.00	INR Ten Thousand Only
1.38	Providing and fixing water closet squatting pan (Indian type W.C. Asian Pan Ultra White Parryware C01231C, CERA Orissa Pan S3020102) with 100 mm sand cast Iron P or S trap, with all fittings and fixtures complete,with flush valve American standard /Grohe WC 38987000,Kohler 7702IN-P-NA, Jaquar JCS-WHT-2400 Flushing cistern GD 2 & 38732000 Skate Cosmopolitan Wall plate/Kholer 8857IN-M-MS1 ROCA RE890195001 Jaquar JCP-CHR-392415 approved including brass / SS screws and washer complete including cutting, making good the walls, floors, slab wherever required as per direction of Engineer-Incharge.	Item38	3.00	each	7000.00	21000.00	INR Twenty One Thousand Only
1.39	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge Internal work - Exposed on wall 20 mm nominal dia pipes.	Item39	50.00	mtr	800.00	40000.00	INR Forty Thousand Only

	Item Description	Item Code / Make	Quantity	Units	RATE (excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1.40	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge Internal work - Exposed on wall 32 mm nominal dia Pipes.	Item40	25.00	mtr	1000.00	25000.00	INR Twenty Five Thousand Only
1.41	Providing, fixing, joints and testing in position the following UPVC Pipe confirming to IS:4985 of 6kg sqcm for sanitary and sewage system cut to required length pipe to be laid below level in trenches up to required depth, including excavation in all kind of soil (hard rock) dewatering, refilling, watering, ramming and removing the surplus excavated material and putting 100 m sand all-round and making good the same. 50 mm OD	Item41	10.00	mtr	1000.00	10000.00	INR Ten Thousand Only
1.42	Providing, fixing, joints and testing in position the following UPVC Pipe confirming to IS:4985 of 6kg sqcm for sanitary and sewage system cut to required length pipe to be laid below level in trenches up to required depth, including excavation in all kind of soil (hard rock) dewatering, refilling, watering, ramming and removing the surplus excavated material and putting 100 m sand all-round and making good the same. 75 mm OD	Item42	10.00	mtr	1500.00	15000.00	INR Fifteen Thousand Only
1.43	Providing, fixing, joints and testing in position the following UPVC Pipe confirming to IS:4985 of 6kg sqcm for sanitary and sewage system cut to required length pipe to be laid below level in trenches up to required depth, including excavation in all kind of soil (hard rock) dewatering, refilling, watering, ramming and removing the surplus excavated material and putting 100 m sand all-round and making good the same. 110 mm OD	Item43	25.00	mtr	2000.00	50000.00	INR Fifty Thousand Only
1.44	Providing and fixing beveled edge mirror of superior glass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete.	Item44	4.20	sqm	2000.00	8400.00	INR Eight Thousand Four Hundred Only
1.45	Providing and fixing 100 mm stainless steel (304 Grade) grating with cockroach floor These floor trap feature a hinged grating top that can be opened or closed. The hinged design allows for easy access to the drain for cleaning and maintenance purposes. When closed, the grating top provides a barrier, preventing debris and odour from escaping while still allowing water to flow into the drain.	Item45	5.00	each	4000.00	20000.00	INR Twenty Thousand Only
1.46	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately). Second class teak wood	Item46	0.16	cum	100000.00	16000.00	INR Sixteen Thousand Only

उप महाप्रबंधक (अभि. सिविल)
Dy. General Manager (Engg-Civil)
भारतीय विमानपत्तन प्राधिकरण
Airports Authority of India
लाल बहादुर शास्त्री हवाई अड्डा, वाराणसी
Lal Bahadur Shastri Airport, Varanasi

Sl. No.	Item Description	Item Code / Make	Quantity	Units	RATE (excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Rs. P	TOTAL AMOUNT In Words
1.47	Providing & Fixing decorative high pressure laminated sheet of plain / wood grain in gloss / matt/ suede finish with high density protective surface layer and reverse side of adhesive bonding quality conforming to IS : 2046 Type S, including cost of adhesive of approved quality. 1.5mm thick	Item47	3.90	sqm	3000.00	11700.00	INR Eleven Thousand Seven Hundred Only
1.48	Providing and fixing bright /matt finished Stainless Steel handles of approved quality & make with necessary screws etc all complete.200mm	Item48	4.00	each	900.00	3600.00	INR Three Thousand Six Hundred Only
1.49	Providing and fixing chromium plated brass 100 mm mortice latch and lock with 6 levers and a pair of lever handles of approved quality with necessary screws etc. complete.	Item49	2.00	each	2000.00	4000.00	INR Four Thousand Only
1.50	Providing and placing SS 304 Padalbin 7ltr Dustbin in Terminal building at required places as per direction of EIC.	Item50	8.00	each	5000.00	40000.00	INR Forty Thousand Only
1.51	Providing and fixing SS 304 grade Gutterman channel of size 100x30 mm with Top Grating of load class Human load . Steel tray (drip tray) of standard design with necessary fabrication, hanger and support under the horizontal suspended soil / waste header. Tray shall be installed in slope with drain connection at end. The installation shall be to the satisfaction / approval of Engineer-in-charge. The installation shall be to the satisfaction / approval of Engineer-in-charge.	Item51	6.40	mtr	1000.00	6400.00	INR Six Thousand Four Hundred Only
1.52	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	Item52	6.00	cum	500.00	3000.00	INR Three Thousand Only
1.53	Providing and fixing CP quarter turn pillar cock of Kholer, Roca, Jaquar ,Hindware Q403114120 or equivalent 15mm nominal bore as per satisfaction of EIC.	Item53	5.00	each	2000.00	10000.00	INR Ten Thousand Only
1.54	Providing and fixing CP bib cock long nose with wall flange and aerator of CERA F-1017152 or equivalent 15mm nominal bore as per satisfaction of EIC.	Item54	8.00	each	3000.00	24000.00	INR Twenty Four Thousand Only
1.55	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade :(a) Two or more coats on new work	Item55	8.00	sqm	200.00	1600.00	INR One Thousand Six Hundred Only
1.56	Wall painting with acrylic emulsion paint, having VOC (Volatile Organic Compound) content less than 50 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour Two coats	Item56	41.14	sqm	200.00	8228.00	INR Eight Thousand Two Hundred & Twenty Eight Only
1.57	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	Item57	41.14	sqm	200.00	8228.00	INR Eight Thousand Two Hundred & Twenty Eight Only
1.58	Carriage of material By Mechanical Transport (Tractor with trolly) including loading,unloading and stacking of serviceable material at designated locations/Store and disposal of unserviceable material as per direction of EIC.	Item58	2.00	trip	1500.00	3000.00	INR Three Thousand Only

	Item Description	Item Code / Make	Quantity	Units	RATE (excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1.59	Deduct for taking away of C.P. brass/Brass bib cock, stop cock, long body bib cock, long nose bib cock, angle valve, ball valve, close hole basin mixer, C.P. waste in basin/ sink and the like received from dismantling at all levels. The material so received shall be the property of contractor after dismantling duly weighed/measured before removing from the site in the presence of Engineer-in-charge or his authorised representative all complete. (the rate (minus) multiple by executed quantity and derived amount shall be deducted from firm's bill amount)	Item59	10.00	Kg	100.00	-1000.00	INR Minus One Thousand Only
1.60	Deduct for taking away of SCI pipe fitting, centrifugal cast (spun)/sand cast iron pipes and fittings, C.I. flushing cistern, G.I. pipes and fittings, steel doors, window, ventilators, grill, round or square bars etc. and the like item received from dismantling. The material so received shall be the property of contractor after dismantling duly weighed/ measured before removing from the site in the presence of Engineer-in-charge or his authorised representative all complete. [the rate (minus) multiple by executed quantity and derived amount shall be deducted from firm's bill amount]	Item60	20.00	Kg	200.00	-4000.00	INR Minus Four Thousand Only
1.61	Providing and placing decorative artificial imported plastic foliage, branches and other parts of plants, without flowers or flower buds and flower buds of a kind suitable for bouquets or for ornamental purposes, dried, dyed, bleached, impregnated or otherwise prepared decorative plants of premium quality with decorative pot/basket marble finish as per approval of EIC representative. The sample kept in the office of the Engineer-In-Charge, the supplied item must be resemble with the sample. All work completed as per satisfaction of Engineer-In-Charge. (a) Areca Palm-Cat No:KH1186 of height 6.5 Ft (From pot base to top most part)	Item61	2.00	Each	4000.00	8000.00	INR Eight Thousand Only
1.62	Providing and placing decorative artificial imported plastic foliage, branches and other parts of plants, without flowers or flower buds and flower buds of a kind suitable for bouquets or for ornamental purposes, dried, dyed, bleached, impregnated or otherwise prepared decorative plants of premium quality with decorative pot/basket marble finish as per approval of EIC representative. The sample kept in the office of the Engineer-In-Charge, the supplied item must be resemble with the sample. All work completed as per satisfaction of Engineer-In-Charge. (b) Areca Palm-Cat No:KH1162 of height 5.5 Ft (From pot base to top most part)	Item62	2.00	Each	3000.00	6000.00	INR Six Thousand Only
1.63	Providing and placing decorative artificial imported plastic foliage, branches and other parts of plants, without flowers or flower buds and flower buds of a kind suitable for bouquets or for ornamental purposes, dried, dyed, bleached, impregnated or otherwise prepared decorative plants of premium quality with decorative pot/basket marble finish as per approval of EIC representative. The sample kept in the office of the Engineer-In-Charge, the supplied item must be resemble with the sample. All work completed as per satisfaction of Engineer-In-Charge. (c) Banyan Tree-Cat No:KH1183 of height 5Ft (From pot base to top most part)	Item63	2.00	Each	3000.00	6000.00	INR Six Thousand Only

Sl. No.	Item Description	Item Code / Make	Quantity	Units	RATE (excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Rs. P	TOTAL AMOUNT In Words
1.64	Providing and placing decorative artificial imported plastic foliage, branches and other parts of plants, without flowers or flower buds and flower buds of a kind suitable for bouquets or for ornamental purposes, dried, dyed, bleached, impregnated or otherwise prepared decorative plants of premium quality with decorative pot/basket marble finish as per approval of EIC representative. The sample kept in the office of the Engineer-In-Charge, the supplied item must be resemble with the sample. All work completed as per satisfaction of Engineer-In-Charge. (d) Sapota Tree-Cat No:KH1151 of height 5.5 Ft (From pot base to top most part)	Item64	2.00	Each	5000.00	10000.00	INR Ten Thousand Only
1.65	Providing and placing decorative artificial imported plastic foliage, branches and other parts of plants, without flowers or flower buds and flower buds of a kind suitable for bouquets or for ornamental purposes, dried, dyed, bleached, impregnated or otherwise prepared decorative plants of premium quality with decorative pot/basket marble finish as per approval of EIC representative. The sample kept in the office of the Engineer-In-Charge, the supplied item must be resemble with the sample. All work completed as per satisfaction of Engineer-In-Charge. (e) Rubber Plant-Cat No:KH1046 of height 5Ft (From pot base to top most part)	Item65	2.00	Each	1000.00	2000.00	INR Two Thousand Only
1.66	Providing and placing decorative artificial imported plastic foliage, branches and other parts of plants, without flowers or flower buds and flower buds of a kind suitable for bouquets or for ornamental purposes, dried, dyed, bleached, impregnated or otherwise prepared decorative plants of premium quality with decorative pot/basket marble finish as per approval of EIC representative. The sample kept in the office of the Engineer-In-Charge, the supplied item must be resemble with the sample. All work completed as per satisfaction of Engineer-In-Charge. (f) Ficus Tree-Cat No:KH1127 of height 5.3Ft (From pot base to top most part)	Item66	2.00	Each	1500.00	3000.00	INR Three Thousand Only
1.67	Providing and placing decorative artificial imported plastic foliage, branches and other parts of plants, without flowers or flower buds and flower buds of a kind suitable for bouquets or for ornamental purposes, dried, dyed, bleached, impregnated or otherwise prepared decorative plants of premium quality with decorative pot/basket marble finish as per approval of EIC representative. The sample kept in the office of the Engineer-In-Charge, the supplied item must be resemble with the sample. All work completed as per satisfaction of Engineer-In-Charge. (g) Bougainvillea Tree-Cat No:KH1051 of height 5.6 Ft (From pot base to top most part)	Item67	2.00	Each	1500.00	3000.00	INR Three Thousand Only

11/07/2025
 Dy. General Manager (Engg-Civil)
 भारतीय विमानपत्तन प्राधिकरण
 Airports Authority of India
 लाल बहादुर शास्त्री हवाई अड्डा, वाराणसी
 Lal Bahadur Shastri Airport, Varanasi

	Item Description	Item Code / Make	Quantity	Units	RATE (excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT in Words
1.68	Providing and placing decorative artificial imported plastic foliage, branches and other parts of plants, without flowers or flower buds and flower buds of a kind suitable for bouquets or for ornamental purposes, dried, dyed, bleached, impregnated or otherwise prepared decorative plants of premium quality with decorative pot/basket marble finish as per approval of EIC representative. The sample kept in the office of the Engineer-In-Charge, the supplied item must be resemble with the sample. All work completed as per satisfaction of Engineer-In-Charge. (h) Banana Tree-Cat No:KH1087 of height 5Ft (From pot base to top most part)	Item68	2.00	Each	3000.00	6000.00	INR Six Thousand Only
1.69	Providing and placing decorative artificial imported plastic foliage, branches and other parts of plants, without flowers or flower buds and flower buds of a kind suitable for bouquets or for ornamental purposes, dried, dyed, bleached, impregnated or otherwise prepared decorative plants of premium quality with decorative pot/basket marble finish as per approval of EIC representative. The sample kept in the office of the Engineer-In-Charge, the supplied item must be resemble with the sample. All work completed as per satisfaction of Engineer-In-Charge. (i) Banana Tree-Cat No:KH1086 of height 5.4 Ft (From pot base to top most part)	Item69	2.00	Each	3000.00	6000.00	INR Six Thousand Only
1.70	Providing and placing decorative artificial imported plastic foliage, branches and other parts of plants, without flowers or flower buds and flower buds of a kind suitable for bouquets or for ornamental purposes, dried, dyed, bleached, impregnated or otherwise prepared decorative plants of premium quality with decorative pot/basket marble finish as per approval of EIC representative. The sample kept in the office of the Engineer-In-Charge, the supplied item must be resemble with the sample. All work completed as per satisfaction of Engineer-In-Charge. (j) Coconut Tree-Cat No:KH1211 of height 7.5Ft (From pot base to top most part)	Item70	2.00	Each	5000.00	10000.00	INR Ten Thousand Only
1.71	Supplying and installation of one seater modular toilet of size 4*4 with 1000ltr bio-disester including Toilet Patform, 1 no 200 ltr water tank with all conection and all standard sanitary fitting Indian type / European type / handicapped as per manufacturer's specification & direction of Engineer-in-Charge.	Item71	4.00	Each	30000.00	120000.00	INR One Lakh Twenty Thousand Only
1.72	Supplying and installation of handicapped one seater modular toilet of size 6*4ft with 1000ltr bio-disester including Toilet Patform, 1 no 200 ltr water tank with all conection and all standard sanitary fitting suitable WC and washbasin adequate for disabled person as per manufacturer's specification & direction of Engineer-in-Charge.	Item72	1.00	Each	50000.00	50000.00	INR Fifty Thousand Only
1.73	Providing SS 304 grade satin finish L shaped grab bar with Ø 73mm inner cap and Ø 75mm outer cap of KICH Make (GB213224S) size Ø 32 x 600 (L) x 600 (W) mm including Anchor Fastening fixing System with necessary fixing Accessoties as per drawing and as directed by Engineer-In-Charge.	Item73	1.00	Each	25000.00	25000.00	INR Twenty Five Thousand Only

उप महाप्रबंधक (अभ्र. - सिविल)
General Manager (Civil)
भारतीय विमानपत्तन प्राधिकरण
Airports Authority of India
लाल बहादुर शास्त्री हवाई अड्डा, वाराणसी
Lal Bahadur Shastri Airport, Varanasi

Sl. No.	Item Description	Item Code / Make	Quantity	Units	RATE (excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1.74	Providing SS 304 grade satin finish Swing -Wall Mounted grab bar of KICH Make (GB3132325S) size Ø 32 x 800 (L) x 187 (W) mm including Anchor Fastening fixing System with necessary fixing Accessoties as per drawing and as directed by Engineer-In-Charge.	Item74	2.00	Each	18000.00	36000.00	INR Thirty Six Thousand Only
1.75	Providing SS 304 grade satin straight grab bar with Ø 73 mm inner cap and Ø 75 mm Outer Cap of KICH Make (GB513216S) size Ø 32 x 400 (c/c) x 432 (T/L) including Anchor Fastening fixing System with necessary fixing Accessoties as per drawing and as directed by Engineer-In-Charge.	Item75	1.00	Each	15000.00	15000.00	INR Fifteen Thousand Only
1.76	Providing and fixing sun control film (Cosmo sunshield or equivalent) of ultra cool series CS 650-AC 7090.after thorough cleaning on glass surface, the rate include installation, cleaning of glass, scaffolding wherever required.	Item76	36.80	Sqm	2000.00	73600.00	INR Seventy Three Thousand Six Hundred Only


11/08/2025

उप महाप्रबंधक (सिविल)
Dy. General Manager (Engg-Civil)
भारतीय विमानपत्तन प्राधिकरण
Airports Authority of India
लाल बहादुर शास्त्री हवाई अड्डा, वाराणसी
Lal Bahadur Shastri Airport, Varanasi

	Item Description	Item Code / Make	Quantity	Units	RATE (excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT in Words
2.00	Electricial works :						
2.01	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed steel conduit, with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable etc. as required. Group C	Item77	14.00	Point	1500.00	21000.00	INR Twenty One Thousand Only
2.02	Wiring for group controlled (looped) light point/fan point/exhaust fan point/ call bell point (without independent switch etc.) with 1.5 sq. mm FRLS PVC insulated copper conductor single core cable in surface/ recessed steel conduit, and earthing the point with 1.5 sq. mm FRLS PVC insulated copper conductor single core cable etc. as required. Group C	Item78	18.00	Point	1500.00	27000.00	INR Twenty Seven Thousand Only
2.03	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed steel conduit as required. (a)(2 X 2.5 sq. mm +1 X 2.5 sq. mm earth wire)	Item79	65.00	Meter	1000.00	65000.00	INR Sixty Five Thousand Only
2.04	Supplying and fixing suitable size GI box with modular plate and cover in front on surface or in recess , including providing and fixing 6 pin 5/6 & 15/16 A modular socket outlet and 15/16 A modular switch, connections etc. as required.	Item80	5.00	Each	600.00	3000.00	INR Three Thousand Only
2.05	Wiring for light/ power plug with 2X4 sq. mm FRLS PVC insulated copper conductor single core cable in surface/ recessed steel conduit alongwith 1 No 4 sq. mm FRLS PVC insulated copper conductor single core cable for loop earthing as required.	Item81	60.00	Metre	800.00	48000.00	INR Forty Eight Thousand Only
2.06	Supplying and fixing of following sizes of steel conduit along with accessories in surface/recess including painting in case of surface conduit, or cutting the wall and making good the same in case of recessed conduit as required.(Conduit 25 mm)	Item82	15.00	Meter	800.00	12000.00	INR Twelve Thousand Only
2.07	Supplying and fixing following way, single pole and neutral, sheet steel, MCB distribution board, 240 V, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator)8 way SPN DB, Double door	Item83	2.00	Meter	1500.00	3000.00	INR Three Thousand Only
2.08	Supplying and fixing 5 amps to 32 amps rating, 240/415 volts, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.(Single pole MCB 6-32 Amp)	Item84	8.00	Each	1200.00	9600.00	INR Nine Thousand Six Hundred Only
2.09	Supplying and fixing following rating, double pole, (single phase and neutral), 240 volts, Miniature circuit breaker (MCB), in the existing MCB DB complete with connections, testing and commissioning etc. as required.(40 amps)	Item85	2.00	Each	2000.00	4000.00	INR Four Thousand Only
2.10	Supply of recessed mounted LED circular downlighter of rated capacity of 15W to 20 W, pre die- cast aluminium housing, integrated driver and suitable to operate on 230-240V, 50Hz AC supply complete as per technical specification etc as required.	Item86	24.00	Each	1500.00	36000.00	INR Thirty Six Thousand Only

Sl. No.	Item Description	Item Code / Make	Quantity	Units	RATE (excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT In Rs. P	TOTAL AMOUNT In Words
2.11	Supply of approx 4 feet length recessed LED luminaire of rated capacity 14 W to 20 W, with pre-wired luminaire, aluminium extruded linear lighting luminaires, internal wiring, integral electronic control driver complete etc. as required.	Item87	4.00	Each	2500.00	10000.00	INR Ten Thousand Only
2.12	Supplying , installation , testing and commissioning of Passive Infrared(PIR) technology based occupancy sensor having high performance , non regulated programmable type , suitable for connected load upto 10Amp , for mounting height up to 2.8 mtr and for 5 m diameter coverage area along with necessary fixing arrangements i/c programming at site etc. complete as required.	Item88	2.00	Each	2000.00	4000.00	INR Four Thousand Only
2.13	Installation, testing and commissioning of pre-wired, LED Recess/ surface Mounted, 15-20W LED fitting etc of item mentioned above fixtures with all accessories including nut bolt washer and hanging/fixing arrangements if required directly on existing in False ceiling / surface/ including connection as per site requirement.	Item89	24.00	Each	1300.00	31200.00	INR Thirty One Thousand Two Hundred Only
2.14	Installation, testing and commissioning of pre-wired, 14-20 watt LED Recess/ surface Mounted, LED light etc of item as mentioned above fixtures with all accessories including nut bolt washer and hanging/fixing arrangements if required directly on existing in False ceiling / wall / surface including connection as per site requirement.	Item90	4.00	Each	1500.00	6000.00	INR Six Thousand Only
2.15	Supply of following sizes of Power Cables, multi stranded conductor, XLPE Insulated, cores laid up, PVC tape / Extruded Inner sheathed , Armour, FRLS at outer sheathed, 1100V grade as per IS 7098(Part 1) 1988(a) 3 CORE 10 sq.mm. CU Ar. XLPE cable)	Item91	25.00	Meter	2000.00	50000.00	INR Fifty Thousand Only
2.16	Laying and fixing of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 kV grade of following size on cable tray as required. Upto 35 sq. mm (clamped with 0.55mm thick saddle)	Item92	10.00	Meter	2000.00	20000.00	INR Twenty Thousand Only
2.17	Laying and fixing of one number PVC insulated and PVC sheathed power cable of 1.1 KV grade of following size on wall surface as required. Upto 35 sq mm (clamped with 0.55mm thick saddle)	Item93	15.00	Meter	1500.00	22500.00	INR Twenty Two Thousand Five Hundred Only
2.18	Supplying and making end termination with brass compression gland and copper lugs for following size of PVC insulated and PVC sheathed / XLPE copper conductor cable of 1.1 KV grade as required. (a)(3C X 10 sq. mm)	Item94	2.00	Each	2000.00	4000.00	INR Four Thousand Only
2.19	Supplying and installing following size of perforated Hot Dipped Galvanised Iron cable tray with perforation not more than 17.5%, in convenient sections, joined with connectors, suspended from the ceiling with G.I. suspenders including G.I. bolts & nuts, etc. as required. 100 mm width X 50 mm depth X 1.6 mm thickness	Item95	15.00	Meter	900.00	13500.00	INR Thirteen Thousand Five Hundred Only
2.20	Supply & fixing of Heavy duty, Wall mounted, fully Automatic Hand Dryers suitable to operate on single phase, 230V, 50Hz AC supply having Stainless steel body, motor speed upto 2500 RPM, noise level upto 70dB, etc.	Item96	3.00	Each	3000.00	9000.00	INR Nine Thousand Only

Item Description		Item Code / Make	Quantity	Units	RATE (excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Rs. P	TOTAL AMOUNT In Words
2.21	Providing and fixing illuminated signs for washroom and drinking water (refer design drawing 2.4a-S, 2.4a-G, Tata Elxsi Limited guidelines) including all operations from fabrication to installation all complete as per drawings, technical specifications, signage schedule and to the satisfaction of the Engineer-in-Charge. Wall mounted/ Wall hanging (Single side content-Sign Face: acrylic & Back:3mm ACP)a) Wall Mounted/ Wall hanging Utility Sign as per Tata elxi Guide Lines for Toilets Gents/ Ladies/ Drinking Water / PH Toilet (if required). (450mm x 450mm x 50mm)Sign faceSign face shall be made in 8mm thick 040 white acrylic (as specified) having graphics pasted in Plotter cut Blockout vinyl. Entire panel covered with a protective overlamine. The films to wrap around the edge of the acrylic to a distance of 25mm on the back side. The Plotter cut blockout vinyl shall match the specified colour (colour Pantone Black 6C) and vinyl for text Pantone Cyan 311C as per graphics and of specified make duly approved by the Engineer-in-Charge. Sign FrameProviding and fixing sign frame 50mm wide powder coated, colour RAL 9006 special aluminium extrusion with inbuilt frame to receive the sign face. The sign face shall be fixed to sign frame with the 3M brand dual	Item97	4.00	Each	40000.00	160000.00	INR One Lakh Sixty Thousand Only
2.22	Supply, installation, balancing and commissioning of fabricated at site GSS sheet metal rectangular/round ducting complete with neoprene rubber gaskets, elbows, splitter dampers, vanes, hangers, supports etc. as per approved drawings and specifications of following sheet thickness complete as required. (Thickness 0.63 mm sheet)	Item98	80.00	Sqmtr.	1000.00	80000.00	INR Eighty Thousand Only
2.23	Supply, installation, balancing and commissioning of fabricated at site GSS sheet metal rectangular/round ducting complete with neoprene rubber gaskets, elbows, splitter dampers, vanes, hangers, supports etc. as per approved drawings and specifications of following sheet thickness complete as required (Thickness 0.80 mm sheet)	Item99	15.00	Sqmtr.	1000.00	15000.00	INR Fifteen Thousand Only
2.24	Supplying & fixing of powder coated extruded aluminium Return Air Grills with louvers but without volume control dampers complete as required.	Item100	1.50	Sqmtr.	10000.00	15000.00	INR Fifteen Thousand Only
2.25	Supplying, installation, testing and commissioning of heavy duty inline exhaust fan with centrifugal blower and motor encased in sheet metal casing. The motor shall be suitable for 220 volt, 1 phase, 50 Hz, AC supply. The price shall include fan speed regulator etc. as required as per specification of following sizes.(2700 CFM With 15 mm static pressure)	Item101	1.00	Each	4000.00	4000.00	INR Four Thousand Only
Total in Figures						2647176.00	INR Twenty Six Lakh Forty Seven Thousand One Hundred & Seventy Six Only
Quoted Rate in Words		INR Twenty Six Lakh Forty Seven Thousand One Hundred & Seventy Six Only					

11/08/2025
 Dy. General Manager (Engg-C)
 भारतीय विमानपत्तन प्राधिकरण
 Airports Authority of India
 लाल बहादुर शास्त्री हवाई अड्डा, वार
 Lal Bahadur Shastri Airport, Varanasi