

संदर्भ सं.: भाविप्रा/सूरत/व.प्र.(अभि-सि)/ GP & LLZ/2025-26/1245-1255  
Ref. No: AAI/SURAT/SM (E-C)/GP & LLZ/2025-26/

दिनांक: 06/01/2026  
Date: 06/01/2026

**(कार्य आदेश / Work Order)**

सेवा में,  
मेसर्स, जय प्रकाशभाई तिलारा  
"श्रीजी सदन", सत्यम पार्क,  
अमर नगर रोड,  
जेटपुर, राजकोट-360370।  
ई-मेल: jptilara2015@gmail.com

To,  
M/s. Jay Prakashbhai Tilara,  
"Shreeji Sadan", Satyam Park,  
Amarnagar Road,  
Jetpur, Rajkot - 360370.  
E-mail: jptilara2015@gmail.com

**कार्य का नाम:-** Civil works for Installation of Glide path (GP) & Localizer (LLZ) equipment including Frangible Huts and other related works at Surat International Airport, Surat.

**संदर्भ/Ref.:-** आपका दिनांक 03/09/2025 को खोला गया टेंडर (निविदा आईडी सं.: 2025\_AAI\_242331\_1)

Your tender opened on 03/09/2025 (Tender Id No: 2025\_AAI\_242331\_1)

महोदय / Dear Sir,


1. ऊपर उल्लेखित कार्य हेतु आपकी ई-निविदा, संलग्न अनुसूची के अनुसार, नियत मद दर पर उद्धृत कुल राशि रु. 2,84,28,627.51 (बिना GST) (रुपए दो करोड़ चौरासी लाख अठ्ठाईस हजार छह सौ सत्ताईस और इक्यावन पैसे मात्र) जो निविदा की अनुमानित लागत राशि रु. 3,62,19,000.00 (रुपए तीन करोड़ बासठ लाख उन्नीस हजार मात्र) से 21.51% (इक्कीस दशमलव इक्यावन प्रतिशत) से नीचे है, अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से स्वीकार की जाती है।

Your e-tender for the work mentioned above is hereby accepted as per attached schedule on behalf of the Chairman, Airports Authority of India, at the item rates quoted by you totalling to Rs. 2,84,28,627.51 (Without GST) (Rupees Two Crore Eighty-Four Lakhs Twenty-Eight Thousand Six-Hundred Twenty-Seven and Fifty-One Paise Only), which is 21.51% (Twenty-One Decimal Fifty-One Percent) below the estimated cost put to tender of Rs. 3,62,19,000.00 (Rupees Three Crore Sixty-Two Lakhs Nineteen Thousand Only).

2. वरिष्ठ प्रबंधक (अभि-सिविल), भाविप्रा, सूरत अंतर्राष्ट्रीय हवाई अड्डा, सूरत-394550 कार्य के प्रभारी अभियंता होंगे। आपसे निवेदन है कि आप संविदा करार पर हस्ताक्षर करने एवं उसे पूरा करने हेतु दिनांक 30/01/2026 तक वरिष्ठ प्रबंधक (अभि-सिविल), भाविप्रा सूरत अंतर्राष्ट्रीय हवाई अड्डा, सूरत-394 550 के कार्यालय में उपस्थित हों। संविदा करार रु. 300/- (रुपये तीन सौ मात्र) के गैर न्यायिक स्टॉप पेपर पर निष्पादित किया जाएगा और स्टॉप पेपर की लागत आपके द्वारा वहन की जायेगी।

Sr. Manager (Engg-Civil), AAI, Surat International Airport, Surat-394550 shall be Engineer-In-Charge of this work. You are requested to attend the office of Sr. Manager (Engg.-Civil), AAI, Surat International Airport, Surat-394550 by date 30/01/2026 to sign and complete the Contract Agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs. 300/- (Rupees Three Hundred Only) and the cost of the stamp paper shall be borne by you.

पृष्ठ / Page-1

  
06.01.2026  
S.m (E.C)



Less Oil More Life  
Less Sugar, More Life

**भारतीय विमानपत्तन प्राधिकरण**  
AIRPORTS AUTHORITY OF INDIA  
**सूरत अंतर्राष्ट्रीय हवाई अड्डा**  
SURAT INTERNATIONAL AIRPORT

3. आपकी निविदा के साथ प्राप्त अग्रिम धरोहर राशि रु. 10,86,600.00 (रुपए दस लाख छियासी हजार छह सौ मात्र) निविदा दस्तावेज के पृष्ठ GCC-4 पर दी गई अनुच्छेद 1 की शर्त के अनुसार प्रतिभूति जमा के रूप में प्रयुक्त तथा संपरिवर्तित किया जायेगा। सी.पी.पी. पोर्टल पर AOC होने पर उक्त राशि आपको पुनः देय हो जाएगी। कृपया इस पत्र के जारी होने की तिथि से 10 दिनों के भीतर पूर्ण जमानत राशि रु. 28,42,863.00 (रुपए अट्ठाईस लाख बयालीस हजार आठ सौ तिरसठ मात्र) जमा करना है, असफल होने पर पृष्ठ संख्या GCC-16 पर दी गई शर्त 1 (A) के अनुसार चालू बिल से काट लिया जायेगा एवं AOC अग्रिम धरोहर राशि के मूल्य की जमानत राशि संग्रहीत होने पर ही किया जाएगा।

The earnest money amount of Rs. 10,86,600.00 (Rupees Ten Lakhs Eighty-Six Thousand Six Hundred Only) received along with your tender as per para-1 on page GCC-04 of the contract document, same shall be returned to you after doing AOC on CPP Portal. Please deposit amount of Rs. 28,42,863.00 (Rupees Twenty-Eight Lakhs Forty-Two Thousand Eight Hundred Sixty-Three Only) towards security deposit within 10 days from the date of issue of this letter, failing which the same will be deducted from your running bills as per condition of clause no.1 (A) on page GCC-16 of the contract document and AOC shall be done after accumulation of Security Deposit amount equal to EMD amount.

4. आपसे अनुरोध है कि ठेका श्रम (विनियमन और उन्मूलन) अधिनियम 1970 के प्रावधान का पालन करें और ठेका श्रम (विनियमन और उन्मूलन) केंद्रीय नियम 1971, बाल श्रम (निषेध और विनियमन) अधिनियम 1986, निर्माण श्रमिक (रोजगार का विनियमन और सेवा की शर्त) अधिनियम 1996, भवन एवं अन्य निर्माण श्रमिक कल्याण उपकर अधिनियम 1996 जैसा कि निविदा के जीसीसी के पृष्ठ संख्या 50 पर खंड 19 में और केंद्र और राज्य सरकार के नियम में निर्दिष्ट है।

You are requested to comply with the provision of Contract Labour (Regulation and Abolition) ACT 1970 and Contract Labour (Regulation and Abolition) Central Rules 1971, Child Labour (Prohibition & Regulation) Act 1986, Construction Workers (Regulation of Employment and Condition of Service) Act 1996, Building and other Construction Workers Welfare Cess Act 1996 as specified in Clause 19 at page no. 50 of GCC of tender and rules of Central and State Government.

5. आपको यह भी निर्देश दिया जाता है कि आप तुरंत सहायक प्रबंधक (अभि.-सिविल), सूरत हवाईअड्डे से संपर्क करें जो आपको साईट सौंपने की व्यवस्था करेंगे।

You are also directed to contact Asstt. Manager (Engg.Civil), Surat Airport immediately, who will arrange to hand over the site to you.

6. ई-टेंडरिंग प्रक्रिया के दौरान उठाए गए सभी शुद्धिपत्र, प्रश्न, स्पष्टीकरण आदि और उनके उत्तर भी समझौते का हिस्सा होंगे।

All Corrigendum, queries, clarifications etc. raised during e-tendering process and replies thereof shall also form part of the agreement.

7. कृपया ध्यान दें कि कार्य पूरा करने के लिए आपको **06 (छह) माह** का समय प्रदान किया जाता है, जो इस कार्य आदेश जारी करने के दसवें दिन से गिना जायेगा।

Please note that the time allowed for carrying out the work shall be **06 (Six) Months** which shall be reckoned from the 10th day after the issue of this letter.

पृष्ठ / Page - 2

8. अनुबंध के संबंध में आगे कोई भी पत्राचार सामान्य रूप से प्रभारी अभियंता को संबोधित किया जाना चाहिए।

Any further correspondence in connection with the contract should normally be addressed to the Engineer-In-Charge.

9. कृपया पत्र की पावती भेजे और इस पत्र की नकल पर स्वीकृति की निशानी के रूप में विधिवत हस्ताक्षर करने के बाद अधोहस्ताक्षरी को भेजें।

Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

10. संदर्भ के तहत यह पत्र करारनामे का हिस्सा होगा।

This letter under reference shall form part of Agreement.

11. हिंदी और अंग्रेजी संस्करण के बीच किसी भी विसंगति के मामले में, अंग्रेजी संस्करण मान्य होगा।

In case of any discrepancies between Hindi and English version, English version will prevail.

धन्यवाद / Thanking You,

भवदीय / Yours faithfully,



06.01.202

(रविकांत मेश्राम)

(Ravikant Meshram)

वरिष्ठ प्रबंधक (अभि.-सिविल)

Sr. Manager (Engg.-Civil)

सूरत अंतर्राष्ट्रीय हवाई अड्डा, सूरत।

Surat International Airport, Surat.

कृते तथा ओर से अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण

For and on behalf of the Chairman, Airports Authority of India.

संलग्नक : मात्रा की सूची (पृष्ठ - 1 से 4)

Encl.: Schedule of Quantity (Page 1 to 4)

| Government eProcurement System<br>Created By: Ravikant Meshram<br>Created Date/Time: 03-Sep-2025 12:23 PM<br>Tender Title: Civil Works for Installation of Glide Path (GP) and Localizer (LLZ) equipment including frangible Huts and other related works at Surat International Airport, Surat<br>Tender ID: 2025_AAI_242331_1 |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |           |       |                                                    |              |
|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------|-------|----------------------------------------------------|--------------|
| Tender Inviting Authority: Sr. Manager (Engg-Civil), AAI, Surat International Airport, Surat                                                                                                                                                                                                                                    |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |           |       |                                                    |              |
| Name of Work: Civil Works for Installation of Glide Path (GP) & Localizer (LLZ) equipment including frangible Huts and other related works at Surat International Airport, Surat.                                                                                                                                               |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |           |       |                                                    |              |
| Contract No: 2025_AAI_242331_1                                                                                                                                                                                                                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |           |       |                                                    |              |
| SCHEDULE OF WORK / ITEM(S)                                                                                                                                                                                                                                                                                                      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |           |       |                                                    |              |
| Sl.No                                                                                                                                                                                                                                                                                                                           | Description of Work / Item(s)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | No.of Qty | Units | Jay Prakashbhai Tilara<br>(GSTN-NA) BID ID -885554 |              |
|                                                                                                                                                                                                                                                                                                                                 |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |           |       | Rate                                               | Amount       |
| 1.00                                                                                                                                                                                                                                                                                                                            | Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge.<br>a) Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | 73.00     | cum   | 452.38                                             | 33,023.74    |
| 2.00                                                                                                                                                                                                                                                                                                                            | Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and for all lift , as directed by Engineer-incharge.<br>a) All kinds of soil                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | 13596.00  | cum   | 130.95                                             | 17,80,396.20 |
| 3.00                                                                                                                                                                                                                                                                                                                            | Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and for all lift.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | 500.00    | cum   | 95.24                                              | 47,620.00    |
| 4.00                                                                                                                                                                                                                                                                                                                            | Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | 6.00      | cum   | 1945.58                                            | 11,673.48    |
| 5.00                                                                                                                                                                                                                                                                                                                            | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :<br>a) 1:4:8 (1 Cement : 4 coarse sand (zone-III) derived from natural sources : 8 graded stone aggregate 40 mm nominal size derived from natural sources)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | 958.00    | cum   | 5150.42                                            | 49,34,102.36 |
| 6.00                                                                                                                                                                                                                                                                                                                            | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :<br>1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | 50.00     | cum   | 6166.46                                            | 3,08,323.00  |
| 7.00                                                                                                                                                                                                                                                                                                                            | Providing and laying in position ready mixed or site batched design mix cement concrete for plain cement concrete work; using coarse aggregate and fine aggregate derived from natural resources, Portland Pozzolana/Ordinary Portland /Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; but excluding the cost of centering, shuttering and finishing as per direction of the engineer-in-charge; for the following grades of concrete.<br>Note: Extra cement up to 10% of the minimum specified cement content in design mix shall be payable separately. In case the cement content in design mix is more than 110% of the minimum specified cement content, the contractor shall have discretion to either re-design the mix or bear the cost of extra cement.<br>All works upto plinth level : Concrete of M25 grade with minimum cement content of 300 kg /cum | 25.00     | cum   | 6141.50                                            | 1,53,537.50  |

  
S.M (EC)

| SCHEDULE OF WORK / ITEM(S) |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |           |       |                                                    |              |
|----------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------|-------|----------------------------------------------------|--------------|
| Sl.No                      | Description of Work / Item(s)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | No.of Qty | Units | Jay Prakashbhai Tilara<br>(GSTN-NA) BID ID -885554 |              |
|                            |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |           |       | Rate                                               | Amount       |
| 8.00                       | Centering and shuttering including strutting, propping etc. and removal of form work for :<br>(a) Foundations, footings, bases of columns, etc. for mass concrete                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | 200.00    | Sqm   | 357.14                                             | 71,428.00    |
| 9.00                       | Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. a) Thermo-mechanically Treated bars of grade Fe-500D or more.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            | 3000.00   | Kg    | 90.98                                              | 2,72,940.00  |
| 10.00                      | Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in:<br>Cement mortar 1:4 (1 cement : 4 coarse sand)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | 11.00     | Cum   | 6847.01                                            | 75,317.11    |
| 11.00                      | Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | 550.00    | Kg    | 115.42                                             | 63,481.00    |
| 12.00                      | Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required.<br>In stringers, treads, landings etc. of stair cases, including use of chequered plate wherever required, all complete                                                                                                                                                                                                                                                                                                                                                                                                                                              | 162.00    | Kg    | 123.28                                             | 19,971.36    |
| 13.00                      | Providing and laying Vitrified tiles in floor in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS:15622, of approved brand & manufacturer, in all colours and shade, laid on 20 mm thick cement mortar 1:4 (1 cement: 4 coarse sand) jointing with grey cement slurry @3.3 kg/sqm including grouting the joints with white cement and matching pigments etc. The tiles must be cut with the zero chipping diamond cutter only . Laying of tiles will be done with the notch trowel, plier, wedge, clips of required thickness, leveling system and rubber mallet for placing the tiles gently and easily.<br>Glazed Vitrified tiles Matt/Antiskid finish of size<br>Size of Tile 600 x 600 mm | 92.00     | Sqm   | 801.91                                             | 73,775.72    |
| 14.00                      | 12 mm cement plaster finished with a floating coat of neat cement of mix : 1:4 (1 cement: 4 fine sand)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | 44.00     | Sqm   | 276.25                                             | 12,155.00    |
| 15.00                      | Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50 m thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete all as per direction of Engineer-in-Charge.:<br>60 mm thick C.C. paver block of M-35 grade with approved colour design and pattern.              | 3100.00   | Sqm   | 720.26                                             | 22,32,806.00 |
| 16.00                      | Laying old cement concrete interlocking paver blocks of any design/ shape laid in required line, level, curvature, colour and pattern over and including 50 mm thick compacted bed of coarse sand, filling the joints with fine sand etc. all complete as per the direction of Engineer-in-charge. (Old CC paver blocks shall be supplied by the department free of cost).                                                                                                                                                                                                                                                                                                                                                                                              | 4840.00   | sqm   | 200.69                                             | 9,71,339.60  |
| 17.00                      | Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required :<br>W.C. pan with ISI marked white solid plastic seat and lid                                                                                                                                                                                                                                                                                                                      | 2.00      | Each  | 6024.01                                            | 12,048.02    |

| SCHEDULE OF WORK / ITEM(S) |                                                                                                                                                                                                                                                                                                                                                                                                                                                       |           |       |                                                    |             |
|----------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------|-------|----------------------------------------------------|-------------|
| Sl.No                      | Description of Work / Item(s)                                                                                                                                                                                                                                                                                                                                                                                                                         | No.of Qty | Units | Jay Prakashbhai Tilara<br>(GSTN-NA) BID ID -885554 |             |
|                            |                                                                                                                                                                                                                                                                                                                                                                                                                                                       |           |       | Rate                                               | Amount      |
| 18.00                      | Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require:<br>White Vitreous China Flat back wash basin size 550x400 mm with single 15 mm C.P. brass pillar tap                                                                                                                   | 2.00      | Each  | 4455.21                                            | 8,910.42    |
| 19.00                      | Providing and fixing 8 mm dia C.P. / S.S. Jet with flexible tube upto 1 metre long with S.S. triangular plate to European type W.C. of quality and make as approved by Engineer - in - charge                                                                                                                                                                                                                                                         | 2.00      | Each  | 1008.88                                            | 2,017.76    |
| 20.00                      | Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete.<br>Semi rigid pipe : 32 mm dia                                                                                                                                                                                                                                                                                                                | 2.00      | Each  | 151.33                                             | 302.66      |
| 21.00                      | Providing and fixing toilet paper holder : C.P. brass                                                                                                                                                                                                                                                                                                                                                                                                 | 2.00      | Each  | 605.33                                             | 1,210.66    |
| 22.00                      | Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge.<br>Internal work - Exposed on wall - 15 mm nominal dia Pipes | 20.00     | mtr   | 168.04                                             | 3,360.80    |
| 23.00                      | Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge.<br>External work - 50 mm nominal dia Pipes                                                          | 100.00    | mtr   | 744.31                                             | 74,431.00   |
| 24.00                      | Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc.<br>External work: 50 mm dia nominal bore                                                                                                                                                                                                                                                                                                           | 440.00    | mtr   | 467.31                                             | 2,05,616.40 |
| 25.00                      | Providing and fixing gun metal gate valve with C.I. wheel of approved quality (screwed end) :<br>50 mm nominal bore                                                                                                                                                                                                                                                                                                                                   | 2.00      | Each  | 1065.58                                            | 2,131.16    |
| 26.00                      | Providing and fixing ball valve (brass) of approved quality, High or low pressure, with plastic floats complete: 15mm nominal bore                                                                                                                                                                                                                                                                                                                    | 2.00      | Each  | 696.31                                             | 1,392.62    |
| 27.00                      | Providing and placing on terrace (at all floor levels) polyethylene water storage tank, IS : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank.                                                                                                                                                                            | 1000.00   | ltr   | 10.23                                              | 10,230.00   |
| 28.00                      | Providing and fixing C.P. brass bib cock of approved quality conforming to IS:8931 :<br>15 mm nominal bore                                                                                                                                                                                                                                                                                                                                            | 2.00      | Each  | 504.44                                             | 1,008.88    |
| 29.00                      | Providing and fixing C.P. brass long nose bib cock of approved quality conforming to IS standards and weighing not less than 810 gms.<br>15 mm nominal bore                                                                                                                                                                                                                                                                                           | 2.00      | Each  | 554.88                                             | 1,109.76    |
| 30.00                      | Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931<br>15mm nominal bore                                                                                                                                                                                                                                                                                                          | 2.00      | Each  | 302.66                                             | 605.32      |
| 31.00                      | Making soak pit 2.5 m diameter 3.0 metre deep with 45 x 45 cm dry brick honey comb shaft with bricks and S.W. drain pipe 100 mm diameter, 1.8 m long complete as per standard design.<br>With common burnt clay F.P.S. (non modular) bricks of class designation 7.5                                                                                                                                                                                  | 2.00      | Each  | 20177.56                                           | 40,355.12   |

*[Signature]*  
S.m (E.C.)

| SCHEDULE OF WORK / ITEM(S)                                      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |           |       |                                                    |              |
|-----------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------|-------|----------------------------------------------------|--------------|
| Sl.No                                                           | Description of Work / Item(s)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | No.of Qty | Units | Jay Prakashbhai Tilara<br>(GSTN-NA) BID ID -885554 |              |
|                                                                 |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |           |       | Rate                                               | Amount       |
| 32.00                                                           | Taking out existing CC interlocking paver blocks from footpath/ central verge, including removal of rubbish etc., disposal of unserviceable material to the dumping ground, for which payment shall be made separately and stacking of serviceable material within 50 metre lead as per direction of Engineer-in-Charge.                                                                                                                                                                                                                                                                                                                                                                                                                                    | 4840.00   | sqm   | 23.81                                              | 1,15,240.40  |
| 33.00                                                           | Construction of granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by tippers to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge. (a) With material conforming to Grade-I (size range 75 mm to 0.075 mm) having CBR Value-30.                                                                                                                                                                                                 | 1845.00   | cum   | 2669.64                                            | 49,25,485.80 |
| 34.00                                                           | Supply and installation of fire retardant water proof Frangible shelter/hut of make Plastrone India/ Lloyd Insulation India Ltd/ or equivalent make for GP & LPDME equipment & Localizer equipment ( Wall and Roof 50mm thick with both side FRP Sheet 2mm thick) size 8.0Mtr *5.0Mtr *3.5Mtr having one partition and 2 nos. doors,PUF Density: 40±2 Kg/m3 complete as per directions of Engineer in- charge.<br>L1 Bidder will have to get the Design and detailed drawings vetted and certified from NIT/IT, for complying under ICAO norms " ICAO AERODROME DESIGN MANUAL " (Doc. No.9157, Part-6 Frangibility). the cost of design, vetting of drawings from NIT/IT is included in this scope of work and nothing extra shall be paid on this account. | 2.00      | Each  | 546811.95                                          | 10,93,623.90 |
| 35.00                                                           | Providing and fixing High Density Polyethylene (HDPE) pipes, including all HDPE plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step HDPE solvent cement and testing of joints complete as per direction of Engineer in Charge.<br>Internal work - Exposed on wall<br>B).160 mm                                                                                                                                                                                                                                                                                                                                                                               | 960.00    | mtr   | 707.14                                             | 6,78,854.40  |
| 36.00                                                           | Supplying and laying stone soling with stone boulders of size 150 mm to 225 mm in layers not exceeding 225 mm thick including hand packing with small stone chips and binding materials (gravel or moorum) including watering and compacting with road roller / hand rammer as per direction of Engineer - in - charge. (Nothing extra to be paid for packing the voids and making surface levelled)                                                                                                                                                                                                                                                                                                                                                        | 476.00    | cum   | 2092.31                                            | 9,95,939.56  |
| 37.00                                                           | Providing and laying graded granular material (moorum) in layers not exceeding 20cm (loose) in thickness (each layer) and as directed by the Engineer-in-charge. Breaking clods, watering, consolidating each layers with power road roller 8-10 tonne, under optimum moisture content to give density not less than that specified of the maximum modified standard proctor density at OMC including levelling, fine dressing to the required camber, grade and slope etc. complete. The K-value of 30MN/M3 shall be ensured on top of this layer (payment to be made for the compacted quantity only).                                                                                                                                                    | 5940.00   | cum   | 1547.62                                            | 91,92,862.80 |
| Total in Figures                                                |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |           |       | 2,84,28,627.51                                     |              |
| Lowest Amount Quoted BY: Jay Prakashbhai Tilara(2,84,28,627.51) |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |           |       |                                                    |              |

  
रविकान्त मेश्राम / RAVIKANT MESHAM

वरिष्ठ प्रबंधक (अभि - सिविल) / Sr. Manager (Engg.-Civil)  
भारतीय विमानपत्तन प्राधिकरण / Airport Authority Of India