



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA

29/09/2025

संदर्भ सं / Ref. No. AAI/BD/Engg.(Civil)/DVOR Katihar/W.O.-02/25-20 / बिनांक / Date

1827-37

To
M/s M. L. Brother,
F-22/177, Sector-3, Rohini,
Delhi -110085.

विषय:- कटिहार हवाई अड्डे, कटिहार में डीवीओआर भवन और संबंधित कार्यों का निर्माण।

Sub.: - Construction of DVOR building and allied works at Katihar Airport, Katihar.

संदर्भ:- i) आपकी ई-बोली 28/08/2025 को खोली गई।

[ओपन टेंडर आईडी: 2025_AAI_242349_1]।

Ref:- i) Your E-Bid opened on 28/08/2025.

[Open Tender ID: 2025_AAI_242349_1].

महोदय/Dear Sir(s),

1. उपर्युक्त कार्य के लिए आपकी निविदा, आपके द्वारा उद्धृत मद दरों पर, अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से स्वीकार की जाती है, जिसकी कुल कीमत **1,09,33,399.99 रुपये (एक करोड़ नौ लाख तैंतीस हजार तीन सौ निन्यानवे ओर निन्यानवे पैसे मात्र)** है, जिसमें जीएसटी शामिल नहीं है, जो कि निविदा में रखी गई अनुमानित लागत **1,43,82,477.00 रुपये से 23.98% कम** है।

1. Your tender for the work mentioned above is hereby accepted on behalf of Chairman, Airports Authority of India at the item rates quoted by you totaling to **Rs. 1,09,33,399.99 (Rupees One Crore Nine Lacs Thirty-Three Thousand Three Hundred Ninety-Nine and Ninety-Nine Paise Only)** excluding GST which is **23.98% below** the estimated cost put to tender of Rs. 1,43,82,477.00.

2. सहायक जनरल मैनेजर (ई-सी), एएआई, बागडोगरा एयरपोर्ट कार्य के प्रभारी इंजीनियर होंगे। आपसे अनुरोध है कि अनुबंध समझौते पर हस्ताक्षर करने और उसे पूरा करने के लिए 09/10/2025 तक सहायक जनरल मैनेजर (ई-सी), एएआई, बागडोगरा एयरपोर्ट, जिला:- दार्जिलिंग, पिन:- 734421 के कार्यालय में उपस्थित हों। अनुबंध समझौता रु. 100/- (केवल एक सौ रुपये) मूल्य के गैर-न्यायिक स्टाम्प पेपर पर निष्पादित किया जाएगा और स्टाम्प पेपर की लागत आपको वहन करनी होगी।

2. Asstt. Gen. Manager (E-C), AAI, Bagdogra Airport shall be the Engineer-in-charge of the work. You are requested to attend the office of Asstt. Gen. Manager (E-C), AAI, Bagdogra Airport, Dist.: - Darjeeling, Pin: - 734421 by **09/10/2025** to sign and complete the contract agreement. The contract agreement shall be executed on a **non-judicial stamp paper of value Rs. 100/- (Rupees One Hundred only)** and the cost of the stamp paper shall be borne by you.

3. आपके टेंडर के साथ प्राप्त बयाना राशि **₹ 4,31,474.00** (चार लाख इकतीस हजार चार सौ चौहत्तर मात्र) को अनुबंध दस्तावेज़ के पृष्ठ 16 पर दी गई शर्त 1A के अनुसार सुरक्षा जमा के हिस्से के रूप में परिवर्तित कर दिया गया है। कृपया इस पत्र के जारी होने की तिथि से 10 (दस) दिनों के भीतर शेष सुरक्षा जमा के रूप में **₹ 6,61,866.00** (छह लाख इकसठ हजार आठ सौ छियासठ रुपये मात्र) जमा करें, अन्यथा अनुबंध की सामान्य शर्त के पृष्ठ 16 पर दिए गए खंड 1A के अनुसार यह राशि आपके चालू बिलों से काट ली जाएगी।

3. The Earnest Money amount of **Rs. 4,31,474.00 (Rupees Four Lacs Thirty-One Thousand Four Hundred Seventy-Four Only)** received along with your tender has been converted as part of **Security Deposit**, as per condition 1A on page 16 of the contract document. Please deposit **Rs. 6,61,866.00 (Rupees Six Lacs Sixty One Thousand Eight Hundred Sixty Six Only)** towards balance Security Deposit within **10 (Ten) days** from the date of issue of this letter, failing which the same will be deducted from your running bills as per clause 1A on page 16 of General condition of contract.

विमानपत्तन निदेशक का कार्यालय
OFFICE OF THE AIRPORT DIRECTOR

बागडोगरा हवाई अड्डा, बागडोगरा, जिला: दार्जिलिंग
BAGDOGRA AIRPORT, BAGDOGRA, DIST. DARJEELING

पिन- 734021, दुरभाष : (0353) 2698431, फैक्स : 2698317
Pin : 734421, Phone : (0353) 2698431, Fax : 2698317

आपसे अनुरोध है कि आप ठेका श्रम (विनियमन एवं उन्मूलन) अधिनियम 1970 तथा ठेका श्रम (विनियमन एवं उन्मूलन) केन्द्रीय (यम, 1971, बाल श्रम (प्रतिषेध एवं विनियमन) अधिनियम 1986, निर्माण श्रमिक (रोजगार एवं सेवा शर्त विनियमन) अधिनियम 1996, भवन एवं अन्य निर्माण श्रमिक कल्याण उपकर अधिनियम 1996 आदि समय-समय पर संशोधित प्रावधानों या केन्द्र एवं राज्य सरकारों द्वारा समय-समय पर इससे संबंधित किसी अन्य कानून एवं इसके अंतर्गत बनाए गए नियमों का अनुपालन करें।

4. You are requested to comply with the provision of Contract Labour (Regulation and Abolition) Act 1970 and Contract Labour (Regulation and Abolition) Central Rules, 1971, Child Labour (Prohibition & Regulation) Act 1986, Construction workers (Regulation of Employment and Conditions of Service) Act 1996, Building and other Construction workers Welfare Cess Act 1996 etc. amended from time to time or any other laws relating thereto and rules made there under from time to time of Central and State Governments.

5. आपको सहा. महा. प्रबंधक (ई-सी), बागडोगरा हवाई अड्डा, बागडोगरा से भी संपर्क करने का निर्देश दिया जाता है, जो आपको साइट सौंपने की व्यवस्था करेंगे।

5. You are also directed to contact **The Asstt. General Manager (E-C), Bagdogra Airport, Bagdogra** who will arrange to hand over the site to you.

6. कृपया ध्यान दें कि कार्य करने के लिए अनुमत समय 08 (आठ) महीने है जिसमें 2025 का वर्ष ऋतु का एक महीना भी शामिल है और इसकी गणना इस पत्र के जारी होने के 10वें दिन से की जाएगी।

6. Please note that the time allowed for carrying out the work is **08 (Eight) Months including one-month rainy season 2025** and same shall be reckoned from the 10th day after issue of this letter.

7. अनुबंध के संबंध में कोई भी आगे का पत्राचार सामान्यतः **प्रभारी इंजीनियर** को संबोधित किया जाना चाहिए।

7. Any further correspondence in connection with the contract should normally be addressed to the **Engineer-in-charge**.

8. कृपया प्राप्ति की सूचना दें तथा स्वीकृति के प्रतीक के रूप में हस्ताक्षर करने के पश्चात संलग्न इस पत्र की प्रतिलिपि नीचे हस्ताक्षरकर्ता को लौटा दें।

8. Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

9. हिन्दी एवं अंग्रेजी संस्करण में किसी भी प्रकार की विसंगति पाए जाने पर अंग्रेजी संस्करण को सही माना जाएगा तथा अनुबंध पर बाध्यकारी माना जाएगा।

9. In case of any discrepancy between Hindi & English version found, English version shall be taken as correct and binding on the contract.

धन्यवाद/Thanking you.

Enclosure: - **कीमतों की सूची/Schedule of Rates.**

Yours faithfully
-Sd-

अश्विनी कुमार / (Ashwini Kumar),
सहा. महा. प्रबंधक इंजी. (सिविल)/ Asstt. General Manager (E-C),
भारतीय विमानपत्तन प्राधिकरण/ Airports Authority of India,
बागडोगरा हवाई अड्डा/ Bagdogra Airport
अध्यक्ष के लिए और उनकी ओर से/ For and on behalf of the Chairman

N. O. O:

Copy to: -

बाहरी/ External: -

1. The Labour Enforcement Officer (Central) Shiv Mandir Road, Bara Bazar, Katihar – 854105 (Bihar).

Internal: -

1. GM (Engg.), AAI, NSCBI Airport, Kolkata - 700052.
2. GM (F&A), AAI, NSCBI Airport, Kolkata - 700052.
3. Airport Director, AAI, Bagdogra Airport, Bagdogra-734421.
4. Jt. GM (CNS), AAI, A.C.S Katihar Airport – 854106.
5. DGM Engg. (C), AAI, Bagdogra Airport - 734421.
6. DGM (Fin.), AAI, Bagdogra Airport, Bagdogra – 734421.
7. DGM Engg. (E), AAI, Bagdogra Airport - 734421.
8. AGM Engg. (E), AAI, Bagdogra Airport - 734421.
9. Mgr. Engg. (E), AAI, Bagdogra Airport - 734421.
10. Asstt. Mgr. Engg. (C), AAI, Bagdogra Airport - 734421.
11. Work File.

अश्विनी कुमार / (Ashwini Kumar),

सहा. महा. प्रबंधक इंजी. (सिविल)/ Asstt. General Manager (E-C),
भारतीय विमानपत्तन प्राधिकरण/ Airports Authority of India,
बागडोगरा हवाई अड्डा/ Bagdogra Airport
अध्यक्ष के लिए और उनकी ओर से/ For and on behalf of the Chairman

Tender Inviting Authority: AGM (E-C)

Name of Work: Construction of DVOR building and allied works at Katihar Airport, Katihar.

Contract No: 2025_AAI_242349_1

SCHEDULE OF WORK / ITEM(S)

Sl.No	Description of Work / Item(s)	No.of Qty	Units	Rate	Amount
	Civil Works				
1.00	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and for all lift, as directed by Engineer-in-charge. All kinds of soil.	607.00	Cum	200.00	121400.00
2.00	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, for all lift, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.	53.00	Cum	200.00	10600.00
3.00	Excavating trenches by mechanical / manual means of required width for pipes, cables, etc including excavation for sockets, and dressing of sides, ramming of bottoms, for all depth, including getting out the excavated soil, and then returning the soil as required, in layers not exceeding 20 cm in depth, including consolidating each deposited layer by ramming, watering, etc. and disposing of surplus excavated soil as directed, within a lead of 50 m : All kinds of soil. Pipes, cables etc. exceeding 80 mm dia. but not exceeding 300 mm dia.	684.00	Mtr	200.00	136800.00
4.00	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 and for all lift.	660.00	Cum	120.00	79200.00
5.00	Extra for every additional lift of 1.5 m or part thereof in excavation /banking excavated or stacked materials. All kinds of soil.	182.00	Cum	100.00	18200.00
6.00	Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete.	175.00	Cum	1200.00	210000.00
7.00	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 Cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 40 mm nominal size derived from natural sources).	6.00	Cum	5500.00	33000.00
8.00	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand (zone-III) derived from natural sources : 8 graded stone aggregate 40 mm nominal size derived from natural sources).	269.00	Cum	5200.00	1398800.00
9.00	Centering and shuttering including strutting, propping etc. and removal of form work for : Foundations, footings, bases for columns.	141.00	Sqm	400.00	56400.00
10.00	Centering and shuttering including strutting, propping etc. and removal of form for Suspended floors, roofs, landings, balconies and access platform.	39.00	Sqm	400.00	15600.00
11.00	Centering and shuttering including strutting, propping etc. and removal of form for Lintels, beams, plinth beams, girders, bressumers and cantilevers.	84.00	Sqm	400.00	33600.00
12.00	Centering and shuttering including strutting, propping etc. and removal of form for Columns, Pillars, Piers, Abutments, Posts and Struts.	264.00	Sqm	400.00	105600.00
13.00	Centering and shuttering including strutting, propping etc. and removal of form for Edges of slabs and breaks in floors and walls. Under 20 cm wide.	51.00	Mtr	100.00	5100.00
14.00	Steel reinforcement for R.C.C. work including straightening, cutting,bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	5120.00	Kg	90.00	460800.00


Ashwini Kumar

Sl.No	Description of Work / Item(s)	No.of Qty	Units	Rate	Amount
15.00	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	7810.00	Kg	90.00	702900.00
16.00	Add for plaster drip course/ groove in plastered surface or moulding to R.C.C. projections.	67.00	Mtr	100.00	6700.00
17.00	Providing and laying in position ready mixed or site batched design mix cement concrete for reinforced cement concrete work; using coarse aggregate and fine aggregate derived from natural sources, Portland Pozzolana / Ordinary Portland / Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; but excluding the cost of centering, shuttering, finishing and reinforcement as per direction of the engineer-in-charge; for the following grades of concrete. Note: Extra cement up to 10% of the minimum specified cement content in design mix shall be payable separately. In case the cement content in design mix is more than 110% of the specified minimum cement content, the contractor shall have discretion to either re-design the mix or bear the cost of extra cement. All works upto plinth level. Concrete of M25 grade with minimum cement content of 330 kg /cum.	64.00	Cum	7000.00	448000.00
18.00	Providing and laying in position ready mixed or site batched design mix cement concrete for reinforced cement concrete work; using coarse aggregate and fine aggregate derived from natural sources, Portland Pozzolana / Ordinary Portland / Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; but excluding the cost of centering, shuttering, finishing and reinforcement as per direction of the engineer-in-charge; for the following grades of concrete. Note: Extra cement up to 10% of the minimum specified cement content in design mix shall be payable separately. In case the cement content in design mix is more than 110% of the specified minimum cement content, the contractor shall have discretion to either re-design the mix or bear the cost of extra cement. All works above plinth level upto floor V level. Concrete of M25 grade with minimum cement content of 330 kg /cum.	71.00	Cum	7000.00	497000.00
19.00	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6 coarse sand).	83.00	Cum	9000.00	747000.00
20.00	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:6 (1 cement : 6 coarse sand).	100.00	Cum	9000.00	900000.00
21.00	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level. Cement mortar 1:4 (1 cement : 4 coarse sand).	20.00	Sqm	700.00	14000.00
22.00	Extra for providing and placing in position 2 Nos 6mm dia. M.S. bars at every third course of half brick masonry.	20.00	Sqm	150.00	3000.00
23.00	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately). Second class teak wood.	.79	Cum	100000.00	79000.00
24.00	Providing and fixing ISI marked flush door shutters conforming to IS : 2202 (Part I) decorative type, core of block board construction with frame of 1st class hard wood and well matched teak 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters. 35 mm thick including ISI marked Stainless Steel butt hinges with necessary screws.	22.00	Sqm	3500.00	77000.00
25.00	Extra if louvers (not exceeding 0.2 sqm) are provided in flush door shutters (overall area of door shutters to be measured). Decorative type door.	3.00	Sqm	500.00	1500.00
26.00	Providing and fixing bright finished brass tower bolts (barrel type) with necessary screws etc. complete : 250x10 mm.	9.00	Each	250.00	2250.00
27.00	Providing and fixing bright finished brass tower bolts (barrel type) with necessary screws etc. complete : 150x10 mm.	3.00	Each	100.00	300.00

Handwritten signature and date:

 14/11/22


Sl.No	Description of Work / Item(s)	No.of Qty	Units	Rate	Amount
28.00	Providing and fixing bright finished brass hanging type floor door stopper with necessary screws, etc. complete.	6.00	Each	200.00	1200.00
29.00	Providing and fixing aluminium extruded section body tubular type universal hydraulic door closer (having brand logo with ISI, IS : 3564, embossed on the body, door weight upto 36 kg to 80 kg and door width from 701 mm to 1000 mm), with double speed adjustment with necessary accessories and screws etc. complete.	6.00	Each	1000.00	6000.00
30.00	Providing and fixing aluminium sliding door bolts, ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etc. complete : 300x16 mm.	9.00	Each	300.00	2700.00
31.00	Providing and fixing pre-laminated medium density fibre board exterior grade (Grade-I) IS:14587:1998 marked, to frame, backing or studding with screws etc. complete (Frames, backing or studding to be paid separately). Pre-laminated with decorative lamination on both side exterior Grade - I MDF Board 12 mm thick conforming to IS:14587.	78.00	Sqm	1100.00	85800.00
32.00	Providing and fixing bright /matt finished Stainless Steel handles of approved quality & make with necessary screws etc all complete. 125 mm.	14.00	Each	100.00	1400.00
33.00	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In stringers, treads, landings etc. of stair cases, including use of chequered plate wherever required, all complete.	3555.00	Kg	100.00	355500.00
34.00	Providing & fixing fly proof wire gauze to windows, clerestory windows & doors with M.S. Flat 15x3 mm and nuts & bolts complete. Stainless steel (grade 304) wire gauze of 0.5 mm dia wire and 1.4 mm aperture on both sides.	1.00	Sqm	100.00	100.00
35.00	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3kg/sqm including grouting the joints with white cement and matching pigments etc., complete. Size of Tile 600x600 mm.	64.00	Sqm	1000.00	64000.00
36.00	Providing and laying Vitrified tiles in different sizes (thickness to be specified by the manufacturer), with water absorption less than 0.08% and conforming to IS: 15622, of approved brand & manufacturer, in all colours and shade, in skirting, riser of steps, laid with cement based high polymer modified quick set tile adhesive (water based) conforming to IS: 15477, in average 6 mm thickness, including grouting of joints (Payment for grouting of joints to be made separately). Size of Tile 600x600 mm.	11.00	Sqm	1000.00	11000.00
37.00	Providing gola 75x75 mm in cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 stone aggregate 10 mm and down gauge), including finishing with cement mortar 1:3 (1 cement : 3 fine sand) as per standard design : In 75x75 mm deep chase.	34.00	Mtr	300.00	10200.00
38.00	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes. 110 mm diameter.	15.00	Mtr	400.00	6000.00
39.00	Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion. Bend 87.5° 110 mm bend.	5.00	Each	300.00	1500.00

Am
Amir

Sl.No	Description of Work / Item(s)	No. of Qty	Units	Rate	Amount
40.00	Providing and fixing tiled false ceiling of approved materials of size 595x595 mm in true horizontal level, suspended on interlocking metal grid of hot dipped galvanized steel sections (galvanized @ 120 grams/ sqm, both side inclusive) consisting of main "T" runner with suitably spaced joints to get required length and of size 24x38 mm made from 0.30 mm thick (minimum) sheet, spaced at 1200 mm center to center and cross "T" of size 24x25 mm made of 0.30 mm thick (minimum) sheet, 1200 mm long spaced between main "T" at 600 mm center to center to form a grid of 1200x600 mm and secondary cross "T" of length 600 mm and size 24x25 mm made of 0.30 mm thick (minimum) sheet to be interlocked at middle of the 1200x600 mm panel to form grids of 600x600 mm and wall angle of size 24x24x0.3 mm and laying false ceiling tiles of approved texture in the grid including, required cutting/making, opening for services like diffusers, grills, light fittings, fixtures, smoke detectors etc. Main "T" runners to be suspended from ceiling using GI slotted cleats of size 27 x 37 x 25 x 1.6 mm fixed to ceiling with 12.5 mm dia and 50 mm long dash fasteners, 4 mm GI adjustable rods with galvanized butterfly level clips of size 85 x 30 x 0.8 mm spaced at 1200 mm center to center along main T, bottom exposed width of 24 mm of all T-sections shall be pre-painted with polyester paint, all complete for all heights as per specifications, drawings and as directed by Engineer-in-charge. 8 mm thick fully perforated calcium silicate board made with Calcareous & Siliceous materials reinforced with cellulose fiber manufactured through autoclaving process to give stable crystalline structure with minimum compressive strength 225 kg/ sq. cm, bending strength 100 kg/sq. cm , of size 595x595 mm, having perforation of dia. 10 mm with minimum perforated area 18 % with non woven tissue on the back side, having an NRC (Noise Reduction Coefficient) of 0.85, with 50 mm thick rockwool of 48 kg /cum backing.	52.00	Sqm	1500.00	78000.00
41.00	12 mm cement plaster of mix : 1:6 (1 cement: 6 fine sand).	259.00	Sqm	220.00	56980.00
42.00	15 mm cement plaster on the rough side of single or half brick wall of mix : 1:6 (1 cement: 6 fine sand).	273.00	Sqm	250.00	68250.00
43.00	6 mm cement plaster of mix : 1:3 (1 cement : 3 fine sand).	100.00	Sqm	200.00	20000.00
44.00	Distempering with 1st quality acrylic distemper (ready mixed) having VOCcontent less than 50 gram/litre, of approved manufacturer and of requiredshade and colour all complete to achieve even shade and colour : New work (two or more coats) over and including waterthinnable priming coat with cement primer having VOC contentless than 50 gram/litre.	596.00	Sqm	80.00	47680.00
45.00	Finishing walls with Acrylic Smooth exterior paint of required shade : New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @0.90 litre/ 10 sqm).	2064.00	Sqm	80.00	165120.00
46.00	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture	100.00	Sqm	100.00	10000.00
47.00	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	532.00	Sqm	80.00	42560.00
48.00	Repair to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sqm and under, including cutting the patch in proper shape, raking out joints and preparing plastering the wall surface with white cement based polymer modified self curing mortar, including disposal of rubbish, all complete as per the direction of Engineer-In-Charge.	500.00	Sqm	350.00	175000.00
49.00	Providing and laying APP (Atactic Polypropylene Polymer) modified prefabricated five layer, 3 mm thick water proofing membrane, black finished reinforced with glass fibre matt consisting of a coat of bitumen primer for bitumen membrane @ 0.40 litre/sqm by the same membrane manufactured of density at 25°C, 0.87 - 0.89 kg/litre and viscosity 70 - 160 cps. Over the primer coat the layer of membrane shall be laid using butane torch and sealing all joints etc., and preparing the surface complete. The vital physical and chemical parameters of the membrane shall be as under : Joint strength in longitudinal and transverse direction at 23°C as 350/300 N/5 cm. Tear strength in longitudinal and transverse direction as 60/80N. Softening point of membrane not less than 150°C. Cold flexibility shall be upto -2°C when tested in accordance with ASTM, D - 5147. The laying of membrane shall be got done through the authorised applicator of the manufacturer of membrane : 3 mm thick.	188.00	Sqm	800.00	150400.00
50.00	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer - in- charge.	50.00	Cum	800.00	40000.00

AN
Ammur

No.	Description of Work / Item(s)	No. of Qty	Units	Rate	Amount
51.00	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. In cement mortar.	50.00	Cum	600.00	30000.00
52.00	Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40 mm nominal size) in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete.	39.00	Cum	5000.00	195000.00
53.00	Providing and fixing concertina coil fencing with punched tape concertina coil 600 mm dia 10 metre openable length (total length 90 m), having 50 nos rounds per 6 metre length, upto 3 m height of wall with existing angle iron 'Y' shaped placed 2.4m or 3.00 m apart and with 9 horizontal R.B.T. reinforced barbed wire, stud tied with G.I. staples and G.I. clips to retain horizontal, including necessary bolts or G.I. barbed wire tied to angle iron, all complete as per direction of Engineer-in-charge, with reinforced barbed tape(R.B.T.) / Spring core (2.5 mm thick) wire of high tensile strength of 165 kg/ sq. mm with tape (0.52 mm thick) and weight 43.478 gm/ metre (cost of M.S. angle, C.C. blocks shall be paid separately).	740.00	Mtr	350.00	259000.00
54.00	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50 mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete all as per direction of Engineer-in-Charge. 80 mm thick C.C. paver block of M-35 grade with approved colour design and pattern.	1182.00	Sqm	800.00	945600.00
55.00	Providing and fixing water closet squatting pan (Indian type W.C. pan) with 100 mm sand cast Iron P or S trap, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required: White Vitreous china Orissa pattern W.C. pan of size 580x440 mm with integral type foot rests.	1.00	Each	4000.00	4000.00
56.00	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require: White Vitreous China Wash basin size 630x450 mm with a pair of 15 mm C.P. brass pillar taps.	1.00	Each	2500.00	2500.00
57.00	Providing and fixing Stainless Steel A ISI 304 (18/8) kitchen sink as per IS:13983 with C.I. brackets and stainless steel plug 40 mm, including painting of fittings and brackets, cutting and making good the walls wherever required : Kitchen sink with drain board. 510x1040 mm bowl depth 250 mm.	1.00	Each	5000.00	5000.00
58.00	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete. Semi rigid pipe. 32 mm dia.	1.00	Each	100.00	100.00
59.00	Providing and fixing 600x450 mm beveled edge mirror of superior glass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete.	2.00	Each	1000.00	2000.00
60.00	Providing and fixing toilet paper holder : C.P. brass.	1.00	Each	500.00	500.00
61.00	Providing and fixing soil, waste and vent pipes : 100 mm dia. Sand cast iron S&S pipe as per IS: 1729.	45.00	Mtr	1000.00	45000.00
62.00	Providing and fixing soil, waste and vent pipes : 75 mm diameter. Sand cast iron S&S pipe as per IS: 1729.	65.00	Mtr	700.00	45500.00
63.00	Providing and fixing PTMT towel rail complete with brackets fixed to wooden cleats with CP brass screws with concealed fittings arrangement of approved quality and colour. 600 mm long towel rail with total length of 645 mm, width 78 mm and effective height of 88 mm, weighing not less than 190 gms.	1.00	Each	300.00	300.00


AUM 12-2

No	Description of Work / Item(s)	No. of Qty	Units	Rate	Amount
64.00	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings and fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. Concealed work, including cutting chases and making good the walls etc. 15 mm nominal dia Pipes.	50.00	Mtr	250.00	12500.00
65.00	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings and fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. Concealed work, including cutting chases and making good the walls etc. 20 mm nominal dia Pipes.	50.00	Mtr	250.00	12500.00
66.00	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. External work. 32 mm nominal outer dia Pipes.	50.00	Mtr	300.00	15000.00
67.00	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, ISI : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank complete in all respects.	1000.00	Per litre	9.00	9000.00
68.00	Providing and fixing C.P. brass long nose bib cock of approved quality conforming to IS standards and weighing not less than 810 gms. 15 mm nominal bore.	2.00	Each	1000.00	2000.00
69.00	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931. 15mm nominal bore.	1.00	Each	800.00	800.00
70.00	Providing and fixing PTMT soap dish holder having length of 138mm, breadth 102mm, height of 75mm with concealed fitting arrangements, weighing not less than 106 gms.	1.00	Each	600.00	600.00
71.00	Providing and fixing square-mouth S.W. gully trap class SP-1 complete with C.I. grating brick masonry chamber with water tight C.I. cover with frame of 300 x300 mm size (inside) the weight of cover to be not less than 4.50 kg and frame to be not less than 2.70 kg as per standard design: 100x100 mm size P type. With common burnt clay F.P.S. (non modular) bricks of class designation 7.5.	1.00	Each	2000.00	2000.00
72.00	Constructing brick masonry manhole in cement mortar 1:4 (1 cement : 4 coarse sand) with R.C.C. top slab with 1:1.5:3 mix (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size), foundation concrete 1:4:8 mix (1 cement : 4 coarse sand (zone-III) : 8 graded stone aggregate 40 mm nominal size), inside plastering 12 mm thick with cement mortar 1:3 (1 cement : 3 coarse sand) finished with floating coat of neat cement and making channels in cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) finished with a floating coat of neat cement complete as per standard design : Inside size 90x80 cm and 45 cm deep including C.I. cover with frame (light duty) 455x610 mm internal dimensions, total weight of cover and frame to be not less than 38 kg (weight of cover 23 kg and weight of frame 15 kg) : With common burnt clay F.P.S. (non modular) bricks of class designation 7.5.	3.00	Each	12000.00	36000.00
73.00	Making soak pit 2.5 m diameter 3.0 metre deep with 45 x 45 cm dry brick honey comb shaft with bricks and S.W. drain pipe 100 mm diameter, 1.8 m long complete as per standard design. With common burnt clay F.P.S. (non modular) bricks of class designation 7.5.	1.00	Each	15000.00	15000.00
74.00	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately): For fixed portion. Powder coated aluminium (minimum thickness of powder coating 50 micron).	85.00	Kg	600.00	51000.00

(Signature)
M. M. K. S.

	Description of Work / Item(s)	No. of Qty	Units	Rate	Amount
	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately): For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately). Powder coated aluminium (minimum thickness of powder coating 50 micron).	34.00	Kg	600.00	20400.00
76.00	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge. (Cost of aluminium snap beading shall be paid in basic item): With float glass panes of 5 mm thickness (weight not less than 12.50 kg/sqm).	3.00	Sqm	1000.00	3000.00
77.00	Providing and fixing anodised aluminium grill (anodised transparent or dyed to required shade according to IS: 1868 with minimum anodic coating of grade AC 15) of approved design/pattern, with approved standard section and fixed to the existing window frame with C.P. brass/ stainless steel screws @ 200 mm centre to centre, including cutting the grill to proper opening size for fixing and operation of handles and fixing approved anodised aluminium standard section around the opening, all complete as per requirement and direction of Engineer-in-charge. (Only weight of grill to be measured for payment).	47.00	Kg	600.00	28200.00
78.00	Grading roof for water proofing treatment with Cement mortar 1:4 (1cement : 4 coarse sand).	3.00	Cum	7000.00	21000.00
79.00	Construction of embankment/filling in Plinth with approved materials soil obtained from borrow pits (outside airport premises) with all lifts and leads, transporting to site, spreading grading to required slope and compacting to achieve the desired compactions as specified in technical specifications (based on MORTH) etc complete in all respects and as directed by Engineer-in-charge. All kind of soil.	2292.00	Cum	400.00	916800.00
80.00	Providing and fixing Jaquar's handshower (ALD-573) (Health Faucet with brass handle and tube) with 8mm dia, 1 meter long flexible tube and wall hook or equivalent.	1.00	Each	1200.00	1200.00
81.00	Providing and operating 3D hydraulic excavator with back hoe (JCB or equivalent) including fuel, driver and others for removal of wild growth, jungle, and heaps etc. as per the direction and satisfaction of EIC (measurement shall be based on per hour of effective operation).	20.00	Per hour	1000.00	20000.00
	Electrical Works				
82.00	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLSH PVC insulated copper conductor single core cable in surface / recessed steel conduit/raceways, with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sq.mm. FRLSH PVC insulated copper conductor single core cable etc as required. (a) Group C	20.00	Point	600.00	12000.00
83.00	Wiring for group controlled (looped) light point/fan point/exhaust fan point/ call bell point (without independent switch etc.) with 1.5 sq. mm FRLS PVC insulated copper conductor single core cable in surface/ recessed steel conduit/raceways, and earthing the point with 1.5 sq. mm FRLS PVC insulated copper conductor single core cable etc as required.	25.00	Point	600.00	15000.00
84.00	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLSH PVC insulated copper conductor, single core cable in surface/ recessed steel conduit/raceways i/c supply and laying of suitable size medium class steel conduit complete as required. 2 x 2.5 Sq.mm + 1 x 2.5 Sq.mm Earth Wire	150.00	Mtr	250.00	37500.00
85.00	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLSH PVC insulated copper conductor, single core cable in surface/ recessed steel conduit/raceways i/c supply and laying of suitable size medium class steel conduit complete as required. 2 x 4 Sq.mm + 1 x 4 Sq.mm Earth Wire	150.00	Mtr	250.00	37500.00


Handwritten signature
Amm 12/2

	Description of Work / Item(s)	No. of Qty	Units	Rate	Amount
	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLSH PVC insulated copper conductor, single core cable in surface/ recessed steel conduit/raceways i/c supply and laying of suitable size medium class steel conduit complete as required. 2 x 6 Sq.mm + 1 x 6 Sq.mm Earth Wire	100.00	Mtr	350.00	35000.00
87.00	Wiring for light/ power plug with 2X4 sq. mm FRLSH PVC insulated copper conductor single core cable in surface/ recessed steel conduit/raceways alongwith 1 No 4 sq. mm FRLSH PVC insulated copper conductor single core cable for loop earthing as required.	350.00	Mtr	300.00	105000.00
88.00	Supplying and fixing of following sizes of steel conduit along with accessories in surface/recessed including painting in case of surface conduit or cutting the wall and making good the same in case of recessed conduit as required. 20 mm	30.00	Mtr	100.00	3000.00
89.00	Supplying and fixing of 25 mm sizes of steel conduit along with accessories in surface/recess including cutting the wall and making good the same in case of recessed conduit as required.	30.00	Mtr	100.00	3000.00
90.00	Supply and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/recessed steel/PVC conduit as required. 2 x 1.5 sq.mm.	30.00	Mtr	250.00	7500.00
91.00	Supply and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/recessed steel/PVC conduit as required. 3 x 4.0 sq.mm.	30.00	Mtr	300.00	9000.00
92.00	Supplying and fixing suitable size GI box with modular plate and cover in front on surface or in recess, including providing and fixing 6 pin 5/6 & 15/16 A modular socket outlet 15/16 A modular switch, including connections etc. complete as required.	55.00	Each	250.00	13750.00
93.00	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required. (A). Telephone Socket Outlet	3.00	Each	250.00	750.00
94.00	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required. (A). 15/16 A Switch	5.00	Each	300.00	1500.00
95.00	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required. (A). 6 pin 15/16 A socket outlet	5.00	Each	250.00	1250.00
96.00	Supplying and fixing following size/ modules, GI box alongwith modular base & cover plate for modular switches in recess etc as required. 1 or 2 Module (75mm x 75mm)	5.00	Each	250.00	1250.00
97.00	Supplying and fixing following size/ modules, GI box alongwith modular base & cover plate for modular switches in recess etc as required. 3 Module (100mmX75mm)	5.00	Each	300.00	1500.00
98.00	Supplying and fixing of following size/ modules, GI box along with modular base & cover plate for modular switches in recess etc as required. 6 Module (200 mm x 75 mm)	5.00	Each	350.00	1750.00
99.00	Supplying and fixing of following ways surface/recess mounting, vertical type, 415 volts, IP 43, TPN MCB distribution board of sheet steel, dust protected, duly powder painted, inclusive of 100 amps tinned copper bus bar, common neutral link, earth bar, din bar for mounting MCB's (but without MCB's and incomer) as required. 8 way (4 + 24), double door	2.00	Each	7000.00	14000.00
100.00	Supplying and fixing of 12 way (2+10), Double Door, Metal, Single pole and neutral (SPN), Metalica MCB distribution board, 240 V, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing, blanking plates etc. as required. (But without MCB/RCCB/Isolator)	5.00	Each	10000.00	50000.00
101.00	Supplying and fixing of 6 way (2+4), Double Door, Metal, Single pole and neutral (SPN), Metalica MCB distribution board, 240 V, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing, blanking plates etc. as required. (But without MCB/RCCB/Isolator)	2.00	Each	6000.00	12000.00
102.00	Supplying and fixing 63A rating, 415 V, 10 kA, 4 Pole MCB suitable for inductive load in the existing TPN MCB DB complete with connections, testing and commissioning etc. as required.	2.00	Each	2500.00	5000.00
103.00	Supplying and fixing 63A rating, 240/415 V, 10 kA, "C" curve, DP miniature circuit breaker suitable for inductive load in the existing MCB DB complete with connections, testing and commissioning etc. as required.	6.00	Each	3000.00	18000.00

Handwritten signature and initials

No	Description of Work / Item(s)	No. of Qty	Units	Rate	Amount
104.00	Supplying and fixing 40A rating, 240/415 V, 10 kA, "C" curve, DP miniature circuit breaker suitable for inductive load in the existing MCB DB complete with connections, testing and commissioning etc. as required.	2.00	Each	2500.00	5000.00
105.00	Supplying and fixing 5 A to 32 A rating SP MCB, 240/415 V, 10 kA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.	106.00	Each	250.00	26500.00
106.00	Supply and Fixing of Modular type Socket Residual Current Device (SRCD) Socket with steel enclosure 25 Amps DP MCB having Over current protection suitable for 1.5 TR Inverter AC complete as required.	8.00	Each	5000.00	40000.00
107.00	Supply of Recessed mounting 2' x 2' LED panel Luminaire, 36W, IP 20, 6500K CRCA deep-drawn housing suitable for 600 mm X 600 mm modular ceiling complete as per technical specifications.	12.00	Each	3500.00	42000.00
108.00	Supply of Recessed mounting 2' x 2' LED panel Luminaire, 36W, IP 20, 6500K CRCA deep-drawn housing suitable for 600 mm X 600 mm modular ceiling having battery back up complete as per technical specifications.	10.00	Each	4000.00	40000.00
109.00	Supply of 18 W LED BATTEN type Luminaire of 4ft long having minimum system Lumen output of 1800 lumen , epoxy powder coated white CRCA housing for efficient dissipation equipped with high efficiency long life LED module to ensure better lumen output, Milky white, polycarbonate diffuser for glare-free efficient light distribution, elegantly designed white coloured end caps to enhance the aesthetic view of the fixture, integral electronic driver (SMPS based constant current supply) with output short-circuit protection, surge protection & other safety tests as per latest IS specification having battery back up complete as per technical specifications suitable for fixing directly on the wall / ceiling by mounting SS clips provided with the fixture complete as required as per technical specification of the item.	4.00	Each	800.00	3200.00
110.00	Supply of 35 Watt LED type Road/ Street light with minimum protection level IP 66, pressure die cast housing with epoxy power coated prismatic poly carbonate cover with individual LED lenses and complete assembly with LED, driver and accessories pre-wired up to terminal block i/c suitable mounting accessories etc. as required.	14.00	Each	5000.00	70000.00
111.00	Supply of single Dome LED type Aviation Obstruction light as per ICAO requirement suitable to operate on 1Phase, 50 Hz, AC supply with all accessories complete as required .(Bajaj model no BGJV 302 or equivalent)	2.00	Each	5500.00	11000.00
112.00	Installation, testing and commissioning of pre-wired, LED fitting of all types, complete with all accessories etc. directly on/in ceiling/ wall, including connection with 1.5 Sq.mm FRLS PVC insulated, copper conductor, single core cable and earthing etc. as required.	28.00	Each	500.00	14000.00
113.00	Fixing of LED street light fitting on pole / wall including supply and bending the 40mm GI pipe upto 2.00 mtr length to the required shape, iron clamps with nuts, bolts and washer, painting the flat iron with primer and finish paint including connection with 1.5 Sq.mm PVC insulated copper conductor single core cable, testing and commissioning complete as required.	14.00	Each	300.00	4200.00
114.00	Supply of 1200 mm sweep five star BLDC ceiling fan of rating from 26 watt to 32 watt and all standard accessories etc., complete as required.	3.00	Each	4000.00	12000.00
115.00	Supplying and fixing 5 stepped type electronic fan regulator on the existing modular plate switch box including connections but excluding modular plate etc. as required.	3.00	Each	500.00	1500.00
116.00	Installation, testing and commissioning of ceiling fan, including wiring the down rods of standard length (upto 30 cm) with 1.5 Sq.mm FRLSH PVC insulated, copper conductor, single core cable etc. as required.	3.00	Each	200.00	600.00
117.00	Supplying and fixing extra down rod of 10 cm length G.I. pipe ,15 mm dia, heavy gauge including painting etc. as required. (Note : More than 5 cm length shall be rounded to the nearest 10 cm and 5 cm or less shall be ignored)	3.00	Each	500.00	1500.00
118.00	Supply of 230 v , 50 Hz industrial heavy duty exhaust fan with louver having 300 mm sweep 1400 rev/minute including Installation of exhaust fan in the existing opening, including making good the damage, connection, testing, commissioning etc. as required.	2.00	Each	3500.00	7000.00
119.00	Supply of 230 v , 50 Hz industrial heavy duty exhaust fan with louver having 450 mm sweep 1400 rev/minute including Installation of exhaust fan in the existing opening, including making good the damage, connection, testing, commissioning etc. as required.	1.00	Each	5009.99	5009.99
				Total Rs.	10933399.99

(Rupees One Crore Nine Lacs Thirty-Three Thousand Three Hundred Ninety-Nine and Ninety-Nine Paise Only)


 (Ashwini Kumar)
 AGM (E-C)
 AAI, Bagdogra Airport