

No: AAI/ TUT/ Engg (E-C)/Misc/ /2025-26 /61

दिनांक /Date: 16.09.2025

To,

M/s. SVEM Infrastructures
No.109-C, Brindhavan,
Nagar, OPP TNSTC Depot Avinashi Road,
Karumathampatti, Coimbatore,
Tamil Nadu - 641 659

Name of Work: - "Miscellaneous Civil works at Tuticorin Airport."

SH: Bituminous work in Operational area of Tuticorin Airport. - Award letter

Ref :- 1. Your E-Tender opened on 29.08.2025 (Financial Bid)

Bid No :- 2025_AAI_244435_1

Dear Sir,

- 1 Your E-Tender for the work mentioned above is hereby accepted on behalf of Chairman, Airports Authority of India, at the item rates quoted by you for an amount of **Rs. Rs. 1,92,72,235/- (Rupees One Crore Ninety-Two Lakhs Seventy-Two Thousand and Two Thirty-Five only) excluding GST** which is **10.29 % Above** the estimated cost of **Rs. 1.75 Crores (excluding GST)** And **1.94 % Above** the Justified cost of **Rs. 1,89,05,588.60 (Rupees One Crore Eighty-Nine Lakhs Five Thousand Five Eighty-Eight and Sixty Paise only) excluding GST.**
- 2 **Dy. General Manager (Engg-Civil), AAI, Tuticorin Airport, Tuticorin** shall be the Engineer-in-charge of the work. You are requested to attend the office of Dy. General Manager (Engg-Civil), AAI, Tuticorin Airport, within 15 days from the stipulated date of start of work to sign and complete the contract agreement. The Contract Agreement shall be executed on a non-judicial stamp paper of value **Rs.100 /- (Rupees One Hundred only)** and the cost of the stamp paper shall be borne by you.
- 3 The Earnest Money Amount of **Rs. 5,25,000 /- (Rupees Five Lakhs Twenty-Five Thousand only)** received online through CPP Portal along with your tender will be refunded to your source of account. Please deposit **Rs. 19,27,223.50/- (Rupees Nineteen Lakhs Twenty-Seven Thousand Two Hundred and Twenty-Three and Fifty Paise only)** towards security deposit within 10 days from issue of this letter, failing which the same will be deducted from each running bill as per Clause No-1A, of Page No. 16 GCC of contract document.
- 4 You are hereby requested to get yourself registered with provident fund organization, Employees state insurance organization & obtain the necessary PF, ESI & GST code numbers from these departments. Copy of the documents should be submitted to this office. Further,




भारतीय विमानपत्तन प्राधिकरण
Airports Authority of India
तूतीकोरिन हवाईअड्डा
Tuticorin Airport

you are also requested to deposit the requisite PF, ESI and GST amounts and submit copy of periodical returns to AAI.

- 5 You are requested to comply with the provision of Contract Labour (Regulation and abolition) Act 1970 and Contract Labour (Regulation and Abolition) Central Rules 1971, Child Labour (Prohibition & Regulation Act 1986, Construction Workers (Regulation of Employment and Conditions of Service Act 1996, Building and other construction workers Welfare Cess Act 1996 and rules thereof Central and State Governments.
- 6 You are also directed to contact Dy. General Manager (Engg-Civil), AAI, Tuticorin Airport immediately, who will arrange to hand over the site to you.
- 7 Please note that the time allowed for carrying out the work is **01 (One) Month** & shall be reckoned from **10th day** of issue of this letter.
- 8 All taxes as applicable will be deducted from your bill.
- 9 The temporary aerodrome entry permit (TAEP) initially for a period of 30 days will be issued by Airport Director, Tuticorin Airport, with whom the entity entered into written agreement following the due procedures to commence the work inside the airport. Immediately thereafter, formalities to comply with the instruction of BCAS i.e. obtaining provisional security clearance / security clearance through E-sahaj Portal and submission of security program are to be strictly adhere to (If applicable).
- 10 Any further correspondence in connection with the contract should normally be addressed to the Dy. General Manager (Engg-Civil), AAI, Tuticorin Airport, Tuticorin.
- 11 Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

Yours Sincerely,


(S Godwin)

Dy.Gen.Manager (Engg -Civil)
AAI, Tuticorin Airport
For and on behalf of Chairman,
Airports Authority of India.


"Schedule A"

Name of work:- Miscellaneous civil Works at Tuticorin Airport. SH: Bituminous work in operational area of Tuticorin Airport.

S.No	Description of Item	Qty	Unit	Rate	Amount
1	Earth work in excavation by mechanical means(Hydraulic excavator)/ manual means over areas(exceeding 30 cm in depth,1.5 m in width as well as 10 sqm on plan)including getting out and disposal of excavated earth lead upto 50 m and for all lift,as directed by Engineer-in- charge	1040.00	Cum	110.00	114400.00
2	Extra for compaction of earthwork in embankment under optimum moisture conditions to give at least 95%of the maximum dry density (proctor density).	915.00	Cum	35.00	32025.00
3	Construction of Embankment with Moorum having CBR not less than 20% obtained from approved quarry with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement of morth table 300-2	105.00	Cum	1100.00	115500.00
4	Preparation of granular sub-base by providing close graded material, conforming to specifications mixing in a mechanical mix plant at OMC, carriage of mixed material by mechanical transport to work site, for all leads and lifts, spreading in uniform layers of specified thickness with mechanical means including neatly leveling & dressing on prepared surface and compacting with vibratory power roller to achieve the desired density, complete and as per direction of Engineer-in-charge: Conforming to Grading-I requirement.(size range 75 mm to 0.075 mm) having CBR Value-30	105.00	Cum	1950.00	204750.00
5	Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm to 0.075 mm) to wet mix macadam (WMM) specification including premixing the material with water at OMC in mechanical mix plant, carriage of mixed material by mechanical transport to site, for all leads & lifts, laying in uniform layers with mechanical paver finisher in sub-base /base course on well prepared surface and compacting with vibratory roller of 8 to 10 tonne capacity to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge.	640.00	Cum	2250.00	1440000.00
6	Providing and applying primer coat with bitumen emulsion SS1 grade conforming to IS:8887 on prepared surface of Granular Base including clearing of surface and spraying primer at the rate of 0.70 kg/sqm using mechanical means complete in all respects as per direction of Engineer-In-Charge.The contractor shall quote his rates assuming quantity of bitumen emulsion as 0.70 Kg/Sqm.If the actual quantity of bitumen emulsion varies from the quantity assumed above,necessary cost adjustment for deviation in the quantity of bitumen emulsion shall be done as per rate in actual supply voucher from nearest refinery at the time of execution.The rate of bitumen emulsion exclusive of GST shall only be considered for payment.	7810.00	Sqm	52.00	406120.00

S.No	Description of Item	Qty	Unit	Rate	Amount
7	Providing and laying of Hot Mix Dense Bituminous Macadam(DBM)using crushed stone aggregate of quality,size and grading as specified and #filler as specified and Viscosity Grade Bitumen (supplied in bulk)in proportions as per job mix formula and laid to specified levels,grade and camber as per specification,drawings and as directed by the Engineer-in-Charge including compacting with 8-10 tonne, preferably vibratory road roller of adequate capacity to achieve the specified values of compaction,strength,surface accuracy complete [for tendering purpose VG bitumen of grade VG-30 shall be taken as 110 kg/m3 of mix supplied in bulk produced by Govt. Refineries and 2% stone dust by weight of aggregates as filler material].	395.00	Cum	11230.00	4435850.00
8	Providing and applying tack coat (using bitumen emulsion (Rapid setting)complying with IS:8887 ,spraying the bitumen with mechanically operated spray unit at the rate specified below,cleaning and preparing the existing pavement surface as per specifications complete in all respects as per direction of Engineer-In-Charge.If the actual quantity of bitumen varies from the quantity specified,necessary cost adjustment for deviation in the quantity of bitumen shall be done as per rate in actual supply voucher from nearest refinery at the time of execution.The rate of bitumen exclusive of GST shall only be considered for payment. a) 0.20 Kg/Sqm on existing bituminous surface	20545.00	Sqm	22.00	451990.00
9	Providing and laying of Hot Mix Semi Dense Asphaltic Concrete (SDAC)using crushed stone aggregate of quality,size and grading as specified and filler as specified and Viscosity Grade Bitumen (supplied in bulk)in proportions as per job mix formula and laid to specified levels,grade and camber as per specification,drawings and as directed by the Engineer-in-Charge including compacting with 8-10 tonne preferably vibratory road roller of adequate capacity to achieve the specified values of compaction,strength,surface accuracy complete [for tendering purpose VG bitumen of grade VG-30 content shall be taken as 120 kg/m3 of mix supplied in bulk produced by Govt.Refineries and 2% stone dust by weight of aggregates as filler material].	1030.00	Cum	11720.00	12071600.00
Total Amount (Excl.GST)					19272235.00

Amount in Words : One Crore Ninety Two Lakhs Seventy Two Thousand Two Hundred and Thirty Five Only


 (S Godwin)
 Dy.Gen.Manager (Engg -Civil)
 AAI, Tuticorin Airport
 For and on behalf of Chairman,
 Airports Authority of India.