



रजिस्टर्ड ए.डी. द्वारा/By Regd. A.D.

सं.सं. भाविप्रा/भोपाल/वरि. प्रबंधक(अभि.-वि.)/का.आ.-16/केपिटल/2025-26 /1461(1-9) दिनांक: 30.10.2025
Ref. No: AAI/BPL/Sr.Manager(E-E)/16/Capital/2025-26 Date: 30.10.2025
103(1-9)

सेवा में,

मेसर्स रुही इंटरप्राइजेस,
जैन धरमशाला के पास,
चिक सेंटर, मोरार, ग्वालियर - 474006
ई-मेल: ruhienterprises0202@gmail.com

M/s Ruhi Enterprises,
Near Jain Dharamsala,
Chick Santer, Morar, Gwalior - 474006
E-mail: ruhienterprises0202@gmail.com

विषय : "राजा भोज विमानतल, भोपाल पर फ्रेंजाइल लेटिस स्ट्रक्चर के साथ नये विंड डायरेक्शन इंडिकेटर का प्रावधान।"

Subject: "Provision of new wind direction indicator with frangible lattice structure mast at R.B. Airport, Bhopal."

संदर्भ : 1) दिनांक 15.10.2025 को खोली गई आपकी निविदा
Your tender opened on dated 15.10.2025

महोदय/Dear Sir,

- उल्लेखित कार्य हेतु आपकी ई-निविदा आपके द्वारा उद्धृत कुल राशि **रु. 6,86,750.00** (रु. छह लाख छियासी हजार सात सौ पचास मात्र - जी.एस.टी. रहित) की नियत मद दर पर अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से एतद् द्वारा स्वीकृत की जाती है, जो कि ई-निविदा की न्यायसंगत राशि **रु. 8,12,327.50** (रु. आठ लाख बारह हजार तीन सौ सत्ताईस एवं पचास पैसे मात्र) जी.एस.टी. रहित से **15.46% कम** है।

Your E-Tender for the work mentioned above is hereby accepted on behalf of the Chairman, Airports Authority of India at the item rates quoted by you totaling to **Rs. 6,86,750.00 (Rupees Six Lakh Eighty Six Thousand Seven Hundred Fifty Only - Excl. GST)** which is **15.46% below** the justified cost put to E-Tender of **Rs. 8,12,327.50 (Rupees Eight Lakh Twelve Thousand Three Hundred Twenty Seven and Fifty Paise Only) Excl. GST.**

- वरि.प्रबंधक (अभि.-विद्युत), भारतीय विमानपत्तन प्राधिकरण, राजा भोज विमानतल, भोपाल इस कार्य के इंजीनियरिंग प्रभासी होंगे। आपसे निवेदन है कि आप संविदा करार पर हस्ताक्षर करने एवं उसे पूरा करने हेतु **24.11.2025** तक वरि.प्रबंधक (अभि.-विद्युत), भारतीय विमानपत्तन प्राधिकरण, भोपाल विमानपत्तन के कार्यालय में उपस्थित हो। संविदा करार **रु. 500/- (पाँच सौ रुपये)** के न्यायिकेतर (नॉन - ज्युडिशियल) स्टॉप पेपर पर बनाया जायगा तथा स्टॉप पेपर की लागत आपके द्वारा वहन की जाएगी।

Sr. Manager (Engg.-Elect.), Airports Authority of India, Raja Bhoj Airport, Bhopal shall be the Engineer-In-Charge of the work. You are requested to attend the office of the Sr. Manager (Engg.-Elect.), Airports Authority of India, Raja Bhoj Airport, Bhopal by **24.11.2025** to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value **Rs. 500/- (Rupees Five Hundred only)** and the cost of the stamp paper shall be borne by you.

Contd...2

- 3- कृपया इस पत्र के जारी होने के 10 दिनों के अंदर प्रतिभूति जमा के रूप में रु. **68,675/-** (रु. अड़सठ हजार छह सौ पचहत्तर मात्र) की राशि इस कार्यालय में जमा करा दें अन्यथा करारनामों की संविदा की सामान्य शर्त के पृष्ठ संख्या - 15 पर दी गई शर्त 1ए के अनुसार उक्त राशि आपके बिल से काट ली जाएगी।

Please deposit **Rs. 68,675/-** (Rupees Sixty Eight Thousand Six Hundred Seventy Five Only) towards Security Deposit within 10 days from the date of issue of this letter, failing which, the same will be deducted as per condition of Clause 1A on page 15 of the contract document.

- 4- आपसे अनुरोध है कि आप ठेका श्रमिक (विनियम एवं उन्मूलन) अधिनियम 1970 के उपबंधों एवं ठेका श्रमिक (विनियम एवं उन्मूलन) केन्द्रीय नियमावली 1971, बालक श्रम (प्रतिषेध एवं विनियमन) अधिनियम 1986, निर्माण श्रमिकों (नियोजन और सेवा शर्त विनियमन) अधिनियम 1996, भवन और अन्य सन्निर्माण कर्मकार उपकर अधिनियम 1996 जैसा कि निविदा की ठेका सामान्य शर्तों के पृष्ठ क्र. 48 की शर्त 19 एवं केन्द्रीय एवं राज्य सरकार के नियमों में निर्दिष्ट है का अनुपालन करें।

You are requested to comply with the provision of Contract labour (Regulation and Abolition) Act 1970 and contract labour (Regulation and Abolition) Central rules 1971 Child Labour (Prohibition & Regulation) Act 1986, Construction Workers (Regulation of Employment and Condition of Service) Act 1996, Building and other construction Workers Welfare Cess Act 1996 as specified in Clause 19 on page no. 48 of GCC of tender and rules of Central and State Government.

- 5- आपको प्रबंधक (अभि.-वि.)-II, भारतीय विमानपत्तन प्राधिकरण, राजा भोज विमानतल, भोपाल से तत्काल संपर्क करने का भी निर्देश दिया जाता है। आपको कार्यस्थल (साइट) सौंपने का कार्य उनके द्वारा किया जाएगा।

You are also directed to contact Manager (Engg.-Elect.)-II, AAI, Bhopal Airport immediately who will arrange to hand over the site to you.

- 6- कृपया नोट करे की कार्य हेतु आपको **03** माह का समय प्रदान किया जाता है। यह समय इस पत्र के जारी करने की तिथि के 10वे दिन से माना जाएगा।


Please note that the time allowed for carrying out the work shall be **03 months** to complete the work. The same shall be reckoned from 10th day from date of issue of this letter.

- 7- कृपया ध्यान दें कि दोष दायित्व आवधि कार्य समाप्ति होने की तारीख से **12** (बारह) महीने की होगी।

Please note that the defect liability period shall be **12 (Twelve)** months from the certified date of completion of work.

- 8- इस ठेके से संबंधित किसी भी प्रकार के पत्र व्यवहार के लिए वरि. प्रबंधक (अभि.-विद्युत), भा.वि.प्रा., राजा भोज विमानतल भोपाल - 462036 को संबोधित करें।

Any further correspondence in connection with the contract should normally be addressed to the Sr. Manager (Engg.-Elect.), Airports Authority of India, R. B. Airport, Bhopal - 462036.


30/10/25

- 9- कृपया इस पत्र की प्राप्ति की सूचना दें तथा इसके साथ अनुलग्न अनुप्रति पर हस्ताक्षर करके टोकन के प्रतिग्रहण के रूप में अधोहस्ताक्षरी को वापस भेज दें।

Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

- 10- यदि कोई विसंगति पाई जाती है तो अंग्रेजी भाषा ही मान्य होंगी।

In case any discrepancy is found, then English version will be taken as correct.

संलग्नक / Enclosure: 1. BOQ (Total 04 Pages)

भवदीय / Yours Faithfully


(सुमित गुप्ता / Sumit Gupta)

वरि.प्रबंधक (अभि.-विद्युत)

Sr.Manager (Engg.-Elect.)

भा.वि.प्रा., राजा भोज विमानतल, भोपाल - 462036

AAI, Raja Bhoj Airport, Bhopal - 462036.

कृते तथा ओर से, अध्यक्ष,

For and on behalf of Chairman,

भारतीय विमानपत्तन प्राधिकरण.

Airports Authority of India

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: SM(E-E), AAI, R.B. Airport, Bhopal

Name of Work: Provision of new wind direction indicator with frangible lattice structure mast at R.B. Airport, Bhopal.


Contract No: AAI/BPL/ENGG(E)/NIT-06/2025-26

Name of the Bidder/
Bidding Firm /
Company : RUHI ENTERPRISES GWALIOR

PRICE SCHEDULE


(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER # Sl. No.	TEXT # Item Description	NUMBER # Quantity	TEXT # Units	BASIC RATE In Figures To be entered by the Bidder (Without GST) Rs. P	NUMBER # TOTAL AMOUNT in Rs. P	TEXT # TOTAL AMOUNT In Words
1 1.00	2 Supply, Installation, Testing and Commissioning of 7.75 meter approx. Frangible lattice mast type Wind Direction Indicator with base hinge for aviation (colour red white) with external lighting arrangement, obstruction light (LED), wind cone as per ICAO, Annex - 14, chapter 5, section 5.1.1 requirement, FAA type L-807(L), style I - A, size 2 (AC 150/5345 - 27) and suitable RCC foundation including base plate and SS mounting, template, J-bolts, pipe for cable entry as recommended by the OEM of the Frangible lattice mast with base hinge complete etc. as required. (The lighting arrangement having LED flood lights (4 nos.) 30 W, each, 01 aviation light shall be suitable for working at 230V , 50 Hz AC supply). Complete as per Technical Specification.	4 1.00	5 Each	13 2250000.00	53 2250000.00	55 INR Two Lakh Twenty Five Thousand Only




NUMBER # Sl. No.	TEXT # Item Description	NUMBER # Quantity	TEXT # Units	NUMBER # BASIC RATE In Figures To be entered by the Bidder (Without GST) Rs. P	NUMBER # TOTAL AMOUNT in Rs. P	TEXT # TOTAL AMOUNT In Words
1	2	4	5	13	53	55
2.00	Supply, Installation, Testing and Commissioning of 7.30 meter approx. Frangible lattice mast type Wind Direction Indicator with base hinge for aviation (colour red white) with external lighting arrangement, obstruction light (LED), wind cone as per ICAO, Annex - 14, chapter 5, section 5.1.1 requirement, FAA type L-807(L), style I - A, size 2 (AC 150/5345 - 27) and suitable RCC foundation including base plate and SS mounting, template, J-bolts, pipe for cable entry as recommended by the OEM of the Frangible lattice mast with base hinge complete etc. as required. (The lighting arrangement having LED flood lights (4 nos.) 30 W, each, 01 aviation light shall be suitable for working at 230V , 50 Hz AC supply). Complete as per Technical Specification.	1.00	Each	225000.00	225000.00	INR Two Lakh Twenty Five Thousand Only
3.00	Dismantling of existing Wind Direction Indicator from site and shifting the wind direction indicator to store/dismantle area as required by EIC.	2.00	Job	5000.00	10000.00	INR Ten Thousand Only
4.00	Retrieving existing underground cable not exceeding 35sq.mm and DWC pipe not exceeding OD 63 mm by excavation in any kind of soil with depth upto 1.2 m including getting out the excavated soil, refilling with good soil after retrieval of cable/pipe etc in layers of 20 cm, ramming, watering and disposal of surplus excavated soil as directed, within a lead of 50 meters. Excavation shall be carried out by manual means wherever directed by AAI.	20.00	Cum	500.00	10000.00	INR Ten Thousand Only
5.00	Laying of following size DWC HDPE pipe ISI marked along with all accessories like socket, bend, couplers etc. conforming to IS 14930, Part II complete with fitting and cutting, jointing etc. direct in ground (75 cm below ground level) including excavation and refilling the trench but excluding sand cushioning and protective covering etc.. complete as required. (DWC pipe will be provided by AAI). Excavation shall be carried out by manual means wherever directed by AAI. 63 mm dia (OD-63 mm & ID-51 mm nominal)	50.00	Meter	80.00	4000.00	INR Four Thousand Only
6.00	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed/XLPE aluminium conductor cable of 1.1 KV grade as required. 4 X 10 sq. mm (25mm)	4.00	Set	200.00	800.00	INR Eight Hundred Only

NUMBER # Sl. No.	TEXT # Item Description	NUMBER # Quantity	TEXT # Units	NUMBER # BASIC RATE In Figures To be entered by the Bidder (Without GST) Rs. P	NUMBER # TOTAL AMOUNT in Rs. P	TEXT # TOTAL AMOUNT In Words
1	2 Laying of one number PVC insulated and PVC sheathed/XLPE power cable of 1.1 KV grade of following size in the existing RCC/HUME/META/DWC pipe as required. Upto 35 sq. mm	4	5	13	53	55
7.00		40.00	Meter	20.00	800.00	INR Eight Hundred Only
8.00	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed/XLPE aluminium conductor cable of 1.1 KV grade as required. 3.5 X 35 sq. mm (32mm)	2.00	Set	350.00	700.00	INR Seven Hundred Only
9.00	Providing and laying earth connection from earth electrode with 6 SWG dia G.I. Wire in 15 mm dia G.I. pipe, including supply of 15mm dia G.I. pipe, from earth electrode including connection with G.I. thimble, excavation and re-filling as required. Excavation shall be carried out by manual means wherever directed by AAI.	50.00	Meter	130.00	6500.00	INR Six Thousand Five Hundred Only
10.00	Supply and laying of 50mm GI pipe (medium class) in ground upto 45 cm depth etc. complete as required.	18.00	Meter	550.00	9900.00	INR Nine Thousand Nine Hundred Only
11.00	Demolishing cement concrete manually/by mechanical means including disposal of material within 50 meters lead as per direction of Engineering- in-charge nominal concrete 1:2:4 or richer mix.	1.50	Cum	500.00	750.00	INR Seven Hundred & Fifty Only
12.00	Providing and laying in position cement concrete 1:2:4 (1 cement: 2 cum coarse sand : 4 graded stone aggregate 20 mm nominal size) for foundation etc including form work etc as required	1.50	Cum	6500.00	9750.00	INR Nine Thousand Seven Hundred & Fifty Only
13.00	Earthing with G.I. earth pipe 4.5 metre long, 40 mm dia (Drilling of 300 mm dia, 4.5 Mtr deep by using Borewell machine) including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe etc. (with charcoal/ coke and salt) as required.	2.00	Set	6500.00	13000.00	INR Thirteen Thousand Only
14.00	Supply of Insulating mats as per IS 15652 having size 2.0 mm thick X 1.0 m width X 10 m long, of class: A, for working voltage upto 3.3 kV, colour - Black, antiskid design: dotted, should be CPRI certified.	250.00	Sqm	430.00	107500.00	INR One Lakh Seven Thousand Five Hundred Only



 (Signature)

NUMBER # Sl. No.	TEXT # Item Description	NUMBER # Quantity	TEXT # Units	NUMBER # BASIC RATE In Figures To be entered by the Bidder (Without GST) Rs. P	NUMBER # TOTAL AMOUNT in Rs. P	TEXT # TOTAL AMOUNT In Words
1	2	4	5	13	53	55
15.00	Supply of Insulating mats as per IS 15652 having size 2.5 mm thick X 1.0 m width X 10 m long, of class: B, for working voltage upto 11.0 kV, colour - Black, antiskid design: dotted, should be CPRI certified.	60.00	Sqm	530.00	31800.00	INR Thirty One Thousand Eight Hundred Only
16.00	Supply of Insulating mats as per IS 15652 having size 3.0 mm thick X 1.0 m width X 10 m long, of class: C, for working voltage upto 33.0 kV, colour - Black, antiskid design: dotted, should be CPRI certified.	50.00	Sqm	625.00	31250.00	INR Thirty One Thousand Two Hundred & Fifty Only
Total in Figures					686750.00	INR Six Lakh Eighty Six Thousand Seven Hundred & Fifty Only
Quoted Rate in Words		INR Six Lakh Eighty Six Thousand Seven Hundred & Fifty Only				


 वरिष्ठ प्रबंधक (आर्थिक - विद्युत)
 Senior Manager (Eggr. Elect.)