



भाविप्रा /औरंगाबाद /अमि.-वि/कैप/24-25/डब्ल्यू -05/ 485
AAI/AU/Engg-E/CAP/25-26/W-05/

दिनांक: 06.11.2025
Date: 06.11.2025

सेवा में,
मेसर्स अभिषेक इंटीग्रेशन्स लिमिटेड,
8th, 801, वीनस बेनेशिया,
सरखेज गांधी नगर रोड,
राजपथ क्लब के सामने, बोदकदेव,
अहमदाबाद, गुजरात - 380054

To,
M/s Abhishek Integrations Ltd.
8th, 801, Venus Benecia,
Sarkhej Gandhi Nagar Road,
Opp. Rajpth Club, Bodakdev,
Ahmedabad, Gujarat - 380054

(PAN No. AAQCA2416B)
GST No. 24AAQCA2416B1Z6

कार्य का नाम : औरंगाबाद हवाई अड्डे पर टर्मिनल भवन और सहायक भवन में मौजूदा HPSV/MH फिटिंग को एलईडी लाइट फिटिंग से बदलना।

Replacement of existing HPSV/MH fitting with LED light fitting in Terminal Building and auxiliary building at Aurangabad Airport.

- संदर्भ : 1) निविदा आई. डी संख्या : 2025_AAI_248014_1
2) आपकी ई - निविदा जो दिनांक 13.10.2025 को खोली.

महोदय,/ Dear Sir (S),

- उल्लिखित कार्य हेतु आपकी ई - निविदा अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की और से आपके द्वारा बताए गये मद मूल्यों पर रु. **64,95,708.00** (रु. चौंसठ लाख पंचानबे हजार सात सौ आठ मात्र) (जी एस टी अतिरिक्त) के लिये स्वीकृत की जाती है जो कि अनुमानित लागत राशि रु **76,18,456.00** से **14.74%** कम है।

Your e-tender for the work mentioned above is hereby accepted on behalf of the chairman, Airports Authority of India, at the item rates quoted by you totaling to **Rs. 64,95,708.00** (Rupees Sixty-Four Lakh Ninety-Five Thousand Seven Hundred and Eight Only) (Excluding GST) which is **14.74%** below the justification cost put to tender of **Rs. 76,18,456.00**.

- वचि. प्रबंधक (अभियांत्रिकी- विद्युत), भाविप्रा, औरंगाबाद हवाईअड्डा, महाराष्ट्र कार्य के प्रभारी अभियंता होंगे, आपसे निवेदन है कि, आप दिनांक **21.11.2025** तक वचि. प्रबंधक (अभियांत्रिकी- विद्युत), भाविप्रा, औरंगाबाद हवाईअड्डा, औरंगाबाद, के कार्यालय में उपस्थित हो तथा करारनामे को पुरा करे. ठेके के करार नामा रुपये 100/- के नोनजुडिशियल स्टैम्प पर निष्पादित किया जायेगा तथा पेपर का खर्चा आपके द्वारा उठाया जायेगा।

Senior Manager (E-E), AAI, Aurangabad Airport, Maharashtra, shall be the Engineer -In -Charge of the work. You are requested to attend the office of Senior Manager (E-E), AAI, Aurangabad Airport by **21.11.2025** to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs. 100/- (Rupees one Hundred Only) and the cost of the stamp paper shall be borne by you.

विमानक्षेत्र नियंत्रक का कार्यालय, भा.वि.प्रा., औरंगाबाद, दूरभाष : (0240) 2477802,
O/O The Airport Director, AAI, Aurangabad. Phone No: (0240)2477802,

06.11.25
S M (E-E)

वचि. प्रबंधक (अभि-विद्युत)
भाविप्रा औरंगाबाद हवाईअड्डा

3. आपके निविदा के साथ प्राप्त बयाना राशि **2,28,554.00** रुपए को प्रतिभूति जमा के हिस्से के रूप में परिवर्तित किया जाएगा। कृपया इस पत्र के जारी होने की तिथि से 15 दिनों के भीतर प्रतिभूति जमा राशि **4,21,017.00** रुपये ठेके के दस्तावेज के अनुसार जमा कर दें, अन्यथा निविदा में पृष्ठ जी सी सी 16 पर दी गई धारा 1(A) के अनुसार कटौती की जाएगी।

The earnest money amount of **Rs. 2,28,554.00** received along with your tender will be treated and converted as part of Security Deposit. Please deposit **Rs. 4,21,017.00** towards security deposit within 15 days from the date of issue of this letter, failing which the same will be deducted as per condition of clause 1(A) at GCC Page 16 of the Contract Document.

कृपया अनुबंध दस्तावेज के बीमा जमानत बांड का प्रारूप के पृष्ठ संख्या 1-4 पर अनुलग्नक- V में संलग्न प्रोफार्मा पर अनुसूचित वाणिज्यिक बैंक (अर्थात भारतीय या विदेशी बैंक जो भारतीय रिजर्व बैंक अधिनियम, 1934 की दूसरी अनुसूची में शामिल हैं, सहकारी/क्षेत्रीय ग्रामीण बैंकों को छोड़कर) से जारी अपरिवर्तनीय बीमा जमानत बांड, डिमांड ड्राफ्ट, बैंक गारंटी के रूप में रु. 81,196/- (इक्यासी हजार एक सौ छियानबे मात्र) की अतिरिक्त निष्पादन सुरक्षा राशि इस अवार्ड पत्र के जारी होने की तारीख से 30 दिनों के भीतर अर्थात 06.12.2025 को या उससे पहले जमा करें, क्योंकि आपने अनुमानित लागत से 14.74% कम कोट किया है।

Please deposit additional performance security amount of Rs. 81,196/- (Rupees Eighty One Thousand One Hundred & Ninety Six Only) in the form of an irrevocable Insurance Surety bond, demand draft, bank guarantee issued from Scheduled Commercial Bank (i.e. Indian or Foreign Banks included in the Second Schedule of Reserve Bank of India Act, 1934 excluding Co-Operative/ Regional Rural Banks) on the Proforma appended at Annexure-V on page no. 1 to 4 of Form **within 30 days of date of issue this award letter i.e. on or before 06.12.2025, as you have quoted 14.74% below estimated cost.**

4. आपसे निवेदन है कि आप केन्द्रीय और राज्य सरकारों के 1970 अधिनियम अनुबन्ध श्रम नियम तथा 1971 के केन्द्रीय नियम (नियमन तथा उन्मूलन) एवं केन्द्र तथा राज्य सरकारों के न्यूनतम वेतन अधिनियमों और नियमों के प्रवधानों के अनुपालन करें।

You are requested to comply with the provisions of contract labour (Regulation and abolition) Act of 1970 and contract labour (Regulation and abolition) Central rules 1971 and minimum wages Act & rules thereof Central and State Governments.

5. आपको निर्देश दिया जाता है कि आप तुरंत प्रबंधक (अभियांत्रिकी -विद्युत), से मिलें वह आपको साईट सौंपने कि व्यवस्था करेंगे।

You are also directed to contact **Manager (Engg-Elect.)**, AAI, Aurangabad Airport immediately who will arrange to hand over the site to you.

6. कृपया नोट करें कि कार्य करने का समय **05 (पाच) माह** रहेगा, जोकी कार्य आदेश जारी होने के दसवें दिन से माना जायेगा।

Please note that the time allowed for carrying out the work shall be **05 (Five) Months** and same shall be reckoned from the 10th day of the date of placing of work order.

7. यदि अंग्रेजी और हिंदी पाठ में कोई अंतर पाया जाता है तो अंग्रेजी विवरण सही माना जाएगा।

If there is any discrepancy between English and Hindi then meaning derived in English will be given precedence.

8. ई निविदा प्रक्रिया के दौरान उठाए गए सभी शुद्धी पत्र, प्रश्न, स्पष्टीकरण इत्यादि और उपर उल्लिखित पत्रों सहित उत्तरों के जवाब भी करारनामे के हिस्से होंगे।

All corrigendum, queries, clarifications etc., raised during e-tendering process and replies there of including the letters referred above shall also form part of the agreement.

9. इस ठेके के संबंध में आगे को कोई भी पत्राचार वरि. प्रबंधक (अभि.- विद्युत), भाविप्रा. औरंगाबाद हवाईअड्डा, औरंगाबाद - 431007 के पते पर किया जाए।

Any further correspondence in connection with the contract should normally be addressed to the Sr. Manager (Engg-Elect), AAI, Aurangabad Airport, Aurangabad - 431007.


10. कृपया इस पत्र को स्वीकार करे और हस्ताक्षर करने के बाद इसके साथ संलग्न पत्र की डुप्लिकेट प्रति स्वीकृति के प्रतीक के रूप में अधोहस्ताक्षरी को वापिस करें।

Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

संलग्न : मात्रा की अनुसूची

Encl : Schedule of Quantity (SOQ)

भवदीय/ Yours faithfully,



06.11.25

वरि. प्रबंधक [अभि - विद्युत]

Sr. Manager (E-E)

भाविप्रा, औरंगाबाद हवाईअड्डा, औरंगाबाद
AAI, Aurangabad Airport, Aurangabad

वरि. प्रबंधक (अभि-विद्युत)

भाविप्रा औरंगाबाद हवाईअड्डा

Validate

Print

Help


Item Rate BoQ

Tender Inviting Authority: Senior Manager (Engg.-Electrical), Airports Authority of India, Aurangabad Airport, Aurangabad- 431007.

Name of Work: Replacement of existing HPSV/MH fitting with LED light fitting in Terminal Building and auxiliary building at Aurangabad Airport.


Contract No: 2025_AAI_248014 _1

Name of the Bidder/ Bidding Firm / Company :	Abhishek Integrations Limited					
PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P (Excluding GST)	TOTAL AMOUNT Rs. P (Excluding GST)	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
1	Supply of Recessed mounted 2' x 2' LED panel Luminaire, 36W, IP 20, CRCA deep-drawn housing suitable for 600 mm X 600 mm modular ceiling complete as per technical specifications.	177.00	Each	1228.00	217356.00	INR Two Lakh Seventeen Thousand Three Hundred & Fifty Six Only
2	Supply of Recessed mounted 2' x 2' LED panel Luminaire, 36W, IP 20, IK 07 Warm White (3000 K) CRCA deep-drawn housing suitable for 600 mm X 600 mm modular ceiling complete as per technical specifications.	50.00	Each	1228.00	61400.00	INR Sixty One Thousand Four Hundred Only
3	Installation, testing and commissioning of pre-wired, LED light fitting complete with all accessories including providing MS chain link up to 3.0 meter to support/hang the light to existing false ceiling grid including wiring with 3C X 1.5 sq. mm FRLS PVC insulated, copper conductor cable up to 3.0 m length metallic flexible conduit from existing Terminal Box and connectors for the connections as per the site requirements.	227.00	Each	515.00	116905.00	INR One Lakh Sixteen Thousand Nine Hundred & Five Only
4	Supply of 70/80 W, IP 65 Industrial LED Highbay luminaire completely prewired with accessories up to terminal block complete as per technical specifications.	21.00	Each	4174.00	87654.00	INR Eighty Seven Thousand Six Hundred & Fifty Four Only
5	Supply of 150 W, IP 65 Industrial LED Highbay luminaire completely prewired with accessories up to terminal block complete as per technical specifications.	55.00	Each	6582.00	362010.00	INR Three Lakh Sixty Two Thousand & Ten Only


 एडि. प्रकाश (अभि-विद्युत)

भाद्वि. २०८२ (२०२५) २७ अक्टूबर

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P (Excluding GST)	TOTAL AMOUNT Rs. P (Excluding GST)	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
6	Supply of 200 W, IP665 LED flood Light, Die cast aluminium frame with heat resistant toughned clear glass fixed with SS screws complete as per technical specifications.	84.00	Each	7745.00	650580.00	INR Six Lakh Fifty Thousand Five Hundred & Eighty Only
7	Supply of 45 W, IP 65 Industrial LED Street Light, Die cast aluminium frame with heat resistant toughned clear glass fixed with SS screws complete as per technical specifications.	106.00	Each	1920.00	203520.00	INR Two Lakh Three Thousand Five Hundred & Twenty Only
8	Supply and erection of tubular street light pole of 4.00 meter length made out of 65 mm dia B class MS Pipe including supply of bracket for mounting arrangements for luminair (BOQ Item No. 7) including base plate of 300mm x 300mm x 5 mm thickness welded at the bottom of the pole The entire pole to be fixed above the base plate and foundation and the base plate should be capable of holding the poles in all weather. The base plate and pole should have wire entry for the supply of the luminair including painting with two coats of redoxide primer and two coats of Aluminium (black) paint as required.	90.00	Each	7320.00	658800.00	INR Six Lakh Fifty Eight Thousand Eight Hundred Only
9	Supply of 30/45 W, IP65, LED Post Top Light, warm white (3000K) with die cast aluminium with powder coating with heat resistant toughned clear glass fixed with SS screws with clear acrylic cover, feasible for the pole top mounted (existing pole outer dia 60 mm) complete as per technical specifications.	237.00	Each	1505.00	356685.00	INR Three Lakh Fifty Six Thousand Six Hundred & Eighty Five Only
10	Supply and erection of tubular post top light pole of 1.75- 1.8 meter length made out of 60 mm dia B class MS Pipe including complete mounting arrangements for pole top LED lights (BOQ Item No. 9) including base plate of min 20 mm dia to be fixed at the bottom of the pole and top of the foundation. The entire pole to be fixed inside the base plate with proper nut bolts and base plate should be capable of holding the poles in all weather. The base plate and pole should have wire entry for the supply of the luminair including painting with two coats of redoxide primer and two coats of Aluminium (black) paint as required.	127.00	Each	4313.00	547751.00	INR Five Lakh Forty Seven Thousand Seven Hundred & Fifty One Only




06.11.25

Sm (E-E)

वरि.प्रबंधक (अभि-विद्युत)

महानगर औरंगाबाद हवाई अड्डा

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P (Excluding GST)	TOTAL AMOUNT Rs. P (Excluding GST)	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
11	Supply of 9/12 W, IP65, LED Mushroom Bollard light, warm white (3000K) with die cast aluminium with powder coating with heat resistant toughened clear glass fixed with SS screws, surface/foundation mounted complete as per technical specifications.	18.00	Each	1953.00	35154.00	INR Thirty Five Thousand One Hundred & Fifty Four Only
12	Supply of 9/12 W, IP65, IK 10, LED In Ground/Ground Burial light, warm white (3000K) with Aluminium body and SS trim finishing with heat resistant toughened clear glass fixed with SS screws complete as per technical specifications. The fitting should be fixed to the existing groove as per technical specifications.	198.00	Each	4841.00	958518.00	INR Nine Lakh Fifty Eight Thousand Five Hundred & Eighteen Only
13	Preparation of the foundation of size 300 x 300 x 1000 mm (w x l x h) in cement concrete 1:3:6 (1 Cement : 3 Coarse : 6 graded stone aggregate 40 mm normal size) including fixing of terminal box (IP 66) as per technical specifications. The foundation should be well finished and should be capable of holding base plates and poles for the street lights and post top fittings including painting of foundation as per the direction of EIC.	70.00	Each	3000.00	210000.00	INR Two Lakh Ten Thousand Only
14	ITC of all LED luminaire at the desired location i/c. wiring with 3C X 1.5 sq. mm FRLS PVC insulated, copper conductor cable up to 5.0 m length from existing Terminal Box , with suitable size angle iron stand in case of high bay lights (if required) or reducer in case of post top fittings (if required) etc. complete as per site requirement and technical specifications.	719.00	Each	515.00	370285.00	INR Three Lakh Seventy Thousand Two Hundred & Eighty Five Only




06.11.25

Smt (S. S.)


वरि.प्रबंधक (अभि-विद्युत)

भाविप्रा औरंगाबाद हवाईअड्डा

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P (Excluding GST)	TOTAL AMOUNT Rs. P (Excluding GST)	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
15	Supply, Installation, Testing and Commissioning of 3.5 Meter Double Arm Post Top Pole with Part 1: GI Bottom Pole : Diameter 140 mm, Length 1000 mm, Thickness 4 mm ; Part 2: GI Center Pole : Diameter 89 mm, Length 1500 mm, Thickness 3.6 mm ; Part 3: GI Top Arm Center Pole: Diameter 76mm, Length 1000 mm, Thickness 3.6 mm ; Part 4: GI Arm Bend Pipe: Diameter 42mm, Thickness 2.8mm Length 2200 x 2 = 4400 mm with Base Plate of MS: 350x350x12mm, all-aluminium embellishment design The pole section shall be welded by certified welders using highend MIG welding process. The maintenance door shall be provided at the bottom part of the pole to accommodate a built-in connection box. The control gear tray is with MCB, terminal connectors for loop in loop out arrangement. The Pole coated with epoxy zinc phosphate primer and finished using environmentally stable polyurethane base paint MRF, Silicone rubber gaskets are provided for water protection complete with connection wire, foundation Bolt and Other Accessories as required. Including 30/45 W Drop down light Aluminium Spun/Casting Heatsing Housing housing PC Diffuser Transparent. IP 65 or above. The LED light design should be decorative warm fitting and it should be approved by EIC Including suitable foundation for the erection of pole and cable entry with propoer asthetic look and all conditions are as per technical specifications.	18.00	Each	30015.00	540270.00	INR Five Lakh Forty Thousand Two Hundred & Seventy Only
16	Supply of LED batten light 18W Lighting system comprising of LED of approved make etc as per specifications and complete as required.	300.00	Each	360.00	108000.00	INR One Lakh Eight Thousand Only
17	Supply of 3C X 10 sq.mm size of XLPE insulated & PVC sheathed, armoured, copper conductor under ground cable of 1.1KV grade as per IS 7098:1988 Part-I with upto date amendments complete as required. (Make: As per AAI list of approved makes)	1000.00	Meter	488.00	488000.00	INR Four Lakh Eighty Eight Thousand Only


 06.11.25
 वरि.प्रबंधक (अभियन्ता)
 भाविप्रा औरंगबाद हवाईअड्डा

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P (Excluding GST)	TOTAL AMOUNT Rs. P (Excluding GST)	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
18	Supplying and laying of following size DWC HDPE pipe ISI marked along with all accessories like socket, bend, couplers etc. conforming to IS 14930, Part II complete with fitting and cutting, jointing etc. direct in ground (75 cm below ground level) including excavation and refilling the trench but excluding sand cushioning and protective covering etc., complete as required. A) 63 mm dia (OD-63 mm & ID-51 mm nominal)	560.00	Meter	213.00	119280.00	INR One Lakh Nineteen Thousand Two Hundred & Eighty Only
19	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size in the existing RCC/ HUME/ METAL/DWC-HDPE pipe as required. A) Upto 35 sq. mm	1000.00	Meter	20.00	20000.00	INR Twenty Thousand Only
20	Supply & Laying of 50 mm dia size B class G.I pipe confirming to IS : 1239 part-1 (2004) for road crossing at a depth of 300mm i/c cutting bituminous surface, re-filling with cement concrete of 1:2:4 and making good the same as required.	120.00	Meter	1392.00	167040.00	INR One Lakh Sixty Seven Thousand & Forty Only
21	Supplying and making end termination with brass compression gland and copper lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required. a) 3 X 10 sq. mm (22 mm)	12.00	Each	225.00	2700.00	INR Two Thousand Seven Hundred Only
22	Dismantle of existing installed MH/CFL fittings at Terminal Building and all areas (City Side and Air Side garden area) including arrangements of ladders and tools for the dismantling of fittings upto the height of 60 ft.	1.00	Job	50000.00	50000.00	INR Fifty Thousand Only
23	Supply of Pole Box of dimensions (300 x 200 x 150) (h x w x d) mm having IP 65 protection, made form 1.6 mm CRCA sheet and the pole box should be feasible for the cable entry and exit for the cable size of 3.5 x 35 Sqmm. The pole box should have MCB mounting assembly, it should have 4 nos 63 A stud type terminals including loop in loop out arrangements inclusing the rain protection canopy as per technical specifications.	300.00	Each	546.00	163800.00	INR One Lakh Sixty Three Thousand Eight Hundred Only
Total in Figures					6495708.00	INR Sixty Four Lakh Ninety Five Thousand Seven Hundred & Eight Only
Quoted Rate in Words		INR Sixty Four Lakh Ninety Five Thousand Seven Hundred & Eight Only				


 24.01.21
 हरि प्रदीप (अति विद्युत)
 भाविता औरगवाड़ हवाई अड्डा