



भारतीय विमानपत्तन प्राधिकरण

AIRPORTS AUTHORITY OF INDIA

सोलापुर एयरपोर्ट, सोलापुर

SOLAPUR AIRPORT, SOLAPUR

संदर्भ सं.: भाविप्रा/सोलापुर/स.म.प्र.(अभि-सि)/W-07STP/2025-26/
Ref. No: AAI/SOLAPUR/AGM (E-C)/W-07/STP /2025-26/

दिनांक: 24.12.2025
Date: 24.12.2025

(कार्य आदेश / Work Order)

सेवा में,

मेसर्स ईगल एसोसिएट्स
कार्यालय क्रमांक 305, ऐश्वर्याम डियरस्टोन
महालसाकांत चौक के पास,
निगड़ी, पिंपरी-चिंचवड, पुणे-411044

To,

M/s. Eagle Associates
Office No. 305, Aishwaryam Deerstone
Near Mhalsakant Chowk, Nigdi,
Pimpri-Chinchwad, Pune-411044

कार्य का नाम:- "Design, Supply, Installation, Testing & Commissioning i/c Civil and Electromechanical works required for MBBR Based Sewage Treatment plant to handle total domestic sewage of 25 KLD at Solapur Airport."

संदर्भ / Ref.: - 1. दिनांक 19.11.2025 को ई-निविदा संख्या 2025_AAI_251537_1 की खोली गई वित्तीय बोली ।

1. Financial bid of E-tender ID 2025_AAI_251537_1 opened on 19.11.2025.

महोदय / Dear Sir,

- उपर्युक्त कार्य के लिए आपकी ई-निविदा को भारतीय विमानपत्तन प्राधिकरण के अध्यक्ष की ओर से आपके द्वारा उद्धृत मद दरों पर स्वीकार किया जाता है, जिसका कुल योग 60,00,003/- रुपये (साठ लाख तीन रुपये मात्र) (जीएसटी को छोड़कर) है, जो निविदा में प्रस्तुत अनुमानित लागत 84,82,033/- रुपये से 21.47% कम है।

Your E-tender for the work mentioned above is hereby accepted on behalf of the Chairman, Airport Authority of India at the item rates quoted by you totaling to Rs. 60,00,003/- (Rs. Sixty Lakh and Three only) (Excluding GST) which is 21.47% below the estimated cost put to tender of Rs. 84,82,033/-.

- सहायक महाप्रबंधक (अभि-सिविल), भाविप्रा, सोलापुर एयरपोर्ट, सोलापुर - 413224 कार्य के प्रभारी अभियंता होंगे आपसे निवेदन है कि दिनांक 02/01/2026 तक सहायक महाप्रबंधक (अभि-सिविल), भाविप्रा, सोलापुर एयरपोर्ट, सोलापुर - 413224 के कार्यालय में उपस्थित हों तथा ठेके के करारनामे को पूरा करें। ठेके का करारनामा 500/- (रुपये पाँच सौ मात्र) के नॉन-ज्युडिशियल स्टैम्प पेपर पर निष्पादित किया जायेगा, तथा स्टैम्प पेपर का खर्चा आपके द्वारा वहन किया जायेगा।

अंजना
24/12/2025



भारतीय विमानपत्तन प्राधिकरण

AIRPORTS AUTHORITY OF INDIA

सोलापुर एयरपोर्ट, सोलापुर

SOLAPUR AIRPORT, SOLAPUR

Asst. Genereal Manager (Engg-Civil), AAI, Solapur Airport, Solapur - 413224 shall be Engineer-In-Charge of the work. You are requested to attend the office of Asst. Genereal Manager (Engg-Civil), AAI, Solapur Airport, Solapur - 413224 by date 02/01/2026 to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs. 500/- (Rupees Five Hundred Only) and the cost of the stamp paper shall be borne by you.

3. आपके निविदा के साथ प्राप्त अग्रिम धरोहर राशि रु. 2,54,461/- (रुपए दो लाख चौवन हजार चार सौ इकसठ मात्र) निविदा दस्तावेज के पृष्ठ GCC-16 पर दी गई शर्त 1 (A) के अनुसार प्रतिभूति जमा के रूप में प्रयुक्त तथा संपरिवर्तित किया जाएगा। सी.पी.पी. पोर्टल पर AOC होने पर उक्त राशि आपको पुनः देय हो जाएगी। कृपया इस पत्र के जारी होने की तिथि से 10 दिनों के भीतर पूर्ण जमानत राशि रु. 3,45,540/- (रुपये तीन लाख पैतालीस हजार पाँच सौ चालीस मात्र) जमा करना है, असफल होने पर पृष्ठ संख्या GCC 16 पर दी गई शर्त 1 (A) के अनुसार आपके चालू बिल से काट लिया जायेगा एवं AOC अग्रिम धरोहर राशि के मूल्य की जमानत राशि संग्रहीत होने पर ही किया जायेगा।

The earnest money amount of Rs. 2,54,461/- (Rupees Two Lakh Fifty Four Thousand Four Hundred and Sixty one only) received along with your tender will be treated and converted as part of Security Deposit as per condition of clause no. 1(A) on page GCC-16 of the contract document. The same shall be returned to you after doing AOC on CPP Portal. Please deposit amount of Rs. 3,45,540/- (Rupees Three Lakh Forty Five Thousand Five Hundred Forty only) towards security deposit within 10 days from the date of issue of this letter, failing which the same will be deducted from your running bill as per clause 1(A) on page GCC-16 of the contract document and AOC shall be done after accumulation of Security Deposit amount equal to EMD amount.

4. कृपया इस अवॉर्ड पत्र के जारी करने की तिथि से 30 दिनों के भीतर यानी 23.01.2026 को या उससे पहले अनुबंध दस्तावेज के जीसीसी के पृष्ठ संख्या 108 पर अनुलग्नक - XI में संलग्न प्रोफॉर्मा पर अनुसूचित वाणिज्यिक बैंक (अर्थात भारतीय या विदेशी बैंक जो भारतीय रिसर्व बैंक अधिनियम, 1934 की दूसरी अनुसूचित में शामिल है, सहकारी / क्षेत्रीय ग्रामीण बैंक को छोड़कर) से जारी अपरिवर्तनीय बीमा जमानत बॉन्ड, डिमांड ड्राफ्ट, बैंक गारंटी के रूप में रु. 2,10,000/- (रु. दो लाख दस हजार मात्र) की अतिरिक्त निष्पादन सुरक्षा राशि जमा करें, क्योंकि आपने अनुमानित लागत से 21.47% कम उद्धृत किया है।

Please deposit additional performance security amount of Rs. 2,10,000/- (Rupees Two lacs Ten thousand only) in form of an irrevocable Insurance Serety bond, demand draft, bank guarantee issued from scheduled commercial bank (i.e. Indian or Foreign Banks included in the second schedule of Reserve Bank of India Act, 1934 excluding Co-operative / Regional Rural Banks) on the Proforma appended at Annexure – XI on page 108 of GCC of Contract document within 30 days of date of issue of this award letter i.e. on or before 23.01.2026, as you have quoted 21.47% below estimated cost.

अंजलि
24/12/25



भारतीय विमानपत्तन प्राधिकरण

AIRPORTS AUTHORITY OF INDIA

सोलापुर एयरपोर्ट, सोलापुर

SOLAPUR AIRPORT, SOLAPUR

5. आपसे अनुरोध है कि ठेका श्रम (विनियमन और उन्मूलन) अधिनियम 1970 के प्रावधान का पालन करें और ठेका श्रम (विनियमन और उन्मूलन) केंद्रीय नियम 1971, बाल श्रम (निषेध और विनियमन) अधिनियम 1986, निर्माण श्रमिक (रोजगार का विनियमन और सेवा की शर्त) अधिनियम 1996, भवन एवं अन्य निर्माण श्रमिक कल्याण उपकर अधिनियम 1996 जैसा कि निविदा के जीसीसी के पृष्ठ संख्या 49 पर खंड 19 में और केंद्र और राज्य सरकार के नियम में निर्दिष्ट है।

You are requested to comply with the provision of Contract Labour (Regulation and Abolition) ACT 1970 and Contract Labour (Regulation and Abolition) Central Rules 1971, Child Labour (Prohibition & Regulation) Act 1986, Construction Workers (Regulation of Employment and Condition of Service) Act 1996, Building and other Construction Workers Welfare Cess Act 1996 as specified in Clause 19 at page no. 49 of GCC of tender and rules of Central and State Government.

6. आपको यह भी निर्देश दिया जाता है कि आप तुरंत सहा. माहप्रबंधक (अभी-सिविल), भाविप्रा, सोलापुर एयरपोर्ट, सोलापुर पर संपर्क करे वह आपको साईट सौंपने की व्यवस्था करेंगे।

You are also directed to contact Asst. General Manager (Engg.Civil), Solapur Airport immediately, who will arrange to hand over the site to you.

7. कृपया ध्यान दें कि कार्य पूरा करने के लिए 05 (पाँच) महिना है जो की इस पत्र जारी होने के 10वें दिन से गिना जाएगा।

Please note that the time allowed for carrying out the work shall be **05 (Five) Months** and same shall be reckoned from the 10th day after issue of this letter.

8. अनुबंध के संबंध में आगे कोई भी पत्राचार सामान्य रूप से प्रभारी अभियंता को संबोधित किया जाना चाहिए।

Any further correspondence in connection with the contract should normally be addressed to the Engineer-In-Charge.

9. कृपया रसीद की पावती दें और इसके साथ संलग्न इस पत्र की डुप्लीकेट प्रति हस्ताक्षर करने के बाद अधोहस्ताक्षरी को स्वीकृति के प्रतीक के रूप में लौटाएं।

Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

10. संदर्भ के तहत यह पत्र करारनामे का हिस्सा होगा।

This letter under reference shall form part of Agreement.

अंजली
24/12/25



भारतीय विमानपत्तन प्राधिकरण

AIRPORTS AUTHORITY OF INDIA

सोलापुर एयरपोर्ट, सोलापुर

SOLAPUR AIRPORT, SOLAPUR

11. हिंदी और अंग्रेजी संस्करण के बीच किसी भी विसंगति के मामले में, अंग्रेजी संस्करण मान्य होगा।

In case of any discrepancies between Hindi and English version, English version will prevail.

धन्यवाद /Thanking You,

भवदीय / Yours faithfully,

अंजनी
24/12/2025

(अंजनी कुमारी)

(Anjane Kumari)

सहायक महाप्रबंधक (अभि.-सिविल)

Asst. General Manager (Engg.-Civil)

सोलापुर हवाईअड्डा, सोलापुर

Solapur Airport, Solapur

कृते तथा ओर से अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण

For and on behalf of the Chairman, Airports Authority of India.

संलग्न :

1.01 BOQ Schedule



भारतीय विमानपत्तन प्राधिकरण

AIRPORTS AUTHORITY OF INDIA

सोलापुर एयरपोर्ट, सोलापुर

SOLAPUR AIRPORT, SOLAPUR

प्रतिलिपि :

1. अतिरिक्त आयुक्त आयकर, 15, होतगी रोड, साईनाथ नगर, सोलापुर, महाराष्ट्र - 413003
2. प्रादेशिक श्रम आयुक्त (केन्द्रीय), 1 कौल बिल्डिंग, गुरुनानक नगर, शंकर सेठ रोड, पुणे - 411042
3. क्षेत्रीय भविष्य निधि आयुक्त, सुरवासे टावर, 165-ए, रेल्वे लाइन, सोलापुर - 413001

आंतरिक :

1. क्षेत्रीय कार्यपालक निदेशक, पश्चिमी क्षेत्र, भा.वि.प्रा, रीजनल हेड क्वार्टर्स, मुंबई-400 099
2. महाप्रबंधक (अभियांत्रिकी), पश्चिमी क्षेत्र, भाविप्रा, रीजनल हेड क्वार्टर्स, मुंबई-400 099
3. महाप्रबंधक (सतर्कता), पश्चिमी क्षेत्र, भा.वि.प्रा, रीजनल हेड क्वार्टर्स, मुंबई-400 099
4. महाप्रबंधक (वित्त एवं लेखा), पश्चिमी क्षेत्र, भाविप्रा, रीजनल हेड क्वार्टर्स, मुंबई-400 099
5. विमानपत्तन निदेशक, सोलापुर एयरपोर्ट, सोलापुर
6. प्रबंधक (अभियांत्रिकी-विद्युत), सोलापुर एयरपोर्ट, सोलापुर
7. कार्य की फ़ाइल ।

अंजनी
24/12/25

(अंजनी कुमारी)

(Anjane Kumari)

सहायक महाप्रबंधक (अभि.-सिविल)

Asst. General Manager (Engg.-Civil)

सोलापुर हवाईअड्डा, सोलापुर

Solapur Airport, Solapur

कृते तथा ओर से अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण

For and on behalf of the Chairman,

Airports Authority of India.

Tender Inviting Authority: Asst. General Manager (Engg-Civil), Airports Authority of India, Solapur Airport, Solapur - 413224

Name of Work: Supply, Erection, Installation and Testing & Commissioning & Civil work of MBRR Based Underground Sewage Treatment plant to handle total domestic sewage of 28 KLD at Solapur Airport.

Contract No: AAI/SOLAPUR/AGM(E-C)/STP/2025-26 (Tender ID: 2025_AAI_261537_1)

Name of the Bidder/ Bidding Firm / Company : EAGLE ASSOCIATES

PRICE SCHEDULE

(This BoQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate	BASIC RATE in Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words
1	2	4	5	6	13	53	55
1.01	Earth work in excavation by mechanical means (hydraulic excavator/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. All kinds of soil	92.000	Cum		90.00	8280.00	INR Eight Thousand Two Hundred Eighty & Paise Zero Only
1.02	Earth work in excavation by mechanical means (hydraulic excavator/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. Ordinary Rock	92.000	Cum		130.00	11960.00	INR Eleven Thousand Nine Hundred Sixty & Paise Zero Only
1.03	Earth work in excavation by mechanical means (hydraulic excavator/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. Hard Rock (Blasting prohibited)	157.000	Cum		1145.00	179765.00	INR One Lakh Seventy Nine Thousand Seven Hundred Sixty Five & Paise Zero Only
1.04	Extra for every additional lift of 1.5 m or part thereof in excavation / dumping excavated or stacked materials. Ordinary or hard rock	278.000	Cum		291.00	80881.00	INR Eighty Thousand Eight Hundred Ninety Eight & Paise Zero Only
1.05	Carrriage of material by Mechanical Transport including loading,unloading and stacking Up to 2.0 Km	92.000	Cum		200.00	18400.00	INR Eighteen Thousand Four Hundred & Paise Zero Only
1.06	Carrriage of material by Mechanical Transport including loading,unloading and stacking Up to 2.0 Km	249.000	Cum		200.00	49800.00	INR Forty Nine Thousand Eight Hundred & Paise Zero Only
1.07	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (1 Cement : 3 coarse sand (zone-III) derived from natural sources : 6 graded stone aggregate 20 mm nominal size derived from natural sources)	42.400	Cum		4400.00	186560.00	INR One Lakh Eighty Six Thousand Five Hundred Sixty & Paise Zero Only
1.08	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	218.200	Cum		50.00	10910.00	INR Ten Thousand Nine Hundred Ten & Paise Zero Only
1.09	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6 coarse sand)	20.300	Cum		3000.00	60900.00	INR Sixty Thousand Nine Hundred & Paise Zero Only
1.1	Brick work with common burnt clay FPS (non modular) bricks of class designation 3.5 i superstructure above plinth level upto floor V level i all shapes and size in : Cement Mortar 1:6 (1 Cement : 6 Coarse Sand)	28.400	Cum		3000.00	85200.00	INR Eighty Five Thousand Two Hundred & Paise Zero Only
1.11	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete.	10.500	Sqm		450.00	4725.00	INR Four Thousand Seven Hundred Twenty Five & Paise Zero Only
1.12	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	2400.000	Kg		60.00	144000.00	INR One Lakh Forty Four Thousand & Paise Zero Only
1.13	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	500.000	Kg		60.00	30000.00	INR Thirty Thousand & Paise Zero Only

31/12/25
24/12/25

1.14	Centering and shuttering including strutting, propping etc. and removal of form for Lintel, beams, plinth beams, girders, bressumers and cantilevers	50,000 Sqm				150.00	7500.00	INR Seven Thousand Five Hundred & Paise Zero Only
1.15	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement. - All work up to plinth level : 1:1.5:3 (1 cement : 1.5 coarse sand (zone-II) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	24,000 Cum				4000.00	96000.00	INR Ninety Six Thousand & Paise Zero Only
1.16	Reinforced cement concrete work in walls (any thickness), including attached pillars, buttresses, plinth and string courses, fillers, columns, glass piers, abutments, posts and struts etc. above plinth level up to floor five level, excluding cost of centering, shuttering, finishing and reinforcement : 1:1.5:3 (1 cement : 1.5 coarse sand(zone-II) derived from natural sources, 3 graded stone aggregate 20 mm nominal size derived from natural sources)	5,000 Cum				400.00	2000.00	INR Two Thousand & Paise Zero Only
1.17	Making plinth protection 50mm thick of cement concrete 1:3:6 (1 cement : 3 coarse sand (zone-II) derived from natural sources : 5 graded stone aggregate 20 mm nominal size derived from natural sources) over 75mm thick bed of dry brick ballast 40 mm nominal size, well rammed and consolidated and grouted with lime sand, including necessary excavation, leveling & dressing & finishing the top smooth.	9,500 Sqm				400.00	3800.00	INR Three Thousand Eight Hundred & Paise Zero Only
1.18	12mm Cement Plaster of mix: 1 : 6 (1 Cement : 6 Coarse Sand)	40,000 Sqm				250.00	10000.00	INR Ten Thousand & Paise Zero Only
1.19	18mm cement plaster in two coats under 12mm thick cement plaster 1:5 (1 Cement : 5 coarse sand) finished with a top layer 8mm thick cement plaster 1:6 (1 Cement : 6 Fine sand)	40,000 Sqm				350.00	14000.00	INR Fourteen Thousand & Paise Zero Only
1.2	Providing and fixing Polyethylene-Aluminum- Polyethylene PE-AL-PE Composite Pressure Pipes conforming to IS : 15450, U.V. stabilized with carbon black having thermal stability for hot & cold water supply, capable to withstand temperature up to 80°C, including all special fittings of composite material (engineering plastic blend and brass inserts wherever required) e.g. elbows, tees, reducers, couplers & connectors etc., with trenching, refilling and testing of joints complete as per direction of the engineer in charge.	200,000 Meter				200.00	40000.00	INR Forty Thousand & Paise Zero Only
1.21	Providing and fixing Polyethylene-Aluminum- Polyethylene PE-AL-PE Composite Pressure Pipes conforming to IS : 15450, U.V. stabilized with carbon black having thermal stability for hot & cold water supply, capable to withstand temperature up to 80°C, including all special fittings of composite material (engineering plastic blend and brass inserts wherever required) e.g. elbows, tees, reducers, couplers & connectors etc., with trenching, refilling and testing of joints complete as per direction of the engineer in charge.	200,000 Meter				400.00	80000.00	INR Eighty Thousand & Paise Zero Only
1.22	Providing and fixing Polyethylene-Aluminum- Polyethylene PE-AL-PE Composite Pressure Pipes conforming to IS : 15450, U.V. stabilized with carbon black having thermal stability for hot & cold water supply, capable to withstand temperature up to 80°C, including all special fittings of composite material (engineering plastic blend and brass inserts wherever required) e.g. elbows, tees, reducers, couplers & connectors etc., with trenching, refilling and testing of joints complete as per direction of the engineer in charge.	200,000 Meter				500.00	100000.00	INR One Lakh & Paise Zero Only
1.23	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge.	200,000 Meter				450.00	90000.00	INR Ninety Thousand & Paise Zero Only
1.24	Dispersing with 1st quality acrylic distemper (ready mixed) having VOC content less than 50 gm/litre, of approved manufacturer, of required shade and colour complete, to achieve even shade and colour. New work (two or more coat) over and including wear thurable priming coat with cement primer having VOC content less than 50 gram/ litre.	46,500 Sqm				50.00	2325.00	INR Two Thousand Three Hundred Twenty Five & Paise Zero Only
1.25	Finishing walls with Acrylic Smooth exterior paint of required shade : New work (Two or more coat applied @ 1.67 lit/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm)	40,000 Sqm				70.00	2800.00	INR Two Thousand Eight Hundred & Paise Zero Only

21/01/25
24/1/25

1.26	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : Two or more coats on new work over an under coat of suitable shade With ordinary paint of approved brand and manufacture Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1.2.4 (1) Cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 40 mm nominal size derived from natural sources)	50,000 Sqm				100.00		5000.00	INR Five Thousand & Paise Zero Only
1.27	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1.2.4 (1) Cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 40 mm nominal size derived from natural sources)	20,000 Cum				5000.00		100000.00	INR One Lakh & Paise Zero Only
1.28	1.4.8 (1) Cement : 4 coarse sand (zone-III) derived from natural sources : 8 graded stone aggregate 40 mm nominal size derived from natural sources)	10,000 Cum				4800.00		48000.00	INR Forty Eight Thousand & Paise Zero Only
1.29	Constructing brick masonry circular type manhole 0.91 m internal dia at bottom and 0.56m dia at top in cement mortar 1:4 (1) cement : 4 coarse sand), inside cement plaster 12 mm thick with cement mortar 1:3 (1) cement : 3 coarse sand) finished with a floating coat of neat cement, foundation concrete 1:3:6 mix (1) cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size), and making necessary channel in cement concrete 1:2.4 (1) cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) finished with a floating coat of neat cement, all complete as per standard design : 0.91 m deep with S.F.R.C. cover and frame (heavy duty, HD-20 grade designation) 550 mm internal diameter conforming to IS, 12592, total weight of cover and frame to be not less than 182 kg, fixed in cement concrete 1:2.4 (1) cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) including centering, shuttering all complete. (Excavation, test tests and 12mm thick cement plaster at the external surface shall be paid for separately) : With common burnt clay F.P.S. (non modular) bricks of class designation 7.5	20,000 Each				5000.00		100000.00	INR One Lakh & Paise Zero Only
1.3	Extra depth for circular type manhole 0.91m internal dia (at bottom) beyond 0.91 m to 1.67 m With common burnt clay F.P.S. (non modular) bricks of class designation 7.5	20,000 Meter				500.00		10000.00	INR Ten Thousand & Paise Zero Only
1.31	Providing and fixing pressed steel door frames conforming to IS, 4351, manufactured from commercial mild steel sheet of 1.60 mm thickness, including hinges, jamb, lock jamb, bead and if required angle threshold of mild steel angle of section 50x25 mm, or base ties of 1.60 mm, pressed mild steel welded or rigidly fixed together by mechanical means, including M.S. pressed butt hinges 2.5 mm thick with mortar guards, lock strike-plate and shock absorbers as specified and applying a coat of approved steel primer after pre-treatment of the surface as directed by Engineer-in-charge: Profile C Fitting with adjustable lugs with split end ball to each jamb	30,000 Meter				200.00		6000.00	INR Six Thousand & Paise Zero Only
1.32	Providing and fixing factory made ISI marked steel glazed doors, windows and ventilators, side /top /centre hung, with brading and all members such as F7D, F4B, K11 B and K12 B etc. complete of standard rolled steel sections, joints mitred and flash butt welded and eash bars tenoned and riveted, including providing and fixing of hinges, pivots, including priming coat of approved steel primer, but excluding the cost of other fittings, complete all as per approved design. (sectional weight of only steel members shall be measured for payment). Fitting with 15x3 mm lugs 10 cm long embedded in cement concrete block 15x10x10 cm of C.C. 1:3:6 (1) Cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size)	600,000 Kg				55.00		33000.00	INR Thirty Three Thousand & Paise Zero Only
1.33	Steel work in built up tubular (round, square or rectangular hollow tubes etc.), trusses etc., including cutting, hoisting, fitting in position and applying a priming coat of approved steel primer, including welding and bolting with special shaped washers etc. complete. Hot finished welded type tubes	500,000 Kg				85.00		42500.00	INR Forty Two Thousand Five Hundred & Paise Zero Only
1.34	Providing and fixing precasted galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm (+ 0.05 %) in 240 mpa steel grade, S-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal /vertical or curved surfaces, excluding the cost of pulfins, rafters and Trusses and including cutting to size and shape wherever required.	14,000 Sqm				500.00		7000.00	INR Seven Thousand & Paise Zero Only

315106
24/12/25

1.35	Providing and fixing G.I. chain link fabric fencing of required width in mesh size 50x50 mm including strengthening with 2 mm dia wire or nuts, bolts and washers as required complete as per the direction of Engineer-in-charge. Made of G.I. wire of dia. 4 mm, PVC coated to achieve outer dia not less than 5 mm in required colour and shade	240,000	Sqm			600.00	144000.00	INR One Lakh Forty Four Thousand & Paise Zero Only
1.36	Providing and laying non-pressure NP22 class (light duty) R.C.C. pipes with collars joined with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete : 300 mm dia. R.C.C. pipe	300,000	Meter			700.00	210000.00	INR Two Lakh Ten Thousand & Paise Zero Only
1.37	Earth work in excavation by mechanical means (hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, for all lift, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.	90,000	Cum			150.00	13500.00	INR Thirteen Thousand Five Hundred & Paise Zero Only
1.38	Excavation work by mechanical means (hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m. Ordinary rock	60,000	Cum			200.00	12000.00	INR Twelve Thousand & Paise Zero Only
1.39	Providing and fixing Polyethylene-Aluminum- Polyethylene PE-AL-PE Composite Pressure Pipes conforming to IS : 15450, U.V. stabilized with carbon black having thermal stability for hot & cold water supply, capable to withstand temperature up to 80°C, including all special fittings of composite material (engineering plastic blend and brass inserts wherever required) e.g. elbows, tees, reducers, couplers & connectors etc., with trenching, refilling and testing of joints complete as per direction of the engineer in charge. 1250 (20 mm OD) pipe	300,000	Meter			400.00	120000.00	INR One Lakh Twenty Thousand & Paise Zero Only
1.4	Providing and fixing Polyethylene-Aluminum- Polyethylene PE-AL-PE Composite Pressure Pipes conforming to IS : 15450, U.V. stabilized with carbon black having thermal stability for hot & cold water supply, capable to withstand temperature up to 80°C, including all special fittings of composite material (engineering plastic blend and brass inserts wherever required) e.g. elbows, tees, reducers, couplers & connectors etc., with trenching, refilling and testing of joints complete as per direction of the engineer in charge. 1216 (16 mm OD) pipe	200,000	Meter			200.00	40000.00	INR Forty Thousand & Paise Zero Only
1.41	Providing and applying integral crystalline slurry of hydrophilic in nature for waterproofing treatment to the RCC structures like retaining walls of the basement, water tanks, roof slabs, podiums, reservoir, sewerage & water treatment plant, tunnels / subway and bridge deck etc., prepared by mixing in the ratio of 5 : 2 (5 parts integral crystalline slurry : 2 parts water) for vertical surfaces and 3 : 1 (3 parts integral crystalline slurry : 1 part water) for horizontal surfaces and applying the same from negative (internal) side with the help of synthetic fiber brush. The material shall meet the requirements as specified in ACI-212.3R-2010 i.e by reducing permeability of concrete by more than 90% compared with control concrete as per DIN 1048 and resistant to 16 bar hydrostatic pressure on negative side. The crystalline slurry shall be capable of self-healing of cracks up to a width of 0.50 mm. The work shall be carried out all complete as per specification and the direction of the engineer-in-charge. The product performance shall carry guarantee for 10 years against any leakage. For vertical surface two coats @ 0.70 kg per sqm per coat	20,000	Sqm			400.00	8000.00	INR Eight Thousand & Paise Zero Only

Original
24/12/25

1.42	Providing and applying integral crystalline slurry of hydrophilic in nature for waterproofing treatment to the RCC structures like retaining walls, of the basement, water tanks, roof slabs, podiums, reservoir, sewage & water treatment plant, tunnels / subway and bridge deck etc., prepared by mixing in the ratio of 5 : 2 (5 parts integral crystalline slurry - 2 parts water) for vertical surfaces and 3 : 1 (3 parts integral crystalline slurry : 1 part water) for horizontal surfaces and applying the same from negative (internal) side with the help of synthetic fiber brush. The material shall meet the requirements as specified in ACl-212-3R-2010 i.e by reducing permeability of concrete by more than 90% compared with control concrete as per DIN 1048 and resistant to 16 bar hydrostatic pressure on negative side. The crystalline slurry shall be capable of self-healing of cracks up to a width of 0.50 mm. The work shall be carried out all complete as per specification and the direction of the engineer-in-charge. The product performance shall carry guarantee for 10 years against any leakage. For horizontal surface one coat @ 1.10 kg per sqm.	19,020 Sqm	400.00	7608.00 INR Seven Thousand Six Hundred Eight & Paise Zero Only
1.43	Centering and shuttering including strutting, propping etc. and removal of form for Foundations, footings, bases of columns, etc. for mass concrete	1,800 Sqm	200.00	360.00 INR Three Hundred Sixty & Paise Zero Only
1.44	Centering and shuttering including strutting, propping etc. and removal of form for Walls (any thickness) including attached plasters, buttresses, plinth and string courses etc.	40,000 Sqm	350.00	14000.00 INR Fourteen Thousand & Paise Zero Only
1.45	Centering and shuttering including strutting, propping etc. and removal of form for Suspended floors, roofs, landings, balconies and access platform	1,800 Sqm	300.00	540.00 INR Five Hundred Forty & Paise Zero Only
1.46	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	500,000 Kg	75.00	37500.00 INR Thirty Seven Thousand Five Hundred & Paise Zero Only
1.47	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	500,000 Kg	75.00	37500.00 INR Thirty Seven Thousand Five Hundred & Paise Zero Only
1.48	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, IS : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank.	5000,000 per litre	5.50	27500.00 INR Twenty Seven Thousand Five Hundred & Paise Zero Only
1.49	Supplying and Filling with Sand/ aggregate of size between 4.5 mm to 12.5 mm surrounding Underground STP tank including watering, ramming, consolidating and dressing complete as per direction of EIC.	18,500 Cum	800.00	14880.00 INR Fourteen Thousand Eight Hundred Eighty & Paise Zero Only
1.50	Supply, installation, commissioning of 25 KLD capacity underground compact portable, ready to install type STP as per following technical specifications, terms and conditions. The process of sewage treatment plant shall be MBBR and compartments included in separation & sedimentation tank, Anaerobic Chamber, Aerobic Chamber and sedimentation chamber. Specifications and materials include in 25 KLD capacity Compact STP (MBBR Type) :- a) Air Blower with accessories for STP - 2 no (54 m3/Hr Each, 2 HP Each) - (1W+1S) b) Raw Sewage Lift Pump (No dog submersible)- 2nos - (9.00 m3/Hr, Head 10 m, 1.00 HP & Kridoskar/Equivalent) - (1W+1S) c) Filter Feed Pump 02no's - (2 m3/Hr, Head 22 m, 2 HP & Kridoskar/Equivalent) - (1W+1S) d) Plumbing & Misc. Erection & Commissioning Material -Up to 5 meters length, As per requirement. e) Relay based Electrical Control Panel (Automated):-TBD as per requirement. f) Pressure Sand Filter (PSF) with Media & Accessories:-1 no.- 16" Diam, X 65" HOS & FRP. g) Activated Carbon Filter (ACF) with Media & Accessories:-1 no.- 16" Diam, X 65" HOS & FRP. h) Bar Screen (Mesh) 0.5x0.5, FRP i) Underground tank of 25000 lit/day capacity of FRP j) FRP underground tank of intermediate cum treated water tank of capacity 10000 lit k) Recirculation pump - 01 no, 9.0m3/hr capacity, 1.00HP, 10m head, non-dog submersible l) Chlorine (Sodium Hypochlorite dosing) system	1,000 job	3050000.00	3050000.00 INR Thirty Lakh Fifty Thousand & Paise Zero Only
2	Electrical Works			

31.10.25
24.11.25
24.11.25 (2188-18)

2.01	Execution of any item of work as per CPWD Delhi Schedule of Rates (EAM)-2022. (If quoted rate is same as per DSR EAM 2022 item rates, the value is 1. If quoted rate is 10% below DSR EAM 2022 item rates, the value should be 0.9 If quoted rate is 10% above DSR EAM 2022 item rates, the value should be 1.1)	500000.000	Percentage		0.60	300000.00	INR Three Lakh & Paise Zero Only
2.02	Supply of following size of XLPE insulated & PVC sheathed, armoured aluminium conductor under ground cable of 1.1KV grade as per IS 7098:1988 Part-I with upto date amendments complete as required. 4C x 70 Sq.mm	100.000	Metre		140.00	14000.00	INR Fourteen Thousand & Paise Zero Only
2.03	Supply of Aluminium Tiltable tower ladder with bucket type type having reach height of 40-50 FOOT and weight capacity of minimum 170 kg	1.000	Each		245000.00	245000.00	INR Two Lakh Forty Five Thousand & Paise Zero Only
2.04	Supply of Aluminium platform step ladder Step on one side and rung on the other side of total extended height of 15 FEET and weight capacity of minimum 200 kg.	2.000	Each		16146.00	32292.00	INR Thirty Two Thousand Two Hundred Ninety Two & Paise Zero Only
Total in Figures						6000003.00	INR Sixty Lakh Three & Paise Zero Only
Quoted Rate in Words						INR Sixty Lakh Three & Paise Zero Only	

राजेश
 अ. स. प्र. (प्रति-प्र)
 29/10/25

Signature Not Verified

Digitally signed by ANJANEI KUMARI
 Date: 2026.02.11 18:42:52 IST
 Location: eProcurement System for Central PSUs