

Ref. No: AAI/IMP/CIVIL/Redevelopment works /W.O.18 /2025 -26/249 Date: 01/12/2025

To,
M/s R.K. Fortune Developers Pvt. Ltd.
Changangei Awang Leikai,
Imphal West, Manipur- 795140
Bid ID: 923566

Sub: - Letter of Award – Miscellaneous Redevelopment works of Passenger Toilet Blocks at Imphal Airport.

Ref: 1) Your E- tender opened on 19/11/2025
2) Your letter no. NIL dated: 05/11/2025

Dear Sir (s),


1. Your e-tender for the work mentioned above is hereby accepted on behalf of Chairman, Airports Authority of India, at the Item rate quoted by you totaling to Rs. 1,24,89,407/- (Ex. GST) which is 28.92% below the estimated cost and which is 16.69% below the justification cost.
2. Senior Manager (Engg-Civil), AAI, Imphal Airport, shall be the Engineer-in-charge of the work. You are requested to attend the office of Senior Manager (Engg-Civil), AAI, Imphal Airport by **08/12/2025** to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs.100 (Rupees One hundred only) and the cost of the stamp paper shall be borne by you.
3. The earnest money amount of Rs. 5,27,162/- (Rupees Five Lakh Twenty Seven Thousand One Hundred Sixty Two only) received along with your tender will be treated and converted as part of Security deposit as per Clause No.1 (a) on page no: 16 of contract document. Please deposit Rs. 7,21,779/- (Rupees Seven Lakh Twenty One Thousand Seven Hundred Seventy Nine only) towards security deposit within 10 days from the date of issue of this letter failing which, the same will be deducted from running bills as per condition of Clause no1(a) at page no: 16 of the contract document.
4. Within 30 days of issue of acceptance letter, you shall submit to AAI, additional performance security as per condition of clause 1b of GCC for an amount of Rs. 9,91,660/- (Rupees nine lakh ninety one thousand six hundred and sixty only) in the form of irrevocable insurance surety bond, demand draft, bank guarantee issued from scheduled commercial bank.
5. You are requested to comply with the Provision of Contract Labour (Regulation and Abolition) Act 1970 and Contract Labour (Regulation and Abolition) Central Rules 1971 Child Labour (Prohibition & Regulation) Act 1986, Construction Workers (Regulation of Employment and Condition of Service) Act 1996, Building and other construction Workers Welfare Cess Act 1996 as specified in of GCC of tender and Rules of Central and State Government.
6. You are also directed to contact Senior Manager (Engg-Civil), AAI, Imphal Airport, immediately who will arrange to hand over the site to you.

Page-1

7. Please note that the time allowed for carrying out the work shall be **10 (Tenth) months** and same shall be reckoned from the 10th day after issue of this letter.
8. Any further correspondence in connection with the contract should normally be addressed to the Engineer-in-charge.
9. This Work order is allotted the number: **AAI/IMP/CIVIL/Redevelopment works /W.O.18 /2025 -26** which shall be quoted by you for all future correspondence in connection with this work.
10. Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

Encl: Schedule -A

Yours faithfully,



(M. Rajalakshmi)

Senior Manager (E-C)

For and on behalf of the Chairman
Airports Authority of India

SCHEDULE -"A"

Name of Work: Miscellaneous Redevelopment works of Passenger Toilet Blocks at Imphal Airport.

Sl. No	Description of Work / Item(s)	No.of Qty	Units	Rate	Amount
1	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge.	4.00	cum	2111.23	8444.92
2	Dismantling doors, windows and clerestory windows (steel or wood) shutter, cubicles including chowkhats, architrave, holdfasts etc. complete and stacking within 50 metres lead : Of area 3 sq. metres and below	50.00	each	376.29	18814.50
3	Dismantling W.C. Pan, wash basin, urinal etc including fixture of all sizes including disposal of dismantled materials i/c malba all complete as per directions of Engineer-in- Charge.	81.00	each	137.42	11131.02
4	Dismantling aluminium/ Gypsum partitions, doors, windows, fixed glazing and false ceiling including disposal of unserviceable surplus material and stacking of serviceable material with in 50 meters lead as directed by Engineer-in-charge.	292.00	sqm	57.74	16860.08
5	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead. For thickness of tiles 10 mm to 25 mm	283.00	sqm	75.22	21287.26
6	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer in - charge. Nominal concrete 1:4:8 or leaner mix (i/c equivalent design mix)	30.00	cum	1540.81	46224.30

Sl. No	Description of Work / Item(s)	No.of Qty	Units	Rate	Amount
7	Excavating trenches of required width for pipes, cables, etc including excavation for sockets, and dressing of sides, ramming of bottoms, depth upto 1.5 m, including getting out the excavated soil, and then returning the soil as required, in layers not exceeding 20 cm in depth, including consolidating each deposited layer by ramming, watering, etc. and disposing of surplus excavated soil as directed, within a lead of 50 m : Pipes, cables etc. exceeding 80 mm dia. but not exceeding 300 mm dia	440.00	meter	360.86	158778.40
8	Providing and laying Non Pressure NP-4 class (Heavy duty) R.C.C. pipes including collars/spigot jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete 450 mm dia RCC pipes.	110.00	meter	3129.11	344202.10
9	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. 20 mm nominal outer dia Pipes	400.00	mtr	363.78	145512.00
10	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. 25 mm nominal outer dia Pipes	400.00	mtr	411.49	164596.00

Sl. No	Description of Work / Item(s)	No.of Qty	Units	Rate	Amount
11	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. 32 mm nominal outer dia Pipes	40.00	mtr	531.59	21263.60
12	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. 40 mm nominal outer dia Pipes	400.00	mtr	720.35	288140.00
13	Providing and fixing uplasticised PVC connection pipe with brass unions : 45 cm length 15 mm nominal bore	77.00	each	100.17	7713.09
14	Providing and fixing C.P. brass long body bib cock of (Jaquar make or equivalent) approved quality conforming to IS standards and weighing not less than 690 gms. 15 mm nominal bore	18.00	each	1172.79	21110.22
15	Providing and fixing C.P. brass angle valve (Jaquar make or equivalent) for basin mixer and geyser points of approved quality conforming to IS:8931 as per direction of Engineer-in-charge. 15mm nominal bore	94.00	each	823.94	77450.36

Sl. No	Description of Work / Item(s)	No.of Qty	Units	Rate	Amount
16	Providing and laying Polished Granite stone flooring in required design and patterns, in linear as well as curvilinear portions of the building, all complete as per the architectural drawings, with 18 mm thick stone slab over 20 mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand), laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade, including rubbing, curing and polishing etc. all complete as specified and as directed by the Engineer-in-Charge. Polished Granite stone slab colour of Black, Cherry/RubyRed or equivalent	300.00	sqm	4592.19	1377657.00
17	Providing and laying vitrified tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shade, in skirting, riser of steps, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand), including grouting the joints with white cement and matching pigments etc. complete as per direction of Engineer-in-charge. Size of Tile 600x600 mm	856.00	sqm	1663.21	1423707.76

Sl. No	Description of Work / Item(s)	No.of Qty	Units	Rate	Amount
18	Providing and fixing tiled false ceiling of specified materials of size 595x595 mm in true horizontal level, suspended on inter locking metal grid of hot dipped galvanized steel sections (galvanized @ 120 grams/ sqm, both side inclusive) consisting of main "T" runnerwith suitably spaced joints to get required length and of size 24x38 mm made from 0.30 mm thick (minimum) sheet, spaced at 1200 mm center to center and cross "T" of size 24x25 mm made of 0.30 mm thick (minimum) sheet, 1200 mm long spaced between main "T" at 600 mm center to center to form a grid of 1200x600 mm and secondary cross "T" of length 600 mm and size 24x25 mm made of 0.30 mm thick (minimum) sheet to be interlocked at middle of the 1200x600 mm panel to form grids of 600x600 mm and wall angle of size 24x24x0.3 mm and laying false ceiling tiles of approved texture in the grid including, required cutting/making, opening for services like diffusers, grills, light fittings, fixtures, smoke detectors etc. Main "T" runners to be suspended from ceiling using GI slotted cleats ofsize 27 x 37 x 25 x1.6 mm fixed to ceiling with 12.5 mm dia and 50 mm long dash fasteners, 4 mm GI adjustable rods with galvanised butterfly level clips of size 85 x 30 x 0.8 mm spaced at	283.00	sqm	2119.94	599943.02
19	Providing and fixing water closet squatting pan (Indian type W.C. pan) with 100 mm sand cast Iron P or S trap, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever) conforming to IS:7231, wih all fittings and fixtures complete , including cutting and making good the walls and floors wherever required. White Vitreous china Orissa pattern W.C. Pan of size 580x440 mm with integral type of foot rests.	18.00	each	6934.85	124827.30

Sl. No	Description of Work / Item(s)	No.of Qty	Units	Rate	Amount
20	Providing and fixing of modular toilet cubicles consisting of high pressure 12 mm thick compact laminate board (merino or equivalent) as per IS 20146 and as per fire retardant BS-476/97 standards with phenolic core panels for partitions of intermediate divider, doors and pilasters. The cubicle shall have dimensions of 1500mm depth x 900mm width x 2000mm height with a door size of minimum head rail on top of panels and panels shall be fixed on the floor with a clearance of maximum 150mm using stainless steel satin finish adjustable legs screwed to the floor included stainless steel (SS) lock set, SS door knob, SS gravity self closing hinge, SS coat hook with door stopper, SS U channel, SS head rail, SS adjustable foot, SS tabular holder, SS head rail wall bracket, SS head rail corner connection and SS noise reducing tape, etc. all complete as per direction of Engineer in charge.	47.00	each	40441.83	1900766.01
21	Providing and fixing of CP Brass toilet paper holder with flap guard (Jaquar Cat no. ACN-CHR-1153S/Cera/Kohlar or equivalent i/c fixing with brass screws complete as per direction of Engineer in-Charge.	50.00	each	100.98	5049.00

Sl. No	Description of Work / Item(s)	No.of Qty	Units	Rate	Amount
22	Providing & fixing of white vitreous China cascade type water closet (American Standard Cat No. TF-3128 / Kohler Cat No. K-18131X-O / Hindware cat. no. 270409 /Roca Cat No. R038046+R039046 / Cera cat No. 2058/Jaquar Cat no. CNS-WHT-755S220SPPZ or approved equivalent) with CP bolts, nuts, CI chair hanging arrangements, bakelite seat & cover with CP hinges & rubber buffers, CP brass screw, washer with all accessories with WC connector with Rubber Lip / Buffer and side gap filled with silicon sealant wherever required with concealed type dual flush cistern (Hindware cat no. 506743 + 506751 / Grohe Cat No. 38661 / Kohler cat no. K-4178 / Roca Cat No. R490299+R490128 /Cera cat No. 2607 or approved equivalent) comprising of actuator button facia assembly including brass / SS screws and washer complete including cutting, making good the walls, floors, slab wherever required as per direction of Engineer-Incharge.	32.00	each	9867.12	315747.84
23	Providing and fixing of following C.P. Brass fittings and fixture of approved make completer as per direction Engineer in charge. Chromium plated anti cockrage Jali of approved make of 100 mm dia fixing over water outlet complete as per direction and satisfaction of Engineer-in-charge	79.00	each	477.33	37709.07
24	Providing and fixing of following C.P. Brass fittings and fixture of approved make completer as per direction Engineer in charge. P/F two way Bib cock 15mm nominal bore of approved make (Jaquar Cat no. LYR-CHR-38041 / Cera or equivalent) complete as per direction of Engineer-in-charge.	32.00	each	9884.93	316317.76
25	Providing and fixing CP Brass 32mm size Bottle Trap of approved quality & make and as per the direction of Engineer-in-charge.	36.00	each	1366.26	49185.36

Sl. No	Description of Work / Item(s)	No.of Qty	Units	Rate	Amount
26	Providing and fixing mirror of superior glass (of approved quality) and of required shape and size with wooden beading frame of approved make and shade with 12 mm thick plyboard backing all complete as per direction of Engineer in charge.	32.00	sqm	1671.04	53473.28
27	P/F health faucet of make Cera model no. F8030101/ Jaquar Cat no. ALD-CHR-573 or Equivalent ABS body with wall hook and 1 meter PVC hose pipe or equivalent as per direction of Engineer-in- charge.	32.00	each	1090.62	34899.84
28	Providing and fixing table top wash basin (Ivory colour) of make Cera Model CASKET (Code no. S2020108) / parry ware/ hindware/Jaquar Cat no. KUS-WHT-35935 of size 565X425X140 mm including painting of fittings and brackets, cutting and making good the walls wherever require all completer as per direction of Engineer-in-charge.	43.00	each	7292.21	313565.03
29	Providng and fixing stainless steel soap dispenser in the toilets/Terminal Building etc. Complete as per direction of Engineer-in-charge. Stainless steel Soap dispenser -800ml capacity (model no. ES81A Euronics make / Kohlar or equivelant)	45.00	each	3445.91	155065.95
30	Providng and fixing stainless steel swing PRM grab bar in the toilets/Terminal Building etc. Complete as per direction of Engineer-in-charge. Stainless steel swing handicap grab bar (model no. EGR (S02) Euronics make or equivelant)	4.00	each	5121.43	20485.72
31	Providng and fixing stainless steel PRM grab rail in the toilets/Terminal Building etc. Complete as per direction of Engineer-in-charge. Stainless steel handicap grab rail 600mm length, 32mm dia (model no. EGR 1-600mm) Euronics make / Kohlar or equivelant)	4.00	each	1658.34	6633.36

Sl. No	Description of Work / Item(s)	No.of Qty	Units	Rate	Amount
32	Supplying of WASHROOM PANEL/RECESSED/S.STEEL (3IN1) MANUAL PAPER DISPENSER / HIGH SPEED HAND DRYER / WASTE RECEPTACLE), Capacity : 600 C-Fold or 800 Multi Fold Paper Towel, Hand Dryer : 1350W, Waste Container : 18-8, Type-304, Stainless Steel, Capacity : 21 Litres Wall Opening Required : 315mm (W) x 1665mm (H) x 126mm (D) in the toilets/Terminal Building etc. Complete as per direction of Engineer-in-charge. KMR2N, Recess Panel (Euronics make / Kohlar or equivalent)	16.00	each	38156.01	610496.16
33	Providing and fixing stainless steel wall mounted waste receptacle in the toilets/Terminal Building etc. Complete as per direction of Engineer-in-charge. Stainless steel wall mounted waste receptacle (model no. KINOX (KWR) Euronics make / Kohlar or equivalent)	47.00	each	6126.89	287963.83
34	Providing, supplying and fixing 12mm clear toughened glass of Saint Gobain or equivalent with necessary fittings with stainless steel cover and the glass should be fixed to the wall including filling the gaps with silicon sealant complete in all respects as per the directions of Engineer-in-charge.(Fittings should be of make of DORMA/OZONE or Equivalent)	23.00	sqm	2917.04	67091.92
35	P/F Gurware/Avery dennison/3M film on glass panes after thoroughly cleaning of existing surface all complete as per direction and satisfaction of Engineer in charge. a) Designer printed coloured film high quality graphics on self adhesiv vinyl Note: The sample of film shall be got approved by the Engineer - in charge. The agency shall give minimum 03 years warranty of the film.	23.00	sqm	1056.26	24293.98

Sl. No	Description of Work / Item(s)	No.of Qty	Units	Rate	Amount
36	Providing and fixing 19mm thick water proof marine plywood of Centuray /Merino/Greenply make or equivalent conforming to IS: 710 on the wooden frame work with necessary screws and nails e.t.c ., complete as per the directions of Engineer in Charge.	108.00	sqm	3501.19	378128.52
37	Providing and fixing of acrylic solid surface Hanex/Corian dupont/Samsung staron/LG Hausys HIMACS make 12mm thick as per specifications, colour, shape and size as per drawing/design approved. Fixed to 12mm thick or thicker ply with silicon sealant inclusive of all bending, moulding, jointing, adhesive polishing etc., complete as per the directions of Engineer in charge. (sample, shade and series shall be approved by EIC)	81.00	sqm	13052.33	1057238.73
38	Credit for taking away old dismantled C.P. Brass bib cock, bottle trap, Pillar cock, health faucet, toilet paper holder and similar C.P. Brass items including loading from as and where basis all complete.	72.00	Kg	0.00	0.00
39	Credit for taking away old dismantled flush door, laminated board cubicle and similar wooden items including loading from as and where basis all complete.	50.00	each	0.00	0.00
40	Credit for taking away old dismantled G.I. Angles, G.I. pipes and similar items including loading from as and where basis all complete.	300.00	kg	0.00	0.00
41	Providing and fixing half stall back electronic flushing system (EFS) OF CERA make model no S4010102 / parryware / kohlar/Jaquar Cat no.URS-WHT-13253N & Jaquar Cat no. SNR-STL-51087 or equivalent i/c battery operated sensor, cp brassbottle trap all complete as per direction of engineer in charge.	36.00	each	13809.04	497125.44

Sl. No	Description of Work / Item(s)	No.of Qty	Units	Rate	Amount
42	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes. 110 mm diameter	800.00	mtr	386.74	309392.00
43	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes. 75 mm diameter	300.00	mtr	254.96	76488.00
44	Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion. Single tee without door 110x110x110 mm	50.00	each	226.84	11342.00
45	Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion. Single tee without door 75x75x75 mm	50.00	each	147.87	7393.50
46	Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion. Bend 87.5° 110 mm bend	32.00	each	154.06	4929.92

Sl. No	Description of Work / Item(s)	No.of Qty	Units	Rate	Amount
47	Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion. Bend 87.5° 75 mm bend	32.00	each	108.53	3472.96
48	Providing and fixing urinal partition made up to 10mm thick toughened frosted glass of size 1050 mm length 450 mm width one side and 300 mm other side with edge moulding & polishing.	36.00	each	1819.69	65508.84
49	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete : 150 x 10 mm	6.00	each	84.54	507.24
50	Providing and fixing S.S handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete : 125 mm	6.00	each	67.97	407.82
51	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. Brass pillar taps, 32 mm C.P. brass waste of standard pattern, including white vitreous china pedestal, painting of fittings and brackets, cutting and making good the walls wherever require: White Vitreous China Wash basin size 540 x 400 mm with a single 15 mm C.P. brass pillar tap.	2.00	each	1925.50	3851.00
52	Providing and fixing ISI marked flush door shutters conforming to IS : 2202 (Part I) decorative type, core of block board construction with frame of 1st class hard wood and well matched teak 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters. 25 mm thick including ISI marked Stainless Steel butt hinges with necessary screws.	7.00	sqm	288.91	2022.37

Sl. No	Description of Work / Item(s)	No.of Qty	Units	Rate	Amount
53	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately). Sal wood	1.00	cum	119403.38	119403.38
54	Providing and fixing 8 mm dia C.P. / S.S. Jet with flexible tube upto 1 metre long with S.S. triangular plate to European type W.C. of quality and make as approved by Engineer - in - charge.	32.00	each	357.80	11449.60
55	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand (zone-III) : 4 graded stone aggregate 20 mm nominal size).	48.00	cum	8073.46	387526.08
56	Constructing brick masonry manhole in cement mortar 1:4 (1 cement : 4 coarse sand) with R.C.C. top slab with 1:1.5:3 mix (1 cement : 1.5 coarse sand (zone-III) : 3 graded stone aggregate 20 mm nominal size), foundation concrete 1:4:8 mix (1 cement : 4 coarse sand (zone-III) : 8 graded stone aggregate 40 mm nominal size), inside plastering 12 mm thick with cement mortar 1:3 (1 cement : 3 coarse sand) finished with floating coat of neat cement and making channels in cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) finished with a floating coat of neat cement complete as per standard design : Inside size 90x80 cm and 45 cm deep including C.I. cover with frame (light duty) 455x610 mm internal dimensions, total weight of cover and frame to be not less than 38 kg (weight of cover 23 kg and weight of frame 15 kg) With common burnt clay F.P.S. (non modular) bricks of class designation 7.5	16.00	each	13086.58	209385.28

Sl. No	Description of Work / Item(s)	No.of Qty	Units	Rate	Amount
57	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	1512.00	Kg	176.87	267427.44
				Total	1,24,89,407.00

(Rupees One Crore Twenty Four Lakh Eighty Nine Thousand Four Hundred Seven Only)

Senior Manager (E-C)
AAI, Imphal Airport