

सन्दर्भ सं०: भा.वि.प्रा/वारा/अभियंत्रण/आकस्मिक मरम्मत /डब्लू.ओ-124/

दिनांक: 11.12.2025

Ref. No.: AAI/VNS/ENGG/Contingent repair/ WO-124/774-84/9680-90

Date: 11.12.2025

सेवा में,

मेसर्स माँ शारदा इन्टरप्राइजेज,
भुपतपट्टी, मुरादगन्ज,
जौनपुर-222002

M/s Maa Sharda Enterprises,
Bhupatpatti, Muradganj,
Jaunpur-222002

विषय: वर्ष 2025-26 के दौरान ला.ब.शा.अं हवाई अड्डा वाराणसी में आकस्मिक मरम्मत कार्य।
Contingent repair works at LBSI Airport, Varanasi during year 2025-26.
(Tender ID : 2025_AAI_254329_1)

संदर्भ : ई-निविदा खुलने की तिथि : 03.12.2025

प्रिय महोदय/Dear Sir,

- 1) उपरोक्त कार्य की, कुल निविदा रकम रुपये 74,06,037.25 (रुपया चौहत्तर लाख छः हजार सैतीस एवं पचीस पैसे मात्र) (जी.एस.टी. रहित) की मद दर निविदा, जो कि कार्य की अनुमानित लागत रुपये 76.53 लाख (जी.एस.टी. रहित) से 3.23% (तीन दशमलव दो तीन प्रतिशत) कम है, आपके द्वारा निविदा प्रपत्र की अनुसूची 'अ' में दर्शायी गयी मद दरों पर भरी गई है, अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से स्वीकृत की जाती है।

Your tender for the work mentioned above is hereby accepted on behalf of the Chairman, Airports Authority of India at the net tender amount Rs. 74,06,037.25 (Rupees Seventy Four Lakhs Six Thousand Thirty Seven point Two Five only) (excluding GST) which is 3.23% (Threepoint Nine Five percent) below to the estimated cost put to tender of Rs. 76.53 lakhs (excluding GST).

- 2) उप महा प्रबन्धक (अभि०-सिविल), भा.वि.प्रा., लाल बहादुर शास्त्री अन्तर्राष्ट्रीय विमानपत्तन, वाराणसी इस कार्य के कार्य प्रभारी अभियन्ता होंगे। आपसे अनुरोध है कि दिनांक 21.12.2025 तक उप महा प्रबन्धक (अभि०-सिविल) के कार्यालय में उपस्थित होकर संविदा अनुबन्ध को हस्ताक्षरित कर पूर्ण करें। अनुबन्ध 100/- रुपये के गैर न्यायिक स्टाम्प पेपर पर सम्पादित किया जाएगा, स्टाम्प पेपर की कीमत आपके द्वारा वहन की जाएगी।

The DGM (Engg-Civil), AAI, Lal Bahadur Shastri International Airport, Varanasi shall be the Engineer-in-charge of the work. You are requested to attend the office of the DGM (Engg-Civil) by 21.12.2025 to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs. 100/- and the cost of stamp paper shall be borne by you.

- 3) धरोहर राशि रुपये 2,29,590.00 (रुपया दो लाख उन्तीस हजार पॉच सौ नब्बे मात्र) संविदा प्रपत्र के अनुच्छेद 1ए पेज 16 के अनुसार प्रतिभूति निक्षेप राशि का हिस्सा मानकर उसमें बदल दिया जाएगा। कृपया शेष प्रतिभूति निक्षेप राशि रुपये 5,11,014.00 (रुपया पाँच लाख इग्यारह हजार चौदह मात्र) इस पत्र के निर्गत दिनांक से दस दिनों के भीतर जमा करें अन्यथा उक्त धनराशि की कटौती संविदा प्रपत्र की उक्त संदर्भित शर्त के अनुसार चालू लेखा बिलों से की जाएगी।

The earnest money amount of Rs. 2,29,590.00 (Rupees Two Lakh Twenty Nine Thousand Five Hundred Ninety only) received along with your tender will be treated and converted as a part of security deposit. Please deposit Rs. 5,11,014.00 (Rupees Five Lakh Eleven Thousand Fourteen only), towards balance security deposit within 10 days from the date of issue of this letter, failing which the same will be deducted from the Running Account Bills as per condition GCC 1A on page 16 of the contract document.

शेष पृष्ठ 2 पर....

लाल बहादुर शास्त्री अन्तरराष्ट्रीय हवाई अड्डा वाराणसी-221006
Lal Bahadur Shastri International Airport, Varanasi-221006

दूरभाष: 2622155 फ़ैक्स: 0542-2622320
Phone: 2622155 Fax: 0542-2622320

भारतीय विमानपत्तन प्राधिकरण
Airports Authority of India

लाल बहादुर शास्त्री हवाई अड्डा, वाराणसी
Lal Bahadur Shastri Airport, Varanasi

-2-

- 4) आपसे अनुरोध है कि संविदा श्रमिक प्रावधान (विनिमय एवं उन्मूलन) एक्ट 1970, श्रमिक प्रावधान (विनिमय एवं उन्मूलन)-केन्द्रीय नियम 1971, न्यूनतम मजदूरी अधिनियम एवं इस सम्बन्ध में केन्द्र/राज्य सरकार के नियमों का पालन करना सुनिश्चित करें।
You are requested to comply with the provisions of Contract Labour (Regulation & Abolition) Act of 1970 and Contract Labour (Regulation & Abolition) Central rules 1971 and Minimum Wages Act & Rules thereof Central and State Governments with upto date amendments.
- 5) आपको निर्देशित किया जाता है कि आप तुरन्त प्रभाव से कनिष्ठ कार्यपालक (अभि०-सि०), भा.वि.प्रा., लाल बहादुर शास्त्री अन्तर्राष्ट्रीय विमानपत्तन, वाराणसी से सम्पर्क करें जो आपको कार्यस्थल सौंपने की व्यवस्था करेंगे।
You are also directed to contact the Jr. Executive (E-C), AAI, Lal Bahadur Shastri International Airport, Varanasi, immediately who will arrange to hand over the site to you.
- 6) कृपया ध्यान दें कि कार्य पूर्ण करने की अवधि 03 (तीन) महीने हैं जो कि दिनांक 21.12.2025 से प्रभावी मानी जाएगी।
Please note that time allowed for carrying out the work shall be 03 (Three) months and the same shall be reckoned from 21.12.2025.
- 7) संविदा के सन्दर्भ में किसी भी प्रकार का पत्राचार सामान्यतः उप महा प्रबन्धक (अभि०-सिविल), भा.वि.प्रा., लाल बहादुर शास्त्री अन्तर्राष्ट्रीय विमानपत्तन, वाराणसी-221006, को सम्बोधित करें।
Any further correspondence in connection with the contract should normally be addressed to the DGM (Engg-Civil), AAI, Lal Bahadur Shastri International Airport, Varanasi-221006
- 8) कृपया इस पत्र की पावती भेजें एवं पत्र कि अनुलिपि जो कि संलग्न है को हस्ताक्षरित कर अधोहस्ताक्षरी को स्वीकृत चिन्ह के रूप में वापस करें।
Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.
- 9) विषयक कार्य से संबंधित अनुसूची-अ, (कुल प्रष्ठ 5 (सिविल कार्य रु. 74,06,037.25) संलग्न है।
Schedule 'A' (total page 5) (Civil works Rs. 74,06,037.25) of the work is enclosed.

उपरोक्त के हिन्दी पाठ में कोई अन्तर या द्विधार्थकता होने की स्थिति में अंग्रेजी पाठ मान्य होगा।
In case of difference or ambiguity in Hindi and English version, the English version will prevail.

धन्यवाद।

संलग्नक : उपरोक्त
Encl : As above

भवदीय

उप महा प्रबन्धक (अभि-सिविल)
Dy. General Manager (Engg-Civil)
अध्यक्ष, भा०वि०प्रा० के लिए व उनकी तरफ से
For and on behalf of the Chairman, AAI
Airports Authority of India

लाल बहादुर शास्त्री हवाई अड्डा, वाराणसी
Lal Bahadur Shastri Airport, Varanasi

प्रतिलिपि: मूल प्रति पर नहीं / (NOO)

अ. बाहरी :

1. संयुक्त महा प्रबन्धक (अभि0)—उ0क्षे0, भाविप्रा, नई दिल्ली-110037 : सूचनार्थ
2. सहायक श्रम आयुक्त (सी), 189-ए/4ए, अलोपी बाग, पोस्ट-दारागंज, प्रयागराज : सूचनार्थ
3. श्रम प्रवर्तन अधिकारी (सी), 189-ए/4ए, अलोपी बाग, पोस्ट-दारागंज, प्रयागराज : सूचनार्थ (फार्म-7 संलग्न)

ब. आंतरिक :

- | | | |
|---|---|----------|
| 1. निदेशक विमानपत्तन, वाराणसी | : | सूचनार्थ |
| 2. महा प्रबन्धक (अभि0)—प्रोजेक्ट, वाराणसी | : | -तदैव- |
| 3. प्रभारी (वित्त), वाराणसी | : | -तदैव- |
| 4. सं0 महा प्रबन्धक (अभि0—विद्युत), वाराणसी | : | -तदैव- |
| 5. कनिष्ठ कार्यपालक (अभि0—सिविल), वाराणसी | : | -तदैव- |
| 6. कार्यादेश फाईल | : | |
| 7. अनुबन्ध | : | |



उप महा प्रबन्धक (अभि.-सिविल)
Dy. General Manager (Engg-Civil)
भा.वि.प्रा, लाल बहादुर शास्त्री अन्तराष्ट्रीय विमानपत्तन
वाराणसी
भारतीय विमानपत्तन प्राधिकरण
Airports Authority of India
लाल बहादुर शास्त्री हवाई अड्डा, वाराणसी
Lal Bahadur Shastri Airport, Varanasi

Tender Inviting Authority: Airports Authority of India

Name of Work: Contingent repair works at LBSI Airport, Varanasi during year 2025-26


Contract No : 2025_AAI_254329_1

SCHEDULE OF WORK / ITEM(S)

Sl.No	Description of Work / Item(s)	No.of Qty	Units	Maa Sharda Enterprises (GSTN-09AAVFM4065C1Z0) BID ID -926151	
				Rate	Amount
.10	Civil Works				
1.00	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. All kinds of soil	217.05	Cum	150.00	32557.50
2.00	Boring with tractor mounted hydraulic piling rigs with power units, providing and installing cast in situ single under reamed piles of specified diameter and length below pile cap all complete. (Length of pile for payment shall be measured upto to the bottom of pile cap / Ground level) : 300 mm dia piles.	228.60	Mtr	160.00	36576.00
3.00	Consolidation of sub grade with power road roller of 8 to 12 tonne capacity dressing to camber and consolidating with road roller including making good the undulations etc.	375.00	Sqm	2.00	750.00
4.00	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:4:8 (1 Cement : 4 coarse sand (zone-III) derived from natural sources : 8 graded stone aggregate 40 mm nominal size derived from natural sources). Only black aggregate of Dala will be allowed to be used in concrete work.	42.10	Cum	7300.00	307330.00
5.00	Cement concrete 1:1.50:3 (1 cement : 1.50 coarse sand : 3 graded stone aggregate 10, 20 & 40 mm nominal size) in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete. Note-Compaction shall be done with needle vibrator and screed vibrator. The panel shall be made with C-Channel of the full height of concrete to be laid and floater machine will be applied there upon and proper texture will be made with brooming if required. Initially Mechanically cutting of dummy joints 3mm wide x 1/3rd thickness shall have to cut. Subsequently groove cutting as per dummy / construction/expansion joints will be done 10mm width x 50mm deep as per satisfaction of Engineer-in-Charge and Noting extra shall be paid for performing these activity. Note: Ajax will not be allowed for concrete work at any cost. For curing suitable curing compound shall have to be used / sprayed. Only black aggregate of Dala will be allowed to be used in concrete work.	56.25	Cum	7000.00	393750.00
6.00	Cleaning & filling dummy/longitudinal/transverse Joints in existing PQC with polysulphide joint sealing compound (confirming to grade BS:5212, Part-I, 1990 or IS:11433-1995) of approved make Dr. Fixit/Sika/Fosroc/Clean coat/Choksey/STP or equivalent including painting the sides of slab with approved primer and filling the groove 10mm width x 25mm deep including inserting the backer rod of appropriate dia of approved make to receive the specified sealing compound, providing and applying bond breaking tape and masking tape on top edges of joint to prevent accidental spillage of sealant on top surface and to give a neat finish to the sealant has been applied and tooled, all complete as per specification and direction of Engineer-in-Charge Note: This work shall be carried out through authorized or experienced applicator of M/s CHOKSY/SIKA/ PIDILITE /STP/Clean Coat etc.	205.00	Mtr	130.00	26650.00

उप महाप्रबंधक (आर.ए.सी.विल)
Dy. General Manager (Engg-Civil)
भारतीय विमानपत्तन प्राधिकरण
Airports Authority of India
लाल बहादुर शास्त्री हवाई अड्डा, वाराणसी
Lal Bahadur Shastri Airport, Varanasi

Sl.No	Description of Work / Item(s)	No. of Qty	Units	Maa Sharda Enterprises (GSTN-09AAVFM4065C1Z0) BID ID -926151	
				Rate	Amount
7.00	Construction of granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by tippers to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge : With material conforming to Grade-I (size range 75 mm to 0.075 mm) having CBR Value-30	75.00	Cum	2500.00	187500.00
8.00	Carriage of materials by mechanical transport including loading,unloading and stacking of Earth for a lead upto 1 km beyond 50 mtr	187.50	Cum	200.00	37500.00
9.00	Providing and fixing ornamental decorative Cast Iron railings & spikes (member dimension L=840mm, W=170mm & Wt=3.60 Kg) which is fixed with mild steel hollow pipes at top and bottom 40mm mild steel, vertical post of 40mm tube. Suited to railings and fixed at a distance of 1.50 to 2.50 mtr c/c or where ever required including welding, grinding, buffing, finishing, provision of gate wherever required with locking & swingin arrangement and making curvature (wherever required) fasteners, bolts etc. of required size on the top of the C.C column with suitable arrangement as per approval of Engineer-in-charge. Note: Fabrication of decorative railing of cast iron with MS steel section shall be done in workshop with experienced and capable fabricator. The design of the cast iron grill should be similar to the grill already erected in the colony.	13429.00	Kg	100.00	1342900.00
10.00	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering -All work up to plinth level:1:1.5:3 (1 Cement: 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	19.90	Cum	8000.00	159200.00
11.00	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level1:4:8 (1 Cement : 4 coarse sand (zone-III) derived from natural sources : 8 graded stone aggregate 40 mm nominal size derived from natural sources)	63.00	Cum	6500.00	409500.00
12.00	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in:Cement mortar 1:6 (1 cement : 6 coarse sand)	1.00	Cum	6500.00	6500.00
13.00	12 mm cement plaster : 1:6 (1 cement : 6 coarse sand)	18.00	Sqm	300.00	5400.00
14.00	Providing and laying good quality of grass carpet i/c spreading, blending and mowing the earth with required quantity of vermicompost i/c raking out and moistening the soil of existing ground prepared with proper level and ramming with required tools wooden and than rolling the surface with light roller make the surface smoothen and light watering the same and maintenance for 30 days or more till the grass establish properly, as per direction of the officer in charge. Vermicompost will be paid for seperately.	525.00	Sqm	325.00	170625.00
15.00	Supplying and plantation of hedge (Kamni Minimum 1 feet height) at site including spreading manure / sludge or other required material after removal of unserveiceable material's as per direction of Engineer in charge. Manure / sludge or other material will be paid in separate / corresponding items.	584.00	Each	50.00	29200.00
16.00	Supplying and plantation of Trees of Areca plam/Fox tail Palm/ Fish tail palm /Red lipistic palm (Minimum 10 feet height) at site including cast of manure or sludge after removal of unserveiceable material's as per direction of Engineer in charge.	40.00	Each	700.00	28000.00
17.00	Supply of organic medium / manure / chemical including loading, unloading & delivery as specified for Grass, Plants,Trees, Ground Cover and all related to Horticulture works. (a) Cocopeat	263.00	Kg	50.00	13150.00


 उप महाप्रबन्धक (उप-निर्देशक)
 Dy. General Manager (Engg-Civil)
 भारतीय विमानपत्तन प्राधिकरण
 Airports Authority of India
 लाल बहादुर शास्त्री हवाई अड्डा, वाराणसी
 Lal Bahadur Shastri Airport, Varanasi

Sl.No	Description of Work / Item(s)	No. of Qty	Units	Maa Sharda Enterprises (GSTN-09AAVFM4065C1Z0) BID ID -926151	
				Rate	Amount
18.00	Supply of organic medium / manure / chemical including loading, unloading & delivery as specified for Grass, Plants, Trees, Ground Cover and all related to Horticulture works. (b) Vermicompost sealed packed in 40 kg. bag.	4.00	Bag	520.00	2080.00
19.00	Supply of organic medium / manure / chemical including loading, unloading & delivery as specified for Grass, Plants, Trees, Ground Cover and all related to Horticulture works. (c) NPS in sealed packed bag containing 50 kg.	3.00	Bag	1800.00	5400.00
20.00	Supply of organic medium / manure / chemical including loading, unloading & delivery as specified for Grass, Plants, Trees, Ground Cover and all related to Horticulture works. (d) Antitermite chemical emulsion FURDON-3G or equivalent	6.00	Kg	140.00	840.00
21.00	Providing and fixing of Basketball court tiles made of PP Interlocking tiles, tiles material polypropylene and co-polypropylene Shock absorption 35% ball rebound 98% lifespan 10-12 years, weight, 3.7 kg per square meter marking as per BFI norms, number of locks and shape must be square shaped with 5 big and mini locks for better strength with 2d Rhombus shape, Modular pp tiles designed for outdoor sports surface should be tested in accordance to EN14877:2013 or a higher standard. Size of 304.8mm x 304.8mm x 15.8mm, double layered material color, 2D rhombus shape Tiles must have 10 locks including 2 smaller locks fastener insertion provision, weight type of interlocking tiles fitflex/ sportcraft/ keepfit Basketball court tiles i/c demarcation strips as per satisfaction of EIC. Note: Rate for the item shall include the cost of all materials, installations, transportation, adhesive if required, electricity charges, T & P and labours etc and the installation of the basketball court tiles, made of PP interlocking tiles, will be carried out by an approved vendor who meets the qualification criteria specified in the technical specifications.	750.00	Sqm	1400.00	1050000.00
22.00	Providing of Fixed type basketball poles made of ISI marked Round Make KeepFit/ FitFlex/ ThermoBlow/ Sports Craft, M.S pipe in 8 inches diameter, board as the BFI norms in 25 mm thickness made of Transparent Acrylic board made in Malaysia/Taiwan, extension of the pole is 2.2/3.2 meters with spring action slam Dunk. Note: Rates are inclusive of supply, erection, transportation, warranty, labour, T & P, Crane, loading & unloading etc and providing & fixing of fixed type basketball poles, will be carried out by an approved vendor who meets the qualification criteria specified in the technical specifications.	1.00	Pair	130000.00	130000.00
23.00	Providing and laying at or near ground level factory made Silicon mould kerb stone of M-25 grade cement concrete in position to the required line, level and curvature, jointed with cement mortar 1:3 (1 cement: 3 coarse sand), including making joints with or without grooves (thickness of joints except at sharp curve shall not to more than 5mm), including making drainage opening wherever required complete etc. as per direction of Engineer-in-charge (length of finished kerb edging shall be measured for payment). (Precast C.C. kerb stone shall be approved by Engineer-in-charge).	11.80	Cum	10000.00	118000.00
24.00	Painting with synthetic enamel paint of required colour to give an even shade :Two coats of approved brand and manufacture on new work and one coat of suitable shade with ordinary paint of approved brand and manufacture with electric-powered handheld airless sprayers machine i/c cleaning, sand papering, metallic putty and repair of any holes/gaps/patches/cracks to provide smooth finish with satisfaction of Engg-In-Charge.	224.95	Sqm	225.00	50613.75

11/12/2020

उप महाप्रबंधक (अभि.-सिविल)

Dy. General Manager (Engg-Civil)

भारतीय विमानपत्तन प्राधिकरण

Airports Authority of India

लाल बहादुर शास्त्री हवाई अड्डा, वाराणसी

Lal Bahadur Shastri Airport, Varanasi

Sl.No	Description of Work / Item(s)	No.of Qty	Units	Maa Sharda Enterprises (GSTN-09AAVFM4065C1Z0) BID ID -926151	
				Rate	Amount
25.00	Providing and laying in walls / floors anti skid homogenous premium quality vitrified tiles with water absorption less than 0.08% and conforming to IS:15622 of approved Belgium Grey NITCO/Marbonite -Ash Grey/Porselano – Dew Grey JOHNSON/ RAK CERAMICS brand/ manufacturer, of size 600 x 1200 mm in combination as per approved drawing without warpage of approved make and colour shades laid with cement based high polymer modified quick set tile adhesive (water based) conforming to IS : 15477, in average 6 to 10 mm thickness with hand held vibrator, Grooves/grinding/roughness shall have to be created with cutting disc before laying tiles, including grouting the joints of thickness 3 mm with solid epoxy grout of PIDILITE / LATICRETE / BAL ENDURA / FERROUS CRETE or approved equivalent of desired shade etc. complete and as per pattern specified in approved drawings and specifications complete as per directions of Engineer-in-charge. (Note : -Basic price of vitrified Wall tiles shall not be less than Rs 55/Sqft for any size without GST, freight upto destination, loading and unloading etc. Purchase voucher shall have to be submitted for price verification before bill payment of this bill)	897.00	Sqm	1500.00	1345500.00
26.00	Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete : 300 mm dia. R.C.C. pipe.	25.00	Mtr	990.00	24750.00
27.00	Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete : 600 mm dia. R.C.C. pipe.	10.00	Mtr	2100.00	21000.00
28.00	Providing and fixing mild steel round holding down bolts with nuts and washer plates complete.	142.00	Kg	90.00	12780.00
29.00	Providing & fixing 4mm thick ACP sheet of required colour on existing board with necessary screws as per specification and as directed by E. I. C.	5.00	Sqm	1920.00	9600.00
30.00	Providing and fixing with Radium computer cut letters of any colour and shade with adhesive backing which shall be paste over required surface evenly and justified way, the letter should not be warped or unequally adjusted etc.conforming to class-2 of ASTM-D-4656-01.complete as per direction of Engineer-in-charge.	5.00	Sqm	5000.00	25000.00
31.00	Providing and fixing precoated galvanised iron profile sheets of any curvature (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	185.00	Sqm	720.00	133200.00
32.00	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	4629.00	Kg	130.00	601770.00

11/12/2020

उप महाप्रबंधक (अभि.- सिविल)
Dy. General Manager (Engg-Civil)
भारतीय विमानपत्तन प्राधिकरण
Airports Authority of India
लाल बहादुर शास्त्री हवाई अड्डा, वाराणसी
Lal Bahadur Shastri Airport, Varanasi

Sl.No	Description of Work / Item(s)	No. of Qty	Units	Maa Sharda Enterprises (GSTN-09AAVFM4065C1Z0) BID ID -926151	
				Rate	Amount
33.00	Providing and fixing required colour of powder coated aluminium work for doors, sliding windows, ventilators and partitions with fixed frame of extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / panelling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, steel mesh panelling and dash fasteners to be paid for separately) :For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately) Powder coated aluminium (minimum thickness of powder coating 50 micron)	626.00	Kg	500.00	313000.00
34.00	Providing and fixing Fly proof stainless steel grade 304 wire gauge with 0.5 mm dia. wire and 1.4 mm wide aperture to windows.	209.00	Sqm	1500.00	313500.00
35.00	Providing and fixing hard drawn steel wire fabric of size 75x25mm mesh with 4mm dia or other suitable size wire mesh to be fixed to the welded with existing MS angle including the cost of materials, labour, tool & plants as approved by EIC.	211.00	Kg	85.00	17935.00
36.00	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. 20 mm nominal dia Pipes	175.00	Mtr	240.00	42000.00
37.00	Providing and fixing ISI marked heavy duty plastic sprinkler with all accessories as per direction of Engineer in Charge. 15 mm nominal dia.	6.00	Each	330.00	1980.00

Total in Figures

7406037.25

Lowest Amount Quoted BY: Maa Sharda Enterprises(7406037.25)


 11/12/2025
 उप महाप्रबंधक (अभि. - सिविल)
 Dy. General Manager (Engg-Civil)
 भारतीय विमानपत्तन प्राधिकरण
 Airports Authority of India
 लाल बहादुर शास्त्री हवाई अड्डा, वाराणसी
 Lal Bahadur Shastri Airport, Varanasi