



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA
डिब्रूगढ़ हवाई अड्डा, डिब्रूगढ़
DIBRUGARH AIRPORT, DIBRUGARH

AAI/DIB/ENGG(E)/CW-04/W.O.-07/2025-26/ 594

Date: 06.01.2026

To,
M/s Universal Electrical & Electronics,
House No.69 First Floor, PNGB Road
Bharalumukh, Shantipur Hill Side,
Kamrup, Assam, 781009

Name of Work: Enhancing the illumination level of City Side at Dibrugarh Airport.

Ref: 1. Tender Id: 2025_AAI_254589_1


महोदय/Sir,

1. उल्लिखित कार्य हेतु आपकी ई निविदा के सम्बन्ध में, आपके द्वारा उद्धरित राशि कुल रु. 15,77,640.00.00 (मात्र पंद्रह लाख सतहत्तर हजार छह सौ चालीस रुपये) (जी.एस.टी. के बिना), जो कि निविदा की औचित्तीय मूल्य राशि रु. 18,52,402.00 मात्र से 14.83 % कम है, को अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से स्वीकृत किया जाता है। जीएसटी चालान के उत्पादन पर वास्तविक के अनुसार अतिरिक्त जीएसटी राशि का भुगतान किया जाएगा।

Your E-tender for the above-mentioned work is hereby accepted on behalf of the Chairman, Airports Authority of India at the item rates quoted by you totaling Rs. 15,77,640.00 (Rupees Fifteen Lakhs Seventy Seven Thousand Six Hundred and Forty Only) (excluding GST) which is 14.83 % below the justified cost of Rs. 18,52,402.00/- only. Amount of GST will be paid extra as per actual on production of GST invoice.

2. वरिष्ठ प्रबंधक (इंजी.-विद्युत), डिब्रूगढ़ हवाई अड्डा, कार्य के लिए प्रभारी इंजीनियर होंगे। आपसे अनुरोध है कि आप अपना प्राधिकृत प्रतिनिधि जिसे कि आप की ओर से संविदा करार पर हस्ताक्षर करने की शक्ति दी गई है को वरिष्ठ प्रबंधक (इंजी.-विद्युत) के कार्यालय में करार पर हस्ताक्षर करने के लिए दिनांक 21.01.2026 तक तैनात करें। (संविदा करार सौ रुपये के नॉन ज्युडिशियल स्टाम्प पेपर पर निष्पादित किया जाएगा और स्टाम्प पेपर की लागत आपको ही वहन करनी होगी।)

Senior Manager (Engg.-E), Dibrugarh Airport, shall be the Engineer-In-Charge of the work. You are requested to depute your accredited representative, empowered to sign the contract agreement on your behalf to attend the office of the Senior Manager (Engg.-E) by 21.01.2026 to sign and complete the agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs.100.00 (Rupees One Hundred) only and the cost of the stamp paper shall be borne by you.



3. कृपया सुरक्षा जमा राशि रु 1,57,764.00 (मात्र एक लाख सत्तारह हजार सात सौ चौंसठ रुपये) इस पत्र के जारी होने की तारीख से 10 (दस) दिनों के भीतर जमा करें। ऐसे न करने पर, सविदा के अनुसार यह राशि आपके रजिग बिल् से से काट दिया।
- Please deposit Rs. 1,57,764.00 (Rupees One Lakh Fifty-Seven Thousand Seven Hundred and Sixty-Four Only) towards security deposit within 10 (Ten) days from the date of issue of this letter, failing which, the same will be deducted from your running bill as per contract agreement.
4. स्वीकृति पत्र जारी होने के 30 दिनों के भीतर, आपको अनुबंध दस्तावेज़ के अनुलक्षक-0-n में संलग्न प्रोक्वामा पर बैंक गारंटी के रूप में 20,000/- रुपये (केवल बीस हजार रुपये) की राशि के लिए, पृष्ठ GCC पर खंड 1-B की शर्त के अनुसार, AAI की एक अतिरिक्त प्रदर्शन गारंटी प्रस्तुत करनी होगी।
- Within 30 days of issue of acceptance letter, you shall submit to AAI, an additional Performance Guarantee as per condition of clause 1 B on page GCC for an amount of Rs 20,000/- (Rupees Twenty Thousand only) in the form of Bank Guarantee on the Proforma appended at Annexure – o n of Contract Document.
5. आपसे अनुरोध है कि अनुबंध श्रम (विनियमन और उन्मूलन) अधिनियम 1970 और अनुबंध श्रम (विनियमन और उन्मूलन) केंद्रीय नियम 1971, बाल श्रम (निबंध और विनियमन) अधिनियम 1986, निर्माण कार्यकर्ताओं (रोजगार और सेवा की शर्त का विनियमन) अधिनियम 1996, बिजिनिंग और अन्य निर्माण श्रमिक कल्याण सेस अधिनियम 1996 केंद्रीय और राज्य सरकार के नियमों का पालन करें।
- You are requested to comply with the provision of Contract labour (Regulation and Abolition) Act 1970 and contract labour (Regulation and Abolition) Central rules 1971 Child Labour (Prohibition & Regulation) Act 1986, Construction Workers (Regulation of Employment and Condition of Service) Act 1996, Building and other construction Workers Welfare Cess Act of Central and State Government.
6. आपको निर्देश दिए जाते हैं कि आप **सहायक प्रबंधक (आयु. वि. प्र., डिब्रुगढ़ विद्युत), भा. वि. प्र., डिब्रुगढ़** से तत्काल समक करें जो कि आपको कठिनाई सुपट करने की व्यवस्था करेंगे। कृपया यह नोट कर लें कि काम करने का समय **04 महीना** है जिसे तारीख 15.01.2026 से गिना जाएगा।
- You are directed to contact **Manager (Engg-E), AAI, Dibrugarh Airport**, immediately who will arrange to handover the site to you. Please note that the time allowed for carrying out the work is **04 MONTHS**, which shall be reckoned from **15.01.2026**.
7. अनुबंध की दोष देयता अवधि पूरा होने की तारीख से **12 (बारह) महीने** Defects liability period of contract is **12 (Twelve) Months** from the recorded date of completion.
8. सविदा के संबंध में आगे किया जाने वाला पत्राचार समान्यतः **वरिष्ठ प्रबंधक (इंजी. विद्युत), भा. वि. प्र., डिब्रुगढ़ विद्युत, डिब्रुगढ़ -786012**, से किया जाए।
- Any further correspondence in connection with the contract should normally be addressed to the **Senior Manager (Engg.-E), AAI, Dibrugarh Airport, Dibrugarh -786012**.
9. कृपया प्रतिगृहण के टोकन के रूप में कार्य आदेश की प्राप्ति की स्वीकार करें।


9. कृपया प्रतिग्रहण के टोकन के रूप में कार्य आदेश की प्राप्ति को स्वीकार करें ।

Please acknowledge the receipt of the Letter of Award as a token of acceptance.

10. यदि कहीं विसंगति पाई जाती है तो अंग्रेज़ी भाषा ही मान्य होगी ।

In case any discrepancy is found, then English version will be taken as correct.

भवदीय / Yours faithfully,



(के.के. सुरेशकुमार)

(K.K. Sureshkumar)

वरिष्ठ प्रबंधक (अभि.-विधुत)

Senior Manager (Engg.- Elect.)

कृते तथा की ओर से अध्यक्ष, भा.वि.प्रा.

For and on behalf of Chairman, AAI

भा.वि.प्रा. डिब्रूगढ़ विमानपत्तन

AAI, Dibrugarh Airport

Validate

Print

Help

Item Rate Boq

Tender Inviting Authority: Airports Authority of India, Dibrugarh Airport

Name of Work: Enhancing the Illumination level of City Side at Dibrugarh Airport..


Contract No: 2025_AAI_264589_1

Name of the Bidder/ Bidding Firm / Company
UNIVERSAL ELECTRICAL AND ELECTRONICS

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE in Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words
1	2 Supply of LED Bollard having lumen output not less than 11 Watts with luminaire efficacy of not less than 70 lumens per watt, CCT 3000 K, driver and accessories suitable for outdoor applications complete as per technical specifications.	4 60	5 Each	13 3360.00	53 201600.00	55 INR Two Lakh One Thousand Six Hundred & Paise Zero Only
2	Supply of LED decorative post top luminaire consisting of a high-pressure powdercoated die-cast aluminium housing suitable for vertical mounting on pole having system lumen output wattage not less than 30 W and system efficacy of not less than 70 lumens per watt, CCT 3000 K, complete with driver and all accessories suitable for outdoor applications complete as per technical specifications.	15	Each	4440.00	66600.00	INR Sixty Six Thousand Six Hundred & Paise Zero Only
3	TTC of LED Bollard light in ground with required foundation, providing suitable cable entry with HDPE pipe in the foundation, providing end termination of the loop in loop out cable inside the bollard, providing and laying wire if required, interconnections complete as required.	55	Job	3600.00	198000.00	INR One Lakh Ninety Eight Thousand & Paise Zero Only
4	Supply of 4C x 2.5 Sq.mm XLPE Insulated PVC sheathed Copper Conductor round wire armoured Control Cable of grade 1.1 kV conforming to IS : 7098 with up to date amendments.	350	Meter	228.00	79800.00	INR Seventy Nine Thousand Eight Hundred & Paise Zero Only
5	Laying of one number PVC Insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size in the existing RCC/ HUMF/ METAL pipe as required.	800	Meter	30.00	24000.00	INR Twenty Four Thousand & Paise Zero Only
6	Supplying and laying of following size HDPE pipe (SDR 11) ISI marked along with all accessories like socket, bend, couplers etc. conforming to IS 4984 complete with fitting and cutting, jointing etc. in the existing trench, complete as required.	300	Meter	240.00	72000.00	INR Seventy Two Thousand & Paise Zero Only
7	25 mm nominal Excavation of the cable trenches in soft soil not exceeding 30 centimeters in width, and depth upto 50 Centimeters, including getting out the excavated soil and refilling the excavated soil after laying the HDPE pipe in the cable trench, making good the area.	660	Meter	84.00	55440.00	INR Fifty Five Thousand Four Hundred Forty & Paise Zero Only
8	Cutting road/concrete including equipment, labour etc. and disposal of material as directed, within a lead of 50 m.	5	CUM	4800.00	24000.00	INR Twenty Four Thousand & Paise Zero Only


 Senior Manager (अति. विद्युत)
 Senior Manager (Engg-Elect)
 भारतीय विमानपत्तन प्राधिकरण
 Airports Authority of India

15	Supply of 4C x 25 Sq.mm XLPE Insulated PVC sheathed Aluminium Conductor armoured Power Cable of grade 1.1 KV conforming to IS : 7098 with up to date amendments.	100	Meter	288.00	28800.00	INR Twenty Eight Thousand Eight Hundred & Paise Zero Only
16	Supply, Installation, Testing and Commissioning of LT Panel, cubicle type, made out of 14 SWG CRCA sheet steel, totally enclosed, IP-54, protection free standing, floor mounting, dust and vermin proof, indoor, compartmentalized, powder coated painting suitable for operation on 3 Phase and neutral, 415V, 50 Hz AC supply system with bus bars extensible on both sides, interconnections with suitable size of copper leads/ solid aluminium strips. INCOMER 1 Nos. 40 Amp, Thermal Magnetic release adjustable type 4 pole Moulded Case Circuit Breaker (Ics = Icu = 25KA) With thermal magnetic release, O/L & S/C Protection with neutral link, 3 Nos.phase indicating LED lamps each with 2 amp back up MCB with each Incomer On & Off Indication lamp with back up Mcb. BUSBARS TPN aluminium bus bars of minimum 100 Amps capacity with heat shrinkable coloured sleeves and i/c, SMC bus bars supports at required intervals complete for cross section, side supports & their spacing etc. for withstanding fault level of 25 KA for 1 sec. OUTGOING 1. Timer Switch along with suitable 3 phase contactor 3 phase MCB for controlling lights. 2. Arrangement for raising and lower the High Mast with suitable Amp. rating contactors and raise lower push button, LED indication lamp for ON indication. 3. Spare MCB 4 Pole 10 A. - 2 Sets.	1	Job	54000.00	54000.00	INR Fifty Four Thousand & Paise Zero Only
17	Earthing with G.I. earth plate 600 mm X 600 mm X 6 mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 meter long etc. with charcoal/ coke and salt as required.	6	Job	6000.00	36000.00	INR Thirty Six Thousand & Paise Zero Only
18	Providing and laying earth connection from earth electrode with 6 SWG dia G.I. Wire in 15 mm dia G.I. pipe from earth electrode including connection with G.I. thimble excavation and re-filling as required.	50	Meter	240.00	12000.00	INR Twelve Thousand & Paise Zero Only
19	Providing and fixing 6 SWG dia G.I. wire on surface or in recess for loop earthing as required.	360	Meter	60.00	21600.00	INR Twenty One Thousand Six Hundred & Paise Zero Only
20	Dismantling of existing pole of height 3 Meter from existing location and shifting to a location not more than 100 meters. The job includes the removing of bolts, removing the pole by providing suitable arrangement, removing the lights fixed to the pole, demolishing the RCC structure by mechanical means and matching to the ground level, complete as required	20	Job	3000.00	60000.00	INR Sixty Thousand & Paise Zero Only

[Handwritten Signature]

श्रीरंज प्रबंधक (अभि. विद्युत)
Senior Manager (Engg-Elect)
भारतीय विमानपत्तन प्राधिकरण
Airports Authority of India
डिब्रुगढ़ हवाई अड्डा/Dibrugarh Airport
PIN-786012

Item Rate Boq

Tender Inviting Authority: Airports Authority of India, Dibrugarh Airport

Name of Work: Enhancing the illumination level of City Side at Dibrugarh Airport..

Contract No: 2025_AAI_254589_1

Name of the Bidder/ Bidding Firm / Company : UNIVERSAL ELECTRICAL AND ELECTRONICS

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE in Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
1	Supply of LED Bolland having lumen output not less than 11 Watts with luminaire efficacy of not less than 70 lumens per watt, CCT 3000 K, driver and accessories suitable for outdoor applications complete as per technical specifications.	60	Each	3360.00	201600.00	INR Two Lakh One Thousand Six Hundred & Paise Zero Only
2	Supply of LED decorative post top luminaire consisting of a high-pressure powdercoated die-cast aluminium housing suitable for vertical mounting on pole having system lumen output wattage not less than 30 W and system efficacy of not less than 70 lumens per watt, CCT 3000 K, complete with driver and all accessories suitable for outdoor applications complete as per technical specifications.	15	Each	4440.00	66600.00	INR Sixty Six Thousand Six Hundred & Paise Zero Only
3	ITC of LED Bolland light in ground with required foundation, providing suitable cable entry with HDPE pipe in the foundation, providing end termination of the loop in loop out cable inside the bollard, providing and laying wire if required, interconnections complete as required.	55	Job	3600.00	198000.00	INR One Lakh Ninety Eight Thousand & Paise Zero Only
4	Supply of 4C x 2.5 Sq.mm XLPE Insulated PVC sheathed Copper Conductor round wire armoured Control Cable of grade 1.1 kV conforming to IS : 7098 with up to date amendments.	350	Meter	228.00	79800.00	INR Seventy Nine Thousand Eight Hundred & Paise Zero Only
5	Laying of one number PVC Insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size in the existing RCC/ HUMET/ METAL pipe as required.	800	Meter	30.00	24000.00	INR Twenty Four Thousand & Paise Zero Only
6	Supplying and laying of following size HDPE pipe (SDR 11) IS1 marked along with all accessories like socket, bend, couplers etc. conforming to IS 4984 complete with fitting and cutting, jointing etc. in the existing trench, complete as required.	300	Meter	240.00	72000.00	INR Seventy Two Thousand & Paise Zero Only
7	Excavation of the cable trenches in soft soil not exceeding 30 centimeters in width, and depth upto 50 Centimeters, including getting out the excavated soil and refilling the excavated soil after laying the HDPE pipe in the cable trench, making good the area.	660	Meter	84.00	55440.00	INR Fifty Five Thousand Four Hundred Forty & Paise Zero Only
8	Cutting road/concrete including equipment, labour etc. and disposal of material as directed, within a lead of 50 m.	5	CUM	4800.00	24000.00	INR Twenty Four Thousand & Paise Zero Only

Senior Manager (Engg-Elect)
आरपीएच विभाग
Airports Authority of India
Dibrugarh Airport
786001

9	Providing and laying in position cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) including form work etc. as required.	5	CUM	8400.00	42000.00	INR Forty Two Thousand & Paise Zero Only
10	Dismantling of Existing 30 Meter High Mast Pole including lights, SS rope, trailing cable from the existing location and shifting the same to a location not more than 100 Meters. The Job includes the lowering of the Mast head Assembly, removing the lights attached to the Mast Head Assembly, removing the foundation bolts, detaching the High Mast Pole from the foundation by providing suitable crane (Crane to be provided by the Agency) without making any damage to the pole and accessories, removing the existing SS rope and trailing cable, Demolishing the RCC structure by mechanical means and the matching it to the ground level complete as required.	1	Job	72000.00	72000.00	INR Seventy Two Thousand & Paise Zero Only
11	Erection of existing 30 meter High Mast Pole with all accessories by providing reinforced cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) foundation (foundation drawing to be obtained from OEM as per the site conditions and should be approved by AAI) including excavation and refilling including positioning of template & foundation bolts (to be supplied by agency) & providing and fixing of HDPE pipe of size 50 mm dia in the foundation for the cable complete as required and as specified.	1	Job	108000.00	108000.00	INR One Lakh Eight Thousand & Paise Zero Only
12	Overhauling, Testing and Commissioning of the existing 30 Meter High Mast Pole by removing the rust, painting the double sided winch, checking the operation of the High Mast head assembly by raising and lower the same, providing grease to the moving parts, making the entire connections for the operation of the High Mast. The Job also includes the fixing of the flood lights, making the connections of the flood light, replacing the cables/wires of the flood light system making good for operation.	1	Job	48000.00	48000.00	INR Forty Eight Thousand & Paise Zero Only
13	Supply and replacement of AISI 316 Grade 6 mm SS steel wire ropes suitable for 30 Meter High Mast Pole installed in Dibrugarh Airport. The job includes the supply and installation of 6 mm rope on the 30 Meter High Mast Pole including replacement of stainless steel thimbles, copper splicing, galvanized turnbuckle eye and bull dog grips including using suitable equipments, tools, safety harness etc. complete as required for replacement of the wire rope complete as required. The job also includes removal of existing wire ropes from the High Mast Pole. The High Mast is equipped with double drum winch and length of the SS steel wire shall be compatible for the double drum winch.	1	Job	36000.00	36000.00	INR Thirty Six Thousand & Paise Zero Only
14	Supply and replacement of EPR Insulated and PCP sheathed trailing cable (8C x 1.5 Sq.mm) suitable for 30 Meter High Mast Pole installed in Dibrugarh Airport. The job including providing and replacing the connectors, the supply and installation of trailing cable on the 30 Meter High Mast Pole including replacement of trailing cable using suitable equipments, tools, safety harness etc. complete as required for replacement of the trailing cable complete as required.	1	Job	18000.00	18000.00	INR Eighteen Thousand & Paise Zero Only



वरिष्ठ प्रबंधक (अभि. विद्युत)
Senior Manager (Engg-Elect)
भारतीय विमानपत्तन प्राधिकरण
Airports Authority of India
डिब्रुगढ़ हवाई अड्डा/Dibrugarh Airport
PIN-786012

15	Supply of 4C x 25 Sq.mm XLPE Insulated PVC sheathed Aluminium Conductor armoured Power Cable of grade 1.1 kV conforming to IS : 7098 with up to date amendments.	100	Meter	288.00	28800.00	INR Twenty Eight Thousand Eight Hundred & Paise Zero Only
16	Supply, Installation, Testing and Commissioning of LT Panel, cubicle type, made out of 14 SWG CRCA sheet steel, totally enclosed, IP-54, protection free standing, floor mounting, dust and vermin proof, indoor, compartmentalized, powder coated painting suitable for operation on 3 Phase and neutral, 415V, 50 Hz AC supply system with bus bars extendible on both sides, interconnections with suitable size of copper leads/ solid aluminium strips. INCOMER 1 Nos. 40 Amp, Thermal Magnetic release adjustable type 4 pole Moulded Case Circuit Breaker (ICS = Icu = 25KA) With thermal magnetic release, O/L & S/C Protection with neutral link, 3 Nos. phase indicating LED lamps each with 2 amp back up MCB with each Incomer On & Off Indication lamp with back up MCB. BUSBARS TPN aluminium bus bars of minimum 100 Amps capacity with heat shrinkable coloured sleeves and I/c, SMC bus bars supports at required intervals complete for cross section, side supports & their spacing etc. for withstanding fault level of 25 KA for 1 sec. OUTGOING 1. Timer Switch along with suitable 3 phase contactor 3 phase MCB for controlling lights. 2. Arrangement for raising and lower the High Mast with suitable Amp, rating contactors and raise lower push button, LED indication lamp for ON indication. 3. Spare MCB 4 Pole 10 A. - 2 Sets.	1	Job	54000.00	54000.00	INR Fifty Four Thousand & Paise Zero Only
17	Earthing with G.I. earth plate 600 mm X 600 mm X 6 mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 meter long etc. with charcoal/ coke and salt as required.	6	Job	6000.00	36000.00	INR Thirty Six Thousand & Paise Zero Only
18	Providing and laying earth connection from earth electrode with 6 SWG dia G.I. Wire in 15 mm dia G.I. pipe from earth electrode including connection with G.I. thimble excavation and re-filling as required.	50	Meter	240.00	12000.00	INR Twelve Thousand & Paise Zero Only
19	Providing and fixing 6 SWG dia G.I. wire on surface or in recess for 1000 earthing as required.	360	Meter	60.00	21600.00	INR Twenty One Thousand Six Hundred & Paise Zero Only
20	Dismantling of existing pole of height 3 Meter from existing location and shifting to a location not more than 100 meters. The Job includes the removing of bolts, removing the pole by providing suitable arrangement, removing the lights fixed to the pole, demolishing the RCC structure by mechanical means and matching to the ground level, complete as required.	20	Job	3000.00	60000.00	INR Sixty Thousand & Paise Zero Only

29/11/20

वरिष्ठ प्रबंधक (अभि. विद्युत)
Senior Manager (Engg-Elect)
भारतीय विमानपत्तन प्राधिकरण
Airports Authority of India
डिब्रुगढ़ हवाई अड्डा/Dibrugarh Airport
PIN-786012

21	Erection of 3 Mr. high street light pole with all accessories in reinforced cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling including positioning of template & foundation bolts (supplied with pole to match with pole base plate) & providing and fixing of HDPE pipe of size 50 mm dia in the foundation for loop-in-loop-out of the cable to the pole complete as required and as specified	20	Job	4800.00	96000.00	INR Ninety Six Thousand & Paise Zero Only
22	Laying of following size DMC HDPE pipe ISI marked along with all accessories like socket, bend, couplers etc. conforming to IS 14930 complete with fitting and cutting, jointing etc. in the existing trench, complete as required.	360	Meter	120.00	43200.00	INR Forty Three Thousand Two Hundred & Paise Zero Only
23	All pipe size less than 50 mm nominal TTC of Post top LED light on the Street light Pole of Height 3. meters including making end termination of the loop in loop out cable of size not larger than 4 x 16 sq.mm at syntax box, providing required hole for laying the cable for the light connection, connecting the GI wire for earthing, providing and laying 3 core x 1.5 sq.mm wire for LED light connection, interconnections complete as required for TTC of post top LED light.	35	Job	960.00	33600.00	INR Thirty Three Thousand Six Hundred & Paise Zero Only
24	Supply and fixing of IP 65 loop in loop out box of inside dimension 155 x 210 x 92 (equivalent to Hensel make model No.KF 1616 G) including suitable 20 A 4 way DMC connector and din rail etc, including making required interconnections as required.	35	Job	4200.00	147000.00	INR One Lakh Forty Seven Thousand & Paise Zero Only
Total in Figures					1577640.00	INR Fifteen Lakh Seventy Seven Thousand Six Hundred Forty & Paise Zero Only
Quoted Rate in Words					INR Fifteen Lakh Seventy Seven Thousand Six Hundred Forty & Paise Zero Only	



वरिष्ठ प्रबंधक (अभि. विद्युत)
Senior Manager (Engg-Elect)
भारतीय विमानचरन प्राधिकरण
Airports Authority of India
डिब्रुगढ़ हवाई अड्डा/Dibrugarh Airport
PIN-786012