

सन्दर्भ सं०: भा.वि.प्रा/वारा/अभियंत्रण/कचरा संग्रहण केंद्र /डब्लूओ-126/798-807/9758-69
Ref. No.: AAI/VNS/ENGG/ Garbage Collection Center/WO-126/

दिनांक: 15.12.2025

Date: 15.12.2025

सेवा में,

मेसर्स उत्कर्ष इंटरप्राइजेज,
कैथौली, पिन्द्रा,
वाराणसी-221006

M/s Utkarsh Enterprises,
Kaithauli, Pindra,
Varanasi-221006

विषय: ला.ब.शा.अं हवाई अड्डा, वाराणसी के आवासीय कॉलोनी में सामुदायिक केंद्र के पीछे मौजूदा कचरा संग्रहण केंद्र को स्थानांतरित करना तथा पहुंच मार्ग का प्रावधान करना।

Shifting of existing garbage collection center and provision of approach road behind the community center in the residential colony of LBSI Airport, Varanasi. (Tender ID: 2025_AAI_256213_1)

संदर्भ : ई-निविदा खुलने की तिथि : 05.12.2025

प्रिय महोदय/Dear Sir,

- उपरोक्त कार्य की, कुल निविदा रकम रुपया 20,04,266.15 (रुपया बीस लाख चार हजार दो सौ छह एवं पन्द्रह पैसे मात्र) (जी.एस.टी. रहित) की मदद निविदा, जो कि कार्य की अनुमानित लागत रुपया 27.69 लाख (जी.एस.टी. रहित) से 27.63% (सत्ताइस दशमलव छः तीन प्रतिशत) कम है, आपके द्वारा निविदा प्रपत्र की अनुसूची 'अ' में दर्शायी गयी मद दरों पर भरी गई है, अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से स्वीकृत की जाती है।
Your tender for the work mentioned above is hereby accepted on behalf of the Chairman, Airports Authority of India at the net tender amount **Rs. 20,04,266.15** (Rupees Twenty Lakh Four Thousand Two Hundred Sixty Six point One Five only) (excluding GST) which is **27.63%** (Twenty Seven point Six Three percent) below to the estimated cost put to tender of **Rs. 27.69 lakhs** (excluding GST).
- उप महा प्रबन्धक (अभि०-सिविल), भा.वि.प्रा., लाल बहादुर शास्त्री अन्तर्राष्ट्रीय विमानपत्तन, वाराणसी इस कार्य के कार्य प्रभारी अभियन्ता होंगे। आपसे अनुरोध है कि दिनांक 25.12.2025 तक उप महा प्रबन्धक (अभि०-सिविल) के कार्यालय में उपस्थित होकर संविदा अनुबन्ध को हस्ताक्षरित कर पूर्ण करें। अनुबन्ध 100/- रुपए के गैर न्यायिक स्टाम्प पेपर पर सम्पादित किया जाएगा, स्टाम्प पेपर की कीमत आपके द्वारा वहन की जाएगी।
The DGM (Engg-Civil), AAI, Lal Bahadur Shastri International Airport, Varanasi shall be the Engineer-in-charge of the work. You are requested to attend the office of the DGM (Engg-Civil) by **25.12.2025** to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs. 100/- and the cost of stamp paper shall be borne by you.
- धरोहर राशि रुपया 83,070.00 (रुपया तिरासी हजार सत्तर मात्र) संविदा प्रपत्र के अनुच्छेद 1 ए पेज 16 के अनुसार प्रतिभूति निक्षेप राशि का हिस्सा मानकर उसमें बदल दिया जाएगा। कृपया शेष प्रतिभूति निक्षेप राशि रुपया 1,17,357.00 (रुपया एक लाख सत्तर हजार तीन सौ सत्तावन मात्र) इस पत्र के निर्गत दिनांक से दस दिनों के भीतर जमा करें अन्यथा उक्त धनराशि की कटौती संविदा प्रपत्र की उक्त संदर्भित शर्त के अनुसार चालू लेखा बिलों से की जाएगी।
The earnest money amount of **Rs. 83,070.00** (Rupees Eighty Three Thousand Seventy only) received along with your tender will be treated and converted as a part of security deposit. Please deposit **Rs. 1,17,357.00** (Rupees One Lakh Seventeen Thousand Three Hundred Fifty Seven only), towards balance security deposit within 10 days from the date of issue of this letter, failing which the same will be deducted from the Running Account Bills as per condition GCC 1A on page 16 of the contract document.

Deependra
15.12.2025

शेष पृष्ठ 2 पर....

[Signature]
15/12/2025

उप महाप्रबन्धक (अभि. - सिविल)
Dy. General Manager (Engg-Civil)

भारतीय विमानपत्तन प्राधिकरण

लाल बहादुर शास्त्री अन्तर्राष्ट्रीय हवाई अड्डा वाराणसी-221006
Lal Bahadur Shastri International Airport, Varanasi-221006

दूरभाष: 2622155-2622155 Authority फैक्स: 0542-2622320
Phone: 2622155-2622155 हवाई अड्डा फैक्स: 0542-2622320
Lal Bahadur Shastri Airport, Varanasi

इस कार्य आदेश के जारी होने 30 दिनों के अन्दर, निविदा दस्तावेज के जीसीसी के अनुच्छेद-1ब, पृष्ठ संख्या-17 के शर्त के अनुसार एक अतिरिक्त परफार्मेंस सुरक्षा अपरिवर्तनीय बीमा जमानत बाण्ड, डिमाण्ड ड्राफ्ट, अनुसूचित वाणिज्यिक बैंक से जारी बैंक गारन्टी के रूप में रु. 1,45,000/- (रुपया एक लाख पैतालीस हजार मात्र), निविदा दस्तावेज के जीसीसी में शामिल प्रोफार्मा पृष्ठ संख्या -108 एवं 109/अनुलग्नक-11 के अनुसार आप एएआई को जमा करेंगे।

Within 30 days of issue of this award letter, you shall submit to AAI, a **Additional Performance Security** as per GCC clause 1B/Page no. 17 of tender document for an amount of **Rs. 1,45,000/-** (Rupees One Lakh Fourty Five Thousand only) in the form of an irrevocable Insurance Surety bond, demand draft, bank guarantee issued from Scheduled Commercial Bank as per the Performa GCC Annexure-XI/Page no. 108 & 109 of tender document.

- 4) आपसे अनुरोध है कि संविदा श्रमिक प्रावधान (विनिमय एवं उन्मूलन) एक्ट 1970, श्रमिक प्रावधान (विनिमय एवं उन्मूलन)-केन्द्रीय नियम 1971, न्यूनतम मजदूरी अधिनियम एवं इस सम्बन्ध में केन्द्र/राज्य सरकार के नियमों का पालन करना सुनिश्चित करें।
You are requested to comply with the provisions of Contract Labour (Regulation & Abolition) Act of 1970 and Contract Labour (Regulation & Abolition) Central rules 1971 and Minimum Wages Act & Rules thereof Central and State Governments with upto date amendments.
- 5) आपको निर्देशित किया जाता है कि आप तुरन्त प्रभाव से कनिष्ठ कार्यपालक (अभि0-सि0), भा.वि.प्रा., लाल बहादुर शास्त्री अन्तर्राष्ट्रीय विमानपत्तन, वाराणसी से सम्पर्क करें जो आपको कार्यस्थल सौंपने की व्यवस्था करेंगे।
You are also directed to contact the Jr. Executive (E-C), AAI, Lal Bahadur Shastri International Airport, Varanasi, immediately who will arrange to hand over the site to you.
- 6) कृपया ध्यान दें कि कार्य पूर्ण करने की अवधि 02(दो) महीने हैं जो कि दिनांक 25.12.2025 से प्रभावी मानी जाएगी।
Please note that time allowed for carrying out the work shall be **02 (Two) months** and the same shall be reckoned from **25.12.2025**.
- 7) संविदा के सन्दर्भ में किसी भी प्रकार का पत्राचार सामान्यतः उप महा प्रबन्धक (अभि0-सिविल), भा.वि. प्रा., लाल बहादुर शास्त्री अन्तर्राष्ट्रीय हवाईअड्डा, वाराणसी-221006, को सम्बोधित करें।
Any further correspondence in connection with the contract should normally be addressed to the DGM (Engg-Civil), AAI, Lal Bahadur Shastri International Airport, Varanasi-221006
- 8) कृपया इस पत्र की पावती भेजें एवं पत्र कि अनुलिपि जो कि संलग्न है को हस्ताक्षरित कर अधोहस्ताक्षरी को स्वीकृत चिन्ह के रूप में वापस करें।
Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.
- 9) विषयक कार्य से संबंधित अनुसूची-अ, (कुल पृष्ठ 5 (सिविल कार्य रु. 20,04,266.15) संलग्न है।
Schedule 'A' (total page 5) (Civil works **Rs. 20,04,266.15**) of the work is enclosed.

उपरोक्त के हिन्दी पाठ में कोई अन्तर या द्विधार्थकता होने की स्थिति में अंग्रेजी पाठ मान्य होगा।
In case of difference or ambiguity in Hindi and English version, the English version will prevail.

धन्यवाद।

संलग्नक : उपरोक्त
Encl : As above

भवदीय



15/12/2025

उप महा प्रबन्धक (अभि.-सिविल)
Dy. General Manager (Engg-Civil)
अध्यक्ष, भा0वि0प्रा0 के लिए व उनकी हस्ताक्षर से
For and on behalf of the Chairman, AAI
Airports Authority of India
लाल बहादुर शास्त्री हवाई अड्डा, वाराणसी
Lal Bahadur Shastri Airport, Varanasi

प्रतिलिपि : मूल प्रति पर नहीं/(NOO)

(अ) बाहरी :

1. संयुक्त महा प्रबन्धक (अभि0)—उ0क्षे0, भाविप्रा, नई दिल्ली-110037 : सूचनार्थ
2. सहायक श्रम आयुक्त (सी), 189-ए/4ए, अलोपी बाग, पोस्ट-दारागंज, प्रयागराज : सूचनार्थ
3. श्रम प्रवर्तन अधिकारी (सी), 189-ए/4ए, अलोपी बाग, पोस्ट-दारागंज, प्रयागराज : सूचनार्थ (फार्म-7 संलग्न)

(ब) आंतरिक :

- | | | |
|---|---|------------------------|
| 1. निदेशक विमानपत्तन, वाराणसी | : | सूचनार्थ |
| 2. महा प्रबन्धक (अभि0)—प्रोजेक्ट, वाराणसी | : | —तदैव— |
| 3. प्रभारी (वित्त), वाराणसी | : | —तदैव— |
| 4. संयुक्त महा प्रबन्धक (अभि0—विद्युत), वाराणसी | : | —तदैव— |
| 5. उप महा प्रबन्धक (अभि—सिविल), वाराणसी | : | —तदैव— |
| 6. कनिष्ठ कार्यपालक (अभि0—सिविल), वाराणसी | : | आवश्यक कार्यवाही हेतु। |
| 7. कार्यादेश फाईल | : | |
| 8. अनुबन्ध | : | |

15/12/2025

उप महा प्रबन्धक (अभि—सिविल)
Dy. General Manager (Engg Civil)

भा.वि.प्रा, लाल बहादुर शास्त्री अन्तराष्ट्रीय विमानपत्तन
AAI, LBSI Airport, Varanasi
लाल बहादुर शास्त्री हवाई अड्डा, वाराणसी
Lal Bahadur Shastri Airport, Varanasi

Government eProcurement System
Created By: Pradip Kumar Gupta
Created Date/Time: 05-Dec-2025 12:52 PM
Tender Title: Shifting of existing garbage collection center and provision of approach road behind the community center in the residential colony of LBSI Airport, Varanasi
Tender ID: 2025_AAI_256213_1

Tender Inviting Authority: Airports Authority of India

Name of Work: Shifting of existing garbage collection center and provision of approach road behind the community center in the residential colony of LBSI Airport, Varanasi.

Contract No: 2025_AAI_256213_1

SCHEDULE OF WORK / ITEM(S)					
Sl.No	Description of Work / Item(s)	No.of Qty	Units	Utkarsh Enterprises (GSTN-NA) BID ID -934026	
				Rate	Amount
.10	Civil Works				
1.00	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge.All kinds of soil.	130.50	Cum	70.00	9135.00
2.00	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 and for all lift.	82.15	Cum	45.00	3696.75
3.00	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1)1:2:4 (1 cement : 2 coarse sand (zone-III) : 4 graded stone aggregate 20 mm nominal size. Note: The Aggregate used should be black aggregate from Dala quarry.	10.60	Cum	5500.00	58300.00
4.00	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:4:8 (1 Cement : 4 coarse sand (zone-III) derived from natural sources : 8 graded stone aggregate 40 mm nominal size derived from natural sources). Note: The Aggregate used should be black aggregate from Dala quarry.	42.40	Cum	4500.00	190800.00
5.00	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement -All work up to plinth level :1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources). Note: The Aggregate used should be black aggregate from Dala quarry.	15.25	Cum	6000.00	91500.00
6.00	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level.Thermo-Mechanically Treated bars of grade Fe-5000 or more.	3633.25	Kg	75.00	272493.75
7.00	Centering and shuttering including strutting, propping etc. and removal of form for Foundations, footings, bases of columns, etc. for mass concrete.	68.00	Sqm	200.00	13600.00

उप महाप्रबंधक (अभि - सिविल)
Dy. General Manager (Civil)
भारतीय विमानपत्तन प्राधिकरण
Airports Authority of India
लाल बहादुर शास्त्री हवाई अड्डा, वाराणसी
Lal Bahadur Shastri Airport, Varanasi

SCHEDULE OF WORK / ITEM(S)					
Sl.No	Description of Work / Item(s)	No.of Qty	Units	Utkarsh Enterprises (GSTN-NA) BID ID -934026	
				Rate	Amount
8.00	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in:Cement mortar 1:6 (1 cement : 6 coarse sand).	30.60	Cum	5805.65	177652.89
9.00	Providing and fixing mild steel round holding down bolts with nuts and washer plates complete.	146.70	Kg	72.25	10599.08
10.00	12 mm cement plaster : 1:6 (1 cement : 6 coarse sand)	83.50	Sqm	200.00	16700.00
11.00	15 mm cement plaster on rough side of single or half brick wall of mix:1:6 (1 cement: 6 coarse sand).	102.00	Sqm	220.00	22440.00
12.00	Providing and fixing precoated galvanised iron profile sheets of any curvature (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	168.80	Sqm	514.00	86763.20
13.00	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete.Hot finishshade welded type tubes.	2895.60	Kg	95.00	275082.00
14.00	Dismantling steel work in built up sections in angles, tees, flats and channels including all gusset plates, bolts, nuts, hard drawn steel wire fabric, cutting rivets, welding etc. including dismembering and stacking within AAI premises all lead and lift.	4123.85	Kg	2.75	11340.59
15.00	Dismantling roofing including ridges, hips, valleys and gutters etc., and stacking the material within AAI premises all lead and lift.: precoated galvanised iron profile sheets.	110.25	Sqm	55.00	6063.75
16.00	Demolishing brick work manually/ by mechanical means includingstacking of serviceable material and disposal of unserviceable materialwithin 50 metres lead as per direction of Engineer-in-charge. In cement mortar.	18.85	Cum	500.00	9425.00
17.00	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade :Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture with electric-powered handheld airless sprayers machine i/c cleaning, sand papering, metallic putty and repair of any holes/gaps/patches/cracks to provide smooth finish with satisfaction of Engg-In-Charge.	210.70	Sqm	92.00	19384.40


 उप महाप्रबन्धक (आर. ए. ई. सिविल)
 Dy. General Manager (Engg-Civil)
 भारतीय विमानपत्तन प्राधिकरण
 Airports Authority of India
 लाल बहादुर शास्त्री हवाई अड्डा, वाराणसी
 Lal Bahadur Shastri Airport, Varanasi

SCHEDULE OF WORK / ITEM(S)					
Sl.No	Description of Work / Item(s)	No.of Qty	Units	Utkarsh Enterprises (GSTN-NA) BID ID -934026	
				Rate	Amount
18.00	Finishing walls with Acrylic Smooth exterior paint of required shade : New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm) with electric-powered handheld airless sprayers machine i/c cleaning, sand papering, metallic putty and repair of any holes/gaps/patches/cracks to provide smooth finish with satisfaction of Engg-In-Charge..	113.50	Sqm	82.00	9307.00
19.00	Wall painting with acrylic emulsion paint, having VOC (Volatile Organic Compound) content less than 50 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour with electric-powered handheld airless sprayers machine i/c cleaning, sand papering, metallic putty and repair of any holes/gaps/patches/cracks to provide smooth finish with satisfaction of Engg-In-Charge. Two coats	72.00	Sqm	58.00	4176.00
20.00	Re-fixing of hard drawn steel wire fabric / mesh as desired by Engineer-in-charge, after receiving the steel wire fabric / mesh from the execution of item number 14, to be fixed / welded with existing MS structure including the cost of labour, tool & plants. All complete as per direction and satisfaction of Engineer-in-charge.	396.90	Kg	10.00	3969.00
21.00	Re-assembling of Steel structure work after receiving the steel member / component from the execution of item number 14, in built up tubular/single section trusses including cutting, hoisting, fixing in position welded and bolted including special shaped washers etc. All complete as per direction and satisfaction of Engineer-in-charge.	4123.85	Kg	40.00	164954.00
22.00	Removal of existing gate as and where basis, transportation to designated location within AAI premises and re-installation of modified gate with new ball bearings and hold fasts, if required, with welding, riveting all necessary accessories required to serve the purpose. All complete as per direction and satisfaction of engineer-in-charge. [Note: The rate quoted shall be inclusive of cost of complete gate, transportation, loading, unloading, Manpower welding, riveting, MS material etc].	1.00	Job	4695.00	4695.00


 16/12/2025
 उप महाप्रबंधक (अभि. - सिविल)
 Dy. General Manager (Engg-Civil)
 भारतीय विमानपत्तन प्राधिकरण
 Airports Authority of India
 लाल बहादुर शास्त्री हवाई अड्डा, वाराणसी
 Lal Bahadur Shastri Airport, Varanasi

SCHEDULE OF WORK / ITEM(S)					
Sl.No	Description of Work / Item(s)	No. of Qty	Units	Utkarsh Enterprises (GSTN-NA) BID ID -934026	
				Rate	Amount
23.00	Cement concrete 1:1.50:3 (1 cement : 1.50 coarse sand : 3 graded stone aggregate 10, 20 & 40 mm nominal size) in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete. Note-Compaction shall be done with needle vibrator and screed vibrator. The panel shall be made with C-Channel of the full height of concrete to be laid and floater machine will be applied there upon and proper texture will be made with brooming if required. Initially Mechanically cutting of dummy joints 3mm wide x 1/3rd thickness shall have to cut. Subsequently groove cutting as per dummy / construction/expansion joints will be done 10mm width x 50mm deep as per satisfaction of Engineer-in-Charge and Noting extra shall be paid for performing these activity. Note: Ajax will not be allowed for concrete work at any cost. For curing suitable curing compound shall have to be used / sprayed. Only black aggregate of Dala will be allowed to be used in concrete work.	50.00	Cum	6000.00	300000.00
24.00	Providing and filling in position rubberized bitumen hot sealing compound for sealing of expansion joints in roads / pavements all complete as per direction of the Engineer-in-Charge. Using grade 'A' sealing compound conforming to IS: 1834.	255.00	per cm depth per cm width per metre length	4.00	1020.00
25.00	Re-fixing of precoated galvanised iron profile sheets as desired by Engineer-in-charge, after receiving the sheet from the execution of item number 15. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. The existing holes shall be fillup with m-seal or other suitable material.	110.25	Sqm	85.00	9371.25
26.00	Providing and operating excavator (3D) for cutting thick growth of bushes, soft trees and removal of any heaps and malba etc. wherever grass cutting tractor & labour inaccessible in non-operational area wherever required with transporting to and fro at the site including fuel, driver and any other incidental break down charges on this account etc as directed by Engineer- In-Charge.	36.00	Hrs	1000.00	36000.00
27.00	Boring/drilling bore well of required dia for casing/ strainer pipe, by suitable method prescribed in IS: 2800 (part I), including collecting samples from different strata, preparing and submitting strata chart/ bore log, including hire & running charges of all equipments, tools, plants & machineries required for the job in operational area, all complete as per direction of Engineer-in-charge, upto 90 metre depth below ground level. All types of soil 300 mm dia	180.00	Mtr	392.00	70560.00
28.00	Supplying, assembling, lowering and fixing in vertical position in bore well, unplasticized PVC medium well casing (CM) pipe of required dia, conforming to IS: 12818, including required hire and labour charges, fittings & accessories etc in operational area. all complete, for all depths, as per direction of Engineer -in-charge. 150 mm nominal size dia.	120.00	Mtr	435.00	52200.00


 उप महाप्रबंधक (अभिन. - सिविल)
 Dy. General Manager (Engg-Civil)
 भारतीय विमानपत्तन प्राधिकरण
 Airports Authority of India
 लाल बहादुर शास्त्री हवाई अड्डा, वाराणसी
 Lal Bahadur Shastri Airport, Varanasi

SCHEDULE OF WORK / ITEM(S)					
SI.No	Description of Work / Item(s)	No.of Qty	Units	Utkarsh Enterprises (GSTN-NA) BID ID -934026	
				Rate	Amount
29.00	Supplying, assembling, lowering and fixing in vertical position in bore well unplasticized PVC medium well screen (RMS) pipes with ribs, conforming to IS: 12818, including hire & labour charges, fittings & accessories etc in operational area. all complete, for all depths, as per direction of Engineer-in-charge. 150 mm nominal size dia.	40.00	Mtr	445.00	17800.00
30.00	Gravel packing in tubewell construction in accordance with IS: 4097, including providing gravel fine/ medium/ coarse, in required grading & sizes as per actual requirement in operational area, all complete as per direction of Engineer-in-charge.	9.50	Cum	985.00	9357.50
31.00	Development of tube well in accordance with IS : 2800 (part I) and IS: 11189, to establish maximum rate of useable water yield without sand content (beyond permissible limit), with required capacity air compressor, running the compressor for required time till well is fully developed, measuring yield of well by "V" notch method or any other approved method, measuring static level & draw down etc. by step draw down method, collecting water samples & getting tested in approved laboratory, including disinfection of tubewell, all complete, including hire & labour charges of air compressor, tools & accessories etc in operational area, all as per requirement and direction of Engineer-in-charge.	24.00	Hrs	570.00	13680.00
32.00	Providing and fixing M.S. clamp of required dia to the top of casing/ housing pipe of tubewell as per IS: 2800 (part I), including necessary bolts & nuts of required size complete. 150 mm clamp.	2.00	Each	700.00	1400.00
33.00	Providing and fixing Bail plug/ Bottom plug of required dia to the bottom of pipe assembly of tubewell as per IS:2800 (part I). 150 mm dia	2.00	Each	150.00	300.00
34.00	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. 40 mm nominal dia Pipes	100.00	Mtr	350.00	35000.00
35.00	Credit item for taking away of steel work in frames, shutters, trusses, channels, beams, Tee, angles, bolts, washers, gusset plates etc. and the like received from dismantling & unused. The material so received shall be the property of contractor after dismantling duly weighed/ measured before removing from the site in the presence of Engineer-in-charge or his authorised representative all complete.	150.00	Kg	30.00	-4500.00

Total in Figures

2004266.15

Lowest Amount Quoted BY: Utkarsh Enterprises(2004266.15)

Signature Not Verified
Digitally signed by PRADIP KUMAR GUPTA
Date: 2026.03.19 11:15:13 IST
Location: eProcurement System for Central PSUs Airport, Varanasi