



भाविप्रा/वडोदरा/सहायक महा.प्र(अभि-सि)/डब्ल्यू-294/2025-26/ 1423
AAI/VAD/AGM (Engg-C)/W-294/2025-26/

दिनांक: 10/02/2026

Date: 10/02/2026

सेवा मे,
मेसर्स एम एल ब्रदर,
एफ - 22/117,
सैक्टर - 3, रोहिणी - 110085,
दिल्ली

To,
M/s. M L Brother,
F22/117, Sector 3,
Rohini - 110085
Delhi

कार्य का नाम : वडोदरा एयरपोर्ट पर नए ATC टावर कम टेक्निकल ब्लॉक के लिए पार्किंग
शेड, इलेक्ट्रिकल स्टोर, RCC पानी की टंकी और उससे जुड़े कामों का इंतजाम।
(Tender ID – 2025_AAI_257924_1)

Name of Work: Provision of parking shed for New ATC tower cum Technical Block and Store
for electrical, RCC water Tank and allied works at Vadodara Airport.
(Tender ID – 2025_AAI_257924_1)

संदर्भ:- दिनांक 05/01/2026 को खोला गया आपका ई-टेंडर । (वित्तीय बोली)

Ref: - Your e-tender opened on 05/01/2026 (Financial Bid)

महोदय/Sir,

1. उपर्युक्त कार्य हेतु आपकी निविदा अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से, आपके द्वारा बताए गये मद दर मूल्यों पर निविदा की राशि कुल **₹. 96,70,632.00/- (रुपये छियानवे लाख सत्तर हजार छह सौ बत्तीस, मात्र)** (जीएसटी रहित) स्वीकृत किया जाता है, जो कि निविदा की अनुमानित लागत राशि **₹. 120.14 लाख** (जीएसटी रहित) से 19.51 % नीचे है।

Your tender for the work mentioned above is hereby accepted on behalf of the Chairman, Airports Authority of India at the item rates quoted by you totaling to **Rs. 96,70,632/- (Excluding GST) (Rupees Nineth-Six Lakh Seventy Thousand Six Hundred Thirty-Two, only)**, which is 19.51 % below the estimated cost put to tender of **Rs. 120.14 Lakh (Excluding GST)**.

2. सहायक महाप्रबंधक (अभि-सिविल), भाविप्रा, वडोदरा कार्य प्रभारी अभियंता होंगे । आपसे निवेदन है कि आप स्वयं या आपकी ओर से एक विश्वसनीय प्रतिनिधि प्रतिनियुक्त करे जो करारनामे पर हस्ताक्षर करने के लिए अधिकृत हो तथा वह दिनांक **20/02/2026** तक सहायक महाप्रबंधक (अभि-सिविल), भाविप्रा, वडोदरा के कार्यालय में उपस्थित हो तथा करारनामे को पूरा करे। ठेके का करारनामा **₹. 300/- (₹. तीन सौ, मात्र)** के नोन ज्यूडिशियल स्टैम्प पेपर पर निष्पादित किया जाएगा, तथा पेपर का खर्च आपके द्वारा वहन किया जाएगा ।

Assistant General Manager (Engg-Civil), AAI, Vadodara shall be the Engineer-In-Charge of the work. You are requested to attend or depute your accredited representative, empowered to sign the contract agreement on your behalf, to attend the office of the Assistant General Manager (Engg-Civil), AAI, Vadodara by **20/02/2026** to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value **Rs. 300/- (Rs. Three Hundred, only)** and the cost of the stamp paper shall be borne by you.

पवन नै. पारधी
10.02.2026

पवन नै. पारधी / PAWAN N. PARDHI

सहायक महाप्रबंधक (अभि-सि)

Asstt General Manager (E-C)

भा.वि.प्रा. वडोदरा विमानक्षेत्र / AAI, VADODARA AIRPORT



3. इस पत्र के जारी होने की तारीख से 30 दिनों के भीतर सुरक्षा जमा राशि के लिए, **रु. 9,67,063/- (रुपए नौ लाख सड़सठ हजार तिरसठ, मात्र)** जमा करे जोकि अनुबंध मूल्य का 10% है। ऐसा न करने पर निविदा दस्तावेज के जीसीसी के खंड 1A पृष्ठ 16 के अनुसार चालू खाता बिल से काट लिया जाएगा। आपके टेंडर के साथ प्राप्त ईएमडी राशि **रु. 3,60,420/- (रुपए तीन लाख साठ हजार चार सौ बीस मात्र)** ऑनलाइन वापस कर दी जाएगी जब बिल से काटी गयी एसडी की राशि **रु. 3,60,420/-** हो जाएगी।

आपको दिनांक 21/01/2026 को दिये गए पत्र के अनुसार आपके द्वारा 30 दिनों के भीतर **रु. 2,41,000/- (रुपये दो लाख इकतालीस हजार, मात्र)** अतिरिक्त निष्पादन सुरक्षा राशि जमा करने हेतु निर्देश दिया गया था। निविदा के सामान्य नियम और निर्देश - पैरा 14 (vi) और अनुबंध का क्लॉज़ 1 (B): अतिरिक्त परफॉर्मेंस सिक्योरिटी के अनुसार **रु. 2,41,000/- (रुपये दो लाख इकतालीस हजार, मात्र)** अतिरिक्त निष्पादन सुरक्षा, निविदा दस्तावेज के पृष्ठ संख्या 10 के मुताबिक बैंक गैरंटी के तौर पर अतिरिक्त परफॉर्मेंस सिक्योरिटी के रूप में दिनांक 10/02/2026 को आपके द्वारा प्रस्तुत की गयी है।

Within 10 days from the date of issuance of this letter, please deposit the security deposit amount of **Rs. 9,67,063/- (Rupees Nine Lakh Sixty-Seven Thousand and Sixty-Three only)**, which is 10% of the contract value. Failure to do so will result in the amount being deducted from your running account bill as per Clause 1A, page 16 of the GCC of the tender document. The EMD amount of **Rs. 3,60,420/- (Rupees Three Lakh Sixty Thousand Four Hundred and Twenty only)** received with your tender will be refunded online once the deducted security deposit amount from the bill reaches **Rs. 3,60,420/-**.

As per the letter issued to you on 21/01/2026, you were instructed to deposit an additional performance security amount of **Rs. 2,41,000/- (Rupees Two Lakh Forty-One Thousand only)** within 30 days. In accordance with the General Terms and Conditions of Tender - Paragraph 14 (vi) and Clause 1 (B) of the Agreement: Additional Performance Security, you have submitted an additional performance security of **Rs. 2,41,000/- (Rupees Two Lakh Forty-One Thousand only)** in the form of a Bank Guarantee, as mentioned on page 10 of the tender document on Dt. 10/02/2026.

4. आपसे अनुरोध है कि अनुबंध श्रम (विनियमन और उन्मूलन) अधिनियम 1970 और अनुबंध श्रम (विनियमन और उन्मूलन) 1971 केंद्रीय नियमों के प्रावधान का पालन करे, बाल श्रम (निषेध और विनियमन) अधिनियम 1986, निर्माण कार्यकर्ता (रोजगार का विनियमन और सेवा की शर्त) अधिनियम 1996, बिल्डिंग और अन्य निर्माण कार्यकर्ता कल्याण सेस अधिनियम 1996 जैसा कि निविदा के जीसीसी के खंड 19 पृष्ठ 49 और केंद्रीय तथा राज्य सरकार के नियमों में निर्दिष्ट है। You are requested to comply with the provision of Contract labour (Regulation and Abolition) Act 1970 and Contract labour (Regulation and Abolition) Central rules 1971 Child labour (Prohibition and Regulation) Act 1986, Construction workers (Regulation of Employment and Condition of service) Act 1996, Building and other construction workers welfare cess act 1996 as specified in clause 19 page 49 of GCC of tender & minimum wage act and rules of Central and state government.

5. आपको निर्देश दिया जाता है कि आप तुरंत **प्रबंधक (अभि-सिविल)**, वडोदरा विमानक्षेत्र से मिले वह आपको साइट सौंपने की व्यवस्था करेंगे। कृपया नोट कर ले कि काम करने का अनुमत समय **06 (छह) महीने** होगी जोकि इस पत्र के जारी होने के दस दिन बाद से गिना जाएगा।

You are also directed to contact **Manager (Engg-Civil)** Vadodara Airport immediately who will arrange to hand over the site to you. Please note that the time allowed for carrying out the work is **06 Months (Six) Months** which shall be reckoned from 10th days after the issuance of this letter.

पवन नै. पारधी
10.02.2026

पवन नै. पारधी / PAWAN N. PARDHI

सहायक महाप्रबंधक (अभि-सि)

Asstt General Manager (E-C)

भा.प्र.प्र. वडोदरा विमानक्षेत्र /AAI, VADODARA AIRPORT



6. इस ठेके के संबंध में आगे की कोई भी पत्राचार सहायक महाप्रबंधक (अभि-सिविल), भाविप्रा, वडोदरा विमानक्षेत्र, वडोदरा 390022 के पते पर किया जाए।
Any further correspondence in connection with the contract should normally be addressed to the **Asstt. General Manager (Engg- Civil)**, AAI, Vadodara Airport, Vadodara -390022.
7. उपरोक्त संदर्भित सभी पत्र इस ठेके का भाग होंगे।
All the letters referred above shall form part of contract.
8. उपर्युक्त कार्य के लिए त्रुटि दायित्व की अवधि **12 (बारह)** महीने होगी।
The defects liability period for the above-mentioned work is **12 (Twelve)** months.
9. यदि ठेकेदार सुरक्षा नियमों का भंग करेगा तो उनको कालियादी में सम्मिलित किया जाएगा एवं उचित कानूनी कार्यवाही के लिए भी जिम्मेदार होगा।
If Contractor is found Violate any of Security Regulations, he shall be Black listed and will be subjected to other Legal Proceedings.
10. स्वीकृति के प्रतीक के रूप में अधिसूचना में हस्ताक्षर करने के बाद कृपया इस पावती को स्वीकार करें और इस पत्र की नकल प्रतिलिपि वापस करें।
Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.
11. यदि कोई विसंगति पाई जाती है तो अंग्रेजी संस्करण को सही रूप में लिया जाएगा।
In case any discrepancy is found then English version will be taken as correct.

भवदीय /Yours faithfully

पवन पार्थी
10-02-2016

सहायक महाप्रबंधक (अभि-सिविल) / PAWAN N. PARDHI
सहायक महाप्रबंधक (अभि-सिविल)
वडोदरा हवाई अड्डा, वडोदरा General Manager (E-C)
कृते अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण
AGM (Engg.-Civil), Vadodara Airport
For and on behalf of Chairman
Airports Authority of India

Item Rate BoQ

Tender Inviting Authority: Assistant General Manager (Engg - Civil), Airports Authority of India, Vadodara Airport, Vadodara - 390022

Name of Work: Provision of parking shed for New ATC tower cum Technical Block, Store for electrical, RCC water Tank and allied works at Vadodara Airport.

Contract No: AAI/VAD/AGM(E-C)/ATC Parking & Other works/2025-26 (Tender ID No: 2025_AAI_257924_1)

Name of the Bidder/ Bidding Firm / Company :

M/S M L BROTHER

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words	TEXT #
1	2	4	5	13	53	55	
1.01	SCHEDULE OF QUANTITY Taking out existing CC interlocking paver blocks from footpath/ central verge, including removal of rubbish etc., disposal of unserviceable material to the dumping ground, for which payment shall be made separately and stacking of serviceable material within 50 metre lead as per direction of Engineer-in-Charge.	51.00	Sqm	200.00	10200.00	INR Ten Thousand Two Hundred & Paise Zero Only	
2.01	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer-in-charge. Nominal concrete 1:4:8 or leaner mix (including equivalent design mix)	14.00	Cum	1000.00	14000.00	INR Fourteen Thousand & Paise Zero Only	
3.01	Earth work in excavation by mechanical means (Hydraulic excavator/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and for all lift, as directed by Engineer-in-charge. All kind of soil	821.00	Cum	150.00	123150.00	INR One Lakh Twenty Three Thousand One Hundred Fifty & Paise Zero Only	
4.01	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:4:8 (1 Cement : 4 coarse sand (zone-III) derived from natural sources : 8 graded stone aggregate 40 mm nominal size derived from natural sources)	210.00	Cum	4500.00	945000.00	INR Nine Lakh Forty Five Thousand & Paise Zero Only	




BOQ.1

Signature
Date 10.02.2026

Signature
Date 05.01.2026

Signature
Date 05.01.2026

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words	
1	2	4	5	13	53	55	
5.01	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : 1:1.5:3 (1 cement : 1.5 coarse sand/zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	35.00	Cum	6000.00	210000.00	INR Two Lakh Ten Thousand & Paise Zero Only	
6.01	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. above plinth level up to floor five level, excluding cost of centering, shuttering, finishing and reinforcement : 1:1.5:3 (1 cement : 1.5 coarse sand/zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	4.00	Cum	6000.00	24000.00	INR Twenty Four Thousand & Paise Zero Only	
7.01	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 (1 cement : 1.5 coarse sand/zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	9.00	Cum	6000.00	54000.00	INR Fifty Four Thousand & Paise Zero Only	
8.01	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	12610.00	Kg	79.00	996190.00	INR Nine Lakh Ninety Six Thousand One Hundred Ninety & Paise Zero Only	
9.01	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	910.00	Kg	120.00	109200.00	INR One Lakh Nine Thousand Two Hundred & Paise Zero Only	
10.01	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Hot finished welded type tubes	10589.00	Kg	120.00	1270680.00	INR Twelve Lakh Seventy Thousand Six Hundred Eighty & Paise Zero Only	

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words
1	2 Providing and fixing pre-coated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-Charge) of total coated thickness 0.50mm (base metal of minimum 0.45mm thickness with total coating thickness of 0.05mm) with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	4	5	13	53	55
11.01		572.00	Sqm	750.00	429000.00	INR Four Lakh Twenty Nine Thousand & Paise Zero Only
12.01	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade: Two or more coats on new work	392.00	Sqm	100.00	39200.00	INR Thirty Nine Thousand Two Hundred & Paise Zero Only
13.01	Providing and fixing pre-coated galvanised steel sheet roofing accessories of total coated thickness 0.50mm (base metal of minimum 0.45mm thickness with total coating thickness of 0.05mm) with Zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns using self drilling/ self tapping screws complete : Ridges plain (500 - 600mm)	78.00	Meter	400.00	31200.00	INR Thirty One Thousand Two Hundred & Paise Zero Only
14.01	Providing and fixing pre-coated galvanised steel sheet roofing accessories of total coated thickness 0.50mm (base metal of minimum 0.45mm thickness with total coating thickness of 0.05mm) with Zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns using self drilling/ self tapping screws complete : Gutter (600 mm over all girth)	151.00	Meter	500.00	75500.00	INR Seventy Five Thousand Five Hundred & Paise Zero Only
15.01	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS: 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes. 75 mm diameter	100.00	Meter	400.00	40000.00	INR Forty Thousand & Paise Zero Only
16.01	Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion. Bend 87.5° 75 mm bend	64.00	Each	300.00	19200.00	INR Nineteen Thousand Two Hundred & Paise Zero Only

BOQ 3

44/11/21
21/11/21
10.02.2021

Signature
Date
Page (Final)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words	TEXT #
1	2	4	5	13	53	55	
17.01	Laying old cement concrete interlocking paver blocks of any design/ shape laid in required line, level, curvature, colour and pattern over and including 50 mm thick compacted bed of coarse sand, filling the joints with fine sand etc. all complete as per the direction of Engineer-in-charge. (Old CC paver blocks shall be supplied by the department free of cost).	49.00	Sqm	1000.00	49000.00	INR Forty Nine Thousand & Paise Zero Only	
18.01	Brick work with clay flyash F.P.S. (non modular) bricks of class designation 5 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6 coarse sand)	19.00	Cum	6000.00	114000.00	INR One Lakh Fourteen Thousand & Paise Zero Only	
19.01	Brick work with clay flyash F.P.S. (non modular) brick of class designation 5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:4 (1 cement : 4 coarse sand)	23.00	Cum	6000.00	138000.00	INR One Lakh Thirty Eight Thousand & Paise Zero Only	
20.01	15 mm cement plaster on rough side of single or half brick wall of mix : 1:6 (1 cement : 6 coarse sand)	159.00	Sqm	300.00	47700.00	INR Forty Seven Thousand Seven Hundred & Paise Zero Only	
21.01	12 mm cement plaster of mix : 1:6 (1 cement : 6 coarse sand)	138.00	Sqm	250.00	34500.00	INR Thirty Four Thousand Five Hundred & Paise Zero Only	
22.01	6 mm cement plaster of mix : 1:3 (1 cement : 3 fine sand)	63.00	Sqm	200.00	12600.00	INR Twelve Thousand Six Hundred & Paise Zero Only	
23.01	Applying priming coats with primer of approved brand and manufacture, having low VOC (Volatile Organic Compound) content. With water thinnable cement primer on wall surface having VOC content less than 50 grams/litre.	243.00	Sqm	80.00	19440.00	INR Nineteen Thousand Four Hundred Forty & Paise Zero Only	
24.01	Wall painting with acrylic emulsion paint, having VOC (Volatile Organic Compound) content less than 50 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour. Two coats.	164.00	Sqm	120.00	19680.00	INR Nineteen Thousand Six Hundred Eighty & Paise Zero Only	
25.01	Finishing walls with Acrylic Smooth exterior paint of required shade : New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 0.90 litre/10 sqm)	195.00	Sqm	120.00	23400.00	INR Twenty Three Thousand Four Hundred & Paise Zero Only	
26.01	Kota stone slab flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1 : 4 (1 cement : 4 coarse sand) : 25 mm thick	125.00	Sqm	1500.00	187500.00	INR One Lakh Eighty Seven Thousand Five Hundred & Paise Zero Only	

Pravin Kumar
5-9-22
mya (Fin)

Pravin Kumar
05.01.2024

Pravin Kumar
22/11/23
10-02-2024

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words		
1	2 Providing and fixing ISI marked flush door shutters conforming to IS : 2202 (Part I) non-decorative type, core of block board construction with frame of 1st class hard wood and well matched teak 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters. 30 mm thick including ISI marked Stainless Steel butt hinges with necessary screws Extra for providing lipping with 2nd class teak wood battens 25 mm minimum depth on all edges of flush door shutters (over all area of door shutter to be measured).	4	5	13	53	55		
27.01		8.00	Sqm	3500.00	28000.00	INR Twenty Eight Thousand & Paise Zero Only		
28.01		8.00	Sqm	100.00	800.00	INR Eight Hundred & Paise Zero Only		
29.01		6.00	Each	100.00	600.00	INR Six Hundred & Paise Zero Only		
30.01		4.00	Each	300.00	1200.00	INR One Thousand Two Hundred & Paise Zero Only		
31.01		4.00	Each	100.00	400.00	INR Four Hundred & Paise Zero Only		
32.01		38.00	Cum	100.00	3800.00	INR Three Thousand Eight Hundred & Paise Zero Only		
33.01		54.00	Cum	7000.00	378000.00	INR Three Lakh Seventy Eight Thousand & Paise Zero Only		

BOQ.5

(Signature)
05.01.2016

पंजीकृत
24.12.2015
10-02-2016

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words			
1	2	4	5	13	53	55			
34.01	Add for using extra cement in the items of design mix over and above the specified cement content therein. Providing and mixing integral crystalline admixture for water proofing treatment to RCC structures like basement raft, retaining walls, reservoir, sewage & water treatment plant, tunnels / subway and bridge deck etc. at the time of transporting of concrete into the drum of the ready-mix truck, using integral crystalline admixture @0.80% (minimum) to the weight of cement content per cubic meter of concrete) or higher as recommended by the manufacturer's specification in reinforced cement concrete at site of work. The material shall meet the requirements as specified in ACI212-3R-2010 i.e. by reducing permeability of concrete by more than 90%, compared with control concrete as per DIN 1048 and resistant to 16 bar hydrostatic pressure. The crystalline admixture shall be capable of selfhealing of cracks up to a width of 0.50 mm. The work shall be carried out all complete as per specification and the direction of the Engineer-in-charge. The product performance shall carry guarantee for 10 years against any leakage.	11.00	Qtl.	500.00	5500.00	INR Five Thousand Five Hundred & Paise Zero Only			
35.01		158.00	Kg	350.00	55300.00	INR Fifty Five Thousand Three Hundred & Paise Zero Only			
36.01	Providing and Placing in position suitable PVC water stops conforming to IS:12200 for construction/ expansion joints between two RCC members and fixed to the reinforcement with binding wire before pouring concrete etc. complete : Serrated with central bulb (225 mm wide, 8-11 mm thick)	94.00	Meter	250.00	23500.00	INR Twenty Three Thousand Five Hundred & Paise Zero Only			
37.01	Making plinth protection 50mm thick of cement concrete 1:3:6 (1 cement : 3 coarse sand (zone-II) derived from natural sources : 6 graded stone aggregate 20 mm nominal size derived from natural sources) over 75mm thick bed of dry brick ballast 40 mm nominal size, well rammed and consolidated and grouted with fine sand, including necessary excavation leveling & dressing & finishing the top smooth.	21.00	Sqm	500.00	10500.00	INR Ten Thousand Five Hundred & Paise Zero Only			
38.01	Providing and fixing in position pre-cast R.C.C. manhole cover and frame of required shape and approved quality H D - 20. Circular shape 560 mm internal diameter	2.00	Each	5000.00	10000.00	INR Ten Thousand & Paise Zero Only			
39.01	Providing M.S. foot rests including fixing in manholes with 20x20x10 cm cement concrete blocks 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size) as per standard design : With 20 mm diameter round bar	16.00	Each	200.00	3200.00	INR Three Thousand Two Hundred & Paise Zero Only			

Pravin Kumar
10-12-2016

Pravin Kumar
10-12-2016

Pravin Kumar
10-12-2016

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words	TEXT #
1	2 Supplying and fixing rolling shutters of approved make, made of required size M.S. laths, interlocked together through their entire length and jointed together at the end by end locks, mounted on specially designed pipe shaft with brackets, side guides and arrangements for inside and outside locking with push and pull operation complete, including the cost of providing and fixing necessary 27.5 cm long wire springs manufactured from high tensile steel wire of adequate strength conforming to IS: 4454 - part 1 and M.S. top cover of required thickness for rolling shutters. 80x0.90 mm M.S. laths with 0.90 mm thick top cover	4	5	13	53	55	
40.01		5.00	Sqm	4000.00	20000.00	INR Twenty Thousand & Paise Zero Only	
41.01	Providing and fixing ball bearing for rolling shutters.	2.00	Each	500.00	1000.00	INR One Thousand & Paise Zero Only	
42.01	Centering and shuttering including strutting, propping, etc. and removal of forms for: Foundation, footings, bases of columns, etc for mass concrete.	46.00	Sqm	400.00	18400.00	INR Eighteen Thousand Four Hundred & Paise Zero Only	
43.01	Centering and shuttering including strutting, propping, etc. and removal of forms for: Columns, pillars, piers, abutments, Posts and struts	33.00	Sqm	400.00	13200.00	INR Thirteen Thousand Two Hundred & Paise Zero Only	
44.01	Centering and shuttering including strutting, propping, etc. and removal of forms for: Lintels, beams, plinth beams, girders, bressumers and cantilevers	63.00	Sqm	400.00	25200.00	INR Twenty Five Thousand Two Hundred & Paise Zero Only	
45.01	Centering and shuttering including strutting, propping, etc. and removal of forms for: Walls (any thickness) including attached pilasters, buttresses, plinth and string courses, etc.	156.00	Sqm	400.00	62400.00	INR Sixty Two Thousand Four Hundred & Paise Zero Only	
46.01	Centering and shuttering including strutting, propping, etc. and removal of forms for: Suspended floors, roofs, landings, balconies and access platform	107.00	Sqm	400.00	42800.00	INR Forty Two Thousand Eight Hundred & Paise Zero Only	
47.01	Centering and shuttering including strutting, propping, etc. and removal of forms for: Edges of slabs and breaks in floors and walls Under 20cm wide	64.00	meter	400.00	25600.00	INR Twenty Five Thousand Six Hundred & Paise Zero Only	
48.01	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 and for all lift.	101.00	Cum	150.00	15150.00	INR Fifteen Thousand One Hundred Fifty & Paise Zero Only	

24/12/2019
21/12/2019
10.02.2020

AS per
05.01.2020

5.1.20
Mga (Finan)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words	
1	2	4	5	13	53	55	
49.01	Providing & fixing UV stabilised fiberglass reinforced plastic sheet roofing up to any pitch, including fixing with polymer coated 'J' or 'L' hooks, bolts & nuts 8mm dia. G.I plain/bitumen washers complete but excluding the cost of purlins, rafters, trusses etc. The sheets shall be manufactured out of 2400 TEX panel roving incorporating minimum 0.3% ultra-violet stabiliser in resin system under approximately 2400 psi and hot cured. They shall be of uniform pigmentation and thickness without air pockets and shall conform to IS 10192 and IS 12866. The sheets shall be opaque or translucent, clear or pigmented, textured or smooth as specified. 2 mm thick flat	165.00	Sqm	500.00	82500.00	INR Eighty Two Thousand Five Hundred & Paise Zero Only	
50.01	Providing and fixing mild steel round holding down bolts with nuts and washer plates complete.	133.00	Kg	150.00	19950.00	INR Nineteen Thousand Nine Hundred Fifty & Paise Zero Only	
51.01	Grading roof for water proofing treatment with Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	3.00	Cum	6999.00	20997.00	INR Twenty Thousand Nine Hundred Ninety Seven & Paise Zero Only	
52.01	Forming groove of uniform size from 12x12 mm and upto 25x15 mm in the top layer of washed stone grit plastered surface as per approved pattern, including providing and fixing aluminum channels of appropriate size and thickness (not less than 2 mm), nailed to the under layer with rust proof screws and nails and finishing the groove complete as per specifications and direction of the Engineer-in-Charge.	31.00	Meter	400.00	12400.00	INR Twelve Thousand Four Hundred & Paise Zero Only	
53.01	Providing and laying 60mm thick factory made cement concrete interlocking paver block of M-30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge.	1800.00	Sqm	700.00	1260000.00	INR Twelve Lakh Sixty Thousand & Paise Zero Only	
54.01	Construction of granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by tippers to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge. With material conforming to Grade-II (size range 53 mm to 0.075 mm) having CBR Value-25	239.00	Cum	2500.00	597500.00	INR Five Lakh Ninety Seven Thousand Five Hundred & Paise Zero Only	

10.12.2024
 05.01.2025
 AGC/ED
 05.01.2025
 BOQ 8

Signature
 05.01.2025
 05.01.2025

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words	
1	2	4	5	13	53	55	
55.01	Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm to 0.075 mm) to wet mix macadam (WMM) specification including premixing the material with water at OMC in for all leads & lifts, laying in uniform layers with mechanical paver finisher in sub-base / base course on well prepared surface and compacting with vibratory roller of 8 to 10 tonne capacity to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge.	179.00	Cum	4000.00	716000.00	INR Seven Lakh Sixteen Thousand & Paise Zero Only	
56.01	Providing and laying LDPE Sheet of 300 microns Confirming to IS:2508 on the base course with overlaps of not less than 100 mm longitudinally and 150mm transversely complete as per specification and as directed by Engineer-In-Charge	1193.00	Sqm	50.00	59650.00	INR Fifty Nine Thousand Six Hundred Fifty & Paise Zero Only	
57.01	Providing and laying C.C. pavement of mix M-25 with ready mixed concrete from batching plant. The ready mixed concrete shall be laid and finished with screed board vibrator, vacuum dewatering process and finally finished by floating, brooming with wire brush etc. complete as per specifications and directions of Engineer-in-charge. (The panel shuttering work shall be paid for separately). (Note:- Cement content considered in this item is @ 330 kg/cum. Excess/less cement used as per design mix is payable/ recoverable separately).	179.00	Cum	6000.00	1074000.00	INR Ten Lakh Seventy Four Thousand & Paise Zero Only	
58.01	Construction of dummy/ constructional joint Mechanically by cutting the pavement 3mm wide x 1/3 thickness of slab which is subsequently widened to 10mm for top 10mm Depth all complete as per direction of the Engineer-in-Charge.	356.00	Meter	100.00	35600.00	INR Thirty Five Thousand Six Hundred & Paise Zero Only	
59.01	Providing and fixing pre-moulded joint filler in expansion joints of RCC roads / CC pavements after making the joints dust free with high pressure air jet cleaners, all complete as per direction of the Engineer-in-Charge. (Pre-moulded joint fillers shall be made of bitumen hot sealing compound impregnated fibre board having impregnation more than 35%, conforming to IS:1838 for fibre board and IS: 1834 for hot sealing bitumen compound grade A.)	495.00	per cm depth per cm width per metre length	5.00	2475.00	INR Two Thousand Four Hundred Seventy Five & Paise Zero Only	
60.01	Providing and filling in position rubberized bitumen hot sealing compound for sealing of expansion joints in roads / pavements all complete as per direction of the Engineer-in-Charge. Using grade 'A' sealing compound conforming to IS: 1834.	1734.00	per cm depth per cm width per metre length	5.00	8670.00	INR Eight Thousand Six Hundred Seventy & Paise Zero Only	
Total in Figures					9670632.00	INR Ninety Six Lakh Seventy Thousand Six Hundred Thirty Two & Paise Zero Only	
Quoted Rate in Words							

BOO.9

21/11/2016
10.02.2016



भाविप्रा/वडोदरा/सहायक महा.प्र(अभि-सि)/डब्ल्यू-295/2025-26/
AAI/VAD/AGM (Engg-C)/W-295/2025-26/

दिनांक: 19/02/2026

Date: 19/02/2026

सेवा मे,

मेसर्स एम एल ब्रदर,

एफ - 22/117,

सैक्टर - 3, रोहिणी - 110085,

दिल्ली

To,

M/s. M L Brother,

F22/117, Sector 3,

Rohini - 110085

Delhi

कार्य का नाम : वडोदरा एयरपोर्ट पर नए ATC टावर कम टेक्निकल ब्लॉक के लिए पार्किंग शेड,
इलेक्ट्रिकल स्टोर, RCC पानी की टंकी और उससे जुड़े कामों का इंतज़ाम।
(Tender ID – 2025_AAI_257924_1)

Name of Work: Provision of parking shed for New ATC tower cum Technical Block and Store
for electrical, RCC water Tank and allied works at Vadodara Airport.
(Tender ID – 2025_AAI_257924_1)

संदर्भ:- भाविप्रा/वडोदरा/सहायक महा.प्र(अभि-सि)/डब्ल्यू-294/2025-26/1423 दिनांक: 10/02/2026

Ref: - AAI/VAD/AGM (Engg-C)/W-294/2025-26/1423 Dt. 10/02/2026

महोदय/Sir,


उपर्युक्त कार्य हेतु मे/स एम एल ब्रदर, नई दिल्ली को उक्त कार्य का कार्यदेश संदर्भ संख्या:
भाविप्रा/वडोदरा/सहायक महा.प्र(अभि-सि)/डब्ल्यू-294/2025-26/1423 दिनांक 10/02/2026 को
जारी किया गया था।

उक्त कार्यदेश संख्या भाविप्रा/वडोदरा/सहायक महा.प्र(अभि-सि)/डब्ल्यू-294/2025-26 की बजाए
भाविप्रा/वडोदरा/सहायक महा.प्र(अभि-सि)/डब्ल्यू-295/2025-26 पढ़ा जाए।

The work order for the above said work was issued to M/s M L Brothers, New Delhi
vide reference number: AAI/VAD/AGM (Engg. -C)/W-294/2025-26/1423 dated
10/02/2026.

The work order number mentioned should be read as AAI/VAD/AGM (Engg. -C)/W-
295/2025-26 instead of AAI/Vadodara/AGM (Engg. -C)/W-294/2025-26.

भवदीय /Yours faithfully


19.02.2026

सहायक महाप्रबंधक (अभि-सिविल),

वडोदरा हवाईअड्डा, वडोदरा

कृते अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण

AGM (Engg.-Civil), Vadodara Airport

For and on behalf of Chairman

Airports Authority of India

For M/s ML BROTHER



PARTNER

पवन नै. पारधी / PAWAN N. PARDHI

सहायक महाप्रबंधक (अभि-सि)

Asstt General Manager (E-C)

भाविप्रा. वडोदरा विमानक्षेत्र /AAI, VADODARA AIRPORT



प्रतिलिपि /Copy to :-

1. क्षेत्रीय कार्यपालक निदेशक, पश्चिमी क्षेत्र, भाविप्रा, पारसीवाड़ा के सामने सहार रोड, विले पार्ले (पूर्व) मुंबई-400099
The Regional Executive Director, WR AAI, Opp. Parsiwada, Sahar Road Ville Parle (E) Mumbai-400099
2. महाप्रबंधक (अभियांत्रिकी), पश्चिमी क्षेत्र, भाविप्रा, पारसीवाड़ा के सामने सहार रोड, विले पार्ले (पूर्व) मुंबई-400099
General Manager (Engg) WR, AAI, Office of the RED, Opp. Parsiwada, Sahar Road Ville Parle (E) Mumbai-400099
3. महा प्रबंधक (वित्त), पश्चिमी क्षेत्र, भाविप्रा, पारसीवाड़ा के सामने सहार रोड, विले पार्ले (पूर्व) मुंबई-400099
General Manager (F&A) WR, AAI, Office of the RED, Opp. Parsiwada, Sahar Road Ville Parle (E) Mumbai-400099
4. विभागाध्यक्ष (सतर्कता), पश्चिमी क्षेत्र, भाविप्रा, क्षेत्रीय कार्यपालक निदेशक, पारसीवाड़ा के सामने सहार रोड, विलेपार्ले (पूर्व) मुंबई-400099
HOD (Vigilance), AAI, Office of the RED, WR, Opp. Parsiwada, Sahar Road Ville Parle (E) Mumbai-400099
5. श्रम आयुक्त, 5, देबर सोसायटी, बगीखाना रोड, बरोडा हाई स्कूल के पास, बरोडा-390001
Labour Commissioner, 5, Dhebar Society, Bagikhana Road, Near Baroda High school, Baroda-390001
6. भविष्यनिधि कमिशनर, "भविष्य निधि भवन", वडोदरा सेवासदन कार्यालय नं-6 के पीछे, अकोटा स्टेडियम रोड, अकोटा, वडोदरा-390020
Provident Fund Commissioner, "Bhavishya Nidhi Bhavan", B/H VMC Seva Sadan Office No-6 Akota Stadium Road, Akota, Vadodara-390020

आंतरिक /Internal :-

1. विमानपत्तन निदेशक, भाविप्रा, वडोदरा विमानक्षेत्र, वडोदरा
Airport Director, AAI, Vadodara Airport, Vadodara.
2. संयुक्त महाप्रबंधक (वायु यातायात प्रबंधन), भाविप्रा, वडोदरा विमानक्षेत्र, वडोदरा |
Jt.GM (ATM), AAI, Vadodara Airport, Vadodara.
3. उप महाप्रबंधक (अभि-सिविल)-I, भाविप्रा, वडोदरा विमानक्षेत्र, वडोदरा
DGM (Engg-Civil)-I, AAI, Vadodara Airport, Vadodara.
4. उप महाप्रबंधक (एयरसाइड प्रबंधन), भाविप्रा, वडोदरा विमानक्षेत्र, वडोदरा |
DGM (Airside Management), AAI, Vadodara Airport, Vadodara.
5. वरिष्ठ प्रबंधक (वित्त), भाविप्रा, वडोदरा विमानक्षेत्र, वडोदरा
Asst. General Manager (Finance), AAI, Vadodara Airport, Vadodara.
6. प्रबंधक (अभि-सिविल), भाविप्रा, वडोदरा विमानक्षेत्र, वडोदरा
Manager (Engg-C), AAI, Vadodara Airport, Vadodara.
7. मुख्य सुरक्षा अधिकारी, भाविप्रा, वडोदरा विमानक्षेत्र, वडोदरा
Chief Security officer, AAI, Vadodara Airport, Vadodara.
8. करारनामा प्रतिलिपि
Agreement Copy.
9. राजभाषा धारा 3
10. कार्यफाइल / Work file

भवदीय /Yours faithfully

पवन नै. पारधी
19.02.2016

सहायक महाप्रबंधक (अभि-सिविल),
वडोदरा हवाईअड्डा, वडोदरा

कृते अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण
AGM (Engg. -Civil), Vadodara Airport
For and on behalf of Chairman
Airports Authority of India

Pardhi
20.02.2016

For M/s ML BROTHER

ML BROTHER

PARTNER

पवन नै. पारधी / PAWAN N. PARDHI
सहायक महाप्रबंधक (अभि-सि)
Asstt General Manager (E-C)
भा.वि.प्रा. वडोदरा विमानक्षेत्र /AAI, VADODARA AIRPORT