



Ref: AAI/TRY/ENGG (E)/WO-15/2025-26/2361

Date: 04.02.2026

संदर्भ: एएआई/ट्रिचोई/इएनजीजी(इ)/कव-15/2025-26/2361

दिनांक: 04.02.2026

सेवा मे / To,

एमएस। मिराज एडवर्टाइजिंग वर्ल्ड/ M/S. MIRAGE ADVERTISING WORLD,
सी-44, फेस - 1/ C-44, PHASE - 1,
मंगोल पुरी औद्योगिक क्षेत्र / MANGOL PURI INDUSTRIAL AREA,
डीप हुंडई के पीछे - BEHIND DEEP HYUNDAI,
पश्चिम दिल्ली - 110083 / WEST DELHI - 110083,

विषय/Sub : Provision of additional signages at Trichy Airport.

संदर्भ/Ref : Your financial bid for the subject work is reference to Bid No:
2025_AAI_258963_1 opened on 19.01.2026

महोदय / Dear Sir,

- उपर्युक्त कार्य के लिए आपका टेंडर अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से आप द्वारा उद्धरित मद दर जिसकी कुल राशि रु. 32,21,872/- (बत्तीस लाख इक्कीस हजार आठ सौ बहत्तर मात्र) (जी.एस.टी. सहित) है जो कि अनुमानित दर रु. 42,68,479/- (जी.एस.टी. सहित) से 24.52% प्रतिशत कम है, एतद्वारा स्वीकार किया जाता है।

Your tender for the work mentioned above is hereby accepted on behalf of the Chairman, Airports Authority of India at the item rates quoted by you totaling to **Rs. 32,21,872/-** (Rupees Thirty Two Lakhs Twenty One Thousand Eight Hundred and Seventy Two Only) including GST which is 24.52% Below the estimated cost put to tender of Rs. **42,68,479/-** (i/c. GST).

- वरिष्ठ प्रबंधक (इंजी.-विद्युत), भा.वि.प्रा. तिरुचि हवाईअड्डा, तिरुचि - 620 007 कार्य के लिए प्रभारी इंजीनियर होंगे। आपसे अनुरोध है कि आप अपना प्रत्यायित प्रतिनिधि जिसे कि आप की ओर से संविदा करार पर हस्ताक्षर करने की शक्ति दी गई है को वरिष्ठ प्रबंधक (इंजी.-विद्युत) के कार्यालय में करार पर हस्ताक्षर करने के लिए दिनांक 13/02/2026 तक नियुक्त करें। (संविदा करार रु 100/- के नॉन ज्युडिशियल स्टाम्प पेपर पर निष्पादित किया जाएगा और स्टाम्प पेपर की लागत आपको ही वहन करनी होगी।)

Senior Manager (Engg.-E), AAI, Trichy Airport, Trichy - 620 007 shall be the Engineer-in-charge of the work. You are requested to depute your accredited representative, empowered to sign the contract agreement on your behalf to attend the office of the Senior Manager (Engg.-E) by 13/02/2026 to sign and complete the agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs.100/- (Rupees Hundred only) and the cost of the stamp paper shall be borne by you.

- कृपया इस लेटर के जारी होने की तारीख से 10 दिनों के अंदर सिक्योरिटी डिपॉजिट के तौर पर 2,73,040/- रुपये (दो लाख तिहत्तर हजार चालीस मात्र) जमा करें, ऐसा न करने पर, यह रकम कॉन्ट्रैक्ट डॉक्यूमेंट के पेज नंबर 43 पर कॉन्ट्रैक्ट की शर्त के क्लॉज 1A के अनुसार आपके बिल से काट ली जाएगी।

Please deposit Rs. 2,73,040/- (Rupees Two Lakh Seventy Three Thousand and Forty Only) towards Security Deposit within 10 days from the date of issue of this letter, failing which, the same will be deducted from your bill as per the Clause 1A of condition of contract at page no.43 of the contract document.

Contd., 2/-

आनंत. ए / Ananth. A

वरिष्ठ प्रबंधक (अभि - विद्युत) / Senior Manager (Engg.-E)
भारतीय विमानपत्तन प्राधिकरण / Airports Authority of India
त्रिची अंतरराष्ट्रीय हवाई अड्डा / Trichy International Airport
तिरुचिरापल्ली - 620 007 / Trichy - 620 007.



: 2 :

4. आपसे अनुरोध है कि संविदा श्रमिक (विनियमन एवं समापन) अधिनियम 1970 और संविदा श्रमिक (विनियमन एवं समापन) केन्द्रीय नियमावली 1971 और केन्द्रीय और राज्य सरकार के न्यूनतम मजदूरी अधिनियम और नियमों का पालन करें।
You are requested to comply with the provisions of Contract Labour (Regulation and Abolition) Act of 1970 and Contract Labour (Regulation and Abolition) Central Rules 1971 and Minimum wages Act & Rules there of Central and State Governments.
5. आपको निर्देश दिए जाते हैं कि आप प्रबंधक (इंजी.-विद्युत), भा.वि.प्रा. तिरुचि हवाईअड्डा, तिरुचि -620 007, से तत्काल सम्पर्क करें जो कि आपको कार्यस्थल सुपर्द करने की व्यवस्था करेंगे।
You are also directed to contact Manager (Engg.-E), AAI, Trichy Airport, Trichy- 620 007, immediately who will arrange to handover the site to you.
6. कृपया यह नोट करें कि काम करने का समय 120 (एक सौ बीस) दिन है जिसे इस पत्र के जारी होने की तारीख के दस (10) दिन बाद से गिना जाएगा।
Please note that the time allowed for carrying out the work is 120 (One Hundred and Twenty) Days, which shall be reckoned from the 10th day of issue of this letter.
7. दोष दायित्व अवधि के अनुबंध के कार्यों के पूरा होने की तारीख से चौबीस (24) महीने है, संविदा दस्तावेज के अनुसार पृष्ठा 180 के खण्ड 43 पर दी गई है।
Defect liability period of the contract is Twenty Four (24) Months from the certified date of completion of work as per clause No 43 of special conditions at page no- 180 of contract document.
8. संविदा के संबंध में आगे किया जाने वाला पत्राचार समान्यतः वरिष्ठ प्रबंधक (इंजी.-विद्युत), भा.वि.प्रा. तिरुचि हवाईअड्डा, तिरुचि -620 007, से किया जाए।
Any further correspondence in connection with the contract should normally be addressed to the Senior Manager (Engg.-E), AAI, Trichy Airport, Trichy- 620 007.
9. कृपया इस आदेश की प्रति को स्वीकार करें और स्वीकृति के एक टोकन के रूप में अधिसंख्यता पर हस्ताक्षर करने के बाद इसके साथ संलग्न इस पत्र की डुप्लिकेट प्रतिलिपि वापस करें।
Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

Encl: Schedule of Quantities.

भवदीय / Yours faithfully,


04/02/26

वरिष्ठ प्रबंधक (इंजी.-विद्युत)/ Senior Manager (Engg.-E),
कृते अध्यक्ष की ओर से / For and on behalf of Chairman
भारतीय विमानपत्तन प्राधिकरण/ Airports Authority of India.

तिरुचि हवाईअड्डा / Trichy Airport.
आनंत. ए / Ananth. A

वरिष्ठ प्रबंधक(अभि - विद्युत) / Senior Manager (Engg.- E)
भारतीय विमानपत्तन प्राधिकरण / Airports Authority of India
त्रिची अंतरराष्ट्रीय हवाई अड्डा / Trichy International Airport
तिरुचिरापल्ली - 620 007 / Trichy - 620 007.



N.O.O.: Copy to:
(Internal):

- 1) विमानपत्तन निदेशक, भा.वि.प्रा. तिरुचि हवाईअड्डा, तिरुचि -07
Airport Director, AAI, Trichy Airport, Trichy - 07
- 2) संयुक्त.महाप्रबंधक (Vig.), भा.वि.प्रा. दक्षिणी क्षेत्र, चेन्नै-27
Joint. General Manager (Vig.), AAI, SR, Chennai-27
- 3) संयुक्त.महाप्रबंधक (इंजी.-विद्युत), भा.वि.प्रा. तिरुचि हवाईअड्डा, तिरुचि -07
Jt. GM (Engg-E), AAI, Trichy Airport, Trichy - 07
- 4) उप-महाप्रबंधक (वित्त) भा.वि.प्रा. तिरुचि हवाईअड्डा, तिरुचि -07.
Dy. General Manager (F&A), AAI, Trichy Airport, Trichy-07
- 5) सहायक श्रम आयुक्त (केंद्रीय), पुदुचेरी
Asst. Labour Commissioner (Central), Puducherry
- 6) प्रबंधक (इंजी.-ई), एएआई, त्रिची हवाई अड्डा, त्रिची - 07.
Manager (Engg.-E), AAI, Trichy Airport, Trichy - 07.
- 7) करार /Agreement.
- 8) पत्रावली /File.

वरिष्ठ प्रबंधक(इंजी.-विद्युत)/ Senior Manager (Engg-E),
अध्यक्ष की ओर से / For and on behalf of Chairman,
भारतीय विमानपत्तन प्राधिकरण/ Airports Authority of India.

तिरुचि हवाईअड्डा /Trichy Airport
आनंत. ए / Ananth. A

वरिष्ठ प्रबंधक(अभि - विद्युत) / Senior Manager (Engg-E)
भारतीय विमानपत्तन प्राधिकरण / Airports Authority of India
त्रिची अंतरराष्ट्रीय हवाई अड्डा / Trichy International Airport
तिरुचिरापल्ली - 620 007 / Trichy - 620 007.

Tender Inviting Authority: Senior Manager (Engg-E), Airports Authority of India, Trichy Airport, Trichy- 620 007

Name of Work: Provision of additional signages at Trichy Airport.

Contract No: AAI/TRY/ENGG(E)/CW-01/2025-26 Tender ID: 2025_AAI_258963_1

Name of the Bidder/ Bidding Firm / Company		MIRAGE ADVERTISING WORLD				
PRICE SCHEDULE						
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
1	Providing and fixing illuminated signs including all operations from fabrication to installation all complete as per drawings, technical specifications, signage schedule and to the satisfaction of the Engineer-in-Charge and as per technical specifications (Design attached as Annexure - A). Sign face: Sign face shall be made in 8 mm thick 040 white acrylic having graphics pasted in Plotter cut Blockout vinyl. The Plotter cut blockout vinyl shall match the specified colour (colour Pantone Black 6C) and vinyl for text Pantone yellow C or Cyan 311C as per graphics and of specified make duly approved by the Engineer-in-Charge. Sign Frame: Sign frame 50 mm wide Powder coated, colour RAL 9006 special aluminium extrusion with inbuilt frame to receive the sign face. The sign face shall be fixed to sign frame with 3M brand dual lock system in one side and 3M double side tape from the other side. The panel should be made easily openable for maintenance and as per technical specifications. Sign internal Structure: Providing and fixing Framework of Aluminium 25mmx 25 mm hollow square sections. Shall be directly fixed to the sign frame. Suspender: Providing and fixing Stainless steel 35 x 35 mm Hollow sections (assuming typical length of 1 metre) mounted on slabs/ beams/ walls. All hardware used for fixing of sign shall be Stainless steel. Lighting: All internal illumination shall be using Power LED Lights from Osram or equivalent with electronic controllers, having even spread and overlaps to avoid banding and dark spots. Cost to include all internal connections and Wiring, terminating and connecting the incoming cable laid by Airport contractor at the site. The actual structural design of the sign for its stability shall be responsibility of the contractor. Secret fixing methods should be used to fix parts together and as per technical specifications. Accessories: Providing and fixing all accessories such as thimbles, end connectors, nut-inserts, screws, rivets, bolts, washers, nuts, etc. complete in all respect as per drawing/ specification as required.					
1.01	Size of Signage 2100x 255 mm (signage content / matter shall be as approved by AAI)	18	Each	18000.00	324000.00	INR Three Lakh Twenty Four Thousand & Paise Zero Only
2	Providing and fixing illuminated signs including all operations from fabrication to installation all complete as per drawings, technical specifications, signage schedule and to the satisfaction of the Engineer-in-Charge and as per technical specifications (Design attached as Annexure - A). Sign face: Sign face shall be made in 8 mm thick 040 white acrylic having graphics pasted in Plotter cut Blockout vinyl. The Plotter cut blockout vinyl shall match the specified colour (colour Pantone Black 6C) and vinyl for text Pantone yellow C or Cyan 311C as per graphics and of specified make duly approved by the Engineer-in-Charge. Sign Frame: Sign frame 50 mm wide Powder coated, colour RAL 9006 special aluminium extrusion with inbuilt frame to receive the sign face. The sign face shall be fixed to sign frame with 3M brand dual lock system in one side and 3M double side tape from the other side. The panel should be made easily openable for maintenance and as per technical specifications. Sign internal Structure: Providing and fixing Framework of Aluminium 25mmx 25 mm hollow square sections. Shall be directly fixed to the sign frame. Suspender: Providing and fixing Stainless steel 35 x 35 mm Hollow sections (assuming typical length of 1 metre) mounted on slabs/ beams/ walls. All hardware used for fixing of sign shall be Stainless steel. Lighting: All internal illumination shall be using Power LED Lights from Osram or equivalent with electronic controllers, having even spread and overlaps to avoid banding and dark spots. Cost to include all internal connections and Wiring, terminating and connecting the incoming cable laid by Airport contractor at the site. The actual structural design of the sign for its stability shall be responsibility of the contractor. Secret fixing methods should be used to fix parts together and as per technical specifications. Accessories: Providing and fixing all accessories such as thimbles, end connectors, nut-inserts, screws, rivets, bolts, washers, nuts, etc. complete in all respect as per drawing/ specification as required.					

आनंत ए / Ananth. A

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
2.01	Size of Signage -2100 x 520mm (signage content / matter shall be as approved by AAI)	9	Each	29000.00	261000.00	INR Two Lakh Sixty One Thousand & Paise Zero Only
3	Providing and fixing non-illuminated signs including all operations from fabrication to installation all complete as per drawings, technical specifications, signage schedule and to the satisfaction of the Engineer-in-Charge and as per technical specifications (Design attached as Annexure - A). Sign face: Digitally printed Graphics on vinyl pasted on 3mm thick black acrylic mounted on walls/ claddings/ panelling's using 3M VHB Double Side Tape.					
3.01	Size of Signage - 250 x 300 (signage content / matter shall be as approved by AAI)	11	Each	400.00	4400.00	INR Four Thousand Four Hundred & Paise Zero Only
4	Providing and fixing illuminated signs including all operations from fabrication to installation all complete as per drawings, technical specifications, signage schedule and to the satisfaction of the Engineer-in-Charge and as per technical specifications (Design attached as Annexure - A). Sign face: Sign face shall be made in 8 mm thick 040 white acrylic having graphics pasted in Plotter cut Blockout vinyl. The Plotter cut blockout vinyl shall match the specified colour (colour Pantone Black 6C) and vinyl for text Pantone yellow C or Cyan 311C as per graphics and of specified make duly approved by the Engineer-in-Charge. Sign Frame: Sign frame 50 mm wide powder coated, colour RAL 9006 special aluminium extrusion with inbuilt frame to receive the sign face. The sign face shall be fixed to sign frame with the 3M brand dual lock system in one side and 3M bothway tape from the other side. The panel should be made easily openable for maintenance. Sign Structure: All structural members in SS square post 100 x 100 and horizontal cross tie member square sections 75x75mm, brush finished, base plate embedded below the floor finish and provided with a floor trim ring. All hardware used for fixing of sign shall be Stainless steel. Post including SS base Plate and Gussets in 6mm thick SS Plate as per drawing with holes to fix it on holding down bolts anchored in concrete slab. The post shall closed with a 3 mm thick SS plate as specified and approved by the Engineer-In-charge. The Post shall be always be a single continuous element without any joints. Cost to include all activities and temporary props used for a perfect vertical in plumb installation, etc. required for fixing the sign in an internal location. The actual structural design of the sign for its stability shall be responsibility of the contractor. Secret fixing methods should be used to fix parts together and as per technical specifications. All internal illumination shall be using Power LED Lights from Osram or equivalent with electronic controllers, having even spread and overlaps to avoid banding and dark spots. Cost to include all internal connections and Wiring, terminating and connecting the incoming cable laid by Airport contractor at the site. The actual structural design of the sign for its stability shall be responsibility of the contractor. Secret fixing methods should be used to fix parts together. Foundation: Providing and laying foundation for the sign including its compaction and all activities like Excavation, PCC base layer, providing and fixing in position electrical connection wherever applicable and finished as per drawing. The item cost includes cutting and opening the floor finish at location, and making good the location to the match the original finish after fixing and installation of sign. Accessories: Providing and fixing all accessories such as thimbles, end connectors, nut-inserts, screws, rivets, bolts, washers, nuts, etc. complete in all respect as per drawing/ specification as required and as per technical specifications.					
4.01	Size of Signage - 2100 x 780 (signage content / matter shall be as approved by AAI)	7	Each	85000.00	595000.00	INR Five Lakh Ninety Five Thousand & Paise Zero Only
5	Providing and fixing illuminated signs including all operations from fabrication to installation all complete as per drawings, technical specifications, signage schedule and to the satisfaction of the Engineer-in-Charge and as per technical specifications (Design attached as Annexure - A). Sign face: Sign face shall be made in 8 mm thick 040 white acrylic having graphics pasted in Plotter cut Blockout vinyl. The Plotter cut blockout vinyl shall match the specified colour (colour Pantone Black 6C) and vinyl for text Pantone yellow C or Cyan 311C as per graphics and of specified make duly approved by the Engineer-in-Charge. Sign Frame: Sign frame 50 mm wide powder coated, colour RAL 9006 special aluminium extrusion with inbuilt frame to receive the sign face. The sign face shall be fixed to sign frame with the 3M brand dual lock system in one side and 3M bothway tape from the other side. The panel should be made easily openable for maintenance and as per technical specifications. Lighting: All internal illumination shall be using Power LED Lights from Osram or equivalent with electronic controllers, having even spread and overlaps to avoid banding and dark spots and adhering to the LUX levels mentioned in the performance specification. Cost to include all internal connections and Wiring, terminating and connecting the incoming cable laid by Airport contractor at the site. The actual structural design of the sign for its stability shall be responsibility of the contractor. Secret fixing methods should be used to fix parts together. Accessories: Providing and fixing all accessories such as thimbles, end connectors, nut-inserts, screws, rivets, bolts, washers, nuts, etc. complete in all respect as per drawing/ specification as required.>>					
5.01	Size of Signage 900 x 450 (signage content / matter shall be as approved by AAI)	2	Each	9000.00	18000.00	INR Eighteen Thousand & Paise Zero Only

04/02/26

आनंत. ए / Ananth. A

वरिष्ठ प्रबंधक (अभि - विद्युत) / Senior Manager (Engg - E)

भारतीय विमानपत्तन प्राधिकरण / Airports Authority of India

पुणे अंतराष्ट्रीय विमानतळ / Trichy International Airport

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #	
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
6	Providing and fixing illuminated signs including all operations from fabrication to installation all complete as per drawings, technical specifications, signage schedule and to the satisfaction of the Engineer-in-Charge and as per technical specifications (Design attached as Annexure - A). Sign face: Sign face shall be made in 8 mm thick 040 white acrylic having graphics pasted in Plotter cut Blockout vinyl. Entire panel covered with a protective over laminate. The films to wrap around the edge of the acrylic to a distance of 25mm on the back side. The Plotter cut blockout vinyl shall match the specified colour (colour Pantone Black 6C) and vinyl for text Pantone yellow Cyan 311C as per graphics and of specified make duly approved by the Engineer-in-Charge. Sign Frame: Sign frame 50 mm wide powder coated, colour RAL 9006 special aluminium extrusion with inbuilt frame to receive the sign face. The sign face shall be fixed to sign frame with the 3M brand dual lock system in one side and 3M bothway tape from the other side. The panel should be made easily openable for maintenance. Sign Structure (Type - 1 - Wall Projected) : Wall projected signage internal supports of Stainless Steel 50x50 SHS. Lighting: All internal illumination shall be using Power LED strip edge Lights with electronic controllers, having even spread and overlaps to avoid banding and dark spots. Cost to include all internal connections and Wiring, terminating and connecting the incoming cable laid by Airport contractor at the site. The actual structural design of the sign for its stability shall be responsibility of the contractor. Secret fixing methods should be used to fix parts together. Accessories: Providing and fixing all accessories such as thimbles, end connectors, nut-inserts, screws, rivets, bolts, washers, nuts, etc. complete in all respect as per drawing/ specification as required.>>					
6.01	Size of signage - 450 x 450 - TYPE 1 - WALL PROJECTED - 2.4a-1 (signage content / matter shall be as approved by AAI)	4	Each	6000.00	24000.00	INR Twenty Four Thousand & Paise Zero Only
7	Supply installation ,testing & commissioning of outdoor illuminated LED channel letters made up of SS304 material with 1mm top base & 0.8 mm side thickness walling Material colour ROSEGOLD / Titanium stain less steel return side 1.5 inch depth, including providing LED module (IP 65) with drivers, (Design dimmesions of channel letters shall be as per the illustrative design attached in technical specifications (Design attached in Annexure - B) fixing on existing Brick wall of size approximate 35 Feet X15 Feet with core cutting & fixing hole properly, Providing interconnection cables & laying in conduit, providing loop in-loop out IP 65 polycarbonate boxes with suitable cable gland etc., as per site requirement. Following content required to provide in three languages.(Tamil/Hindi/English) TIRUCHIRAPPALLI INTERNATIONAL AIRPORT, AAI LOGO & Airports Authority of India திருச்சிராப்பள்ளி அंतराष्ट्रीय हवाई अड्डा, एएआई लोगो और भारतीय विमानपत्तन प्राधिकरण திருச்சிராப்பள்ளி சர்வதேச விமான நிலையம், AAI லோகோ & இந்திய விமான நிலையங்கள் ஆணையம்	2	Job	455000.00	910000.00	INR Nine Lakh Ten Thousand & Paise Zero Only
8	Providing and fixing plotter cut Blockout vinyl graphics in specified colours for sign background and graphics, pasted directly on the surface of the existing acrylic sign facia etc., complete as per drawings, technical specifications, signage schedule and to the satisfaction of the Engineer-in-Charge and as per technical specifications. (signage content / matter shall be as approved by AAI)	37	Sq.Mtr	4000.00	148000.00	INR One Lakh Forty Eight Thousand & Paise Zero Only
9	Supply and fixing of 25 mm dia double wall corrugated flexible steel conduit along with accessories in surface /recess including painting in case of surface conduit as per IS, and cutting the wall and making good the same in case of recessed conduit as required.	200	Mtrs	30.00	6000.00	INR Six Thousand & Paise Zero Only
10	Supply of 3C x 2.5 sqmm copper conductor cable of FRLS, PVC inner sheathed, XLPE insulated, Armoured cable, 1.1 KV grade cable as per IS 7098 - Part - I.	500	Mtrs	170.00	85000.00	INR Eighty Five Thousand & Paise Zero Only
11	Supply of 4C x 4 sqmm copper conductor cable of FRLS, PVC inner sheathed, XLPE insulated, Armoured cable, 1.1 KV grade cable as per IS 7098 - Part - I.	200	Mtrs	340.00	68000.00	INR Sixty Eight Thousand & Paise Zero Only
12	Laying of LT cable of 1.1 KV grade cable in existing race way /cable tray/pipe/duct as required (upto 35 sqmm)	600	Mtrs	170.00	102000.00	INR One Lakh Two Thousand & Paise Zero Only
13	Installation of Suspended Sign board of various sizes (2100mmx780mm,900mmx450mm) including providing suitable suspender of SS of size 35x35 mm hallow sections, supporting clamps to support the board weight etc., as per site requirement .(Sign board shall be issued from AAI store)	2	Job	15000.00	30000.00	INR Thirty Thousand & Paise Zero Only
14	Installation of Projected Sign board of various sizes(900mmx450mm) on wall/pillar/column including providing sutiable supporting clamps to support the board weight etc as per site requirement. (Sign board shall be issued from AAI store)	10	Job	10000.00	100000.00	INR One Lakh & Paise Zero Only
15	Installation of surface Sign board of various sizes (450mmx450mm, 400mmx400mm) on wall / plain surface including providing suitable supporting clamps to support the board weight etc., as per site requirement.(Sign board shall be issued from AAI store)	15	Job	3000.00	45000.00	INR Forty Five Thousand & Paise Zero Only

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
16	Fixing of cable G.I Raceway of size upto 300 mm, including junction box including cutting in flooring & Refixing properly with proper alignment inside NITB etc as per site requirement. (Raceway shall be issued from AAI store)	100	Mtrs	100.00	10000.00	INR Ten Thousand & Paise Zero Only
Total in Figures					2730400.00	INR Twenty Seven Lakh Thirty Thousand Four Hundred & Paise Zero Only
Quoted Rate in Words				INR Twenty Seven Lakh Thirty Thousand Four Hundred & Paise Zero Only		


 08/02/26
आनंत. ए / Ananth. A
 सैरिष्ट प्रबंधक (अभि - विद्युत) / Senior Manager (Engg - E)
 भारतीय विमानपत्तन प्राधिकरण / Airports Authority of India
 त्रिची अंतरराष्ट्रीय हवाई अड्डा / Trichy International Airport
 तिरुचिरापल्ली - 620 007 / Trichy - 620 007.

Signature Not Verified

Digitally signed by SURAJ EDACHERI
 Date: 2026.02.05 03:11:33 IST
 Location: eProcurement System for Central PSUs

