

ACCEPTANCE LETTER No : MINUTES OF CWC – II HELD ON 23-07-2025

To

SRI KRISHNA AGENCIES
No. 16/1, KALAINGER STREET,
KAKKANJI NAGAR, PATTABIRAM
CHENNAI – 600 072

Dear Sirs,

Type of Work: ITEM RATE

Sub : **REPAIRS TO THE ROOM No. 1 AND 2, WM OFFICE, HOS ROOM AND QA(NF) OF HULL SHOP-I AT
HVF, AVADI.**

Ref: (i) HVF Tender No. HVF/TE/13025/CEO/2025-26/10, Dt. 14-05-2025 with Tender ID: 2025_AVNL_235279_1

(ii) Your Bid No: 861325 in this tender and Price Reduction Offered vide your negotiated Bid opened on 15-07-2025.

For and on behalf of The President of India, I hereby convey the acceptance of your tender by the competent financial authority for the above mentioned work for a total value of **Rs. 15,16,758.00 /- (Rupees Fifteen Lakhs Sixteen Thousand Seven Hundred and Fifty Eight Only)** and order the services detailed in the schedule enclosed herewith at the item rates quoted by you in Schedule 'A' of the Tender documents as per the terms, conditions and specifications laid therein. List of items, to be issued by factory, is given in Schedule 'B'.

2. The contract is allotted with No. **HVF/CE/17/2025-26/MAINT., Dated. 28-07-2025** which will have to be quoted by you in all future correspondence in connection with this contract.

3. In accordance with condition No. 22 of the General Condition of Contract (IAFW-2249), please submit the security deposit of Rs. 76,000 /- (Rupees Seventy Six Thousand Only) in favour of " The Chief General Manager, Heavy Vehicles Factory, Avadi" as mentioned in tender condition. The Validity of Security Deposit shall be such that it covers the Completion and Maintenance (Warranty) Period plus two months and which will be releasable after successful completion of Warranty / Maintenance / Defect Liability period , and as per conditions elucidated in SOP for Civil Works in AVNL – 2024.

4. The contract shall be governed by the terms and conditions as per the contract documents enclosed and general condition of contract MES IAFW 2249. .

5. Shri. P. Neelakandan, JWM (SG) / IMS / CE (Fy) is nominated as Engineer-in-Charge and Shri. E. Uma Sankar, JWM / IMS / CE (Fy) is nominated as Site In-charge for the subject work respectively.

6. You are requested to contact the Engineer-in-Charge within 7 days of receipt of this letter for taking over of site and to make time and progress chart. You will also maintain wage-cum-muster roll and all other records as required in Contract Labour Rules and Acts.

7. Please acknowledge receipt of this letter and return two copies duly signed by you in proof of acceptance within seven days from the date of receipt of this communication.



(K. TULASI RAO)

GENERAL MANAGER / CEO

For CHIEF GENERAL MANAGER / HVF

For And On Behalf Of THE PRESIDENT OF INDIA

Copy to .

- | | |
|---|-----------------------|
| 1. GM / F&A, HVF, Avadi, Chennai – 600054 | |
| 2. Shri. P. Neelakandan, JWM (SG) / IMS / CE (Fy) | - Engineer-in-Charge |
| 3. Shri. E. Uma Sankar, JWM / IMS / CE (Fy) | - Site-in-Charge. |
| 4. Shri. P.G. Harish Kumar, JWM / CEO | - Technical Examiner. |

IN LIEU OF IAFW-1823(REVISED)
CONTRACTORS' ORDER SHEET

Work Order/Deviation Order No	HVF/CE/17/2025-26/MAINT., Dated 28-07-2025
Acceptance letter No.	MINUTES OF CWC – II HELD ON 23-07-2025
Contractor's Name	SRI KRISHNA AGENCIES
Name of the work	REPAIRS TO THE ROOM No. 1 AND 2, WM OFFICE, HOS ROOM AND QA(NF) OF HULL SHOP-I AT HVF, AVADI.
CA amount	Rs. 15,16,758.00 /-

PARTICULARS

1. Authority	CWC decision of Fy. LEVEL CWC - II
2. Brief Description of work to be carried out	As per details in sheet attached and adhering to your firm Bid No. 861325 in this tender and Price Reduction Offered vide your negotiated Bid opened on 15-07-2025, in this tender bearing Tender Enquiry No. HVF/TE/13025/CEO/2025-26/10, Dt. 14-05-2025 with Tender ID: 2025_AVNL_235279_1 for all Terms & Conditions therein & rate quoted in Schedule 'A' enclosed with tender documents.
3. Time effect	
a. Date of handing over of the site	06/08/2025
b. Date of commencement of work	06/08/2025
c. Date of Completion as per contract	02/02/2026
d. Date for completion shown in previous Orders	NA
e. Revised date of completion	NA
4. Financial effect (Rs.)	
a. Present order	Rs. 15,16,758.00 /-
b. Contract amount as adjusted by previous orders	NA
c. Contract amount adjusted up to including this order	NA
5. Expenditure to be booked under code Head No	809 / 01 (REVENUE GRANT)
6. Certified that no special rate is involved	
7. Technical Examiner	Shri. P.G. Harish Kumar, JWM / CEO
8. Approved	Shri. K. Tulasi Rao, GM / CEO
9. Accepted	SRI KRISHNA AGENCIES

(K. TULASI RAO)
GENERAL MANAGER / CEO
For CHIEF GENERAL MANAGER / HVF
For And On Behalf Of THE PRESIDENT OF INDIA

Distribution to :-

1. M/s SRI KRISHNA AGENCIES
2. GM / F&A, HVF, Avadi, Chennai – 600054
3. Sr. Security Officer
4. Shri. P.G. Harish Kumar, JWM / CEO - Technical Examiner
5. Shri. P. Neelakandan, JWM (SG) / IMS / CE (Fy) - Engineer In-charge
6. Shri. E. Uma Sankar, JWM / IMS / CE (Fy) - Site In-charge.
7. HOS/Safety, 8. HOS/Internal Audit cell, 09. HOS/Test Audit, 10. ALWC, 11. HOS / Hull Shop-I
12. Chief Commissioner of Central Excise, 26/1, Mahatma Gandhi Road, Nungambakkam, Chennai – 600034
13. Dy. Chief Labour Commissioner(c), No: 26, III Block, 5th floor, Shastri Bhavan, Haddows Road, Nungambakkam, Chennai – 600006

NAME OF THE WORK REPAIRS TO THE ROOM No. 1 AND 2, WM OFFICE, HOS ROOM AND QA(NF) OF HULL SHOP-I AT HVF, AVADI.

CONTRACT AGREEMENT NO HVF/CE/17/2025-26/MAINT, Dated. 28-07-2025

SCHEDULE – "A"

Item Code	Item Description	Unit	Quantity	Rate/Unit (Rs.)	Total Cost (Rs.)
01	Taken down door frame with shutter with out taking off shutters from the frame not exceeding 1.5 sq.m and handing over the same to CE-FY (stores)	EACH	4.00	430.00	1720.00
02	Taken down window frame exc 1.5sq.m but not exceeding 4 sq.m and handing over the same to CE - FY (STORES)	EACH	4.00	360.00	1440.00
03	Dismantling of false ceiling boards fibre, pulp, insulation etc.) or insulation boards/slabs. blankets of any thickness and removing to CE - FY Stores as directed.	SQM	55.00	50.00	2750.00
04	Dismantling of floor, hearth or wall tiling including cement mortar bedding (but not backing),removing serviceable tiles to store and rubbish off the premises.	SQM	100.00	100.00	10000.00
05	Material and labour for brick work built in CM 1:6 using sub-class "B" bricks ,straight or curved on plain exc 6m mean radius.	CUM	6.00	6140.00	36840.00
06	Cutting out bricks, forming toothing for, and bonding new into old work including cement mortar 1:4 value of new materials entering old walls and jointing and pointing (measured on vertical face in contact with old wall only)	SQM	2.00	760.00	1520.00
07	M&L for Plastering with 1:4,15mm thick on faces of old brick work and concrete surfaces.	SQM	51.00	310.00	15810.00
08	M &L for vitrified Ceramic tiles light shade 10 mm thick (square/ rectangular) polished, area of each tiles not exceeding 0.36 sqm, in floors etc. set and jointed in neat cement slurry and pointed in white or coloured cement to match including screed bed or bedding layer in CM1:3, 20mm thick for laying floor finishes.	SQM	100.00	2100.00	210000.00

Item Code	Item Description	Unit	Quantity	Rate/Unit (Rs.)	Total Cost (Rs.)
09	M & L for Non - skid Ceramic coloured tiles 7 to 8 mm thick (square/ rectangular) area of each tile exceeding 0.18 sqm but not exceeding 0.38 sqm, in floors etc. set and jointed in neat cement slurry and pointed in white or coloured cement to match including screed bed or bedding layer in CM1:3, 20mm thick for laying floor finishes.	SQM	5.00	2060.00	10300.00
10	Material and Labour for Glazed ceramic Coloured tiles in vertical surface 350x 250x 7 mm/ 450X 350X 7mm thick set and jointed in neat cement slurry and pointed in white or colour cement to match including screed bed in CM 1:4 15mm thick complete.	SQM	20.00	1860.00	37200.00
11	S&F of Anodised aluminium snap grid 605 x 605 mm frame work for false ceiling all as specified.	SQM	140.00	590.00	82600.00
12	M&L for Exposed metal frame ceiling with 8 mm thick calcium silicate board of siliceous and calcareous material reinforced with cellulose fibre for fixing in 600 mm x 600mm grid (Frame work for ceiling shall be measured and paid separately)	SQM	140.00	565.00	79100.00
13	Supply & fixing of anodised aluminium frame for partition, doors, windows, ventilators with one or more rebates including joining cleat for fixing and power coating etc. complete all as specified (minimum thickness of powder coating 50 micron).	KG	87.00	685.00	59595.00
14	Supply and Fixing of structural steel framed work using Fe 410 -W Grade E -250 A quality mild rolled steel section Roof trusses (framed), trussed, purlins, crane gantries, rails and fastenings and heavy bracket framing (Beam, tee, angle, channel or flat sections) including distance pieces, cleats etc.	KG	170.00	135.00	22950.00
15	S & F of 5.5 mm thick Sheet glass, ordinary quality and glazing with oil putty in square exc 0.5 sq. m in each pane.	SQM	12.00	1300.00	15600.00

Item Code	Item Description	Unit	Quantity	Rate/Unit (Rs.)	Total Cost (Rs.)
16	S&F of Anodised aluminium grill (anodised transparent or dyed to required shade according to IS: 1868 with minimum anodic coating of grade AC 15) of approved design/pattern, with approved standard section and fixed to the existing window frame with C.P. brass/ stainless steel screws @ 200 mm centre to centre, including cutting the grill to proper opening size for fixing and operation of handles and fixing approved anodised aluminium standard section around the opening, fixing and powder coating etc. complete all as specified. (minimum thickness of powder coating 50 micron)	SQM	12.00	750.00	9000.00
17	M&L for pre-laminated particle board of 12 mm thick with pre laminated both sides with decorative choice lamination.	SQM	1.00	900.00	900.00
18	S&F of frame size 65X100mm factory made single extruded WPC(wood polymer composite) solid door/ window/ clerestory window& desertory other frames/chowkat comprising of virgin PVC polymer of k value 58-60(suspension grade), calcium carbonate and natural fiber(wood power)/rice husk/wheat husk and non toxic additives(maximum toxicity index of 12 for 100mgs) fabricated with miter joints after applying PVS solvent cement screwed with full body threaded star headed SS screws having minimum frame density of 750kg/cum, screw withdrawal strength of 2200N (face)&1100N (edge) minimum compressive strength of 58N/mm ² , modulus of elasticity 900N/mm ² and resistance to spread of flame of class A category with property of being termite/borer proof, water/moisture proof and fire retardant and fixed in position with MS hold fast/lugs/SS dash fasteners of required dia and length complete as per direction of engineer-in-charge.(MS hold fast/lugs or SS fasteners shall be paid for separately.	RM	4.70	1250.00	5875.00

Item Code	Item Description	Unit	Quantity	Rate/Unit (Rs.)	Total Cost (Rs.)
19	S&F of 30mm thick factory made single extruded WPC(wood polymer composite) solid plain flush door shutter or required size comprising of virgin polymer of k value 58-60(suspension grade), calcium carbonate and natural fiber(wood power)/rice husk/wheat husk and non toxic additives(maximum toxicity index of 12 for 100mgs) having minimum density of 650kg/cum, screw withdrawal strength of 1800N (face)& 900N (edge) minimum compressive strength of 50N/mm2, modulus of elasticity 850N/mm2 and resistance to spread of flame of class A category with property of being termite/borer proof, water/moisture proof and fire retardant and fixing with stainless steel butt hinges of required size with necessary full body threaded star head counter sunk SS screws, all as per direction of engineer-in-charge.	SQM	2.00	3900.00	7800.00
20	S & F of 2nd class hardwood plain, solid ,straight ,chowkats, and frames ,wrought, framed rebated on the solid ,rounded or chamfered, put together with glue pinned at joints, supplied and fixed.	CUM	1.00	108500.00	108500.00
21	S/F of 1st class hardwood Flush, door shutters 30mm thickness, solid core construction with block, board core and plywood face panels, commercial type on both sides.	SQM	10.00	2040.00	20400.00
22	S/F of Aluminium anodised, Barrel tower bolts (150mm) of extruded section and fixed.	EACH	12.00	92.00	1104.00
23	S/F of butt hinges (125mm) cast, brass with mild steel hinge pin,bright polished and fixed but type B-12.	EACH	18.00	340.00	6120.00
24	S/F of Aluminium handles (150 mm), cast type, anodised	EACH	12.00	90.00	1080.00
25	Supply and Fixing of Swivel looking mirror.	EACH	1.00	4700.00	4700.00

Item Code	Item Description	Unit	Quantity	Rate/Unit (Rs.)	Total Cost (Rs.)
26	S & F of Aluminium Door closer hydraulically regulated, designation No. 3, universal type, suitable for door shutters of 851 to 1000 mm in width and of weight between 61 to 80 kg and fixed	EACH	6.00	1500.00	9000.00
27	Supply and Fixing of touch less vitreous china urinals of size 620x320x290mm white including in built automatic flusher with sensor & all other accessories as directed. (Make: ROCA, Belmonte, Kohler, SOCA, DURAVIT) or Suitably Equivalent Make.	EACH	1.00	24500.00	24500.00
28	Supply & fixing of counter top WHB Make: (ROCA, Belmonte, Kohler, SOCA, DURAVIT) or Suitably Equivalent Make.	EACH	1.00	13200.00	13200.00
29	Supply and fixing of pedestal square or rectangular type EWC wall or floor mounted. (Make Jaquar, ROCA, Belmonte & SOCA.) or Suitably Equivalent Make.	EACH	1.00	19500.00	19500.00
30	Supply & Fixing of Health faucet (Make: Jaquar, ROCA, Kohler, SOCA) or Suitably Equivalent Make.	EACH	1.00	3000.00	3000.00
31	Supply & Fixing of bib tap chromium plated.	EACH	1.00	1600.00	1600.00
32	Supply & Fixing of toilet paper holder of recessed type	EACH	1.00	2600.00	2600.00
33	Supply & Fixing of Towel rail SS.	EACH	1.00	2600.00	2600.00
34	Supply & Fixing of venetian blinder.	SQM	15.00	3000.00	45000.00
35	Supply & Fixing of coat hook.(Make: Jaquar, ROCA, Kohler, SOCA) or Suitably Equivalent Make.	EACH	1.00	870.00	870.00
36	Supply & Fixing of Chromium soap dish holder	EACH	1.00	1500.00	1500.00

Item Code	Item Description	Unit	Quantity	Rate/Unit (Rs.)	Total Cost (Rs.)
37	Supplying and laying of CPVC pipes 32 mm outer diameter SDR 11 & Plain CPVC SDR 11 fittings on walls/ceiling or laying in floors, trenches complete all as specified.	RM	10.00	550.00	5500.00
38	Supplying and laying of CPVC pipes 20 mm outer diameter SDR 11 & Plain CPVC SDR 11 fittings on walls/ceiling or laying in floors, trenches complete all as specified.	RM	6.00	265.00	1590.00
39	S & F of PVC 75mm dia Pipes single socketed, in any length with rubber ring joints laid in trenches or in floors.	RM	6.00	280.00	1680.00
40	S & F of PVC (SWR) 110mm dia Pipes single socketed, in any length with rubber ring joints laid in trenches or in wall.	RM	6.00	480.00	2880.00
41	M&L for PVC floor trap 75mm dia outlet of with grating and connecting PVC extension pipe including jointing with solvent cement etc., complete	EACH	1.00	270.00	270.00
42	S & F of PVC Bend with door 75 mm dia any radius,	EACH	2.00	170.00	340.00
43	S & F of PVC Bend with door 110mm dia any radius,	EACH	2.00	200.00	400.00
44	S & F of Gun-metal (32mm) , globe or gate valves, with iron wheel head, screwed both ends for iron pipe and fixed.	EACH	1.00	750.00	750.00
45	S & F of 20 mm Ball valves set Ball valves high pressure of PTMT with epoxy coated Aluminium rod & high density plastic ball screwed for iron pipe and fixed. (Minimum weight 20 mm - 210 gms.	EACH	1.00	500.00	500.00
46	S&F of Rotational moulded polyethylene water storage tanks (cylindrical vertical with closed top) hoisted and fixed in position all as specified(1000 litres)	EACH	2.00	9600.00	19200.00

Item Code	Item Description	Unit	Quantity	Rate/Unit (Rs.)	Total Cost (Rs.)
47	Material and labour for applying two coats of plastic emulsion on calcium silicate board / ceiling paint with one coat primer and preparation new ceiling surfaces of any description over 10 cm girth or width, not other wise described.	SQM	130.00	160.00	20800.00
48	Complete removal of existing treatment on internal wall surfaces	SQM	290.00	10.00	2900.00
49	Material and labour for 3mm thick wall care putty on wall	SQM	80.00	90.00	7200.00
50	Material and labour for 3mm thick wall care putty on ceiling	SQM	45.00	105.00	4725.00
51	Material and labour for applying two coats of plastic emulsion paint with one coat of primer on internal & exterior wall 10 cm grith including preparation of old painted wall surfaces all complete.	SQM	1300.00	165.00	214500.00
52	Material and labour for painting two coats of synthetic enamel paint with one coat pink primer on new wood surfaces of any description, not other wise described, over 10 cm width or girth including preparation of new surfaces .	SQM	30.00	155.00	4650.00
53	Material and labour for white washing on ceiling with two coats including preparation of old ceiling surfaces.	SQM	160.00	28.00	4480.00
54	Material and labour for painting steel surfaces of any description over 10cm width or grith with two coats of synthetic enamel paint over a coat of red oxide primer including preparing new surfaces .	SQM	7.00	165.00	1155.00
55	Removal of debris (rocks) exceeding 1.5Km but not exceeding 5 km and depositing where directed.	CUM	1.00	750.00	750.00

Item Code	Item Description	Unit	Quantity	Rate/Unit (Rs.)	Total Cost (Rs.)
56	Material and labour for Point wiring with PVC insulated sheathed single core cable 1100V grade confirming to IS 694 multi strand copper conductor along with 2mm thick PVC conduit accessories run on wall or roof including M.S. switch box concealed in the wall(made out of 3mm thick sheet) and laminated sun mica sheet 3mm thick cover for housing the switches, regulators and plug socket etc. mount on a wall/roof etc. including same size copper earth continuity wire. a)one light point or one fan point controlled by one switch with cables 1.5 sqmm size.	Point	36.00	1100.00	39600.00
57	Material and labour for Point wiring with PVC insulated sheathed single core cable 1100V grade confirming to IS 694 multi strand copper conductor along with 2mm thick PVC conduit accessories run on wall or roof including M.S. switch box concealed in the wall(made out of 3mm thick sheet) and laminated sun mica sheet 3mm thick cover for housing the switches, regulators and plug socket etc. mount on a wall/roof etc. including same size copper earth continuity wire. b)One 3 pin socket outlet 5 amps on the same board with other switches, with cables 1.5 sqmm size.	Point	18.00	310.00	5580.00
58	Material and labour for Point wiring with PVC insulated sheathed single core cable 1100V grade confirming to IS 694 multi strand copper conductor along with 2mm thick PVC conduit accessories run on wall or roof including M.S. switch box concealed in the wall(made out of 3mm thick sheet) and laminated sun mica sheet 3mm thick cover for housing the switches, regulators and plug socket etc. mount on a wall/roof etc. including same size copper earth continuity wire. c) One 3 pin socket outlet 5 amps on independent with cables 2.5 sqmm size.	Point	9.00	1240.00	11160.00

Item Code	Item Description	Unit	Quantity	Rate/Unit (Rs.)	Total Cost (Rs.)
59	Supply & Fixing of wiring for circuit/sub main wiring along with earth wire with the following sizes of FR PVC insulated copper conductor, single core cable in surface/recessed as required in PVC conduit a) 2x2.5 sqmm + 1x2.5 sqmm earth wire	RM	150.00	205.00	30750.00
60	Supply & Fixing of wiring for circuit/sub main wiring along with earth wire with the following sizes of FR PVC insulated copper conductor, single core cable in surface/recessed as required in PVC conduit b) 2x4.0 sqmm + 1x4.0 sqmm earth wire	RM	125.00	235.00	29375.00
61	Supply & Fixing of wiring for circuit/sub main wiring along with earth wire with the following sizes of FR PVC insulated copper conductor, single core cable in surface/recessed as required in PVC conduit c) 2x6.0 sqmm + 1x6.0 sqmm earth wire	RM	120.00	280.00	33600.00
62	Material & Labour for connecting to the system modular type switches 6A single pole one way (Make: LEGRAND MYRIUS/ Anchor/ Crabtree) or Suitably equivalent make	EACH	63.00	285.00	17955.00
63	Supply, fixing and connecting to the system of socket, 6A-2/3 pin combined modular type 2 module (Make: LEGRAND MYRIUS/ Anchor/ Crabtree) or Suitably equivalent make	EACH	27.00	370.00	9990.00
64	Supply & fixing of 6 module modular white cover plate with frame	EACH	6.00	335.00	2010.00
65	Supply & fixing of metal flush box for 6 module plate	EACH	6.00	300.00	1800.00
66	Supply & fixing of 8 module plate(white cover) with frame	EACH	9.00	410.00	3690.00
67	Supply and fixing LED luminaire 600 mm x 600 mm, 35/36 watt, 220 V AC recessed type with high efficiency PMMA diffuser soft glare free light complete with driver, holders & LED lamp suitable for roof ceiling including connecting up with driver three core flexible copper conductor cases of suitable size complete (Make: Havells/ Philips/ Wipro/ Bajaj/ CG/ Luker) or Suitably equivalent make)	EACH	18.00	4650.00	83700.00

Item Code	Item Description	Unit	Quantity	Rate/Unit (Rs.)	Total Cost (Rs.)
68	Supply fixing of sheet metal enclosure for DBs when MCB s to be used single pole & neutral ,4 way double door, 200 amps rated busbar,.(Make: Legrand/Anchor/ Havells) or suitable equivalent make.	EACH	4.00	1700.00	6800.00
69	Taking down old point wiring(light, fan, socket or power) complete, including fixture and fittings such as switches, ceiling roses, pendants, regulators, sockets, light fitting etc. removing materials to store for keeping in safe custody for reuse at site and making good disturbed surfaces of wall, floors, etc.	Point	32.00	250.00	8000.00
70	Supply and fixing of single pole and neutral enclosure with a two pins and earth plug and socket complete with one single pole MCB 20 amps, 240V (Make : Standard/Havells/Siemens/ Legrend) or Suitably equivalent make	EACH	7.00	1990.00	13930.00
71	Supply and fixing amp rating 240V 10KA 'C' curve miniature circuit breaker (MCB) of SPN 32 AMP current carrying capacity, in the MCB DB complete with connection testing and commissioning.(Make: Legrand/Anchor/Havells) or suitable equivalent make.	EACH	5.00	935.00	4675.00
72	Supply & fixing of galvanised steel tubes, medium grade 20mm dia for ceiling fan down rod.	RM	12.00	120.00	1440.00
73	Supply and fixing LED lights fitting 1x 20W, 220V, AC decorative box type with driver, holder including LED tube light connecting up with three core flexible copper conductor cable of suitable size from ceiling rose complete (Make: Havells/ Philips/ Wipro/ Bajaj/ CG/ Luker) or Suitably equivalent make)	EACH	14.00	1400.00	19600.00

Item Code	Item Description	Unit	Quantity	Rate/Unit (Rs.)	Total Cost (Rs.)
74	Supply & fixing 240 Volt, 10KA 'C' curve MCB of single pole 6 to 32Amps in the MCB DB complete with connection testing and commissioning. (Make: Legrand/Anchor/ Havells) or suitable equivalent make.	EACH	14.00	320.00	4480.00
75	Material and labour for Brick walls cutting chases, pinning in, making good to facing where required and pointing in cement mortar 1:3 to ends and cutting chases for concealed conduit wiring, etc., and making good, cutting exc. 10 cm but not exc. 20 cm grith.	RM	280.00	60.00	16800.00
76	Supply & fixing metal flush box for 8 module plate	EACH	4.00	130.00	520.00
77	Supply & fixing of modular type Dummy plate	EACH	33.00	23.00	759.00
Gross Total of Items (Rs.)		15,16,758.00 /-			


(K. TULASI RAO)
GENERAL MANAGER / CEO
For CHIEF GENERAL MANAGER / HVF
For And On Behalf Of THE PRESIDENT OF INDIA

TERMS & CONDITIONS:

1 Special Condition: The Material required for the subject work which be brought inside the factory by the contractors, should be noted along with challan / vouchers etc., and a copy of the same are to be given to the engineering office for record and copy to be submitted to the contractors along with the bill while claiming the payment.

2 Payment Clause: The contractor has to pay the minimum daily wages to the skilled/semi skilled/unskilled labourers engaged in their work as has been specified by the Government, latest rate and displayed in the wages notice Board at factory.

3 Safety Clause: Annexure-B of MES Safety Code, IAFW 2249 must be observed in general. Work Permit shall be obtained for overhead/hazardous work condition. All the safety precautions/measures have to be taken by the contractor. However, a few points of safety measures to be followed for working at height and on the roof are mentioned hereby :

Use of safety belt and helmet of proper quality is mandatory for all workers working on roofs at height of above 5.00 meters and also in the underground areas. Safety belt with life line should be properly tied at some firm support.

(i) In case any difficulty is faced in proper fastening and securing of safety belt, a safety net may be provided below the workspot so that in case of accident fall, there might not be any fatality.

(ii) A crawling ladder or roof walker must be used for movement on Asbestos/CGI roofing.

(iii) Work Permit system should be followed in proper spirit. Contractors shall start the work after obtaining the Work Permit, wherever applicable. Contractor's supervisor and site-in-charge should brief on safety precautions to be observed by the workmen before start of the work. The workers should be clearly explained about the danger of standing or sitting on an apparently stout & new and neat looking asbestos/CGI sheet which is intrinsically weak.


(iv) The contractor shall clear the site after completion of work.

(v) The contractor must employ the labour force duly insured against life risk.

(vi) The contractors shall ensure compliance of all applicable statutory rules and regulations.

4 DEVIATION CLAUSE:

(i) CWC-I authorised to operate upto (+) or (-) 10 % deviation over the CA amount. The deviation Limits shall be as per SOP for Civil Works in AVNL – 2024..



(K. TULASI RAO)
GENERAL MANAGER / CEO
For CHIEF GENERAL MANAGER / HVF
For And On Behalf Of THE PRESIDENT OF INDIA