

NOTING

Sub: - Replacement of HT Power Cable from OFA to MPF

Ref: (i) MPF Work order No. 01/150523 dated 15/05/2023 (0503/04/2021- 22/EO/MPF.
(ii) Minutes of CWC -I against Replacement of HT Power Cable from OFA to MPF
(iii) Admin Approval No. 2601/EO/Contracts/2025-26 dated 12/09/2025
(iv) TE No. 0503/11/2025-26 dated 01/10/2025

Above referred Work Order was placed on M/s Jha P and Company, Ulhasnagar. The Supply Order cost was 64,69,900.00. Against the referred Work Order, CWC-I dated 16/08/2025 decided to short close the Work Order placed on M/s Jha P & Co. Ulhasnagar on Risk & Cost Basis. Accordingly on the basis of Balance quantity forwarded by EIC, SIC vide Letter No. 0508/HT Cable/EO/2025 dated 25/08/2025, Estimate of Rs. 22.76 Lakh was prepared and admin approval for the same was obtained. Further Tendering Action was initiated with last dated of Tender Submission as 15/10/2025 and Tender Opening Date as 18/10/2025.

M/s Juel Electrical & Electronics vide email dated 07/10/2025 asked some queries against the tender item. The same was intimated to EIC & SIC and EIC, SIC vide letter no. 0508/EO/HT Cable/2025 dated 09/10/2025 intimated to add:

1. Quantity for "Supply & Fixing Cable jointing kit for 11 KV (Earthed) grade cable for straight through heat shrink type joint complete with jointing material and accessories suitable for 3 core XLPE armoured aluminium conductor cable of size 400 sq mm Make:3M / Raychem : Quantity '3 Nos' in place of '0 No'
2. Supply & Fixing Cable jointing kit for 11 KV (Earthed) grade cable for indoor termination heat shrink type joint complete with jointing material and accessories suitable for 3 core XLPE armoured aluminium conductor cable of size 400 sq mm 3M/Raychem : Quantity '6 Nos' instead of '0 no.'
3. S & F Cast iron work grade FG 150, un-machined, Man hole covers exceeding 5 Kgs: Quantity '500 Kg' instead of '40 Kg'

Accordingly estimate was calculated and the cost of revised estimate is Rs. 24.47 Lakhs.

Amended Scope of work is as below:

1.	Excavation in Trenches & Return Filling
2.	Demolition of Concrete & provision of Cement Concrete
3.	Sand Filling & Removing Excavated material.
4.	Provision of Cast Iron work grade FG 150, un-machined, man hole covers exceeding 5 kg
5.	Provision of reinforced precast concrete cable cover, class EHV type 1 with peak, size 450mm x 230 x 50 mm

6	Provision of XLPE insulated, screened, PVC bedded, galvanized steel strip or wire armored, electric power cables (heavy duty) with aluminium conductor, 11000 volts, grade cross sectional area 400 sq. mm make Polycab/Finox/CCI .
7	Provision of Tubes, 'Medium grade' 150 mm, galvanized, with all fitting; laid in trenches
8	Provision of Cross arms, bracings, supports, clamps, back plates fabricated from structural steel sections including nuts, bolts, washers, welding etc. for cable route indicators.
9	Removing of Existing Cables and shifting to store
10	Supply of Fixing Cable Jointing Kit for 11 Kv grade for straight through heat shrink type joint
11	Supply of Fixing Cable Jointing Kit for 11 Kv grade for indoor termination heat shrink type joint

In view of above, it is proposed to cancel the current TE 0503/11/2025-26/EO/MPF dated 01/10/2025 and retender the same with revised Estimate.

Submitted for Approval please.



WM/HR

Rajali,
Jt. GM/HR


Chief General Manager


HOS/EO