

वाहननिर्माणजबलपुर
आर्मर्ड व्हीकल्स निगम लिमिटेडकी इकाई
भारत सरकार का उद्यम
रक्षा मंत्रालय



VEHICLE FACTORY JABALPUR
UNIT OF ARMOURED VEHICLES NIGAM LIMITED
A GOVT. OF INDIA ENTERPRISE
MINISTRY OF DEFENCE

CIN-U35990TN2021GOI145504

CA No.01/Engg/VFJ/26-27/EOC

Vehicle Factory Jabalpur
Jabalpur State-Madhya Pradesh, Pin-482009

ACCEPTANCE LETTER No: 208/RD2516/2026-27/EOC/VFJ

To,

M/s Amit Construction,
Plot No. 38, Vikas Nagar,
Ranjhi, Jabalpur- 482005

Dear Sir,

Type of Work: Item Rate

Sub: - Electrical Renovation work for replacement of Overhead LT Lines with Underground LT cables of suitable current rating along with allied necessary accessories at Type-III, IV&V in VFJ Estate Sector-I

Ref: - Tender Ref. No: RD-2516/VFJ and Tender ID No. 2025_AVNL_253805_2

For and on behalf of the President of India, I hereby convey the acceptance of your tender by the competent financial authority for the above mentioned work for a total value of **Rs. 41,30,585.00 (Rupees Forty-One Lakhs Thirty Thousand Five Hundred Eighty-Five Point Zero-Zero only)** and order the services detailed in the schedule enclosed herewith at the item rates quoted by you in Schedule 'A' of the Tender documents as per the terms, conditions and specifications laid therein. List of items, to be issued by factory, is given in Schedule 'B'.

- The contract is allotted with No.01/Engg/VFJ/2026-27/EOC Dated 13/05/2026 which will have to be quoted by you in all future correspondence in connection with this contract.
- In accordance with condition No. 22 of the General Condition of Contract (IAFW-2249), please submit the security deposit of Rs.2,33,900.00/- (Rupees Two Lakhs Thirty-Three Thousand Nine Hundred Only) in favour of "CGM, Vehicle Factory Jabalpur" as mentioned in tender condition. The maturity date of Security Deposit shall be minimum 12 + 2 = 14 months from date of the completion of contract.
- The contract shall be governed by the terms and conditions as per the contract documents enclosed and general condition of contract MES IAFW 2249. The deviation limit shall be as per the clause No.19.1.1 & 19.1.2 of MES Contract Manual (latest revision).
- Shri Deepak Kumar Pandey, WM, Shri Vikash Kumar, JWM/CMS & Shri Onkar Nath Jaiswal, JWM/CMS are nominated as Engineer-in-Charge, Site in-charge & Alternate Site-in-Charge for the subject work respectively.
- You are requested to contact the Engineer-in-Charge within 7 days of receipt of this letter for taking over of site and to make time and progress chart. You will also maintain wage-cum-muster roll and all other records as required in Contract Labour Rules and Acts.
- Please acknowledge receipt of this letter and return two copies duly signed by you in proof of acceptance within seven (07) days from the date of receipt of this communication.

Copy to:

- F & A Section
- Shri Deepak Kumar Pandey, WM
- Shri Vikash Kumar, JWM/CMS
- Shri Onkar Nath Jaiswal, JWM/CMS

M/s. AMIT CONSTRUCTION
Plot No. 38, Vikas Nagar
Manegaow Ranihi, Jabalpur
मेसर्स अमित कंस्ट्रक्शन, जबलपुर
(ठेकेदार)

(राहुलशर्मा)
जारीकर्ता अधिकारी, उप महाप्रबंधक
कृते मुख्य महाप्रबंधक

वाहननिर्माणजबलपुर / Vehicle Factory Jabalpur
पिन - 482009 / Pin - 482009
दूरभाष सं/ PHONE NO. : 0761-2330520
फैक्स/ FAX - 0761-2330436
ईमेल/Email - vfj@ord.gov.in

पंजीकृत पता : भा.वा.नि. रोड, आवडी, चेन्नई-600 054
REGD. ADDRESS: HVFROAD, AVADI, CHENNAI-600 054
दूरभाष सं/ PHONE NO. : 044-26360050
ईमेल/ E-Mail: info@avn.co.in
वेबसाइट/ Website: avnl.co.in

वाहननिर्माणजबलपुर
आर्मर्ड व्हीकल्स निगम लिमिटेडकी इकाई
भारत सरकार का उद्यम
रक्षा मंत्रालय



VEHICLE FACTORY JABALPUR
UNIT OF ARMOURD VEHICLES NIGAM LIMITED
A GOVT. OF INDIA ENTERPRISE
MINISTRY OF DEFENCE

CIN-U35990TN2021GOI145504

CA No.01/Engg/VFJ/2026-27/EOC

IN LIEU OF IAFW-1823(REVISED)
CONTRACTORS' ORDER SHEET

Work Order/Deviation Order No.	01/2026-27
Acceptance letter No.	208/RD2516/2026-27/EOC/VFJ
Contractor's Name	M/s Amit Construction, JBP
Name of the work	Electrical Renovation work for replacement of Overhead LT Lines with Underground LT cables of suitable current rating along with allied necessary accessories at Type-III, IV&V in VFJ Estate Sector-I
CA amount	41,30,585.00

PARTICULARS

1. Authority	CWC decision
2. Time effect	
a. Date of handing over of the site	13/05/2026
b. Date of commencement of work	20/05/2026
c. Date of Completion as per contract	15/11/2026
d. Date for completion shown in previous Orders	NA
e. Revised date of completion	NA
3. Financial effect (Rs.)	
a. Present order	41,30,585.00
b. Contract amount as adjusted by previous orders	NA
c. Contract amount adjusted up to and including this order	NA
4. Expenditure to be booked under code Head No	809/01
5. Certified that no special rate is involved	
6. Technical Examiner	Smt. Shweta Johari Gupta, DGM
7. Approved	Shri Rahul Sharma, DGM
8. Accepted	M/s Amit Construction, JBP

Distribution to: --

- 1.M/s Amit Construction, JBP
- 2.F&A section
3. Sr. Security Officer
4. Smt. Shweta Johari Gupta, DGM /(TE)
5. Shri Deepak Kumar Pandey, WM/(EIC)
6. Shri Vikash Kumar, JWM/CMS/(SIC)
7. Shri Onkar Nath Jaiswal, JWM/CMS (Alternate SIC)
8. Internal Audit cell, Test Audit, AI.WC
9. Safety Officer
10. JWM/PCS
11. DO/MAINT. & RB

M/s. AMIT CONSTRUCTION
Plot No. 38, Vikas Nagar
Manegawan, Bahini, Jabalpur
(ठिकेदार)

(राहुलशर्मा)
जारीकर्ता अधिकारी, उप महाप्रबंधक
कृते मुख्य महाप्रबंधक

वाहननिर्माणजबलपुर / Vehicle Factory Jabalpur
पिन - 482009 / Pin - 482009
दूरभाष सं/ PHONE NO. : 0761-2330520
फैक्स/ FAX - 0761-2330436
ईमेल/Email - vfj@ord.gov.in

पंजीकृत पता : भा.वा.नि. रोड, आवडी, चेन्नई-600 054
REGD. ADDRESS: HVFROAD, AVADI, CHENNAI-600 054
दूरभाष सं/ PHONE NO. : 044-26360050
ईमेल/ E-Mail: info@avnl.co.in
वेबसाइट/ Website: avnl.co.in

वाहननिर्माणजबलपुर
आर्मर्ड व्हीकल्स निगम लिमिटेडकी इकाई
भारत सरकार का उद्यम
रक्षा मंत्रालय



VEHICLE FACTORY JABALPUR
UNIT OF ARMOURD VEHICLES NIGAM LIMITED
A GOVT. OF INDIA ENTERPRISE
MINISTRY OF DEFENCE

CIN-U35990TN2021GOI145504

CA No.01/Engg/VFJ/2026-27/EOC

SCHEDULE – "A"					
Item Code	Item description	Quantity	Unit	Rate / Unit	Total Cost
1	M&L for XLPE insulated, armoured heavy duty electric cable with aluminium conductor, 3.5 core ,1100volts grade, cross-sectional area 150 sq. mm. Make:Polycab/RR/KEI/Havells/Finolex	990.00	RM	790.00	782100.00
2	M&L for XLPE insulated, armoured heavy duty electric cable with aluminium conductor, 3.5 core ,1100 volts grade, cross-sectional area 95 sq. mm. Make:Polycab/RR/KEI/Havells/Finolex	620.00	RM	700.00	434000.00
3	M&L for XLPE insulated, armoured heavy duty electric cable with aluminium conductor, 3.5 core ,1100 volts grade, cross-sectional area 50 sq. mm. Make:Polycab/RR/KEI/Havells/Finolex	390.00	RM	340.00	132600.00
4	M&L for XLPE insulated, armoured heavy duty electric cable with aluminium conductor, 3.5 core ,1100 volts grade, cross-sectional area 35 sq. mm. Make:Polycab/RR/KEI/Havells/Finolex	2130.00	RM	300.00	639000.00
5	M&L for XLPE insulated, armoured heavy duty electric cable with aluminium conductor, 4 core ,1100 volts grade, cross-sectional area 16sq. mm. Make:Polycab/RR/KEI/Havells/Finolex	1380.00	RM	200.00	276000.00
6	M&L for XLPE insulated, armoured heavy duty electric cable with aluminium conductor, 1100 volts grade, cross-sectional area 4 sq. mm,3core. Make:Polycab/RR/KEI/Havells/Finolex	500.00	RM	90.00	45000.00
7	Excavating in trenches, in hard dense soil n exc 1.5 m wide and n exc 1.5 m in depth; for foundation, etc. or for shafts, wells, cesspits, manholes, pier holes, etc. n exc 10 sq m on plan and n exc 1.5 m in depth and getting out.	951.00	CuM	520.00	494520.00
8	Returning, filling in, including spreading, levelling, watering and well ramming in layers not exc 25 cm. in hard dense soil	951.00	CuM	45.00	42795.00
9	M&L for sand filling under floor or in foundation including watering and consolidation	90.00	CuM	1600.00	144000.00
10	M&L Supplying and laying un- reinforced precast concrete cable cover, class LV, type 2,flat , size 300mm x 180mm x 40mm	11082.00	Each	25.00	277050.00
11	Demolition of Cement Concrete un-reinforced of any description and in any position not otherwise specifically provided	22.50	CuM	1700.00	38250.00
12	M&L for Tubes, 'medium grade' Bore of tube in 25mm galvanised, with all fitting and fixed complete to walls and ceilings or laid in floors	500.00	RM	85.00	42500.00
13	M&L for Tubes, 'medium grade' Bore of tube in 100mm galvanised, with all fitting and fixed complete to walls and ceilings or laid in floors	100.00	RM	600.00	60000.00
14	M&L for Tubes, 'medium grade' Bore of tube in 150mm galvanised, with all fitting and fixed complete to walls and ceilings or laid in floors	100.00	RM	850.00	85000.00
15	M&L for Cement concrete in surface channels and drains Type B2 1:2:4 (40 mm graded aggregate) .	25.50	CuM	5500.00	140250.00
16	M&L Earthing complete with Copper earth plate electrode 60×60cm ×3.15mm thick electrode and copper strip as earthing lead, buried directly in ground (earth pit not less than 2.25 metres deep below ground level) with top edge of the plate not less than 1.5 metres below normal ground level, connected to copper strip 20×3mm as earth lead by means of bolts, nuts, check nuts and washers of galvanised iron or steel all as shown in electrical plate No. 3 connected to earthing test point all as specified or indicated including testing on completion .	4.00	Each Set	18000.00	72000.00

M/s. AMIT CONSTRUCTION
P. मेसर्स अमित कंस्ट्रक्शन, जबलपुर
Maneagar (छेकेदार)

(राहुलशर्मा)
जारीकर्ता अधिकारी, उप महाप्रबंधक
कृते मुख्य महाप्रबंधक

वाहननिर्माणजबलपुर / Vehicle Factory Jabalpur
पिन - 482009 / Pin - 482009
दूरभाष सं/ PHONE NO. : 0761-2330520
फैक्स/ FAX - 0761-2330436
ईमेल/Email - vfj@ord.gov.in

पंजीकृत पता : भा.वा.नि. रोड, आवडी, चेन्नई-600 054
REGD. ADDRESS: HVFROAD, AVADI, CHENNAI-600 054
दूरभाष सं/ PHONE NO. : 044-26360050
ईमेल/ E-Mail: info@avnI.co.in
वेबसाइट/ Website: avnl.co.in

वाहननिर्माणीजबलपुर
आर्मर्ड व्हीकल्स निगम लिमिटेडकी इकाई
भारत सरकार का उद्यम
रक्षा मंत्रालय



VEHICLE FACTORY JABALPUR
UNIT OF ARMoured VEHICLES NIGAM LIMITED
A GOVT. OF INDIA ENTERPRISE
MINISTRY OF DEFENCE

CIN-U35990TN2021GOI145504

CA No.01/Engg/VFJ/2026-27/EOC

17	M&L for Earthing complete with galvanised steel earth plate electrode 60×60cm.× 6mm thick, buried directly in ground (earth pit not less than 2.25 metres deep below ground level) with top edge of the plate not less than 1.5 metres below normal ground level, connected to galvanised earth lead wire 4.0mm dia by means of bolts, nuts, check nuts and washers of galvanised iron or steel all as shown in electrical plate No. 3 connected to earthing test point all as specified or indicated including testing on completion	10.00	Each Set	6700.00	67000.00
18	S&F for GI pipes Heavy Class 25 mm Dia.	28.00	RM	150.00	4200.00
19	M&L for Earth continuity conductor or main earthing lead fixed to wall on batten or recess or chases or buried in ground or drawn in conduit/pipe or fixed to poles or any other indicated situation for loop earthing etc. as required 32x6mm galvanised iron strip.	200.00	RM	180.00	36000.00
20	Supply and fixing of CI cover plate 0.3x0.3M with hinges and frame for earth pit chamber.	14.00	Each	250.00	3500.00
21	S& F G I funnel with wire mesh with 25mm G I socket.	14.00	Each	130.00	1820.00
22	Supply, Installation & commissioning of LT Panel Adjustable type 3 pole MCCB incomer of capacity 400A of current rating with Aluminium Bus Bar of capacity 600A along with proper neutral link having provision of street light control circuit with 63A MCB & Timer and required civil work like; excavation, Grouting of long GI stand etc. (Specification Sheet Attached as Annexure-D)	2.00	Each	48000.00	96000.00
23	Supply, Installation & commissioning of LT Panel having Adjustable type 3 pole MCCB incomer of capacity 160A of current rating with Aluminium Bus Bar of capacity 200A along with proper neutral link and required civil work like; excavation, Grouting of long GI stand etc. (Specification Sheet Attached as Annexure-D)	1.00	Each	37000.00	37000.00
24	Supply, Installation & commissioning of LT Panel having Adjustable type 3 pole MCCB incomer of capacity 125A of current rating with Aluminium Bus Bar of capacity 200A along with proper neutral link and required civil work like; excavation, Grouting of long GI stand etc. (Specification Sheet Attached as Annexure-D)	4.00	Each	25000.00	100000.00
25	M&L for Road boring of diameter 250mm below 1.0m from ground level with required accessories.	50.00	RM	900.00	45000.00
26	Supply & fixing of Outdoor type 3 phase with neutral link, 8 way DB Bus bar for street light Cabling connection along with required civil work like; hole in pole, welding etc.	50.00	Each	700.00	35000.00
Total value of Items of Items Rs.				41,30,585.00	
As Taxes as applicable				0.00	
Gross Rs.				41,30,585.00	

M/s. AMIT CONSTRUCTION
Plot No 38, Vikas Nagar
Manegow Ranhi, Jabalpur
मैसर्स अमित कंस्ट्रक्शन, जबलपुर
(ठेकेदार)

(राहुलशर्मा)
जारीकर्ता अधिकारी, उप महाप्रबंधक
कृते मुख्य महाप्रबंधक

वाहननिर्माणीजबलपुर / Vehicle Factory Jabalpur
पिन - 482009 / Pin - 482009
दूरभाष सं/ PHONE NO. : 0761-2330520
फैक्स/ FAX - 0761-2330436
ईमेल/Email - vfj@ord.gov.in

पंजीकृत पता : भा.वा.नि. रोड, आवडी, चेन्नई-600 054
REGD. ADDRESS: HVFROAD, AVADI, CHENNAI-600 054
दूरभाष सं/ PHONE NO. : 044-26360050
ईमेल/ E-Mail: info@avn.co.in
वेबसाइट/ Website: avnl.co.in

CA No.01/Engg/VFJ/2026-27/EOC

TERMS & CONDITIONS:

1. Special Condition: The Material required for the subject work which be brought inside the factory by the contractors, should be noted along with challan/ vouchers etc. and a copy of the same are to be given to the engineering office for record and copy to be submitted by the contractors along with the bill while claiming the payment.
2. Payment Clause: The contractor has to pay the minimum daily wages to the High skilled/skilled/semi-skilled/unskilled labourer engaged in their work as specified by the Government, latest rate and displayed in the wages notice Board at factory. Contractor has to maintain a record of worker's attendance and wages paid to them.
3. Safety Clause: Annexure-B of MES Safety Code, IAFW 2249 must be observed in general. Work Permit shall be obtained for overhead/hazardous work condition. All the safety precautions/measures have to be taken by the contractor. However, a few points of safety measures to be followed for working at height and on the roof are mentioned here by: -

Use of safety belt and helmet of proper quality is mandatory for all workers working on roofs at height of above 5.00 meters and also in the underground areas. Safety belt with life line should be properly tied at some firm support in

- i. In case any difficulty is faced in proper fastening and securing of safety belt, a safety net may be provided below the work spot so that in case of accident fall, there might not be any fatality.
 - ii. A crawling ladder or roof walker must be used for movement on Asbestos/CGI roofing.
 - iii. Work Permit system should be followed in proper spirit. Contractors shall start the work after obtaining the Work Permit, wherever applicable. Contractor's supervisor and site-in-charge should brief on safety precautions to be observed by the workmen before start of the work. The workers should be clearly explained about the danger of standing or sitting on an apparently stout & new and neat looking asbestos/CGI sheet which is intrinsically weak.
 - iv. The contractor shall clear the site after completion of work.
 - v. The contractor must employ the labour force duly insured against life risk.
 - vi. The contractor shall ensure compliance of all applicable statutory rules and regulations.
4. DEVIATION CLAUSE:
 - (i) $\pm 50\%$ of value of individual item other than freakishly rate quoted items.
 - (ii) For freakishly higher or lower rate quoted items it shall be $\pm 25\%$.
 - (iii) 10% of Work Order value (Contract value maximum Rs. 10 lakhs)
10% of Work Order value (Contract value exceeding Rs. 10 lakhs)


M/s. AMIT CONSTRUCTION
Plot No 38, Vikas Nagar
Manegaow Ranihi, Jabalpur
मेसर्स अमित कंस्ट्रक्शन, जबलपुर
(ठेकेदार)


(राहुलशर्मा)
जारीकर्ता अधिकारी, उप महाप्रबंधक
कृते मुख्य महाप्रबंधक

सी.ए. क्र. 01/इजी/वा.नि.ज./2026-27/ई.ओ.(सिविल)

1. Scope of Work:

This contract covers all works described in schedule "A" and as specified in particular specifications. This work lies in restricted area of Vehicle Factory/Factory Estate of VFJ.

2. General Notes:

- I. The normal deviation limit of this contract of items of any individual trade included in the contract shall be plus/minus **50%**. The total deviation of contract shall not exceed **10 %** for the work up to 10 lakhs, and not exceeding **10%** for the works costing more than 10 lakhs as per condition of point no. 10.8.3 of AVNL SOP for civil works 2024 version 2.0, list of building included in scope of work can be changed at any time but quantity will be restricted as per condition 7 of IAFW-2249.
- II. Water charges will be deducted at Rs. 6.00 per Rs.1000/- from the bill.
- III. Income Tax @ 2.0 % will be deducted from the bill.
- IV. The contract value is inclusive of GST and no extra payment will be made to the contractor for GST.
- V. GST will be applicable as per Rule and Tax slab. In this regard discretion of accepting officer will be final and binding to the contractor.
- VI. The contractor will submit GST invoice with filed status of GSTR-1 (B2B) report along with each bill. Bill for Payment will be forwarded to F&A section only when the particulars of the GST Invoice submitted by contractor, correctly appear on GSTR-2B portal of Vehicle factory Jabalpur. Such particulars should be correct in respect of invoice no., invoice date, taxable amount, GST amount and any other field of such Tax Invoice. Such particulars should appear with 'Filed' status if the GSTR 1 filing periodicity in relation to such tax invoice(s) of the supplier has expired or else the factory shall have the right to withhold the future payments of the firm.
- VII. The contractor will also be fully responsible for payment of Employees Provident Fund in EPF Commissioner's Office, by his own EPF Account No. for the workers engaged for various contract works of VFJ. Contractor should have to deposit EPF amount of workmen under their control directly to EPF office and will send a copy of receipt of challan to EO (Civil) every month through EIC/SIC. In Case of any ambiguity payment will not be processed and action as deemed fit shall be taken against the firm.
In addition, the contractor will also have to submit an affidavit, undertaking that the payment due to EPF, has been made in respective offices by him for the particular months in favour of the workmen employed by him in VFJ only (refer clause no. 07 of tender T&C part-III: Standard Conditions of Contract).
- VIII. The contractor will also be fully responsible for payment to ESIC for the workers engaged for various contract works of VFJ. Contractor should have to deposit ESIC amount of workmen under their control directly to ESIC office and will send a copy of receipt of challan to EO(Civil) every month through EIC/SIC. In Case of any ambiguity payment will not be processed and action as deemed fit shall be taken against the firm.
In addition, the contractor will also have to submit an affidavit, undertaking that the payment due to ESIC, has been made in respective offices by him for the particular months in favour of the workmen employed by him in VFJ only (refer clause no. 08 of tender T&C part-III: Standard Conditions of Contract).
- IX. The contractors, who are going to execute the work at height, should make arrangement for group Insurance for persons who will be executing the work to cover compensation charges an eventuality of any accident, if occurred.
- X. As per The Building and Other Construction Workers (Regulation of employment & condition of service) Act 1996, a Registration Certificate to be obtained from the labour Commission (Central), Jabalpur or Shram Suvidha Portal. The above is a statutory requirement & the contractor has to submit the Registration number.
- XI. Contractor shall be liable to pay element for "Building & Other Construction Workers Welfare Cess" as admissible, at the prevailing rates (presently 01% of the completion cost) and the quoted rates shall be deemed to be inclusive of this element and the same will be deducted from contractor's bill.
- XII. All other taxes imposed by Central/State Govt. from time to time will be paid by the Contractor.
- XIII. The electric supply will be provided by factory on request by the contractor. The contractor has to make arrangement for electric meter, cable, fittings etc. at site. The electricity charges will be deducted from the contractor's bill at the prevailing rate.
- XIV. Detailed measurement of the work will be taken and entered in the Measurement book (IAFW-2261) in the usual manner.
- XV. Day to day progress, persons engaged and material used should be recorded in work diary. The work diary must be signed by contractor or his representative and Site-in-charge on day to day basis.

3. Period of Completion:

Entire contract is to be completed within **180 Days** from the date of commencement of work as indicated in Contract. Time of completion is the essence of contract. Normally, the time of completion as mentioned in contract will not be extended, however time of completion will be extended with **compensation for delay** only as per general condition of contracts IAFW- 2249.

4. Defect liability period:

Defect liability period will be **12 months** from the date of completion of work.

5. Deviation Limit:

- a. Deviation Limit for freakily lower Item No. 08, 10, 12 & 18 shall be restricted up to (-) 25% of quantities against normal deviation limit stated above.
- b. Deviation Limit for freakily higher Item No. 20, & 25 shall be restricted up to (+) 25% of quantities against normal deviation limit stated above.

M/s. AMIT CONSTRUCTION
Plot No. 38, Vikas Nagar
मैसर्स अमित कंस्ट्रक्शन जबलपुर
Managadaw, Jabalpur
(उकेदार)

(राहुल शर्मा)
जारीकर्ता अधिकारी, उप महाप्रबंधक
कृते मुख्य महाप्रबंधक

Signature Not Verified

Digitally signed by TEEKARAM MARAVI
Date: 2026.05.13 16:18:43 IST
Location: eProcurement System for
Central PSUs