

EXECUTIVE ENGINEER, NATIONAL HIGHWAY DIVISION

PWD B&R (BRANCH), AMRITSAR.

E-MAIL:-eecw1asr@gmail.com

TELEPHONE NO:-0183-2277666

LETTER OF ACCEPTANCE/LETTER OF AWARD

To

M/s Satish Aggarwal & Co,
H No. 592, Basant Avenue,
Amritsar.
satishaggarwal99@yahoo.com

No. 1544

Dated: - 14-11-2025

Subject: - SHORT-TERM MAINTENANCE OF TARN TARAN KAPURTHALA ROAD (NH-703AA) AT KM 0.00 TO 50.25 OF NH-703AA IN THE STATE OF PUNJAB.

This is to notify you that your bid date: 16.10.2025 for the work amounting to Rs 1,00,92,291.80/- (Rs One Crore Ninety Two Thousand Two Hundred Ninety One and Eighty Paise Only) is here by accepted by Chief Engineer (NH), Punjab PWD B&R, Patiala Memo No: 2489/NH dated: 12.11.2025 with a time limit of (12) Twenty months coupled with the terms and conditions exhibited in the approved DNIT at the following rates:-

Sr. No.	Description of Work / Item(s)	Units	Rates quoted by Agency (excluding GST)
0	Road Maintenance		
1	Milling on Bitumen Surface		
1.01	Dismantling of Existing Damaged Bitumen Surface by Cold Milling Machine Up to 30mm Depth	Sqm	25.72
2	Providing and applying tack coat with bitumen emulsion RS using emulsion pressure distributor at the rate of 0.25 kg per sqm on the prepared bituminous surface/granular surface treated with prime coat after cleaning the surface complete as per technical clause 503 of MORT&H specifications.	Sqm	12.74
3	Providing and laying bituminous concrete 30mm to 45mm thick with Continuous type hot mix plant using crushed aggregates of specified grading, premixed with bituminous binder VG-40 @ 5.4%, laying with a Paver Finisher Mechanical to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction complete as per technical clause 507 of MORT&H specifications.	Cum	8423.10

4	Cleaning of Rcc Side drain Obtained the waste Material, lifts and leads transporting to site on the road	Mtr.	621.56
5	Construction of embankment with good quality earth obtained from borrow pits including compensation of earth, loading, unloading, carriage to site of work, spreading, grading to required slope and compacting to meet requirement of table 300-2 as per technical clause 305 of MORT&H specifications	Cum	270.34
6	First class brick work laid in cement ,lime sand mortar 1:2:9 (one cement, two lime and nine sand) in the First Storey (upto & meter height) above plinth level	Cum	5083.53
7	Cement Pointing 1:2 deep variety	Sqm	101.56

The work will be executed as per approved DNIT and also subject to the financial, technical administrative & legal regularities and strict compliance of the specifications as included in the tender and execution of the work as per MORT&H specifications&approved DNIT, estimate including ensuring of quality throughout the execution of the work.

You are hereby requested to furnish the **Performance Security** in form detailed in Para 32.1 of ITB for an amount of Rs 5,04,614.59/-within 21 days of the receipt of this letter of acceptance valid upto 28 days from the date of expiry of defects liability period of the conditions of contract.

DA/X

-sdh
Executive Engineer,
National Highway Division,
PWD (B&R) Branch; Amritsar.

Endst No.

1545-48

Dated:

14/11/25

Copy of above forwarded to following for information & necessary action:-

- 1) Superintending Engineer, National Highway Circle, Amritsar w.r.t. his Endst No: 2326 dated: 14.11.2025.
- 2) Sub Divisional Engineer, National Highway Sub Division No:3, Amritsar.
- 3) Divisional Accounts Officer, Amritsar.
- 4) ~~Agreement.~~

DA/X

[Signature]
Executive Engineer,
National Highway Division,
PWD (B&R) Branch; Amritsar

Signature Not Verified

Digitally signed by Simranjeet Singh Gill
Date: 2026.03.06 12:09:00 IST
Location: eProcure-EPROC