

eProcurement System Government of India
Created By: Deepak Kumar
Created Date/Time: 12-Feb-2026 12:53 PM
Tender Title: Special Repair works at 5 locations on NH-17, at Ch. 604.50 km, 609.75 km, 617.275 km, 622.813 km and 628.720 km of NH-31,
Job No. 574.
Tender ID: 2025 MoRTH 890509 1

Tender Inviting Authority: Sr. Superintending Engineer, National Highway Circle No.III, P.W(Roads) Directorate, Government of West Bengal.

Name of Work: Special Repair works at 5 locations on NH-17 (at Ch. 604.50 km, 609.75 km, 617.275 km, 622.813 km & 628.720 km of NH-31) [Job No. NH-17/WB/2025-26/574].

Contract No: WBPW_Rd/SE/NHC3/eNIB-5/2025-26

SCHEDULE OF WORK / ITEM(S)												
Sl.No	Description of Work / Item(s)	No.of Qty	Units	Estimated Rate	ACMEE INSULATION CO PVT LTD (GSTN-19AAMCA5798C1Z8) BID ID - 3351813		THE COMBINED ENGINEERS CO-OP LABOUR CONTRACT AND CONSTRUCTION SCTY LTD (GSTN-NA) BID ID - 3352079		MOHAN TAMANG (GSTN-NA) BID ID -3351843		L1 Amount	L1 Vendor
					Rate	Amount	Rate	Amount	Rate	Amount		
1.00	Bill of Quantities in Details											
1.01	SR work on Sukha Nadi											
1.02	Dismantling of Structures : Dismantling of existing structures culverts, bridges, retaining walls other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting dismantled material, disposal unserviceable material and stacking serviceable material with all lifts lead of 1000 metres (Reference MORT&H's specification clause 202) Cement Concrete Grade M-15 & M-20.	54.00	cum		1000.00	54000.00	421.80	22777.20	430.29	23235.66	22777.20	THE COMBINED ENGINEERS CO-OP LABOUR CONTRACT AND CONSTRUCTION SCTY LTD
1.03	Excavation for Structures in Ordinary soil by Manual Means and Depth upto 3 m : Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material (Reference to MORT&H's specification 304).	588.50	cum		200.00	117700.00	140.60	82743.10	122.26	71950.01	71950.01	MOHAN TAMANG
1.04	Boulder Apron Laid in Wire Crates : Providing and laying of boulder apron laid in wirecrates made with 4mm dia GI wire conforming to IS: 280 & IS:4826 in 100mm x 100mm mesh (weaved diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 40 kg each (Reference to MORT&H's specification 2503).	1191.00	cum		2900.00	3453900.00	3022.90	3600273.90	3212.14	3825658.74	3453900.00	ACMEE INSULATION CO PVT LTD

1.05	Back filling behind abutment, wing wall and return wall complete including sprinkling water and thoroughly compacted with plate compactor/power rammer in layers not exceeding 150mm compacted thickness as per drawing and Technical Specification (710.1.4 of IRC:78 & MoRTH's specification 2200). With River Bed Materials	242.00	cum		1000.00	242000.00	1195.10	289214.20	1194.56	289083.52	242000.00	ACMEE INSULATION CO PVT LTD
1.06	Plain Cement Concrete (1:3:6): Plain/Reinforced cement concrete in open foundation complete all including vibrating and compacting, finishing, curing, sampling, testing etc. as per drawing and Technical Specifications (Reference to MORT&H's specifications 1500, 1700 & 2200).	103.50	cum		5500.00	569250.00	3655.60	378354.60	3595.99	372184.97	372184.97	MOHAN TAMANG
1.07	Plain Cement Concrete Grade M20 : Plain/Reinforced cement concrete in open foundation complete all including vibrating and compacting, finishing, curing, sampling, testing etc. as per drawing and Technical Specifications (Reference to MORT&H's specifications 1500, 1700 & 2200).	144.00	cum		6050.00	871200.00	4499.20	647884.80	4501.65	648237.60	647884.80	THE COMBINED ENGINEERS CO-OP LABOUR CONTRACT AND CONSTRUCTION SCTY LTD
1.08	SR work on Kalikhola											
1.09	Dismantling of Structures : Dismantling of existing structures culverts, bridges, retaining walls other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting dismantled material, disposal unserviceable material and stacking serviceable material with all lifts lead of 1000 metres (Reference MORT&H's specification clause 202) Cement Concrete Grade M-15 & M-20.	78.40	cum		1000.00	78400.00	421.80	33069.12	430.29	33734.74	33069.12	THE COMBINED ENGINEERS CO-OP LABOUR CONTRACT AND CONSTRUCTION SCTY LTD
1.10	Excavation for Structures in Ordinary soil by Manual Means and Depth upto 3 m : Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material (Reference to MORT&H's specification 304).	640.30	cum		200.00	128060.00	140.60	90026.18	122.25	78276.68	78276.68	MOHAN TAMANG
1.11	Boulder Apron Laid in Wire Crates : Providing and laying of boulder apron laid in wirecrates made with 4mm dia GI wire conforming to IS: 280 & IS:4826 in 100mm x 100mm mesh (weaved diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 40 kg each (Reference to MORT&H's specification 2503).	1114.80	cum		2900.00	3232920.00	3022.90	3369928.92	3057.79	3408824.29	3232920.00	ACMEE INSULATION CO PVT LTD

1.12	Back filling behind abutment, wing wall and return wall complete including sprinkling water and thoroughly compacted with plate compactor/power rammer in layers not exceeding 150mm compacted thickness as per drawing and Technical Specification (710.1.4 of IRC:78 & MoRTH's specification 2200). With River Bed Materials	229.22	cum		1000.00	229220.00	1195.10	273940.82	1194.45	273791.83	229220.00	ACMEE INSULATION CO PVT LTD
1.13	Plain Cement Concrete (1:3:6): Plain/Reinforced cement concrete in open foundation complete all including vibrating and compacting, finishing, curing, sampling, testing etc. as per drawing and Technical Specifications (Reference to MORT&H's specifications 1500, 1700 & 2200).	100.20	cum		5500.00	551100.00	3655.60	366291.12	3479.88	348683.98	348683.98	MOHAN TAMANG
1.14	Plain Cement Concrete Grade M20 : Plain/Reinforced cement concrete in open foundation complete all including vibrating and compacting, finishing, curing, sampling, testing etc. as per drawing and Technical Specifications (Reference to MORT&H's specifications 1500, 1700 & 2200).	144.82	cum		6050.00	876191.25	4499.20	651596.64	4380.76	634443.57	634443.57	MOHAN TAMANG
1.15	Cement Grout : Fealing of cracks/porous concrete (within the limits of practical pressure 100kpa -400kpa until refusal) by injection process through nipples/Grouting complete as per Technical Specification (Reference to MORT&H's specification 2806).	324.00	Kg		250.00	81000.00	14.06	4555.44	198.07	64174.68	4555.44	THE COMBINED ENGINEERS CO-OP LABOUR CONTRACT AND CONSTRUCTION SCTY LTD
1.16	Providing and inserting nipples with approved fixing compound after drilling holes for grouting as per Technical Specifications including subsequent cutting/removal and sealing of the hole as necessary of nipples after completion of grouting with Cement/Epoxy (Reference to MORT&H's specification 2800).	648.00	Each		125.00	81000.00	77.33	50109.84	141.38	91614.24	50109.84	THE COMBINED ENGINEERS CO-OP LABOUR CONTRACT AND CONSTRUCTION SCTY LTD
1.17	Applying epoxy mortar over leached, honey combed and spalled concrete surface (@ 20-24 kg of Epoxy mortar/sqm) and exposed steel reinforcement complete as per Technical Specification (Reference to MORT&H's specification 2804). Thickness of epoxy mortar = 10mm	31.20	Sqm		700.00	21840.00	2952.60	92121.12	465.12	14511.74	14511.74	MOHAN TAMANG
1.18	SR work on Shankhini Bridge											
1.19	Excavation for Structures in Ordinary soil by Manual Means and Depth upto 3 m : Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material (Reference to MORT&H's specification 304).	84.00	cum		200.00	16800.00	421.80	35431.20	122.26	10269.84	10269.84	MOHAN TAMANG

1.20	Boulder Apron Laid in Wire Crates : Providing and laying of boulder apron laid in wirecrates made with 4mm dia GI wire conforming to IS: 280 & IS:4826 in 100mm x 100mm mesh (weaved diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 40 kg each (Reference to MORT&H's specification 2503).	600.00	cum		2900.00	1740000.00	3022.90	1813740.00	2982.66	1789596.00	1740000.00	ACMEE INSULATION CO PVT LTD
1.21	Back filling behind abutment, wing wall and return wall complete including sprinkling water and thoroughly compacted with plate compactor/power rammer in layers not exceeding 150mm compacted thickness as per drawing and Technical Specification (710.1.4 of IRC:78 & MoRTH's specification 2200). With River Bed Materials	256.00	cum		1000.00	256000.00	1195.10	305945.60	1194.57	305809.92	256000.00	ACMEE INSULATION CO PVT LTD
1.22	Plain Cement Concrete (1:3:6): Plain/Reinforced cement concrete in open foundation complete all including vibrating and compacting, finishing, curing, sampling, testing etc. as per drawing and Technical Specifications (Reference to MORT&H's specifications 1500, 1700 & 2200).	32.00	cum		5500.00	176000.00	3655.60	116979.20	3423.19	109542.08	109542.08	MOHAN TAMANG
1.23	SR work on Juranti Bridge											
1.24	Dismantling of Structures : Dismantling of existing structures culverts, bridges, retaining walls other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting dismantled material, disposal unserviceable material and stacking serviceable material with all lifts lead of 1000 metres (Reference MORT&H's specification clause 202) Cement Concrete Grade M-15 & M-20.	539.20	cum		1000.00	539200.00	421.80	227434.56	430.29	232012.37	227434.56	THE COMBINED ENGINEERS CO-OP LABOUR CONTRACT AND CONSTRUCTION SCTY LTD
1.25	Excavation for Structures in Ordinary soil by Manual Means and Depth upto 3 m : Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material (Reference to MORT&H's specification 304).	393.00	cum		200.00	78600.00	140.60	55255.80	122.57	48170.01	48170.01	MOHAN TAMANG
1.26	Boulder Apron Laid in Wire Crates : Providing and laying of boulder apron laid in wirecrates made with 4mm dia GI wire conforming to IS: 280 & IS:4826 in 100mm x 100mm mesh (weaved diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 40 kg each (Reference to MORT&H's specification 2503).	805.80	cum		2900.00	2336820.00	3022.90	2435852.82	3156.82	2543765.56	2336820.00	ACMEE INSULATION CO PVT LTD
1.27	Boulder Apron Laid in Wire Crates : Providing and laying of boulder apron laid in wirecrates made with 4mm dia GI wire conforming to IS: 280 & IS:4826 in 100mm x 100mm mesh (weaved diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 40 kg each (Reference to MORT&H's specification 2503). Using Departmental Boulder	537.20	cum		2265.00	1216758.00	3022.90	1623901.88	1962.94	1054491.37	1054491.37	MOHAN TAMANG

1.28	Back filling behind abutment, wing wall and return wall complete including sprinkling water and thoroughly compacted with plate compactor/power rammer in layers not exceeding 150mm compacted thickness as per drawing and Technical Specification (710.1.4 of IRC:78 & MoRTH's specification 2200). With River Bed Materials	360.00	cum		1000.00	360000.00	1195.10	430236.00	1194.56	430041.60	360000.00	ACMEE INSULATION CO PVT LTD
1.29	SR work on Mal Bridge											
1.30	Excavation for Structures in Ordinary soil by Manual Means and Depth upto 3 m : Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material (Reference to MORT&H's specification 304).	715.00	cum		200.00	143000.00	140.60	100529.00	122.25	87408.75	87408.75	MOHAN TAMANG
1.31	Boulder Apron Laid in Wire Crates : Providing and laying of boulder apron laid in wirecrates made with 4mm dia GI wire conforming to IS: 280 & IS:4826 in 100mm x 100mm mesh (weaved diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 40 kg each (Reference to MORT&H's specification 2503).	2088.00	cum		2900.00	6055200.00	3022.90	6311815.20	2908.21	6072342.48	6055200.00	ACMEE INSULATION CO PVT LTD
1.32	Back filling behind abutment, wing wall and return wall complete including sprinkling water and thoroughly compacted with plate compactor/power rammer in layers not exceeding 150mm compacted thickness as per drawing and Technical Specification (710.1.4 of IRC:78 & MoRTH's specification 2200). With River Bed Materials	1148.50	cum		1000.00	1148500.00	1195.10	1372572.35	1194.57	1371963.65	1148500.00	ACMEE INSULATION CO PVT LTD
1.33	Plain Cement Concrete (1:3:6): Plain/Reinforced cement concrete in open foundation complete all including vibrating and compacting, finishing, curing, sampling, testing etc. as per drawing and Technical Specifications (Reference to MORT&H's specifications 1500, 1700 & 2200).	130.00	cum		5500.00	715000.00	3655.60	475228.00	3367.19	437734.70	437734.70	MOHAN TAMANG

Total in Figures

25369659.25

25257808.61

24671554.58

Lowest Amount Quoted BY: MOHAN TAMANG (Rs.2,46,71,554.58)

Signature Not Verified

Digitally signed by DEEPAK KUMAR SINGH
Date: 2026.02.27 18:50:43 IST
Location: eProcure-EPROC

