


Date: September 27, 2025

विषय Subject : कार्य आदेश में हस्ताक्षर करने के संबंध में Work order Signature reg.
कार्य का नाम : वर्ष 2024-2025 के लिए राधापुरम तालुक, तिरुनेलवेली जिले के सरकारी एवं सरकारी सहायता प्राप्त विद्यालयों के लिए रसोईघर ब्लॉक का निर्माण ।
Name of work : Construction of kitchen blocks to government and government aided schools at Radhapuram Taluk, Tirunelveli district for the year 2024-2025
संदर्भ निविदा सं. : एनपीसीआईएल/केकेएनपीपी/एडी/सीएसआर गतिविधियां/पीटी/2025/49
Ref: Tender No. : NPCIL/KKNPP/AD/CSR ACTIVITIES/PT/2025/49

मसौदा कार्य आदेश का वित्त एवं लेखा और प्रभारी अभियंता द्वारा पुनरीक्षण करने के बाद, उनके सुधार को शामिल किया गया, अंतिम कार्य आदेश तैयार किया है और सभी पृष्ठों पर हस्ताक्षर हेतु प्रस्तुत है।


The draft Work Order after being vetted in F&A and ENC, the final Work order is prepared and put up for signature please in all pages.




(डॉ. राजेशकुमार जी. पिल्लै (Dr. Rajeshkumar G Pillai)

वैज्ञानिक अधिकारी-ई (सीएंडएमएम-कार्य समूह) SO/E (C&MM-Works Group)


प्रमुख (सीएंडएमएम-कार्य समूह)
Head (C&MM-Works Group)



27/09/25

गु. माडसामी, Shri. G. Madasamy
वैज्ञानिक अधिकारी/एफ (सिविल) SO/F (Civil)


27/09/2025

मुख्य अभियंता (ईएंडयूस)
Chief Engineer (E&US)


27-9-25



न्यूक्लियर पावर कॉर्पोरेशन ऑफ इंडिया लिमिटेड Nuclear Power Corporation of India Ltd.

(भारत सरकार का उद्यम A Government of India Enterprise)

कुडनकुलम न्यूक्लियर पावर प्रोजेक्ट Kudankulam Nuclear Power Project


कुडनकुलम पोस्ट, राधापुरम तालुक, तिरुनेलवेली जिला, तमिलनाडु 627106-

Kudankulam P.O., Radhapuram Taluk, Tirunelveli District, Tamil Nadu - 627 106

वी.पी. विल्सन, मुख्य अभियंता (ईएंडयूएस) V P WILSON, Chief Engineer (E&US)

☎ 04637- 282553/249801

ई-मेल E-mail: vpwilson@npcil.co.in



सं .No. एनपीसीआईएल NPCIL/केकेएनपीपी KKNPP/C&MM-WG/2025/एस S/816 September ,27 , 2025

To

M/s. S.A.V. Constructions,
885, Radhapuram Main Road,
Vadakkankulam,
Tirunelveli District 627116.
Tamil Nadu.
Phone: 04637-232333
Mobile: 9443130652
E-mail: sav_constructions@yahoo.co.in;

Work Order No.	:	300499
Subledger Code	:	S10057
Account Code	:	78203
Charge Code	:	6185

Dear Sirs,

Subject : "WORK ORDER" – reg.

Name of work : Construction of kitchen blocks to Government and Government aided schools at Radhapuram Taluk, Tirunelveli district for the year 2024-2025

Ref. 1. E-Tender No. : NPCIL/KKNPP/AD/CSR ACTIVITIES/PT/2025/49

2. Our letter No. : NPCIL/KKNPP/ C&MM-WG/2025/S/669, dated: 02.08.2025 (Asking Rate Clarification reg.)

3. Your submission : dated: 04.08.2025 (Submission of Rate Clarification letter reg.)

4. Our letter No. : NPCIL/KKNPP/ C&MM-WG/2025/S/741, dated: 02.09.2025 (Requesting Bid validity extension upto 31.10.2025 reg.)

5. Your submission : dated: 03.09.2025(Acceptance for Extension of Bid validity upto 31.10.2025 reg.)

Please refer to your above cited tender in response to e-TENDER NOTICE No:

NPCIL/KKNPP/AD/CSR ACTIVITIES/PT/2025/49 for the above work, Part-I and Part-II were opened on 03.05.2025 and 14.07.2025 respectively.

1. **BID ACCEPTANCE:**

This is to inform you that the tender submitted by you and modified in subsequent letters referred above has been accepted for and on behalf of Nuclear Power Corporation of India Limited, for the items of work shown in the schedule of quantities and rates covered by the tender for a total value of ₹ **88,25,940 (Rupees Eighty Eight Lakhs Twenty Five Thousand Nine Hundred and Forty only)** inclusive of all applicable taxes, BOCW Cess including Goods and Services Tax (GST).

2. **RATES:**

The rates quoted by the contractor as given in Annexure- 'I' (Schedule of Quantities and rates) are for complete items of work including supply of all materials (unless otherwise specified), consumables, all temporary arrangements, all labours, all taxes (including GST) cess, duties, levies, BOCW cess applicable from time to time and incidental charges as per terms, conditions and specifications mentioned in the tender document will remain firm until the entire period of contract.

Further during execution of the contract due to variation in quantities, if tender structure changes you have agreed to give suitable discount to remain in L1 position as per Rate clarification letter dated 04.08.2025.

3. **EXECUTION OF WORK:**

The work shall be carried out strictly in accordance with the terms and conditions and specifications, drawings stipulated in the tender and also in best workmanlike manner. You shall employ and maintain qualified engineers/supervisors in the job at all times. You shall also bring to the site and employ such machinery and equipments and other materials as are necessary for the satisfactory completion of this work.

4. **CONTRACT PERIOD:**

The work shall be completed in all respects within **12 Months (including monsoon period)** from the date of commencement including Sunday, Holidays and rainy season/days, if any. The date of commencement will be reckoned within 14 days from the date of work order. The time shall be essence of the contract and the work shall be completed as per approved programme of work.

5. CONTRACT PRICE ADJUSTMENT:

Contract Price Adjustment is not applicable as per clause No.11.3.3 of Schedule :A of General Conditions of Contract.

6. AUTHORISED OFFICIALS:

You are requested to submit the name of the authorized Representative who will deal with all matters relating to the contract with the power of Attorney in his favour, duly executed on stamped paper of an appropriate value shall be furnished to Engineer-in-charge.

7. LIABILITY FOR DAMAGE AND INSURANCE: (As per clause No.2, Part-I of Special Instructions in Section-III of tender)

You shall provide the following insurance policies in the joint names of the Corporation and the Contractor with insurance cover from the date of commencement of work to the end of the Defects Liability Period. You will be fully responsible for any loss, damage or destruction of NPCIL plant & machineries, property, persons etc.. Policies submitted should bear the Work Order (WO) number except Group Insurance for which WO number is not mandatory. You shall submit the copies of Insurance policies along with the original policy document to the Engineer-in-charge before the commencement of work.

7.1 Contractor's All Risk(CAR) Policy

You shall take Contractor's All Risk(CAR) Policy for the whole contract value (including GST) including Insurance for Third Party Liability for 10% of the work order value including applicable GST i.e, ₹ 8,82,594.00

7.2 Employees Compensation Policy:

You shall take the Employee,s Compensation Policy for employees who are engaged in this work.

7.3 Group Insurance Policy:

In case the employees engaged on this work are already covered under the Group Insurance policy of the Contractor, same shall be acceptable in lieu of employee compensation policy. In such case the proof of employment shall be submitted.

8. TAXES

8.1 Income tax and statutory levy etc. if any, on this contract, as notified by Central/State Govt. from time to time shall be recovered from your running bills as well as final bill for this work in the prescribed manner. You are requested to submit copy of your GST No. & Permanent Account Number to Engineer-in-charge.

8.2 For GST related compliance (including TDS) refer Special Conditions of Contract (SCC) is attached in Section-IV of tender and clause no 11 of Part-2 of Section-I / NIT.

9. ENGINEER-IN-CHARGE:

Shri. G. Madasamy Scientific Officer-F(Civil) will be the Engineer-in-charge for this work. You may make necessary arrangements for commencing the work immediately in consultation with Engineer-in-charge.

10. SECURITY DEPOSIT:

You may please note that security deposit will be ₹ 8,82,594.00 (@ 10% of the contract value). Initially you will have to submit a performance guarantee for ₹ 4,41,297.00 (50% of security deposit) within 30 days after issue of work order. The remaining amount of security deposit of ₹ 4,41,297.00 will be recovered from the RA bill/ final bill at the rate of 6% of each bill amount. Security deposit amount will not bear any interest. Refer clause No.2, page-3 of Section – II for full details of Security deposit and its release. Defect liability period is **12 months** from the certified date of completion of the contract as per Schedule: A Clause No.9.1.1 of General Conditions of Contract. Failure of furnishing the performance guarantee within 30 days as stated above shall constitute sufficient grounds for cancellation of the award of work.

11. APPLICABLE LAWS & ACTS:

You shall comply with various provisions of Contract Labour (Regulation & Abolition) Act 1970, and Rules framed there under from time to time. In case the Contract Labour Act does not apply to your organization the Contractor should intimate the Engineer-in-charge of this work accordingly before commencing the work. Further you shall also comply with the provisions of other laws such as Workmen's Compensation Act 1923, Minimum Wages Act 1948, E.P.F. Act, Bonus Act, Gratuity Act, BOCW cess Act and other Labour Laws as applicable to your organisation. In case NPCIL is required to incur any expenses as Principal Employer under the provisions of the various laws, NPCIL shall be entitled to recover the same from you from your bills.

12. LABOUR LICENSE :

If labour license is required to be obtained for the work as per the existing labour laws then the Principal Employer's Certificate required for obtaining Labour License for specified number of workmen proposed to be employed for the work and shall be issued on the request of the Contractor. A request for issue of Principal Employer's Certificate (Form – III) shall be submitted to the Engineer in charge of the work immediately after receipt of work

order. You shall ensure the submission of labour license application within 07 days of issue of Form-III.

13. PAYMENT TERMS:

- 13.1 In respect of all items in the schedule of quantities and rates of Work order, the payments shall be made on submission of bills for the work along with the joint measurements, through monthly RA bills, as per General Conditions of Contract of tender & against submission of Tax invoice as applicable to you.
- 13.2 The first running account bill will be paid only after submission of the documents as mentioned in Clause No.15 (A) and 15 (B) of Special instructions in Section-III (Part-I) of tender.
- 13.3 Final bill will be paid only after submission of the documents as mentioned in clause No.15 (C) and 15 (D) of special instructions in Section-III (Part-I) of tender.

14. PENALTIES:


Penalties imposed by Engineer-in-charge for non-compliance of work will be recovered from bills of the contractor before release of payment as per clause No.19 of Section-III (Part-I) of tender.

15. All other terms and conditions not specifically brought out in this work order shall be governed as per Special Conditions of Contract, special instructions and General Conditions of Contract.

16. AGREEMENT:

You shall enter into contract and shall execute and sign the Contract agreement in accordance with the Articles of Agreement. You shall bring appropriate value Bond paper/ Stamp paper (top page)(as per applicable stamp duty Act at work location) at your own cost in the joint name of NPCIL and the contractor, as mentioned in clause No.10, Part-I of Section-III of tender.

You are requested to attend the office for signing the agreement within 30 days from the date of issue of Work order. Till then a formal agreement document is executed, the original tender together with letters under reference and this Work order shall form the binding contract between us.




17. ACCEPTANCE OF WORK ORDER:

Please acknowledge by a letter, the receipt of this work order and the acceptance of the terms and conditions indicated in this contract immediately on issue of work order. Also as a token of acceptance, the Contractor is requested to sign the copy of this work order and send it along with the acceptance letter, to Engineer In-charge (C&MM-Works Group), C-Block, Ground Floor, Kudankulam Nuclear Power Project, Kudankulam P.O, Radhapuram Taluk, Tirunelveli District, Tamil Nadu and a copy to Engineer In-charge of this work.

Thanking you,

Yours faithfully,



वी.पी. विल्सन (V.P.Wilson)

मुख्य अभियंता (ईएंडयूएस) Chief Engineer (E&US)

For and on behalf of
Nuclear Power Corporation of India Ltd

Encl: Schedule of Quantities and Rates – Annexure –'I'

Annexure - 1

Print Date: 18-Sep-2025

Name of Work: Construction of kitchen blocks to government and government aided schools at Radhapuram Taluk, Tirunelveli district for the year 2024-2025
WO / SOQR Number : 300499 Tender No.:NPCIL/KKNPP/AD/CSR ACTIVITIES/PT/2025/49
Agency Name : S.A.V.Constructions

Item No	Item Description	Unit	Quantity	Rate in ₹	Rebate in %	Amount in ₹
		Rate in Words				
Schedule : CSR Activities:A(CIVIL						
1	Earth work excavation by mechanical means(hydraulic excavator)/manual means for foundation, trenches etc., in all types of soils below ground level including shoring, strutting, bailing / pumping of water, leveling, ramming the bottom of excavation, refilling with selected excavated materials in the sides of the foundation in layers, consolidating and disposing off the surplus earth at places as directed with in a lead of 2 Kms all as per drawings and specifications. - up to 1.5m ht	Cu.M	900	100	0.00	90,000.00
				Rupees One Hundreds Only		
2	Providing and laying plain cement concrete 1:3:6, using 40 mm and down graded stone aggregate at all height including mechanical mixing, leveling, compaction, vibrating, finishing smooth the exposed surfaces of concrete, curing etc complete as per drawings and standard specifications.	Cu.M	63	3500	0.00	220,500.00
				Rupees Three Thousand Five Hundreds Only		
3	Providing and laying plain cement concrete 1:2:4, using 20 mm and down graded stone aggregate at all height including mechanical mixing, leveling, compaction, vibrating, finishing smooth the exposed surfaces of concrete, curing etc complete as per drawings and standard specifications.	Cu.M	117	4000	0.00	468,000.00
				Rupees Four Thousand Only		
4	Filling with selected earth in layers of not more than 150 mm thick compacted layer, each layer well rammed, watered and consolidated as per drawings and specifications	Cu.M	360	80	0.00	28,800.00
				Rupees Eighty Only		
5	Providing Pre-construction anti-termite treatment using chlorpyrifos emulsifiable concentrate 20 percentage with 1 percentage concentration as per specifications. Note: The contractor shall furnish from the agency carrying out this work under this item a written guarantee in favour of NPCIL for the satisfactory performance of the treatment for a period of ten years.	Sqm	648	80	0.00	51,840.00
				Rupees Eighty Only		
6	Construction of granular sub-base (GSB) by providing close graded Material conforming to specifications conforming to Grade-I (size range 75 mm to 0.075 mm) , mixing in a mechanical mix plant, carriage of mixed material by tippers to work site, for all leads & lifts, spreading in uniform layers of specified thickness on prepared surface and compacting etc complete as per specifications and directions of Engineer-in-Charge.	Cu.M	99	600	0.00	59,400.00
				Rupees Six Hundreds Only		
7	Providing and constructing Random Rubble masonry in CM 1:6 using hard granite stones including hammer dressing the stones, providing bond stones as per specifications ,raking out the joints, scaffolding, curing etc., complete as per specifications.				0.00	

2. $\frac{1}{2} \frac{d}{dt} \left(\frac{1}{2} \frac{d}{dt} \right)$

Name of Work: Construction of kitchen blocks to government and government aided schools at Radhapuram Taluk, Tirunelveli district for the year 2024-2025
 WO / SOQR Number : 300499 Tender No.:NPCIL/KNPP/AD/CSR ACTIVITIES/PT/2025/49 Agency Name : S.A.V.Constructions

Item No	Item Description	Unit	Quantity	Rate in ₹	Rebate in %	Amount in ₹
				Rate in Words		
7.1	In foundation and basement	Cu.M	360	2800	0.00	1,008,000.00
			Rupees Two Thousand Eight Hundreds Only			
8	Providing and laying M20/M25 Design mix concrete with cement content up to 350kg/Cum using 20mm and down graded stone aggregates including Mixing ,Ramming, Compaction, leveling, curing, placing at all lifts, including scaffolding and Finishing smooth all exposed faces complete as per specification.	Cu.M	108	4300	0.00	464,400.00
			Rupees Four Thousand Three Hundreds Only			
9	Providing ,placing in position and removing Form work for all insitu concrete works including scaffolding etc., complete at all elevations as per drawing and specification (measurement for form work shall be the area of forms in contact with concrete surfaces)	Sq.M	720	300	0.00	216,000.00
			Rupees Three Hundreds Only			
10	Providing cutting ,bending placing and tying mild steel, high yield steel reinforcement in RCC works including providing spacer blocks in CM 1:2, binding wires etc.complete at all elevations as per drawings and specifications including dewatering wherever necessary etc complete as per drawings and specifications	MT	10	78000	0.00	780,000.00
			Rupees Seventy Eight Thousand Only			
11	Providing and constructing brick masonry in CM 1:6, using country bricks, including scaffolding, curing and racking out joints etc complete as per specifications and drawings.In superstructure above plinth at all elevations.	Cu.M	270	4970	0.00	1,341,900.00
			Rupees Four Thousand Nine Hundreds Seventy Only			
12	Providing cement plaster for the internal faces of brickwork / concrete at all elevations in cement mortar 1:5, 12mm thick using River sand finished smooth with a floating coat of neat cement including scaffolding, finishing, curing, forming grooves wherever necessary all complete as per drawings and specifications	Sqm	495	325	0.00	160,875.00
			Rupees Three Hundreds Twenty Five Only			
13	Providing cement plaster for the ceiling with 6 mm thick in cement mortar 1:3 using River sand at all elevations including hacking and preparing the surface, scaffolding, finishing, curing etc all complete as per drawings and specifications	Sqm	540	250	0.00	135,000.00
			Rupees Two Hundreds Fifty Only			
14	Plastering of external faces of brick work/concrete at all elevations in cement mortar 1:4, 20 mm thick using River sand including scaffolding, curing, forming grooves, plaster bands, border, keystone etc wherever required all as per drawings and specifications	Sqm	1845	350	0.00	645,750.00
			Rupees Three Hundreds Fifty Only			
15	Providing, fabricating and erection of Structural steel members made out of M.S. angles, flats, plates, pipes, channels, tubes, rods etc conforming to relevant IS etc., including cost of welding, welding rods, drilling holes, bolts/nuts wherever required and providing and applying two or more coats of approved quality synthetic enamel paint over a coat of zinc chromate yellow primer etc., as per drawings and specifications	MT	7.2	78000	0.00	561,600.00
			Rupees Seventy Eight Thousand Only			

Chaitanya

Item No	Item Description	Unit	Quantity	Rate in ₹	Rebate in %	Amount in ₹
		Rate in Words				
16	Providing and applying Acrylic Emulsion paint of Asian paints (Premium Emulsion)/Lewis Berger (Rangoli) /ICI Dulux (Super smooth)/Matex gold of NIPPON make of approved shade in two or more coats over a coat of primer including preparation of surface with required coats of putty using Birla/ JK make, sand papering etc., to get good finish at all elevations etc all as per as per drawings and specifications	Sq.M	1350	150	0.00	202,500.00
			Rupees One Hundreds Fifty Only			
17	Providing and applying Exterior Emulsion Paint of Apex of Asian paints/Weather cote of Lewis Berger /Weather shield of ICI Dulux/Sumo Xtra of NIPPON make & shade in two or more coats to give an even shade over a coat of primer as per manufacturers instructions to the external plastered surfaces including preparation of surfaces, scaffolding etc. at all elevations, complete as per drawings and specifications	Sq.M	2250	140	0.00	315,000.00
			Rupees One Hundreds Forty Only			
18	Providing, Fixing and testing PVC rain water pipes of 110 mm dia as per IS-13592 of Type A of Prince/Jain/ Kitec/Finox/Supreme make with necessary fittings and fixtures, such as bottom shoe, PVC grating, GI clamps, screws/nails, wooden packing pieces at minimum 1 m spacing, cost inclusive of Fixing the shoes in brick masonry in CM 1:6 and plastering the same with CM 1:4 etc complete all as per drawings and specifications	RM	72	250	0.00	18,000.00
			Rupees Two Hundreds Fifty Only			
19	Providing and laying 20mm thick (+-2mm) polished Natural granite slab of approved colour for name board including writing by engraving, painting etc. as per required etc., with all exposed surfaces buffed, set over a base of cement mortar 1:4, 20 mm thick neatly pointed with white cement/black oxide and colouring pigments to match the shade of the stone as per the requirement, curing, rubbing, polishing, etc complete as per specifications and as per drawings and specifications	Sqm	22.5	6800	0.00	153,000.00
			Rupees Six Thousand Eight Hundreds Only			
20	Providing and Fixing 20mm thick Exterior grade designer tiles of approved colour and design over 20mm thick base cement mortar 1:4 laid and pointed with white cement slurry mixed with pigments to match with the shade of the tile including rubbing, curing, in Staircases (both tread & riser), Walkway areas, Entrances etc., as per drawings and specifications	Sqm	72.9	700	0.00	51,030.00
			Rupees Seven Hundreds Only			
21	Providing and making RCC roof mother slab/sunken slab water proof by injection grout with the approved compound of SIKABASE/ROFF/FOSROC/ Dr.Fixit/ Bostic India make as per the manufacturers procedure/ specification by providing one water proofing membrane system by brush application as water proofing barrier for both slab and inner face of parapet/side wall including water testing by ponding for minimum 7 days and providing joint guarantee for water tightness for 10 years (This item may be got executed by specialized water proofing agents duly approved by NPCIL and 10 years joint guarantee for water proofing is required to be submitted).	Sqm	405	375	0.00	151,875.00
			Rupees Three Hundreds Seventy Five Only			
22	Supply and laying one course of pressed cement tiles 20 mm thick of 250mmX250mm size as per IS:1237 of latest version, laid over the roof slab over a base of 20mm thick CM 1:4 and joints pointed neatly in cement mortar 1:3 mixed with water proofing admixture of approved make etc complete all as per drawings and specifications	Sqm	270	600	0.00	162,000.00
			Rupees Six Hundreds Only			

G. wavy

Item No	Item Description	Unit	Quantity	Rate in ₹	Rebate in %	Amount in ₹
		Rate in Words				
23	Providing drip moulds of CM 1:4, 25mm thick on edges of sunshades including finishing, curing, scaffolding etc complete as per the standard specifications.	RM	135	150	0.00	20,250.00
			Rupees One Hundreds Fifty Only			
24	Providing Rain water harvesting pit as per the drawing.	No	9	1000	0.00	9,000.00
			Rupees One Thousand Only			
25	Providing and Fixing in position 24 guage G.I. Chicken mesh of 150 mm wide in between the junction of column/beams with masonry by placing the mesh with nailing etc before at all elevations etc complete as per drawings and specifications	RM	585	40	0.00	23,400.00
			Rupees Forty Only			
26	Providing and Fixing heavy quality 15 mm dia, CP brass screw down long bodied bib tap with CP brass flanges as per relevant IS, ADSON/CERA/ PARRYWARE make as per drawings and specifications				0.00	
26.1	Supply	No.	54	750	0.00	40,500.00
			Rupees Seven Hundreds Fifty Only			
26.2	Fixing	No.	54	10	0.00	540.00
			Rupees Ten Only			
27	Providing and placing on terrace (at all floor levels) polyethene water Storage Tanks capacity as required of SINTEX JOLISTRAN or other approved equivalent make with cover and suitable locking arrangements and making holes for inlet, outlet, scour and overflow pipes as per specifications and as directed by the Engineer in charge.	litres	9000	7	0.00	63,000.00
			Rupees Seven Only			
28	Providing and fixing Gun metal full way gate valve female ends screwed bonnet integral seat, non rising spindle, class I, marked to IS : 778 tested to 20 kg/Sq.cm. Hydraulic pressure, LEADER/ZOLATO make as directed by Engineer in charge				0.00	
28.1	32mm dia	No.	18	650	0.00	11,700.00
			Rupees Six Hundreds Fifty Only			
28.2	40mm dia	No.	18	800	0.00	14,400.00
			Rupees Eight Hundreds Only			

G. W.

Chalk

Name of Work: Construction of kitchen blocks to government and government aided schools at Radhapuram Taluk, Tirunelveli district for the year 2024-2025
 WO / SOQR Number : 300499 Tender No.:NPCIL/KKNPP/AD/CSR ACTIVITIES/PT/2025/49
 Agency Name : S.A.V.Constructions

Item No	Item Description	Unit	Quantity	Rate in ₹	Rebate in %	Amount in ₹
				Rate in Words		
29	Providing, laying/Fixing in position approved PVC pipes Jain/ Finolex/Kitec/Supreme/Prince make IS - 4985 of latest version with required specials and Fixing arrangements for water Supply works as per standard specifications and providing and Fixing approved nails quality clamps and screws for Fixing as per drawings and specifications. (Excavation if required will be paid under relevant item)				0.00	
29.1	PVC PIPES -- 20mm dia-10kg/cm2	RM			0.00	
29.1.1	Supply	RM	180	20	0.00	3,600.00
				Rupees Twenty Only		
29.1.2	Fixing	RM	180	25	0.00	4,500.00
				Rupees Twenty Five Only		
29.2	PVC PIPES -- 25mm dia-10kg/cm2	RM			0.00	
29.2.1	Supply	RM	225	30	0.00	6,750.00
				Rupees Thirty Only		
29.2.2	Fixing	RM	225	30	0.00	6,750.00
				Rupees Thirty Only		
29.3	PVC PIPES -- 32mm dia-10kg/cm2	RM			0.00	
29.3.1	Supply	RM	315	45	0.00	14,175.00
				Rupees Forty Five Only		
29.3.2	Fixing	RM	315	35	0.00	11,025.00
				Rupees Thirty Five Only		
29.4	PVC PIPES -- 40mm dia-10kg/cm2	RM			0.00	
29.4.1	Supply	RM	270	65	0.00	17,550.00
				Rupees Sixty Five Only		

Handwritten signature

Name of Work: Construction of kitchen blocks to government and government aided schools at Radhapuram Taluk, Tirunelveli district for the year 2024-2025
 WO / SOQR Number : 300499 Tender No.:NPCIL/KKNPP/AD/CSR ACTIVITIES/PT/2025/49
 Agency Name : S.A.V.Constructions

Item No	Item Description	Unit	Quantity	Rate in ₹	Rebate in %	Amount in ₹
				Rate in Words		
29.4.2	Fixing	RM	270	40	0.00	10,800.00
				Rupees Forty Only		
30	Providing and Fixing Stainless Steel Kitchen sink with drain board 1 mm thick of size 1020mm x 535 mm, bowl size 480 x 405 x 200mm, Prince/Supreme/Prayag make, fixed with stainless steel plug 38mm etc complete as per drawings and specifications	No.	9	8000	0.00	72,000.00
				Rupees Eight Thousand Only		
31	Providing and Fixing heavy quality 38mm CP brass waste coupling for Kitchen sink PRINCE/SUPREME /ADSON/CERA make with or without overflow with rubber plug ball chain with necessary check nut as per drawings and specifications				0.00	
31.1	Supply	No.	9	350	0.00	3,150.00
				Rupees Three Hundreds Fifty Only		
31.2	Fixing	No.	9	20	0.00	180.00
				Rupees Twenty Only		
32	Providing and laying Indian Patent stone (IPS) flooring with cement concrete 1:2:4, 40 mm thick using 10mm maximum size stone aggregate including providing and placing glass strips of 5mm thick of approved quality required depth, grooves, consolidating, curing, rubbing the surface smooth, all complete as per drawings and specifications	Sq.M	360	450	0.00	162,000.00
				Rupees Four Hundreds Fifty Only		
Schedule : CSR Activities:B(ELECT						
1	LDB : Supply and erection of 8 way single phase distribution board Single door complete with interconnection Copper busbar, Neutral bar, Earth bar, top and bottom removable gland plates with knockout, and double door with the following 25A 2P RCCB (30 mA) - 1 no, 20A/16A/6A SP MCB - 6 Nos(Make:Legrand/L&T/Havells) Scope includes construction of pedestal cubicle and supply of necessary electrical components, hardware for fixing the panel etc. to complete the work in all respect.	SET	9	6000	0.00	54,000.00
				Rupees Six Thousand Only		
2	PRIMARY:- For lighting, bulkhead fitting and exhaust fan points, supply and wiring for point with two + one (earth-green) runs of 1.5sq.mm (22/0.3)1100V grade FRLS insulated single core multi strand Copper conductor wire (without joint) drawn into the existing PVC conduit (inclusive of supplying and laying of PVC conduits while concreting), complete with angle / batten lamp holder or ceiling rose, 5 Amps modular type Legrand Mylinc/ MK India /Schneider/Anchor panasonic/GM make switch including pulling the wire from existing switch box to lighting point through the conduit and connecting at both ends.(The box, grid plate and the cover plate for the switch has been covered elsewhere.). All items such as 1.5sq.mm (22/0.3) Copper FRLS insulated wire, 6 Amps switch, 3 Plate ceiling rose, hylam sheet for JB's, necessary electrical components for wiring works (wherever applicable) shall be supplied by the contractor as per the requirement, specification (Approximate length 13Mtr)	Point	60	1500	0.00	90,000.00
				Rupees One Thousand Five Hundreds Only		

Chd -

C.V. m...

Name of Work: Construction of kitchen blocks to government and government aided schools at Radhapuram Taluk, Tirunelveli district for the year 2024-2025
 WO / SOQR Number : 300499 Tender No.:NPCIL/KNPP/AD/CSR ACTIVITIES/PT/2025/49 Agency Name : S.A.V.Constructions

Item No	Item Description	Unit	Quantity	Rate in ₹	Rebate in %	Amount in ₹
				Rate in Words		
3	SECONDARY:- For lighting, 6A sockets supply and wiring for point with two + one (earth-green) runs of 1.5sq.mm (22/0.3)1100V grade FRLS insulated single core multi strand Copper conductor wire (without joint) drawn into the existing PVC conduit (inclusive of supplying and laying of PVC conduits while concreting), complete with angle / batten lamp holder or ceiling rose, 5 Amps modular type Legrand Mylinc/ MK India /Schneider/Anchor panasonic/GM make switch including pulling the wire from existing switch box to lighting point through the conduit and connecting at both ends.(The box, grid plate and the cover plate for the switch has been covered elsewhere.). All items such as 1.5sq.mm (22/0.3) Copper FRLS insulated wire, 6 Amps switch, 3 Plate ceiling rose, hylam sheet for JB's, necessary electrical components for wiring works (wherever applicable) shall be supplied by the contractor as per the site requirement. (Approximate length 10.5Mtr)	Point	30	1300	0.00	39,000.00
			Rupees One Thousand Three Hundreds Only			
4	Power point wiring : 16A Power switch & sockets (2 switches+2 sockets in switch board) in seprate switchboard: Supply, installation of 16A, 5 pin socket & switch outlet including supply of 16A 5 pin socket and SP switch modular type. Legrand Mylinc/ MK India /Schneider/Anchor panasonic/GM make (switch & socket separate type). One end of the earthing wire to be connected at the third pin of 16A socket and the another end to be connected at the earth bar in the Distribution Board. Scope includes supply of modular socket and switch, 4 module GI box with base ,cover plate and accessories with point wiring of 3 runs of 4 sq.mm copper wire for 16A-6A , 6 in 1 socket.	Point	36	2000	0.00	72,000.00
			Rupees Two Thousand Only			
5	Supply, installation and wiring of 3R x 4sqmm Cu for FRLS insulated each core multistrand with 1100V Copper wire, drawn into the existing PVC conduit (inclusive of supplying and laying of PVC conduits while concreting) from MCB DB to various switch boards as circuit mains and switch board to switch board looping. The termination shall be done by using crimping type Copper lugs of Dowells make, suitable modular type switch box supply by contractor scope.	RM	300	500	0.00	150,000.00
			Rupees Five Hundreds Only			
6	Tube light LED: Supply and installation of LED tube light fitting 230V,20W(Make:Havells/Crompton/Philips/GM)	Nos	55	600	0.00	33,000.00
			Rupees Six Hundreds Only			
7	Bulk head LED: Supply and installation of 9W LED bulk head light fitting .(Make:Havells/Crompton/Philips)	Nos	18	500	0.00	9,000.00
			Rupees Five Hundreds Only			
8	Exhaust fan: Supply, installation and commissioning of 300 mm sweep heavy duty energy saving Exhaust Fan of metal construction and elegant design with shutter. Energy saving models with CRNO laminations (make/model Almonard/CG/Orient)	Nos	18	4000	0.00	72,000.00
			Rupees Four Thousand Only			
9	Earthing:Supply and installation of Earthing with copper earth plate 600mm X 600mm X 3mm thick including accessories and providing masonry enclosure with cover plate having locking arrangement and water pipe of 2.7 meter long with charcoal/coak and salt etc. as required	Nos	10	8000	0.00	80,000.00
			Rupees Eight Thousand Only			

Handwritten signature

Item No	Item Description	Unit	Quantity	Rate in ₹	Rebate in %	Amount in ₹
				Rate in Words		
10	Supply and Laying of 25mm x 5mm copper strip at 0.50 meter below ground level as strip earth electrode, including connection termination with nut , bolt; spring, washer etc. as required.(jointing shall be done by overlapping with 2 sets of brass nut bolt & spring washer spaced at 50mm.	RM	75	600	0.00	45,000.00
				Rupees Six Hundreds Only		
11	POWER CABLE: Supply of power cable 1100 V, 4C x 4 sq.mmstranded compacted circular aluminum conductor, XLPE insulated, cores laid up. extruded PVC inner sheath, galvanized steel flat strip armoured and overall extruded PVC sheathed cable conforming to IS 7098(part1)/1988.(Make:KEI/Havells/Glosters)	RM	700	250	0.00	175,000.00
				Rupees Two Hundreds Fifty Only		
12	Cable laying: Laying of PVC Insulated and PVC Sheathed /XLPE power cable of 1.1 KV grade of following size(upto 35 Sq mm) direct in ground including excavation, sand cushioning, protective covering and refilling the trench etc as required	RM	700	300	0.00	210,000.00
				Rupees Three Hundreds Only		
13	6 MODULE: supply & installation of concealed in wall mounting 6 Modular switch board with covered plate comprising. (Switches are covered in the Point wiring) (Make: Legrand Mylinc/ MK India /Havells/Schneider) all as directed by Engineer.	Nos	9	600	0.00	5,400.00
				Rupees Six Hundreds Only		
14	3 MODULE: Supply & installation of concealed in wall mounting 3 Modular switch board with covered plate comprising. (Switches are covered in the Point wiring) (Make: Legrand Mylinc/ MK India /havells/Schneider) all as directed by Engineer.	Nos	27	400	0.00	10,800.00
				Rupees Four Hundreds Only		

5. 2. 5.

John

Note: All Item Rates are considered to be in Indian Rupees unless otherwise explicitly specified and in which case shall be always converted appropriately to arrive at the amount in Indian Rupees.

Work Order Total	₹8825940
Overall Rebate (%)	0
Work Order Value After Overall Rebate (in Figure)	₹8825940
Final Work Order Value (in Figure)	₹8825940
Final Work Order Value (in words)	Rupees Eighty Eight Lakh Twenty Five Thousand Nine Hundreds Forty Only

9.4.2017

9.4.2017

Cc: **Distribution:** (Through E-mail)

- | | | |
|-----|--------------------------|---|
| 1. | Site Director | - For kind information |
| 2. | Project Director(KK-3-6) | - -do- |
| 3. | CE (E&US)/Chairman(CSR) | - With Schedule of Quantities & Rates |
| 4. | Head(C&MM) | With Schedule of Quantities & Rates |
| 5. | Head(C&MM-Works Group) | With Schedule of Quantities & Rates |
| 6. | AGM(F&A) | - With Schedule of Quantities & Rates, Approval for Award of work, copy of vetted work order, Rate Clarification Letter, CST, Admin approval & Technical Sanction |
| 7. | Engineer-in-charge | - With Schedule of Quantities & Rates, Approval for Award of work, CST & Rate Clarification Letter |
| 8. | Head (HR) | - |
| 9. | Head (IS&F -1&2) | - with Schedule-A |
| 10. | Smt.Sheeba, SO/F(IT) | |
| 11. | Commandant, CISF | |
| 12. | Tender File | |
| 13. | Work order File | |