

Date: September 27, 2025

विषय Subject : कार्य आदेश में हस्ताक्षर करने के संबंध में Work order Signature reg.

कार्य का नाम : तिरुनेलवेली जिले के राधापुरम तालुक में सरकारी उच्चतर माध्यमिक विद्यालय कुडनकुलम, प्राथमिक विद्यालय इलयनयिनारकुलम, टीडीटीए प्राथमिक विद्यालय चिदंबरापुरम, आरसी प्राथमिक विद्यालय प्रकाशपुरम, हिंदू यादव मिडल स्कूल तिरुवंबलापुरम और सेंट एनीस उच्चतर माध्यमिक विद्यालय कुडनकुलम के लिए शौचालय सुविधा का निर्माण।


Name of work : Construction of Toilet Facility to Govt. Hr. Sec. School Kudankulam, Govt. Primary School Elayanainarkulam, TDTA Primary School Chidambarapuram, RC Primary School Prakasapuram, Hindu Yadava Middel School Thiruvambalapuram & ST.Annes Hr. Sec. School Kudankulam at Radhapuram Taluk, Tirunelveli District.

संदर्भ निविदा सं. : एनपीसीआईएल/केकेएनपीपी/एडी/सीएसआर गतिविधियां/पीटी/2025/51

Ref: Tender No. : NPCIL/KKNPP/AD/CSR ACTIVITIES/PT/2025/51


मसौदा कार्य आदेश का वित्त एवं लेखा और प्रभारी अभियंता द्वारा पुनरीक्षण करने के बाद, उनके सुधार को शामिल किया गया, अंतिम कार्य आदेश तैयार किया है और सभी पृष्ठों पर हस्ताक्षर हेतु प्रस्तुत है।

The draft Work Order after being vetted in F&A and ENC, the final Work order is prepared and put up for signature please in all pages.



27/09/2025

(डॉ. राजेशकुमार जी. पिल्लै (Dr. Rajeshkumar G Pillai)
वैज्ञानिक अधिकारी-ई (सीएंडएमएम-कार्य समूह) SO/E (C&MM-Works Group)


प्रमुख (सीएंडएमएम-कार्य समूह)
Head (C&MM-Works Group)


27/09/25

गु. माडसामी, Shri. G. Madasamy
वैज्ञानिक अधिकारी/एफ (सिविल) SO/F (Civil)


27/09/2025

मुख्य अभियंता (ईएंडयूस)
Chief Engineer (E&US)


27-09-25

(केन्द्रीयकृत निविदा कोश) (Centralized Tender Cell) (सी टी सी) केकेएनपीपी (CTC) KKNPP
आगत सं./inward No. 513.....
दिनांक / Date 27/09/25...

न्यूक्लियर पावर कॉर्पोरेशन ऑफ इंडिया लिमिटेड Nuclear Power Corporation of India Ltd.

(भारत सरकार का उद्यम A Government of India Enterprise)

कुडनकुलम न्यूक्लियर पावर प्रोजेक्ट Kudankulam Nuclear Power Project


कुडनकुलम पोस्ट, राधापुरम तालुक, तिरुनेलवेली जिला, तमिलनाडु 627 106-

Kudankulam P.O., Radhapuram Taluk, Tirunelveli District, Tamil Nadu – 627 106

वी.पी. विल्सन, मुख्य अभियंता (ईएंडयूएस) **V P WILSON, Chief Engineer (E&US)**

☎ 04637- 282553/249801

ई-मेल E-mail: vpwilson@npcil.co.in



सं .No. एनपीसीआईएल NPCIL/केकेएनपीपी KKNPP/C&MM-WG/2025/एस S/818 September , 27 , 2025

To

M/s. Suruthi Constructions,
No: 13C, Kesari Street,
Water Tank Road,
Nagercoil, Pin Code: 629001,
Kanyakumari District.
Tamil Nadu.
Phone No: 04652235272
Mobile: 9443120642
E-Mail ID : ssuruthicotrstructions@yahoo.com

Work Order No.	:	300501
Subledger Code	:	S10018
Account Code	:	78203
Charge Code	:	6185

Dear Sirs,

Subject : “WORK ORDER” – reg.

Name of work : Construction of Toilet Facility to Govt. Hr. Sec. School Kudankulam, Govt. Primary School Elayanainarkulam, TDTA Primary School Chidambarapuram, RC Primary School Prakasapuram, Hindu Yadava Middel School Thiruvambalapuram & ST.Annes Hr. Sec. School Kudankulam at Radhapuram Taluk, Tirunelveli District.

- Ref. 1. E-Tender No. :** NPCIL/KKNPP/AD/CSR ACTIVITIES/PT/2025/51
- 2 Our letter No. :** NPCIL/KKNPP/ C&MM-WG/2025/S/670, dated: 02.08.2025 (Calling for Negotiation & Rate Clarification reg.)
- 3 Our letter No. :** NPCIL/KKNPP/ C&MM-WG/2025/S/676, dated: 05.08.2025 (Minutes of Negotiation / Rate Clarification reg .)
- 4. Your letter :** dated: 30.08.2025 (Acceptance of Bid validity period upto 31.10.2025 reg .)

Please refer to your above cited tender in response to e-TENDER NOTICE No:

NPCIL/KKNPP/AD/CSR ACTIVITIES/PT/2025/51 for the above work, Part-I and Part-II were opened on 02.05.2025 and 05.07.2025 respectively.

1. BID ACCEPTANCE:

This is to inform you that the tender submitted by you and modified in subsequent letters referred above has been accepted for and on behalf of Nuclear Power Corporation of India Limited, for the items of work shown in the schedule of quantities and rates covered by the tender for a total value of ₹ **1,25,66,168 (Rupees One Crore Twenty Five Lakhs Sixty Six Thousand One Hundred and Sixty Eight only)** inclusive of all applicable taxes, BOCW Cess including Goods and Services Tax (GST).

2. RATES:

The rates quoted by the contractor as given in Annexure- 'I' (Schedule of Quantities and rates) are for complete items of work including supply of all materials (unless otherwise specified), consumables, all temporary arrangements, all labours, all taxes (including GST) cess, duties, levies, BOCW cess applicable from time to time and incidental charges as per terms, conditions and specifications mentioned in the tender document will remain firm until the entire period of contract.

Further during execution of the contract due to variation in quantities, if tender structure changes you have agreed to give suitable discount to remain in L1 position as per the Minutes of Negotiation/Rate Clarification dated 05.08.2025.

3. EXECUTION OF WORK:

The work shall be carried out strictly in accordance with the terms and conditions and specifications, drawings stipulated in the tender and also in best workmanlike manner. You shall employ and maintain qualified engineers/supervisors in the job at all times. You shall also bring to the site and employ such machinery and equipments and other materials as are necessary for the satisfactory completion of this work.

4. CONTRACT PERIOD:

The work shall be completed in all respects within **12 Months (including monsoon period)** from the date of commencement including Sunday, Holidays and rainy season/days, if any. The date of commencement will be reckoned within 14 days from the date of work order. The time shall be essence of the contract and the work shall be completed as per approved programme of work.

5. CONTRACT PRICE ADJUSTMENT:

Contract Price Adjustment is not applicable as per clause No.11.3.3 of Schedule :A of General Conditions of Contract.

6. AUTHORISED OFFICIALS:

You are requested to submit the name of the authorized Representative who will deal with all matters relating to the contract with the power of Attorney in his favour, duly executed on stamped paper of an appropriate value shall be furnished to Engineer-in-charge.

7. LIABILITY FOR DAMAGE AND INSURANCE: (As per clause No.2, Part-I of Special Instructions in Section-III of tender)

You shall provide the following insurance policies in the joint names of the Corporation and the Contractor with insurance cover from the date of commencement of work to the end of the Defects Liability Period. You will be fully responsible for any loss, damage or destruction of NPCIL plant & machineries, property, persons etc.,. Policies submitted should bear the Work Order (WO) number except Group Insurance for which WO number is not mandatory. You shall submit the copies of Insurance policies along with the original policy document to the Engineer-in-charge before the commencement of work.

7.1 Contractor's All Risk(CAR) Policy

You shall take Contractor's All Risk(CAR) Policy for the whole contract value (including GST) including Insurance for Third Party Liability for 10% of the work order value including applicable GST i.e, **₹12,56,617.00**

7.2 Employees Compensation Policy:

You shall take the Employees Compensation Policy for employees who are engaged in this work.

7.3 Group Insurance Policy:

In case the employees engaged on this work are already covered under the Group Insurance policy of the Contractor, same shall be acceptable in lieu of employee compensation policy. In such case the proof of employment shall be submitted.

8. TAXES

8.1 Income tax and statutory levy etc. if any, on this contract, as notified by Central/State Govt. from time to time shall be recovered from your running bills as well as final bill for this work in the prescribed manner. You are requested to submit copy of your GST No. & Permanent Account Number to Engineer-in-charge.

8.2 For GST related compliance (including TDS) refer Special Conditions of Contract (SCC) is attached in Section-IV of tender and clause no 11 of Part-2 of Section-I / NIT.

9. ENGINEER-IN-CHARGE:

Shri. G. Madasamy Scientific Officer-F(Civil) will be the Engineer-in-charge for this work. You may make necessary arrangements for commencing the work immediately in consultation with Engineer-in-charge.

10. SECURITY DEPOSIT:

You may please note that security deposit will be ₹ 12,56,617. 00 (@ 10% of the contract value). Initially you will have to submit a performance guarantee for ₹ 6,28,309.00 (50% of security deposit) within 30 days after issue of work order. The remaining amount of security deposit of ₹ 6,28,308.00 will be recovered from the RA bill/ final bill at the rate of 6% of each bill amount. Security deposit amount will not bear any interest. Refer clause No.2, page-3 of Section – II for full details of Security deposit and its release. Defect liability period is 12 months from the certified date of completion of the contract as per Schedule: A Clause No.9.1.1 of General Conditions of Contract. Failure of furnishing the performance guarantee within 30 days as stated above shall constitute sufficient grounds for cancellation of the award of work.

11. APPLICABLE LAWS & ACTS:

You shall comply with various provisions of Contract Labour (Regulation & Abolition) Act 1970, and Rules framed there under from time to time. In case the Contract Labour Act does not apply to your organization the Contractor should intimate the Engineer-in-charge of this work accordingly before commencing the work. Further you shall also comply with the provisions of other laws such as Workmen's Compensation Act 1923, Minimum Wages Act 1948, E.P.F. Act, Bonus Act, Gratuity Act, BOCW cess Act and other Labour Laws as applicable to your organisation. In case NPCIL is required to incur any expenses as Principal Employer under the provisions of the various laws, NPCIL shall be entitled to recover the same from you from your bills.

12. LABOUR LICENSE :

If labour license is required to be obtained for the work as per the existing labour laws then the Principal Employer's Certificate required for obtaining Labour License for specified number of workmen proposed to be employed for the work and shall be issued on the request of the Contractor. A request for issue of Principal Employer's Certificate (Form – III) shall be submitted to the Engineer in charge of the work immediately after receipt of work

order. You shall ensure the submission of labour license application within 07 days of issue of Form-III.

13. PAYMENT TERMS:

- 13.1 In respect of all items in the schedule of quantities and rates of Work order, the payments shall be made on submission of bills for the work along with the joint measurements, through monthly RA bills, as per General Conditions of Contract of tender & against submission of Tax invoice as applicable to you.
- 13.2 The first running account bill will be paid only after submission of the documents as mentioned in Clause No.15 (A) and 15 (B) of Special instructions in Section-III (Part-I) of tender.
- 13.3 Final bill will be paid only after submission of the documents as mentioned in clause No.15 (C) and 15 (D) of special instructions in Section-III (Part-I) of tender.

14. PENALTIES:

Penalties imposed by Engineer-in-charge for non-compliance of work will be recovered from bills of the contractor before release of payment as per clause No.19 of Section-III (Part-I) of tender.

15. All other terms and conditions not specifically brought out in this work order shall be governed as per Special Conditions of Contract, special instructions and General Conditions of Contract.

16. AGREEMENT:

You shall enter into contract and shall execute and sign the Contract agreement in accordance with the Articles of Agreement. You shall bring appropriate value Bond paper/ Stamp paper (top page)(as per applicable stamp duty Act at work location) at your own cost in the joint name of NPCIL and the contractor, as mentioned in clause No.10, Part-I of Section-III of tender.


You are requested to attend the office for signing the agreement within 30 days from the date of issue of Work order. Till then a formal agreement document is executed, the original tender together with letters under reference and this Work order shall form the binding contract between us.

17. ACCEPTANCE OF WORK ORDER:

Please acknowledge by a letter, the receipt of this work order and the acceptance of the terms and conditions indicated in this contract immediately on issue of work order. Also as a token of acceptance, the Contractor is requested to sign the copy of this work order and send it along with the acceptance letter, to Engineer In-charge (C&MM-Works Group), C-Block, Ground Floor, Kudankulam Nuclear Power Project, Kudankulam P.O, Radhapuram Taluk, Tirunelveli District, Tamil Nadu and a copy to Engineer In-charge of this work.

Thanking you,

Yours faithfully,



वी.पी. विल्सन (V.P.Wilson)

मुख्य अभियंता (ईएंडयूस) Chief Engineer (E&US)

For and on behalf of
Nuclear Power Corporation of India Ltd

Encl: Schedule of Quantities and Rates – Annexure – 'I'

NUCLEAR POWER CORPORATION OF INDIA LIMITED

(A Government of India Enterprise)

Kudankulam Nuclear Power Project

Schedule Of Quantities And Rates

Print Date: 17-Sep-2025

Annexure - 1

Name of Work: Construction of Toilet Facility to Govt. Hr. Sec. School Kudankulam, Govt. Primary School Elayanainarkulam, TDTA Primary School Chidambarapuram, RC Primary School Prakasapuram, Hindu Yadava Middle School Thiruvambaluram & ST.Annes Hr. Sec. School Kudankulam at Radhapuram Taluk, Tirunelveli District. WO / SOQR Number : 300501 Tender No.:NPCIL/KKNPP/AD/CSR ACTIVITIES/PT/2025/51.							Agency Name : Suruthi Constructions		
Item No	Item Description	Unit	Quantity	Rate in ₹	Rebate in %	Amount in ₹			
Schedule : CSR Activities:A(CIVIL)									
1	Earth work excavation by mechanical means(hydraulic excavator)/manual means for foundation, trenches etc., in all types of soils below ground level including shoring, strutting, bailing / pumping of water, leveling, ramming the bottom of excavation, refilling with selected excavated materials in the sides of the foundation in layers, consolidating and disposing off the surplus earth at places as directed with in a lead of 2 Kms all as per drawings and specifications. - up to 1.5m ht	CuM	1100	150	0.00	165,000.00			
			Rupees One Hundreds Fifty Only						
2	Providing and laying plain cement concrete 1:3:6, using 40 mm and down graded stone aggregate at all height including mechanical mixing, leveling, compaction, vibrating, finishing smooth the exposed surfaces of concrete, curing etc complete as per drawings and standard specifications.	CuM	92	4000	0.00	368,000.00			
			Rupees Four Thousand Only						
3	Providing and laying plain cement concrete 1:2:4, using 20 mm and down graded stone aggregate at all height including mechanical mixing, leveling, compaction, vibrating, finishing smooth the exposed surfaces of concrete, curing etc complete as per drawings and standard specifications.	CuM	75	4000	0.00	300,000.00			
			Rupees Four Thousand Only						
4	Filling with selected earth in layers of not more than 150 mm thick compacted layer, each layer well rammed, watered and consolidated as per drawings and specifications	CuM	401.84	110	0.00	44,202.40			
			Rupees One Hundreds Ten Only						
5	Providing Pre-construction anti-termite treatment using chlorpyriphos emulsifiable concentrate 20 percentage with 1 percentage concentration as per specifications. Note: The contractor shall furnish from the agency carrying out this work under this item a written guarantee in favour of NPCIL for the satisfactory performance of the treatment for a period of ten years.	SqM	300	110	0.00	33,000.00			
			Rupees One Hundreds Ten Only						
6	Construction of granular sub-base (GSB) by providing close graded Material conforming to specifications conforming to Grade-I (size range 75 mm to 0.075 mm) , mixing in a mechanical mix plant, carriage of mixed material by tippers to work site, for all leads & lifts, spreading in uniform layers of specified thickness on prepared surface and compacting etc complete as per specifications and directions of Engineer-in-Charge.	CuM	135	860	0.00	116,100.00			
			Rupees Eight Hundreds Sixty Only						




G. W. W. T.

Item No	Item Description	Unit	Quantity	Rate in ₹	Rebate in %	Amount in ₹
				Rate in Words		
7	Providing and laying crushed stone aggregate bed of 60mm thick (compacted thickness) for preparation of base to lay interlocking precast concrete paver blocks using 12 mm down graded stone aggregate including, leveling, placing, to the required slope, compacting with roller etc as per drawings and specifications. (Payment shall be made only for compacted thickness)	CuM	20	610	0.00	12,200.00
			Rupees Six Hundreds Ten Only			
8	Providing and laying M30 grade 60 mm thick interlocking precast concrete pavers blocks as pr relevant IS of approved shape over a profiled layer to the required line, pattern etc., all as per drawings and specifications	SqM	280	600	0.00	168,000.00
			Rupees Six Hundreds Only			
9	Providing and constructing Random Rubble masonry in CM 1:6 using hard granite stones including hammer dressing the stones, providing bond stones as per specifications ,raking out the joints, scaffolding,curing etc.,complete as per specifications.In foundation and basement	CuM	140	3000	0.00	420,000.00
			Rupees Three Thousand Only			
10	Providing and laying M20/M25 Design mix concrete with cement content up to 350kg/Cum using 20mm and down graded stone aggregates including Mixing ,Ramming, Compaction, leveling, curing, placing at all lifts, including scaffolding and Finishing smooth all exposed faces complete as per specification.	CuM	190	6000	0.00	1,140,000.00
			Rupees Six Thousand Only			
11	Providing ,placing in position and removing Form work for all insitu concrete works including scaffolding etc., complete at all elevations as per drawing and specification (measurement for form work shall be the area of forms in contact with concrete surfaces)	SqM	1300	375	0.00	487,500.00
			Rupees Three Hundreds Seventy Five Only			
12	Providing cutting ,bending placing and tying mild steel, high yield steel reinforcement in RCC works including providing spacer blocks in CM 1:2, binding wires etc.complete at all elevations as per drawings and specifications including dewatering wherever necessary etc complete as per drawings and specifications	MT	16	80000	0.00	1,280,000.00
			Rupees Eighty Thousand Only			
13	Providing and constructing brick masonry in CM 1:6, using country bricks, including scaffolding, curing and racking out joints etc complete as per specifications and drawings.In superstructure above plinth at all elevations.	CuM	180	6500	0.00	1,170,000.00
			Rupees Six Thousand Five Hundreds Only			
14	Providing cement plaster for the internal faces of brickwork / concrete at all elevations in cement mortar 1:5, 12mm thick, finished smooth with a floating coat of neat cement including scaffolding, finishing, curing, forming grooves wherever necessary all complete as per drawings and specifications	SqM	1450	300	0.00	435,000.00
			Rupees Three Hundreds Only			
15	Providing cement plaster for the ceiling with 6 mm thick in cement mortar 1:3 at all elevations including hacking and preparing the surface, scaffolding, finishing, curing etc all complete as per drawings and specifications	SqM	390	300	0.00	117,000.00
			Rupees Three Hundreds Only			

C.W.

Item No	Item Description	Unit	Quantity	Rate in ₹	Rebate in %	Amount in ₹
				Rate in Words		
16	Plastering of external faces of brick work/concrete at all elevations in cement mortar 1:4, 20 mm thick including scaffolding, curing, forming grooves, plaster bands, border, keystone etc wherever required all as per drawings and specifications	SqM	1250	300	0.00	375,000.00
			Rupees Three Hundreds Only			
17	Plastering the Top of roof slab in Tile pattern design plaster 20mm thick with CM 1:3, 12 mm thick base coat and 8 mm thick for tile pattern design as instructed and the cost inclusive of scaffolding, curing all as per drawings and specifications	SqM	200	750	0.00	150,000.00
			Rupees Seven Hundreds Fifty Only			
18	Providing and applying Acrylic Emulsion paint of Asian paints (Premium Emulsion)/Lewis Berger (Rangoli) /ICI Dulux (Super smooth)/Matex gold of NIPPON make of approved shade in two or more coats over a coat of primer including preparation of surface with required coats of putty using Birla/ JK make, sand papering etc., to get good finish at all elevations etc all as per as per drawings and specifications	SqM	1840	160	0.00	294,400.00
			Rupees One Hundreds Sixty Only			
19	Providing and applying Exterior Emulsion Paint of Apex of Asian paints/Weather cote of Lewis Berger /Weather shield of ICI Dulux/Sumo Xtra of NIPPON make & shade in two or more coats to give an even shade over a coat of primer as per manufacturers instructions to the external plastered surfaces including preparation of surfaces, scaffolding etc. at all elevations, complete as per drawings and specifications	SqM	1250	160	0.00	200,000.00
			Rupees One Hundreds Sixty Only			
20	Providing and applying two coats of First Quality synthetic enamel paint of Asian paints/ Lewis Berger/ ICI Dulux/NIPPON/NEROLAC make of approved colour over a coat of primer on new wood / steel work, suitably prepared for receiving the paint by surface scraping, rubbing applying filler etc., including cost of filler primer, paint etc all complete as per drawings and specifications	SqM	300	160	0.00	48,000.00
			Rupees One Hundreds Sixty Only			
21	Providing, Fixing and testing PVC rain water pipes of 110 mm dia as per IS-13592 of Type A of Prince/Jain/ Kitec/Finolex/Supreme make with necessary fittings and fixtures, such as bottom shoe, PVC grating, GI clamps, screws/nails, wooden packing pieces at minimum 1 m spacing, cost inclusive of Fixing the shoes in brick masonry in CM 1:6 and plastering the same with CM 1:4 etc complete all as per drawings and specifications	RM	120	310	0.00	37,200.00
			Rupees Three Hundreds Ten Only			
22	Supplying, manufacturing and Fixing frames and architraves for windows, ventilators, cupboards etc., with approved quality Malaysian Vengai wood of required sizes fixed in masonry/concrete with three numbers of MS holdfasts of size 40mm width x 5mm thick & 300 mm long on each side of the frame or providing fisher screws of required length for column portions wherever required all as directed, for the various sizes of structural openings including making necessary rebate/stopper for Fixing shutters as per drawings and specifications	CuM	1	110000	0.00	110,000.00
			Rupees One Lakh Ten Thousand Only			

Chk.



Name of Work: Construction of Toilet Facility to Govt. Hr. Sec. School Kudankulam, Govt. Primary School Elayanainarkulam, TDTA Primary School Chidambarapuram, RC Primary School Prakasapuram, Hindu Yadava Middel School Thiruvambaluram & ST. Annes Hr. Sec. School Kudankulam at Radhapuram Taluk, Tirunelveli District.
WO / SOQR Number : 300501 **Tender No.:** NPCIL/KKNPP/AD/CSR ACTIVITIES/PT/2025/51.
Agency Name : Suruthi Constructions

Item No	Item Description	Unit	Quantity	Rate in ₹	Rebate in %	Amount in ₹
		Rate in Words				
23	Providing, fabricating and erection of Structural steel members made out of M.S. angles, flats, plates, pipes, channels, tubes, rods etc conforming to relevant IS etc., including cost of welding, welding rods, drilling holes, bolts/nuts wherever required and providing and applying two or more coats of approved quality synthetic enamel paint over a coat of zinc chromate yellow primer etc., as per drawings and specifications	MT	2	110000	0.00	220,000.00
		Rupees One Lakh Ten Thousand Only				
24	Providing and laying 20mm thick (+-2mm) polished Natural granite slab of approved colour for name board including writing by engraving, painting etc. as per required etc., with all exposed surfaces buffed, set over a base of cement mortar 1:4, 20 mm thick neatly pointed with white cement/black oxide and colouring pigments to match the shade of the stone as per the requirement, curing, rubbing, polishing, etc complete as per specifications and as per drawings and specifications	SqM	20	7500	0.00	150,000.00
		Rupees Seven Thousand Five Hundreds Only				
25	Providing and Fixing 20mm thick Exterior grade designer tiles of approved colour and design over 20mm thick base cement mortar 1:4 laid and pointed with white cement slurry mixed with pigments to match with the shade of the tile including rubbing, curing, in Staircases (both tread & riser), Walkway areas, Entrances etc., as per drawings and specifications	SqM	90	910	0.00	81,900.00
		Rupees Nine Hundreds Ten Only				
26	Providing and making RCC roof mother slab/sunken slab water proof by injection grout with the approved compound of SIKABASF/ROFF/FOSROC/ Dr.Fixit/ Bostic India make as per the manufacturers procedure/ specification by providing one water proofing membrane system by brush application as water proofing barrier for both slab and inner face of parapet/side wall including water testing by ponding for minimum 7 days and providing joint guarantee for water tightness for 10 years (This item may be got executed by specialized water proofing agents duly approved by NPCIL and 10 years joint guarantee for water proofing is required to be submitted).	SqM	280	400	0.00	112,000.00
		Rupees Four Hundreds Only				
27	Supply and laying one course of pressed cement tiles 20 mm thick of 250mmX250mm size as per IS:1237 of latest version, laid over the roof slab over a base of 20mm thick CM 1:4 and joints pointed neatly in cement mortar 1:3 mixed with water proofing admixture of approved make etc complete all as per drawings and specifications	SqM	280	600	0.00	168,000.00
		Rupees Six Hundreds Only				
28	Providing and Fixing Terracotta jally of 75mm thick of approved size and pattern including chasing the masonry/concrete if required and Fixing with CM 1:3 true to line and plumb & making good the surfaces, curing etc. at all elevations, complete all as per drawings and specifications	SqM	35	710	0.00	24,850.00
		Rupees Seven Hundreds Ten Only				
29	Providing drip moulds of CM 1:4, 25mm thick on edges of sunshades including finishing, curing, scaffolding etc complete as per the standard specifications.	SqM	110	161	0.00	17,710.00
		Rupees One Hundreds Sixty One Only				



Name of Work: Construction of Toilet Facility to Govt. Hr. Sec. School Kudankulam, Govt. Primary School Elayanainarkulam, TDTA Primary School Chidambarapuram, RC Primary School Prakasapuram, Hindu Yadava Middel School Thiruvambaluram & ST. Annes Hr. Sec. School Kudankulam at Radhapuram Taluk, Tirunelveli District.
 WO / SOQR Number : 300501 Tender No.: NPCIL/KKNPP/AD/CSR ACTIVITIES/PT/2025/51.
 Agency Name : Suruthi Constructions

Item No	Item Description	Unit	Quantity	Rate in ₹	Rebate in %	Amount in ₹
				Rate in Words		
30	Providing and Fixing in position ceramic glazed wall tiles minimum basic price of tiles shall be Rs.50/- Sq.ft without GST (thickness to be specified by the manufacturer) of premium quality conforming to IS 15622 of JOHNSON/SOMANY/REGENCY/ASIAN/NITCO/BELL/KAJARIA make laid on 20mm thick Cement Mortar 1:3 (1 cement : 3 Coarse sand) and jointing with grey cement slurry @3.3 kg/Sqm including pointing the joint with white cement mixed with colour pigment of matching shade complete at all floors, all as per specification and as directed by the Engineer in charge.	SqM	510.4	900	0.00	459,360.00
				Rupees Nine Hundreds Only		
31	Providing and Fixing in position vitrified wall tiles by using tiles adhesive of premium quality conforming to IS -15622 of JOHNSON/SOMANY/REGENCY/ASIAN/NITCO/BELL/KAJARIA make in all colour and shades in White, ivory, Gray, Fume red and Brown laid on already plastered surface including pointing the joint with spacer Epoxy joint filling and matching colour pigment etc. at all floors complete all as per directed by Engineer in - charge.	SqM	210	900	0.00	189,000.00
				Rupees Nine Hundreds Only		
32	Providing and Fixing in position Anti-Skid ceramic floor tiles of approved sizes (thickness to be specified by the manufacturer) of premium quality conforming to IS-15622 of JOHNSON/ SOMANY/ REGENCY/ASIAN/NITCO/BELL/KAJARIA make. in all colours and shades laid on 20mm thick Cement Mortar 1:4 (1 Cement : 4 Coarse Sand) including pointing the joint with white cement and matching colour pigment etc at all floors complete all as per drawings and specifications	SqM	180	900	0.00	162,000.00
				Rupees Nine Hundreds Only		
33	Providing, laying/Fixing in position approved PVC pipes Jain/ Finolux/Kitec/Supreme/Prince make IS - 4985 of latest version with required specials and Fixing arrangements for water Supply works as per standard specifications and providing and Fixing approved nails quality clamps and screws for Fixing as per drawings and specifications. (Excavation if required will be paid under relevant item)				0.00	
33.1	PVC PIPES -- 20mm dia-10kg/cm2				0.00	
33.1.1	Supply	Meter	100	19	0.00	1,900.00
				Rupees Nineteen Only		
33.1.2	Fixing	Meter	100	30	0.00	3,000.00
				Rupees Thirty Only		
33.2	PVC PIPES -- 25mm dia-10kg/cm2				0.00	

Chh.

q. w. m. t.



Name of Work: Construction of Toilet Facility to Govt. Hr. Sec. School Kudankulam, Govt. Primary School Elayanainarkulam, TDTA Primary School Chidambarapuram, RC Primary School Prakasapuram, Hindu Yadava Middel School Thiruvambaluram & ST. Annes Hr. Sec. School Kudankulam at Radhapuram Taluk, Tirunelveli District.
WO / SOQR Number : 300501 Tender No.:NPCIL/KKNPP/AD/CSR ACTIVITIES/PT/2025/51.
Agency Name : Suruthi Constructions

Item No	Item Description	Unit	Quantity	Rate in ₹	Rebate in %	Amount in ₹
34.1.2	Fixing	Meter	80	110	0.00	8,800.00
34.2	110 mm					Rupees One Hundreds Ten Only
34.2.1	Supply	Meter	200	260	0.00	52,000.00
34.2.2	Fixing					Rupees Two Hundreds Sixty Only
34.3	160 mm	Meter	200	161	0.00	32,200.00
34.3.1	Supply					Rupees One Hundreds Sixty One Only
34.3.2	Fixing					0.00
35	Providing and Fixing in position approved vitreous chinaware orissa pattern Water Closet 580 mm x 440 mm Hindware/Cera/Nycer/ Parryware/Prayag/Johnson/Somany make with S or P trap with all jointing materials including excavation, making hole in masonry, reconstructing the same, encasing the pan and trap with brick jelly concrete 1:2:4 and finishing the same etc., complete as per drawings and specifications	Meter	60	490	0.00	29,400.00
35.1	Supply					Rupees Four Hundreds Ninety Only
35.2	Fixing	Meter	60	255	0.00	15,300.00
						Rupees Two Hundreds Fifty Five Only
35.1	Supply	No.	26	1900	0.00	49,400.00
35.2	Fixing					Rupees One Thousand Nine Hundreds Only
35.2	Fixing	No.	26	1250	0.00	32,500.00
						Rupees One Thousand Two Hundreds Fifty Only



Name of Work: Construction of Toilet Facility to Govt. Hr. Sec. School Kudankulam, Govt. Primary School Elayanainarkulam, TDTA Primary School Chidambarapuram, RC Primary School Prakasapuram, Hindu Yadava Middel School Thiruvambalapuram & ST.annes Hr. Sec. School Kudankulam at Radhapuram Taluk, Tirunelveli District.
WO / SOQR Number : 300501 Tender No.:NPCIL/KNPPI/AD/CSR ACTIVITIES/PT/2025/51. Agency Name : Suruthi Constructions

Item No	Item Description	Unit	Quantity	Rate in ₹	Rebate in %	Amount in ₹
				Rate in Words		
36	Providing and Fixing PVC flushing cistern of 10 liters capacity Hindware/Cera/ Nycer/ Parryware/ Prayag/Johnson/Somany make with all syphonic fittings, including assembling the cistern components and flush pipe, testing etc., Complete all as per drawings and specifications			0.00		
36.1	Supply	No.	26	1050	0.00	27,300.00
				Rupees One Thousand Fifty Only		
36.2	Fixing	No.	26	315	0.00	8,190.00
				Rupees Three Hundreds Fifteen Only		
37	Providing and Fixing in position approved European type water closet of Hindware/Cera/ Nycer/Parryware/Prayag/Johnson/Somany make comprising of a) Wash down EWC in white glazed vitreous chinaware with integral P of S trap with or without vent and jointing the trap with soil pipe in CM 1:1 b) Hindware/Cera/ Nycer/Parryware make PVC 10 liters capacity low level flushing cistern with all syphonic fittings. c)Supply and Fixing of 15 mm, 1 m length Health faucet of JAQUAR/CRABTREE/KOHLER make and with all necessary accessories etc., d) White solid plastic seat cover with CP pillar hinges and rubber buffers etc complete as per drawings and specifications			0.00		
37.1	Supply	No.	16	3000	0.00	48,000.00
				Rupees Three Thousand Only		
37.2	Fixing	No.	16	1250	0.00	20,000.00
				Rupees One Thousand Two Hundreds Fifty Only		
38	Providing and Fixing Prayag or equivalent make PTMT Symet grating for Gully traps	No.	16	164	0.00	2,624.00
				Rupees One Hundreds Sixty Four Only		
39	Providing and Fixing Gun metal full way gate valve female ends screwed bonnet integral seat, non rising spindle, class I, marked to IS : 778 tested to 20 kg/Sq.cm. Hydraulic pressure. LEADER/ZOLATO make as per drawings and specifications			0.00		
39.1	32mm dia			0.00		

Chaitanya

g.v.murthy

Adhik-

5. wavy

John-

Item No	Item Description	Unit	Quantity	Rate in ₹	Rebate in %	Amount in ₹
		Rate in Words				
43	Providing and Fixing best quality PVC 150 x 150 mm size square mouth Gully trap and 100 mm P type outlet, Supreme/Prince/Star/Finolex make as per relevant IS and constructing brick masonry chamber 300 mm x 300 mm internal size in 110 mm thick fly ash brick masonry in CM 1:5 using fly ash bricks as per IS:12894, class designation : 5 from the approved manufacturer by NPCIL, with necessary excavation with bed of 100 mm thick cement concrete 1:4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate of nominal size) for foundation and around the trap and plastering with CM 1:3 (1 cement : 3 fine sand) 15 mm thick on internal and external surfaces on top and up to 150 mm below ground level, finished smooth, curing providing and Fixing double seal CI cover and frame of weight not less than 7.0 kgs (as per relevant IS), at top etc complete as per drawings and specifications. (Earth work excavation will be paid under relevant item.)	No.	24	2500	0.00	60,000.00
		Rupees Two Thousand Five Hundreds Only				
44	Construction of inspection chambers of internal clear dimension 450 x450 up to a maximum depth of 600mm in 230 mm thick fly ash brick masonry in CM 1:6 using fly ash bricks as per IS:12894, class designation : 5 from the approved manufacturer by NPCIL, over a bed of 150mm thick 1:4:8 cement concrete foundation, plastering with CM 1:4, 20mm thick on inside, outside and all exposed surface finished with floating coat of neat cement, PCC 1: 2:4 for benching and channel finished with neat cement, Top covered with 100mm thick RCC 1:2:4 grade slab with required steel reinforcements, including providing & Fixing double seal C.I. manhole cover & frame of 450x 450mm weight not less than 38 kg (as per relevant IS), embedding the C.I. frame in RCC cover slab etc complete as per drawings and specifications. (Earth work excavation and steel reinforcement will be paid under relevant item)	No.	7	6000	0.00	42,000.00
		Rupees Six Thousand Only				
45	Providing and Fixing single/multi PVC Nahani trap of self cleaning design with 75 mm dia outlet, Supreme/Prince/Star/Finolex/Jain/Kitec make as per relevant IS, Stainless steel Grating and including necessary cement concrete 1:2:4 for embedding and making good the floor, connecting the trap to the waste pipe, forming circular hole up to floor level and rendering smooth etc. Complete as per drawings and specifications	No.	42	110	0.00	4,620.00
		Rupees One Hundreds Ten Only				
46	Providing and Fixing heavy quality 15 mm dia, CP brass screw down short bodied bib tap with CP brass flanges as per relevant IS, ADSON/CERA/PARRYWARE make as per drawings and specifications				0.00	
46.1	Supply	No.	44	650	0.00	28,600.00
		Rupees Six Hundreds Fifty Only				
46.2	Fixing	No.	44	10	0.00	440.00
		Rupees Ten Only				
47	Providing and Fixing 15 mm size heavy quality CP brass pillar cock easy clean type as per relevant IS for wash basin with capstan head ADSON/CERA/ PARRYWARE make as per drawings and specifications				0.00	

5. Wavy

Item No	Item Description	Unit	Quantity	Rate in ₹	Rebate in %	Amount in ₹
		Rate in Words				
47.1	Supply	No.	6	650	0.00	3,900.00
			Rupees Six Hundreds Fifty Only			
47.2	Fixing	No.	6	10	0.00	60.00
			Rupees Ten Only			
48	Providing and Fixing heavy quality 15mm dia CP brass angle cock as per relevant IS. ADSON/CERA/PARRYWARE make as per drawings and specifications				0.00	
48.1	Supply	No.	61	650	0.00	39,650.00
			Rupees Six Hundreds Fifty Only			
48.2	Fixing	No.	61	10	0.00	610.00
			Rupees Ten Only			
49	Providing and fixing PTMT Prayag or approved equivalent make push cock as directed by Engineer in charge.	No.	28	110	0.00	3,080.00
			Rupees One Hundreds Ten Only			
50	Supplying plastic bucket 5Ltr capacity a mug of 1Ltr capacity as approved by the Engineer in charge	No.	42	100	0.00	4,200.00
			Rupees One Hundreds Only			
51	Providing and placing on terrace (at all floor levels) polyethene water Storage Tanks capacity as required of SINTEX JOLISTRAN or other approved equivalent make with cover and suitable locking arrangements and making holes for inlet, outlet, scour and overflow pipes as per drawings and specifications	Litres	7000	7	0.00	49,000.00
			Rupees Seven Only			
52	Providing and Fixing C.P. brass three pronged robe hooks of Parry ware /Cera/Adson make with C.P. brass flange as per drawings and specifications				0.00	
52.1	Supply	No.	40	110	0.00	4,400.00
			Rupees One Hundreds Ten Only			

Chet

Chad

Item No	Item Description	Unit	Quantity	Rate in ₹	Rebate in %	Amount in ₹
				Rate in Words		
52.2	Fixing	No.	40	70	0.00	2,800.00
				Rupees Seventy Only		
53	Providing and Fixing heavy quality 15 mm dia, CP brass screw down long bodied bib tap with CP brass flanges as per relevant IS, ADSON/CERA/ PARRYWARE make as per drawings and specifications				0.00	
53.1	Supply	No.	40	850	0.00	34,000.00
				Rupees Eight Hundreds Fifty Only		
53.2	Fixing	No.	40	10	0.00	400.00
				Rupees Ten Only		
54	Providing and Fixing in position best vitreous 450x300mm size China wash hand basin of Hindware/Cera/Nycer/Parryware/Prayag/Johnson/Somany make Fixing with rug bolts as directed				0.00	
54.1	Supply	No.	5	1200	0.00	6,000.00
				Rupees One Thousand Two Hundreds Only		
54.2	Fixing	No.	5	60	0.00	300.00
				Rupees Sixty Only		
55	Supply and Fixing in position approved quality Stainless Steel of Grade-304 for handrails/other areas as directed using SS pipes/tubes/balls etc including chasing the walls/floor for Fixing in position and filling the area by cement concrete 1:2:4, finishing with cement plaster in CM 1:4 etc complete as per drawings and specifications	Kg	100	420	0.00	42,000.00
				Rupees Four Hundreds Twenty Only		
56	Providing the bore well 6 inch dia				0.00	
56.1	Boring/drilling borehole of 6 inch dia, by suitable method including hire & running charges of all equipments, tools, plants , machineries and manpower required for the job, all complete as per direction of Engineer -in-charge, upto 90 meter depth below ground level.	Meter	540	210	0.00	113,400.00
				Rupees Two Hundreds Ten Only		
56.2	Boring/drilling borehole of 6 inch dia, by suitable method including hire & running charges of all equipments, tools, plants , machineries and manpower required for the job, all complete as per direction of Engineer -in-charge, from 91 meter to 120 meter depth below ground level.	Meter	180	230	0.00	41,400.00
				Rupees Two Hundreds Thirty Only		



Name of Work: Construction of Toilet Facility to Govt. Hr. Sec. School Kudankulam, Govt. Primary School Elayanarkulam, TDTA Primary School Chidambaram, RC Primary School Prakasapuram, Hindu Yadava Middle School Thiruvambaluram & ST. Annes Hr. Sec. School Kudankulam at Radhapuram Taluk, Tirunelveli District.
WO / SOQR Number : 300501 **Tender No.:** NPCIL/KKNPP/AD/CSR ACTIVITIES/PT/2025/51.
Agency Name : Suruthi Constructions

Item No	Item Description	Unit	Quantity	Rate in ₹	Rebate in %	Amount in ₹
		Rate in Words				
56.3	Boring/drilling borehole of 6 inch dia, by suitable method including hire & running charges of all equipments, tools, plants , machineries and manpower required for the job, all complete as per direction of Engineer -in-charge, from 121 meter to 150 meter depth below ground level.	Meter	180	270	0.00	48,600.00
			Rupees Two Hundreds Seventy Only			
56.4	Boring/drilling borehole of 6 inch dia, by suitable method including hire & running charges of all equipments, tools, plants , machineries and manpower required for the job, all complete as per direction of Engineer -in-charge, from 151 meter to 180 meter depth below ground level.	Meter	450	290	0.00	130,500.00
			Rupees Two Hundreds Ninety Only			
57	Supplying, assembling, lowering and fixing in vertical position in borehole 7 inch dia PVC casing pipe of including hire & labour charges, fittings & accessories etc. all complete, for all depths, as per direction of Engineer-in-charge.	Meter	150	1200	0.00	180,000.00
			Rupees One Thousand Two Hundreds Only			
58	supplying Bore well materials like 1.5 HP Texmo make submersible pump 32mm dia out let pipe , panel board, 2.5mm cable,nylon rope 16mm dia, GI adopter, GI bend, GI clamp, GI elbo, end caps, insulation tape, mrf tape etc for the successful commissioning of pump in the bore well etc complete.	NO.	6	51000	0.00	306,000.00
			Rupees Fifty One Thousand Only			
58.1	Labour charges for fixing upto 90M	Meter	540	40	0.00	21,600.00
			Rupees Forty Only			
58.2	Labour charges for fixing 90M to 150M(in addition to 49.6.1 above)	Meter	360	20	0.00	7,200.00
			Rupees Twenty Only			
58.3	Labour charges 150m to 305 m	Meter	420	25	0.00	10,500.00
			Rupees Twenty Five Only			
58.4	Supplying UPvc bore well out let threaded pipe of 32mm dia CR/FINOLEX/PRINCE or as per revelant IS make for bore wells.	Meter	1320	185	0.00	244,200.00
			Rupees One Hundreds Eighty Five Only			
Schedule : CSR Activities:B/ELECT						
1	LDB : Supply and erection of 8 way single phase distribution board Single door complete with interconnection Copper busbar, Neutral bar, Earth bar, top and bottom removable gland plates with knockout, and double door with the following 25A 2P RCCB (30 mA) - 1 no, 20A/16A/6A SP MCB - 6 Nos(Make:Legrand/havells) Scope includes construction of pedestal cubicle and supply of necessary electrical components, hardware for fixing the panel etc. to complete the work in all respect.	SET	7	5500	0.00	38,500.00
			Rupees Five Thousand Five Hundreds Only			

Handwritten signature

Handwritten signature



Name of Work: Construction of Toilet Facility to Govt. Hr. Sec. School Kudankulam, Govt. Primary School Elayanainarkulam, TDTA Primary School Chidambarapuram, RC Primary School Prakasapuram, Hindu Yadava Middle School Thiruvambalapuram & ST. Annes Hr. Sec. School Kudankulam at Radhapuram Taluk, Tirunelveli District.
 WO / SOQR Number : 300501 Tender No.:NPCIL/KNPP/AD/CSR ACTIVITIES/PT/2025/51.
 Agency Name : Suruthi Constructions

Item No	Item Description	Unit	Quantity	Rate in ₹	Rebate in %	Amount in ₹
		Rate in Words				
2	PRIMARY WIRING:- For lighting, ceiling fan, bulkhead fitting and exhaust fan points, supply and wiring for point with two + one (earth-green) runs of 1.5sq.mm (22/0.3)1100V grade FRLS insulated single core multi strand Copper conductor wire(without joint) drawn into the existing PVC conduit (inclusive of supplying and laying of PVC conduits while concreting), complete with angle / batten lamp holder or ceiling rose, 5 Amps modular type Legrand Mylinc/ MK India /Schneider make switch including pulling the wire from existing switch box to lighting point through the conduit and connecting at both ends.(The box, grid plate and the cover plate for the switch has been covered elsewhere.). All items such as 1.5sq.mm (22/0.3)Copper FRLS insulated wire(make:polycab/finolex,Havells), 6 Amps switch, 3 Plate ceiling rose, hylam sheet for JB's, necessary electrical components for wiring works (wherever applicable) shall be supplied by the contractor as per the requirement, specification (Approximate length 13Mtr)	Point	100	1600	0.00	160,000.00
		Rupees One Thousand Six Hundreds Only				
3	SECONDARY WIRING :- For lighting, 6A sockets supply and wiring for point with two + one (earth-green) runs of 1.5sq.mm (22/0.3)1100V grade FRLS insulated single core multi strand Copper conductor wire (without joint) drawn into the existing PVC conduit (inclusive of supplying and laying of PVC conduits while concreting), complete with angle / batten lamp holder or ceiling rose, 5 Amps modular type Legrand Mylinc/ MK India /Schneider make switch including pulling the wire from existing switch box to lighting point through the conduit and connecting at both ends.(The box, grid plate and the cover plate for the switch has been covered elsewhere.). All items such as 1.5sq.mm (22/0.3) Copper FRLS insulated wire(Make:Polycab/finolex/Havells), 6 Amps switch, 3 Plate ceiling rose, hylam sheet for JB's, necessary electrical components for wiring works (wherever applicable) shall be supplied by the contractor as per the site requirement.	Point	42	1150	0.00	48,300.00
		Rupees One Thousand One Hundreds Fifty Only				
4	Power point wiring : 16A Power switch & sockets (2 switches+2 sockets in switch board) in separate switchboard: Supply, installation of 16A, 5 pin socket & switch outlet including supply of 16A 5 pin socket and SP switch modular type. Legrand Mylinc/ MK India /Schneider/Anchor panasonic/GM make (switch & socket separate type). One end of the earthing wire to be connected at the third pin of 16A socket and the another end to be connected at the earth bar in the Distribution Board. Scope includes supply of modular socket and switch, 4 module GI box with base ,cover plate and accessories with point wiring of 3 runs of 4 sq.mm copper wire for 16A-6A , 6 in 1 socket .	Point	3	2000	0.00	6,000.00
		Rupees Two Thousand Only				
5	DB to Switch Board wiring : Supply, installation and wiring(Make:Polycab/finolex,Havells) of 3R x 4sqmm Cu for FRLS insulated each core multi strand with 1100V Copper wire, drawn into the existing PVC conduit (inclusive of supplying and laying of PVC conduits while concreting) from MCB DB to various switch boards as circuit mains and switch board to switch board looping. The termination shall be done by using crimping type Copper lugs of Dowells make, suitable modular type switch box supply by contractor scope.	RM	350	500	0.00	175,000.00
		Rupees Five Hundreds Only				

Handwritten signature

Handwritten signature



Name of Work: Construction of Toilet Facility to Govt. Hr. Sec. School Kudankulam, Govt. Primary School Elayanainarkulam, TDTA Primary School Chidambarapuram, RC Primary School Prakasapuram, Hindu Yadava Middel School Thiruvambaluram & ST. Annes Hr. Sec. School Kudankulam at Radhapuram Taluk, Tirunelveli District.
 WO / SOQR Number : 300501 Tender No.:NPCIL/KKNPP/AD/CSR ACTIVITIES/PT/2025/51.
 Agency Name : Suruthi Constructions


Item No	Item Description	Unit	Quantity	Rate in ₹	Rebate in %	Amount in ₹
		Rate in Words				
6	EARTH PIT :Supply and installation of Earthing with copper earth plate 600 mm X 600 mm X 3 mm thick, including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 metre long etc. with charcoal/ coke and salt as required.	NOS	7	8000	0.00	56,000.00
				Rupees Eight Thousand Only		
7	EARTHING : Supplying, laying & Termination with suitable legs, connector, clamp 25 mm X 5 mm copper strip at 0.50 metre below ground as strip earth electrode, including connection/ terminating with nut, bolt, spring, washer etc. as required. (Jointing shall be done by overlapping and with 2 sets of brass nut bolt & spring washer spaced at 50mm)	RM	70	600	0.00	42,000.00
				Rupees Six Hundreds Only		
8	Tube light LED: Supply and installation of LED tube light fitting 230V,20W(Make:Havells/Crompton/Philips/GM)	NOS	40	300	0.00	12,000.00
				Rupees Three Hundreds Only		
9	Area light LED: Supply and installation of LED light fitting 230V, 60W. Light fitting around the building(Make:Havells/Crompton/Philips)	NOS	11	2500	0.00	27,500.00
				Rupees Two Thousand Five Hundreds Only		
10	Bulk head LED: Supply and installation of 9W LED bulk head light fitting (Make:Havells/Crompton/Philips)	NOS	90	879	0.00	79,110.00
				Rupees Eight Hundreds Seventy Nine Only		
11	6 MODULE:Supply & installation of concealed in wall mounting 6 Modular switch board with covered plate comprising. (Switches are covered in the Point wiring) (Make: Legrand Mylinc/ MK India /Schneider) all as directed by Engineer.	NOS	8	500	0.00	4,000.00
				Rupees Five Hundreds Only		
12	8 MODULE :Supply & installation of concealed in wall mounting 8 Modular switch board with covered plate comprising. (Switches are covered in the Point wiring) (Make: Legrand Mylinc/ MK India /Schneider) all as directed by Engineer.	NOS	10	700	0.00	7,000.00
				Rupees Seven Hundreds Only		
13	Providing of power cable 1100 V, 4C x 6 sq.mm FRLS insulated multistranded compacted circular Armoured copper flexible cable, cores laid up, extruded PVC inner sheath, galvanised steel flat strip armoured and overall extruded PVC sheathed cable conforming to IS 7098(part1)/1988. ((Make:KEI/Havells/Glosters)	RM	425	280	0.00	119,000.00
				Rupees Two Hundreds Eighty Only		
14	Laying of one number PVC Insulated and PVC Sheathed /XLPE Armoured power cable of 1.1 KV grade of following size direct in ground including excavation, sand cushioning, protective covering and refilling the trench etc as required	RM	425	290	0.00	123,250.00
				Rupees Two Hundreds Ninety Only		
15	Supply and installation of Sanitary Napkin Disposal Machine. Capacity 750 persons, 2000W, fully automatic. Scope includes fabrication, painting and erection of suitable stand for holding the above machine. (Approximate dimension of machine L x B x H = 350 x 370 x 630)	NOS	3	43000	0.00	129,000.00
				Rupees Forty Three Thousand Only		

Handwritten signature

Handwritten signature

Note:: All Item Rates are considered to be in Indian Rupees unless otherwise explicitly specified and in which case shall be always converted appropriately to arrive at the amount in Indian Rupees.

Work Order Total	₹12566168.4
Overall Rebate (%)	0
Work Order Value After Overall Rebate (in Figure)	₹12566168
Final Work Order Value (in Figure)	₹12566168
Final Work Order Value (in words)	Rupees One Crore Twenty Five Lakh Sixty Six Thousand One Hundreds Sixty Eight Only



Cc: **Distribution:** (Through E-mail)

- | | | |
|-----|--------------------------|--|
| 1. | Site Director | - For kind information |
| 2. | Project Director KK(3-6) | - -do- |
| 3. | CE (E&US) /Chairman, CSR | - With Schedule of Quantities & Rates |
| 4. | Head(C&MM) | With Schedule of Quantities & Rates |
| 5. | Head(C&MM-Works Group) | With Schedule of Quantities & Rates |
| 6. | AGM(F&A) | - With Schedule of Quantities & Rates, Approval for
Award of work, copy of vetted work order, Rate
Clarification Letter, CST, Admin approval &
Technical Sanction |
| 7. | Engineer-in-charge | - With Schedule of Quantities & Rates, Approval for
Award of work, CST & Rate Clarification Letter |
| 8. | Head (HR) | - |
| 9. | Head (IS&F -1&2) | - with Schedule-A |
| 10. | Smt.Sheeba, SO/E(IT) | |
| 11. | Commandant, CISF | |
| 12. | Tender File | |
| 13. | Work order File | |