



न्यूक्लियर पावर कॉर्पोरेशन ऑफ इंडिया लिमिटेड  
NUCLEAR POWER CORPORATION OF INDIA LIMITED  
(भारत सरकार का उद्यम)  
(A Govt. of India Enterprise)  
नरौरा परमाणु विद्युत केंद्र  
Narora Atomic Power Station  
पॉस्ट: एन.ए.पी.एस टाउनशिप, नरौरा जिला बुलंदशहर, (उ.प्र.)-  
203389

PO: NAPS Township, Narora, Distt. Bulandshahr, (UP) – 203389  
दूरभाष Phone: 05734-222167 इंटरकॉम Intercom: 4504  
ई-मेल E-Mail : [anantsingh@npcil.co.in](mailto:anantsingh@npcil.co.in)



पंजीकृत कार्यालय Registered Office  
16वां तल 16<sup>th</sup> Floor,  
विश्व व्यापार केंद्र World Trade Centre  
कफे परेड Cuffe Parade,  
कोलाबा Colaba  
मुम्बई Mumbai – 400 005  
सी.आई.एन.  
सं.: U40104MH1987GOI149458  
CIN No.: U40104MH1987GOI149458  
वेबसाइट Website: [www.npcil.nic.in](http://www.npcil.nic.in)

संदर्भ: एनएपीएस/सीटीसी/सीएसआर/सीपीपीपी/पीटी/1146/ डब्ल्यूओएस/8132 दिनांक Date:

Ref: NAPS/CTC/CSR/CPPP/PT/1146/WOS/8132

To,  
M/S Technical Construction Co.  
9/206, Uday Singh Jain Road  
Aligarh, Uttar Pradesh  
PIN -202001  
GSTIN: 09AAFFT5842C1Z6

|                                     |       |
|-------------------------------------|-------|
| एमएसएमई<br>MSME                     | Yes   |
| कार्यदेश संख्या<br>Work Order No.   | 8132  |
| उपखाता कोड<br>Subledger Code        | T1058 |
| लेखा कोड<br>Account Code            | 78205 |
| लागत केंद्र कोड<br>Cost Centre Code | 644   |

### कार्यदेश WORK ORDER

|                                              |   |                                                                                                                                                                                                                                                                                                                                                                                   |
|----------------------------------------------|---|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Name of work                                 | : | Construction of misc. infrastructure in Raghunath Barahsaini Inter Collage- Rajghat, Shri Devātrya Aadarsh Inter Collage- Karanwas, Bhagirathi Vedang Inter Collage- Ramghat, DB Janta Junior High School- Rampur, Composite UPS-Badarpur, Uchcha Prathmic Vidyalaya- Nodai Bangar, Primary School-Rehmapur, Krishna and Shreeram Memorial Vedic Inter College-Atrauli under CSR. |
| संदर्भ Reference                             | : |                                                                                                                                                                                                                                                                                                                                                                                   |
| 1. निविदा संख्या<br>Tender No.               | : | एनएपीएस/सीटीसी/ सीएसआर /2025/सीपीपीपी/पीटी/1146<br>NAPS/CTC/CSR/2025/CPPP/PT/1146                                                                                                                                                                                                                                                                                                 |
| 2. सीपीपीपी<br>निविदा आईडी<br>CPPP Tender ID | : | 2025_ एनपीसीआईएन_234979_1 दिनांक 26/05/2025<br>2025_NPCIL_234979_1 date 26/05/2025                                                                                                                                                                                                                                                                                                |

प्रिय महोदय / Dear Sir,

कृपया उपर्युक्त कार्य के लिए एनआईटी संख्या एनएपीएस/सीटीसी/ सीएसआर /2025/सीपीपीपी/पीटी/1146 के पक्ष में अपने ऊपर उद्धृत निविदा का संदर्भ लें जिसका भाग-I 18/06/2025 को खोला गया था और भाग-II 12/08/2025 को खोला गया था।

*Shant*



Please refer to your above cited tender in response to NIT No. NAPS/CTC/CSR/2025/CPPP/PT/1146 for the above work part-I of which was opened on 18/06/2025 and part-II on 12/08/2025

- 1) आपको सूचित किया जाता है कि आपके द्वारा प्रस्तुत निविदा को एनपीसीआईएल के लिए एवं की ओर से, निविदा में समाविष्ट दर और मात्रा अनुसूची में दर्शाये गए कार्य की मदों के लिए वस्तु एवं सेवाकर सहित निविदा लागत **रु० 2,86,06,115/- (रुपये दो करोड़ छियासी लाख छ हजार एक सौ पंद्रह मात्र)** के लिए स्वीकार कर लिया गया है। वर्तमान वस्तु एवं सेवाकर 18% लागू है।

This is to inform you that the tender submitted by you has been accepted for and on behalf of NPCIL, for the items of work shown in the schedule of quantities and rates covered by the tender for a contract value of **Rs. 2,86,06,115/- (Rupees Two Crore Eighty Six Lakh Six Thousand One Hundred Fifteen Only)** including Goods and Services tax. The present rate of GST 18% applicable.

- 2) संलग्न मात्रा और दर अनुसूची में मद संख्या 12 असामान्य रूप से उच्च दर (AHR) की हैं। और मद संख्या 2, 3, 5, 7, 9, 11, 13, 14, 15, 16, 17, 18, 20, 21, 22, 23 & 25 असामान्य रूप से निम्न दर की हैं।

Item No. 12 is Abnormally High Rated (AHR) items and Item No. 2, 3, 5, 7, 9, 11, 13, 14, 15, 16, 17, 18, 20, 21, 22, 23 & 25 are Abnormally Low Rated (ALR) items in the attached schedule of quantities and rates.

- 3) निविदा में निर्दिष्ट शर्तों, निबंधनों, विनिर्देशों और ड्राइंगों के अनुसार कार्य सख्ती से और श्रेष्ठतम कौशल के साथ किया जाएगा। आप हर समय कार्य पर योग्य कर्मचारियों को नियुक्त करेंगे हर समय बनाए रखेंगे। आप कार्य स्थल पर ऐसी मशीनरी, उपकरणों और अन्य सामग्री भी लाएंगे एवं कार्य में प्रयोग करेंगे, जोकि इस कार्य को संतोषजनक ढंग से पूरा करने के लिए आवश्यक हैं।

The work shall be carried out strictly in accordance with the terms, conditions, specifications and drawings stipulated in the tender and also in best workmanlike manner. You shall employ and maintain qualified staff in the job at all times. You shall also bring to the site and employ such machinery and equipments and other materials as are necessary for the satisfactory completion of this work.

- 4) प्रारंभ तिथि से **दो सौ चालीस (240) दिन** के भीतर हर प्रकार से कार्य पूरा किया जाएगा। प्रारंभ होने की तारीख की गणना 01/10/2025 से की जाएगी। समय अनुबंध का सार होगी और कार्य अनुमोदित कार्यक्रम के अनुसार पूरा किया जाएगा।

The work shall be completed in all respects within **Two Hundred Forty (240) Days** from the date of commencement. The date of commencement will be reckoned from 01/10/2025. The time shall be essence of the contract and the work shall be completed as per approved program of work.

- 5) भुगतान में वृद्धि जैसा कि निविदा में इंगित किया गया है, भी देय होगी (यदि लागू हो)।

Escalation of payment as indicated in the Contract shall also be payable (if applicable).

*Ant.*



- 6) आपसे अनुरोध है कि इस संविदा के सभी मामलों के पर्यवेक्षण हेतु अपने अधिकृत प्रतिनिधि का नाम सूचित करें और उचित मूल्य के स्टाम्प पेपर पर विधिवत निष्पादित मुख्तारनामा उनके पक्ष में प्रस्तुत करेंगे।

You are requested to inform the name of the authorized representative who will deal with all matters relating to the contract and the Power of Attorney in his favour duly executed on stamped paper of an appropriate value shall be furnished.

- 7) संविदा निष्पादन के दौरान और आपको कार्य समाप्ति प्रमाण पत्र जारी होने तक, आपकी वजह से तृतीय पक्ष को हुई हानि या क्षति सहित किसी भी कार्य, संरचना, संपत्ति आदि की हानि, क्षति या विनाश के लिए सभी संबंधितों को क्षतिपूर्ति करने के लिए आप पूरी तरह से उत्तरदायी होंगे और इसका निर्णय प्रभारी अभियंता द्वारा किया जाएगा और इस संदर्भ में उनका निर्णय अंतिम होगा।

During the execution of the contract and until completion certificate is issued you will be fully liable to compensate all concerned for any loss, damage or destruction of work, structure, property etc. including third party risk arising due to causes attributable to you which will be decided by the Engineer-in-Charge whose decision in this regard will be final.

- 8) अनुबंध की शर्तों के अनुसार आपको सभी लागू बीमा (एससीसी के 3.7.7 के अनुसार ईएसआई सहित) पॉलिसियाँ लेनी होंगी, एवं इससे संबंधित दस्तावेजों को कार्य शुरू होने से पहले प्रभारी-अभियंता को जमा किया जाना चाहिए।

You are required to take all applicable insurance (including ESI as per 3.7.7 of SCC) policies as per the conditions of the contract and documents in this required should be submitted to engineer-in-charge before start of work.

- 9) इस कार्य हेतु कार्य संविदा पर केंद्र अथवा राज्य सरकार द्वारा समय-समय पर यथा अधिसूचित आयकर और अन्य सांविधिक कर, यदि कोई हो, तो उसकी वसूली निर्धारित तरीके से आपके अंतरिम बिलों के अलावा अंतिम बिल से भी की जाएगी। आपसे अनुरोध है कि आप अपना स्थायी खाता संख्या (पैन नंबर) प्रभारी अभियंता सूचित करें।

Income Tax and statutory Levy, if any, on works contract as notified by Central/ State Govt. from time to time shall be recovered from your running bills as well as final bills for this work in the prescribed manner. You are requested to intimate your permanent Account number to Engineer-in-Charge.

- 10) श्री शशांक अग्रवाल , वै. अधि./ई (सिविल),, इस कार्य के प्रभारी अभियंता होंगे। आप प्रभारी अभियंता के साथ परामर्श करके तत्काल कार्य शुरू करने के लिए आवश्यक व्यवस्था करें।

**Shri Shashank Agrawal, SO/E, (Civil)** will be the Engineer-in-Charge of this work. You may make necessary arrangements for commencing the work immediately in consultation with Engineer-in-charge.

- 11) कृपया आप ध्यान दें कि प्रतिभूति जमाराशि **रु० Rs. 28,60,612/-** (संविदा मूल्य के 10% की दर से) होगी। प्रारंभ में आपको **रु० 14,30,306/-** (प्रतिभूति जमाराशि का 50%) निष्पादन गारंटी के रूप में जमा करने होंगे। प्रतिभूति जमाराशि **रु०-**

*Shant*



14,30,306/- की शेष धनराशि प्रत्येक बिल राशि के 6% की दर से अंतरिम बिलों या अंतिम बिल से वसूल की जाएगी। प्रतिभूति जमाराशि पर कोई ब्याज देय नहीं होगा।

You may please note that Security Deposit will be **Rs. 28,60,612/- (@10% of contract value)**. Initially you will have to submit a performance guarantee for **Rs. 14,30,306/- (50% of Security Deposit)**. The remaining amount of Security Deposit of **Rs. 14,30,306/-** will be recovered from the RA bill/ Final bill at the rate of 6% of each bill amount. Security Deposit amount will not bear any interest.

- 12) आपको ठेका श्रमिक (विनियमन एवं उन्मूलन) अधिनियम-1970 के विभिन्न उपबंधों और उसके बाद समय - समय पर बनाए गए नियमों का अनुपालन करना होगा। यदि ठेका श्रमिक अधिनियम आपके प्रतिष्ठान पर लागू नहीं होता है, तो आप कार्य शुरू करने से पहले इस कार्य के प्रभारी अभियंता को तदनुसार सूचित करेंगे। इसके अलावा, आपके प्रतिष्ठान पर लागू अन्य कानूनों जैसे- कामगार क्षतिपूर्ति अधिनियम-1923, न्यूनतम मजदूरी अधिनियम-1948, कर्मचारी भविष्य निधि अधिनियम, उपदान अधिनियम और अन्य श्रम कानूनों का आप अनुपालन करेंगे। यदि एनपीसीआईएल को प्रधान नियोक्ता तौर पर विभिन्न कानूनी उपबंधों के अधीन कोई व्यय करना पड़ता है, तो एनपीसीआईएल उसे आपसे अथवा आपके बिलों से वसूल करने का हकदार होगा।

You shall comply with various provisions of the contract labour (Regulations & Abolition) Act 1970 and rules framed thereafter from time to time. In case, the Contract labour Act does not apply to your organisation you should intimate the Engineer-in-charge of this work accordingly before commencing the work. Further you shall also comply with the provisions of other laws such as Workmen's Compensation Act 1923, Minimum wages Act 1948, E.P.F. Act, Gratuity Act and other labour laws as applicable to your organisation. In case, NPCIL is required to incur any expenses as principal employer under the provisions of the various laws, NPCIL shall be entitled to recover the same from you/your bills.

- 13) आपके द्वारा इस कार्य पर लगाए जाने वाले प्रस्तावित कामगारों की अधिकतम संख्या के आधार पर श्रम लाइसेंस, **यदि लागू हो**, प्राप्त करने के लिए प्रधान नियोक्ता का प्रमाणपत्र आपकी मांग पर जारी किया जाएगा। कृपया ध्यान दें कि इस कार्यदिश के जारी होने की तारीख से 14 दिनों के भीतर, आपको इस कार्य पर लगाए जाने वाले अधिकतम कामगारों हेतु श्रम लाइसेंस के लिए क्षेत्र के सहायक श्रम आयुक्त (केंद्रीय) के कार्यालय में आवेदन करना होगा। आवेदन की एक प्रति कार्य शुरू होने के एक सप्ताह के भीतर कार्य के प्रभारी अभियंता के समक्ष प्रस्तुत करनी होगी।

Principal Employer's certificate for obtaining labour license, **if applicable** based on the maximum number of workmen you propose to employ for this work will be issued upon requisition. You may please note that within 14 days from the date of issue of this work order, you will have to apply for a labour license to the Asstt. Labour Commissioner (Central), of the area, for the maximum number of workers you have to engage on the work. A copy of the application will have to be furnished to the Engineer-in-charge of the work within a week time from start of work.

- 14) प्रथम अंतरिम बिल का भुगतान केवल श्रम लाइसेंस / श्रम लाइसेंस रसीद (**यदि लागू हो**) प्रस्तुत करने पर ही किया जाएगा।

The first running account bill will be paid only on production of labour license/ labour license receipt, **if applicable**.

*Shant*



- 15) आपसे अनुरोध है कि समझौते पर हस्ताक्षर करने के लिए आप कार्यालय में उपस्थित हों। औपचारिक अनुबंध होने तक प्रसंगाधीन पत्रों सहित मूल निविदा और यह कार्यादेश हमारे बीच बाध्यकारी संविदा होगा।

You are requested to attend the office for signing the agreement. Till a formal agreement is executed the original tender together with letters under reference and this work order shall form the binding contract between us.

कृपया इस कार्यादेश की प्राप्ति और स्वीकृति यथाशीघ्र दें।

Kindly acknowledge receipt of this Work Order & acceptance at the earliest.


धन्यवाद Thanking you,

**टिप्पणी:** किसी भी विवाद या निर्वचन की स्थिति में अंग्रेजी पाठ ही मान्य होगा।

**Remark:** In case of any inconsistency or discrepancy the English version shall prevail.

भवदीय

Yours faithfully

  
(अनंत कुमार सिंह Anant Kumar Singh)  
अनुरक्षण अधीक्षक, एनएपीएस  
Maintenance Superintendent, NAPS  
एनपीसीआईएल के लिए एवं की ओर से  
For and on behalf of N.P.C.I.L

- संलग्नक i) सामग्री आपूर्ति अनुसूची  
Encl. (निविदा दस्तावेज के खंड-4 की अनुसूची-बी एवं सी तथा खंड-7)  
Schedule of supply of material  
(Section -VII and Schedule B & C of Section IV of tender document )
- ii) मात्रा एवं दर अनुसूची  
Schedule of Quantities & Rates

|                  |       |                                                                              |                                                                                                                                    |
|------------------|-------|------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------|
| प्रतिलिपि<br>CC: | i)    | के.नि. SD / मु.अ. CS                                                         | सॉफ्ट प्रति का वितरण<br>Distribution of soft copy                                                                                  |
|                  | ii)   | संबंधित समूह प्रमुख Concerned Group Head                                     |                                                                                                                                    |
|                  | iii)  | उप.म.प्र. (मा.सं.) DGM, HR                                                   |                                                                                                                                    |
|                  | iv)   | वरि. कमाण्डेण्ट, के.औ.सु.ब., एनएपीएस स्थल<br>Sr. Commandant, CISF, NAPS Site |                                                                                                                                    |
|                  | v)    | कार्यादेश हस्ताक्षर करने वाले प्राधिकारी<br>WO signing authority             | निविदा दस्तावेज एवं<br>संलग्नकों सहित सॉफ्ट प्रति<br>का वितरण<br>Distribution of soft copy<br>with enclosures & tender<br>document |
|                  | vi)   | प्रभारी अभियंता Engineer In Charge                                           |                                                                                                                                    |
|                  | vii)  | वरि. अभियंता, क्यू.ए. Senior Engineer, QA                                    |                                                                                                                                    |
|                  | viii) | सतर्कता अधिकारी, एनएपीएस Vigilance Officer, NAPS                             |                                                                                                                                    |
|                  | ix)   | उप सतर्कता अधिकारी, एनएपीएस DVO, NAPS                                        |                                                                                                                                    |
|                  | x)    | वरि. प्र. (वि.एवं ले.) Sr. Mgr., F&A                                         | संलग्नकों सहित मुद्रित प्रति<br>का वितरण<br>Distribution of hard copy<br>with enclosures                                           |
|                  | xi)   | ईएनसी, सीटीसी ENC, CTC                                                       |                                                                                                                                    |
|                  | xii)  | फाइल प्रति File Copy                                                         |                                                                                                                                    |

अनुसूची 'बी' SCHEDULE 'B'

**ठेकेदार को जारी की गई सामग्री**  
**MATERIAL ISSUED TO THE CONTRACTOR**

| क्रसं<br>S.No. | विवरण<br>Particulars | यूनिट<br>Unit | दर जिसपर<br>सामग्री जारी<br>की जाएगी<br>Rate at which<br>material will<br>be issued | अधिकतम अदृश्य<br>अपशिष्ट<br>(गैर-वापसी<br>योग्य)<br>Max. invisible<br>wastage (Non-<br>Returnable) % | अधिकतम अनुज्ञेय<br>अपशिष्ट (निःशुल्क<br>जारी के स्थिति में<br>लौटाने योग्य)<br>Max. permissible<br>wastage (Returnable in<br>case of free issue) % | जारी की जाने<br>वाली मात्रा<br>(अनुमानित)<br>Qty. to be issued<br>(approx.) |
|----------------|----------------------|---------------|-------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------|
| 1              | 2                    | 3             | 4                                                                                   | 5                                                                                                    | 6                                                                                                                                                  | 7                                                                           |
| -              | NIL                  | NIL           | NIL                                                                                 | NIL                                                                                                  | NIL                                                                                                                                                | NIL                                                                         |

अनुसूची 'सी' SCHEDULE 'C'

**ठेकेदार को किराए पर दिए जाने वाले उपकरण एवं यंत्र**  
**TOOLS AND PLANT TO BE HIRED TO THE CONTRACTOR**

| क्रसं<br>S.No. | विवरण<br>Particulars | उपलब्ध संख्या<br>Number<br>available | प्रति दिन प्रति<br>यूनिट किराया<br>प्रभार<br>Hire charges<br>per Unit per<br>working day<br>Rs. | अनुरक्षण की<br>आवृत्ति<br>Frequency of<br>Maintenance | प्रति<br>यूनिट<br>मूल्य<br>Value<br>Per<br>Unit | जारी<br>करने का<br>स्थान<br>Place of<br>issue | ठेकेदार को<br>आवश्यक संख्या<br>Number required<br>by the<br>Contractor |
|----------------|----------------------|--------------------------------------|-------------------------------------------------------------------------------------------------|-------------------------------------------------------|-------------------------------------------------|-----------------------------------------------|------------------------------------------------------------------------|
| 1              | 2                    | 3                                    | 4                                                                                               | 5                                                     | 6                                               | 7                                             | 8                                                                      |
| -              | NIL                  | -                                    | NIL                                                                                             | -                                                     | NIL                                             | -                                             | NIL                                                                    |

*Amrit*



## SECTION-07

### SCHEDULE OF MATERIALS TO BE SUPPLIED BY THE CORPORATION TO THE CONTRACTOR

*Material will be issued as per Schedule B of General Conditions of  
Contract, Section-04*

*Grant*



**NUCLEAR POWER CORPORATION OF INDIA LIMITED**  
(A Government of India Enterprise)

Narora Site

**Schedule Of Quantities And Rates**

Print Date: 20-Sep-2025

**CoManas**

*NAAS/CTC/CSR/COPR/PT/1146/WOS/8132*

Name of Work: Construction of misc. infrastructure in Raghunath Baransaini Inter Collage- Rajghat, Shri Devatrya Aadarsh Inter Collage- Karanwas, Bhagirathi Vedang Inter Collage- Ramghat, DB Janta Junior High School- Rampur, Composite UPS-Badarpur, Uchcha Prathmic Vidyalaya-Nodai Bangar, Primary School-Rehmapur, Krishna and Shreeram Memorial Vedic Inter College-Atrauli under CSR.

WO / SOQR Number : 8132

Agency Name : M/S TECHNICAL CONSTRUCTION CO.

| Item No              | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            | Unit | Quantity                                       | Rate in ₹ | Rebate in % | Rebated Rate | Amount in ₹  |
|----------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|------------------------------------------------|-----------|-------------|--------------|--------------|
| Schedule : CIVIL:-NA |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |      |                                                |           |             |              |              |
| 1                    | Earthwork in excavation for foundation in steps as per site in all soils upto required depth including shoring, shuttering and dewatering, as required, compaction as per requirement and side protection, including filling around foundation and in plinth with selected excavated soil from site it self and in layers not exceeding 150mm in thickness watering and consolidation etc. disposing surplus earth with in a distance of 3 km including taking level by bringing suitable leveling machine making grid pillar etc. as per requirement. | CuM  | 1542                                           | 180       | -           | -            | 2,77,560.00  |
|                      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |      | Rupees One Hundreds Eighty Only                |           |             |              |              |
| 2                    | Providing and laying cement concrete 1-4-8 (Mix ratio of -One part Cement, Four Part Fine Aggregate and Eight part Coarse Aggregate) (minimum compressive strength 75Kg / Sqcm) in foundation using graded stone aggregate 20mm maximum size and down graded including formwork consolidation, finishing, curing etc. complete as per specification (cement content 170 Kg./CuM).                                                                                                                                                                      | CuM  | 124                                            | 4400      | -           | -            | 5,45,600.00  |
|                      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |      | Rupees Four Thousand Four Hundreds Only        |           |             |              |              |
| 3                    | Supplying and laying Bricks masonry using locally available approved brick (minimum compressive strength 70Kg/Sqcm) of uniform shape (average size- 225mm x 105mm x 65mm (± 5mm)) cement mortar 1-6 (Mix ratio of -One part Cement and Six part Sand) at all elevation including, simultaneous pointing below plinth level and racking out joints above ground level, curing etc. complete as per specifications.                                                                                                                                      | CuM  | 829.7                                          | 4750      | -           | -            | 39,41,075.00 |
|                      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |      | Rupees Four Thousand Seven Hundreds Fifty Only |           |             |              |              |
| 4                    | Damp proof course (DPC) on top of plinth 40mm thick with cement concrete 1-2-4 (Mix ratio of -One part Cement, Two part Fine Aggregate and Four part Coarse Aggregate) mixed with approved water proofing compound at 2% by weight of cement using graded stone aggregate of 10mm max. size laid to full width of wall including form work, consolidation finishing curing etc. complete.                                                                                                                                                              | SqM  | 68                                             | 400       | -           | -            | 27,200.00    |
|                      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |      | Rupees Four Hundreds Only                      |           |             |              |              |
| 5                    | Supplying structural steel pipes, angles, tee, channel, hollow sections etc. and fabrication with cutting, welding, anchoring by cinch anchors, nut, bolting and fixing in position of all type structural steel as per direction of engineer including painting with two coat of S.E. paint of make Berger Luxol / Asian apoclite / Nerolac - kansai Nerolac over one coat of red oxide primer for door / window, grills etc. complete.                                                                                                               | MT   | 11.94                                          | 82000     | -           | -            | 9,79,080.00  |
|                      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |      | Rupees Eighty Two Thousand Only                |           |             |              |              |
| 6                    | Providing and laying RCC 1-1.5-3 (Mix ratio of -One part Cement, One & half part Fine Aggregate and Three part Coarse Aggregate) (Minimum Compressive Strength 200 Kg. / cm2) for Slab, Beam, Lintel, chajja, column etc. using graded stone aggregate 20 mm maximum size and down graded including scaffolding, form work, mixing, pouring, mechanical vibrating, consolidation, finishing, curing etc. complete but excluding reinforcement all as per specification and directed by EIC. (minimum Cement Content 350 Kg./M3).                       | CuM  | 143                                            | 7300      | -           | -            | 10,43,900.00 |
|                      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |      | Rupees Seven Thousand Three Hundreds Only      |           |             |              |              |

*Quant.*



Name of Work: Construction of misc. infrastructure in Raghunath Barahsaini Inter Collage- Raighat, Shri Devatrya Aadarsh Inter Collage- Karanwas, Bhagirathi Vedang Inter Collage- Ramghat, DB Janta Junior High School- Rampur, Composite UPS-Badarapur, Uchcha Prathmic Vidyalaya-Nodai Bangar, Primary School-Rehmapur, Krishna and Shreeram Memorial Vedic Inter College-Atrauli under CSR.

WO / SOQR Number : 8132

Agency Name : M/S TECHNICAL CONSTRUCTION CO.

| Item No | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | Unit                                     | Quantity | Rate in ₹     | Rebate in % | Rebated Rate | Amount in ₹  |
|---------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------|----------|---------------|-------------|--------------|--------------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |                                          |          | Rate in Words |             |              |              |
| 7       | Supplying reinforcement steel bars as per IS-1786, transporting and placing in position for all concrete including bending, cutting, binding fabricating, fixing, tying in position with 16 gauge wire soft draw binding wire with chairs, supports etc. complete as per specification including cost of binding wire as per specification. (Binding wire will not be measured for payment).                                                                                              | MT                                       | 13.93    | 75000         | -           | -            | 10,44,750.00 |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | Rupees Seventy Five Thousand Only        |          |               |             |              |              |
| 8       | Supply & laying cement concrete 1-2-4 (Mix ratio of -One part Cement, Two part Fine Aggregate and Four part Coarse Aggregate) (minimum compressive strength 150Kg / Sqcm) using graded stone aggregate 20 mm maximum size, preparing of mix using mechanical mixture, including formwork, consolidation, finishing to required level and slope and curing complete as directed by EIC (minimum Cement Content 330 Kg./CuM).                                                               | CuM                                      | 40       | 5800          | -           | -            | 2,32,000.00  |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | Rupees Five Thousand Eight Hundreds Only |          |               |             |              |              |
| 9       | Supplying and laying cement concrete 1-3-6 (Mix ratio of -One part Cement, Three part Fine Aggregate and Six part Coarse Aggregate) (minimum compressive strength 100Kg / Sqcm) for boundary wall coping etc using graded stone aggregate 20mm maximum size including, formwork, consolidation, finishing and curing as per specification (minimum Cement content. 220 Kg./ M3).                                                                                                          | CuM                                      | 18       | 4800          | -           | -            | 86,400.00    |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | Rupees Four Thousand Eight Hundreds Only |          |               |             |              |              |
| 10      | Supply, laying & compacting selected earth (Brought from outer side and not excavated from site it self) with cohesion, for filling etc., the layers not exceeding 150mm in thickness watering, compaction by ramming, compactor, roller etc. as required and consolidation etc. upto all leads and lifts of required depth including disposing surplus earth as per the direction of Engineer - in - charge.                                                                             | CuM                                      | 335      | 300           | -           | -            | 1,00,500.00  |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | Rupees Three Hundreds Only               |          |               |             |              |              |
| 11      | Providing 15 mm thick cement plaster in cement mortar 1-4 (Mix ratio of -One part Cement and Four part Sand) to brick or concrete surface and over parapit wall etc. including preparation of surface hacking, removing of loose materials, cleaning of joints, finishing curing complete all as per direction of EIC including disposal of rubbish.                                                                                                                                      | Sqm                                      | 5585     | 185           | -           | -            | 10,33,225.00 |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | Rupees One Hundreds Eighty Five Only     |          |               |             |              |              |
| 12      | Providing & Fixing Chicken wire mesh 450mm wide at junction of slab and wall on outer surface complete all as per direction of EIC.                                                                                                                                                                                                                                                                                                                                                       | RM                                       | 291      | 150           | -           | -            | 43,650.00    |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | Rupees One Hundreds Fifty Only           |          |               |             |              |              |
| 13      | Providing and laying machine cut double polished uniform colour best quality KOTA stone slab minimum 18mm thick in size 600x600mm (Approx.) or specified with marble stone strip laid over 20mm thick bed with cement mortar 1-4 (Mix ratio of -One part Cement and Four part Fine Aggregate) for floor, skirting and steps, joints with colour matching cement, rubbing, polishing, rounding of edge wherever required & curing etc. complete as per specification and direction by EIC. | Sqm                                      | 1145     | 950           | -           | -            | 10,87,750.00 |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | Rupees Nine Hundreds Fifty Only          |          |               |             |              |              |
| 14      | Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface and to prepare the surface even and smooth all complete.                                                                                                                                                                                                                                                                                   | Sqm                                      | 1440     | 50            | -           | -            | 72,000.00    |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | Rupees Fifty Only                        |          |               |             |              |              |
| 15      | Supplying & applying acrylic distemper of make Berger / Asian / Nerolac of approved shade in class room walls, ceiling in two coats over One coat of approved primer including preparation of surface, scaffolding etc. complete as per specification.                                                                                                                                                                                                                                    | Sqm                                      | 1560     | 60            | -           | -            | 93,600.00    |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | Rupees Sixty Only                        |          |               |             |              |              |



Name of Work: Construction of misc. infrastructure in Raghunath Barahsaini Inter Collage- Raighat, Shri Devatrya Aadarsh Inter Collage- Karanwas, Bhagirathi Vedang Inter Collage- Ramghat, DB Janta Junior High School- Rampur, Composite UPS-Badarpur, Uchcha Prathmic Vidyalaya-Nodai Bangar, Primary School-Rehmapur, Krishna and Shreeram Memorial Vedic Inter College-Atrauli under CSR.

Agency Name : M/S TECHNICAL CONSTRUCTION CO.

WO / SOQR Number : 8132

| Item No | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | Unit          | Quantity | Rate in ₹                             | Rebate in % | Rebated Rate | Amount in ₹  |
|---------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------|----------|---------------------------------------|-------------|--------------|--------------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | Rate in Words |          |                                       |             |              |              |
| 16      | Supplying and applying one coat of compatible Primer of Asian/Berger/Nerolac make & two coat of Exterior plastic emulsion paint of Asian Paints make Apex ultima / Berger make weather coat anti dust / Nerolac make Excel Mica Marble on new / existing surface including cleaning & preparation of surface etc. complete as per direction of Engineer-in-charge.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | SqM           | 3815     | 100                                   | -           | -            | 3,81,500.00  |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |               |          | Rupees One Hundreds Only              |             |              |              |
| 17      | Supplying and fixing circular / hexagonal M.S. Sheet ceiling fan box with clamp, rim, top and bottom lid. Lids shall be screwed into M.S. box by means of round handed screws, clamp shall be made of M.S. bar bent to shape as per standard with required over length.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | Nos           | 30       | 120                                   | -           | -            | 3,600.00     |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |               |          | Rupees One Hundreds Twenty Only       |             |              |              |
| 18      | Providing and laying 75 mm thick brick soling with locally available approved brick (minimum compressive strength 70Kg/Sqcm) of uniform shape (average size- 225mm x 105mm x 65mm (± 5mm)) including leveling and dressing the surface by cutting, transporting and filling the earth, complete to the required level and shape laying bricks with joints staggered and filling with earth and disposal of surplus earth upto a level of 1 Km all as per specification and direction of Engineer.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | SqM           | 9215     | 245                                   | -           | -            | 22,57,675.00 |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |               |          | Rupees Two Hundreds Forty Five Only   |             |              |              |
| 19      | Supplying & Laying 80mm thick (± 3 mm) cement concrete interlocking paver block of M-40 grade coloured tiles as per technical specification (minimum compressive strength 400Kg / cm2 & water absorption should not be more than 6% by mass) having smooth finish and of approved size and design/ shape and pattern over brick soling by providing 50mm thick compacted bed of Ganga Sand and filling the joints with same all complete as per the direction of Engineer - in - charge. Sample of paver block can be seen in the office of section head. (Note:- Existing soling where ever required has to be removed and relaid in required profile. Nothing extra will be paid for this). Note- The manufacturer interlocking tiles should meet technical specifications requirements. Concrete testing lab facility is also required in manufacturer's factory. Each tile should be trade mark of manufacturer.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | SqM           | 9830     | 830                                   | -           | -            | 81,58,900.00 |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |               |          | Rupees Eight Hundreds Thirty Only     |             |              |              |
| 20      | Providing and laying integral cement based water proofing treatment including preparation of surface as required for treatment of roofs, balconies, terraces at etc. after dismantling existing water proofing as required at site and consisting of the following i) Applying & grouting a slurry coat of neat cement using 2.75 Kg/sqm. of cement admixed with water proofing compound @ 2% of cement over RCC slab including adjoining walls upto 300mm height including cleaning the surface before treatment . ii) Laying broken bricks/ brick bats 25 mm to 100 mm size with 50% of cement mortar 1-5 (1 cement 5 coarse sand) admixed with water proofing compound @ 2% of cement over 20 mm thick layer of cement mortar 1-5 (1 cement 5 coarse sand) admixed with water proofing compound @ 2% of cement to required slope and treatment similarly the adjoining walls up to 300 mm height including rounding of junctions of walls and slabs.iii) After two days of proper curing applying a second coat of cement slurry using 2.75 kg/sqm of cement admixed with water proofing compound @ 2% of cement. iv) Finishing the surface with 20 mm thick joint less cement mortar of mix 1-4 admixed with water proofing compound @ 2% of cement and finally finishing the surface with trowel and neat cement slurry and making false marking of size 300X300 m square. v) The whole terrace so finished shall be flooded with water up to for a minimum period of two weeks for curing and for final testing. No seepage spots should be visible. Average thickness of layer 120 mm and minimum thickness at drain point (khurra) as 65 mm. | SqM           | 520      | 675                                   | -           | -            | 3,51,000.00  |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |               |          | Rupees Six Hundreds Seventy Five Only |             |              |              |



Name of Work: Construction of misc. infrastructure in Raghunath Barahsaini Inter Collage- Rajghat, Shri Devatrya Aadarsh Inter Collage- Karanwas, Bhagirathi Vedang Inter Collage- Ramghat, DB Janta Junior High School- Rampur, Composite UPS-Badarpur, Uchcha Prathmic Vidyalaya-Nodai Bangar, Primary School-Rehmapur, Krishna and Shreeram Memorial Vedic Inter Collage-Atrauli under CSR.

WO / SOQR Number : 8132

Agency Name : M/S TECHNICAL CONSTRUCTION CO.

| Item No | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | Unit          | Quantity | Rate in ₹ | Rebate in % | Rebated Rate | Amount in ₹  |
|---------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------|----------|-----------|-------------|--------------|--------------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | Rate in Words |          |           |             |              |              |
| 21      | Dismantling/breaking of existing concrete and brick work, cleaning of bricks stacking serviceable material and disposal of rubbish by Tractor/buggi for a lead of 2 km. as directed by engineer.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | CuM           | 29       | 700       | -           | -            | 20,300.00    |
| 22      | Providing and fixing 110mm dia PVC pipe ISI mark with necessary standard holder bat clamps including bends / shoes bends, jointing etc. as per the direction of Engineer - in - charge.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | RM            | 120      | 220       | -           | -            | 26,400.00    |
| 23      | Letter writing with synthetic Enamel Paint of approved brand & shade including preparation of base and border lining scaffolding etc. complete.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | /letter/cm    | 4300     | 1.5       | -           | -            | 6,450.00     |
| 24      | Providing and fixing Black granite stone 18mm thick (Approx.) of required size for Inauguration board with writing Golden colour letters 1" to 2" in height 75 Nos. (Approx.), maximum 1" Golden border all around complete as per requirement at various locations. Writing matter will be provided by NAPS. (Note- Brick pedestal for fixing Inauguration board will be made separately and paid in relevant items).                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | SqM           | 9        | 8000      | -           | -            | 72,000.00    |
| 25      | Providing and laying vitrified tiles (Double charge) of size 595mm x 595mm (Approx. thickness - 8 mm) of make H&R JOHNSON or KAJARIA or NITCO or equal range in price / quality as approved of required colours & shade, on floor, on walls, in skirting & riser of steps, over average 12mm thick bed of cement mortar 1-3 (Mix ratio of -One part Cement and Three part Fine Aggregate) jointing with grey cement slurry @3.3 kg / sqm including grouting the joints with required cement including finishing, curing and dismantling of existing floor / tiles and remove the debris etc, all complete as per Technical specification. Note- In order to maintain the slope of the flooring of the room, the extra mortar at the high and of the rooms will have to be provided by the contractor at his own cost. No extra payment will be made for the extra thickness of mortar provided by the contractor to maintain the minimum slope of the tile flooring. | SqM           | 6720     | 1000      | -           | -            | 67,20,000.00 |

Note: All Item Rates are considered to be in Indian Rupees unless otherwise explicitly specified and in which case shall be always converted appropriately to arrive at the amount in Indian Rupees.

|                                                 |                  |
|-------------------------------------------------|------------------|
| Work Order Total                                | ₹ 2,86,06,115.00 |
| Overall Rebate (%)                              | 0                |
| Work Order Value After Overall Rebate in Figure | ₹ 2,86,06,115.00 |



Work Order Value After Overall Rebate in  
Words

Rupees Two Crore Eighty Six Lakh Six Thousand One Hundreds Fifteen  
Only

Signature  
S2. Mgr (F&A)

Amount  
23/9/15