



न्यूक्लियर पावर कॉर्पोरेशन ऑफ इंडिया लिमिटेड
NUCLEAR POWER CORPORATION OF INDIA LIMITED

(भारत सरकार का उद्यम)
(A Govt. of India Enterprise)

नरौरा परमाणु विद्युत केंद्र
Narora Atomic Power Station

प्लॉट: एन.ए.पी.एस टाउनशिप, नरौरा जिला बुलंदशहर, (उ.प्र.) - 203389

PO: NAPS Township, Narora, Distt. Bulandshahr, (UP) - 203389

दूरभाष Phone: 05734-222167 इंटरकॉम Intercom: 4504

ई-मेल E-Mail: anantsingh@npcil.co.in



पंजीकृत कार्यालय Registered Office
16वां तल 16th Floor,
विश्व व्यापार केंद्र World Trade Centre
कफे परेड Cuffe Parade,
कोलाबा Colaba
मुम्बई Mumbai - 400 005
सी.आई.एन.
सं.: U40104MH1987GOI149458
CIN No.: U40104MH1987GOI149458
वेबसाइट Website: www.npcil.nic.in

संदर्भ: एनएपीएस/सीटीसी/सीवीएल/सीपीपीपी/पीटी/1155/ डब्ल्यूओएस/8130 दिनांक Date: 18/9/25

Ref: NAPS/CTC/CVL/CPPP/PT/1155/WOS/8130

To,
M/S Technical Construction Co.
9/206, Uday Singh Jain Road
Aligarh, Uttar Pradesh
PIN -202001
GSTIN: 09AAFFT5842C1Z6

एमएसएमई MSME	Yes
कार्यदेश संख्या Work Order No.	8130
उपखाता कोड Subledger Code	T1058
लेखा कोड Account Code	74300
लागत केंद्र कोड Cost Centre Code	645

कार्यदेश WORK ORDER

Name of work	:	Miscellaneous Civil Maintenance Works at NAPS Plant Site.
संदर्भ Reference	:	
1. निविदा संख्या Tender No.	:	एनएपीएस/सीटीसी/सीवीएल/2025/सीपीपीपी/पीटी/1155 NAPS/CTC/CVL/2025/CPPP/PT/1155
2. सीपीपीपी निविदा आईडी CPPP Tender ID	:	2025_ एनपीसीआईएल_238313_1 दिनांक 26/06/2025 2025_NPCIL_238313_1 Date: 26/06/2025

प्रिय महोदय / Dear Sir,

कृपया उपर्युक्त कार्य के लिए एनआईटी संख्या एनएपीएस/सीटीसी/सीवीएल/2025/सीपीपीपी/पीटी/1155 के पक्ष में अपने ऊपर उद्धृत निविदा का संदर्भ लें जिसका भाग-1 18/07/2025 को खोला गया था और भाग-II 12/08/2025 को खोला गया था।

Please refer to your above cited tender in response to NIT No. NAPS/CTC/CVL/2025/CPPP/PT/1155 for the above work part-1 of which was opened on 18/07/2025 and part-II on 12/08/2025

Signature

- 1) आपको सूचित किया जाता है कि आपके द्वारा प्रस्तुत निविदा को एनपीसीआईएल के लिए एवं की ओर से, निविदा में समाविष्ट दर और मात्रा अनुसूची में दर्शाये गए कार्य की मदों के लिए वस्तु एवं सेवाकर सहित निविदा लागत **रु० 2,33,52,975/- (रुपये दो करोड़ तेतीस लाख बावन हजार नौ सौ पचत्तर मात्र)** के लिए स्वीकार कर लिया गया है। वर्तमान वस्तु एवं सेवाकर 18% लागू है।

This is to inform you that the tender submitted by you has been accepted for and on behalf of NPCIL, for the items of work shown in the schedule of quantities and rates covered by the tender for a contract value of **Rs. 2,33,52,975/- (Rupees Two Crore Thirty Three Lakh Fifty Two Thousand Nine Hundred Seventy Five Only)** including Goods and Services tax. The present rate of GST 18% applicable.

- 2) संलग्न मात्रा और दर अनुसूची में मद संख्या 43, 52.28, 52.31, 52.42, 52.51, 52.52, 52.53, 52.57, 52.64 असामान्य रूप से उच्च दर (AHR) की हैं। और मद संख्या 1, 10, 13, 15, 16, 17, 20, 24, 25, 26, 27, 28, 29, 30, 31, 32.01, 32.02, 32.03, 33.01, 33.02, 33.03, 35, 38, 40, 41, 45, 46, 47, 48, 49, 50, 51, 52.05, 52.12, 52.14, 52.15, 52.18, 52.21, 52.23, 52.41, 52.50, 52.60, 52.61, 52.69, 52.70, 52.74, 52.77, 52.78, 52.79 असामान्य रूप से निम्न दर की हैं।

Item No. 43, 52.28, 52.31, 52.42, 52.51, 52.52, 52.53, 52.57, 52.64 are Abnormally High Rated (AHR) items and Item No. 1, 10, 13, 15, 16, 17, 20, 24, 25, 26, 27, 28, 29, 30, 31, 32.01, 32.02, 32.03, 33.01, 33.02, 33.03, 35, 38, 40, 41, 45, 46, 47, 48, 49, 50, 51, 52.05, 52.12, 52.14, 52.15, 52.18, 52.21, 52.23, 52.41, 52.50, 52.60, 52.61, 52.69, 52.70, 52.74, 52.77, 52.78, 52.79 are Abnormally Low Rated (ALR) items in the attached schedule of quantities and rates.

- 3) निविदा में निर्दिष्ट शर्तों, निबंधनों, विनिर्देशों और ड्राइंगों के अनुसार कार्य सख्ती से और श्रेष्ठतम कौशल के साथ किया जाएगा। आप हर समय कार्य पर योग्य कर्मचारियों को नियुक्त करेंगे हर समय बनाए रखेंगे। आप कार्य स्थल पर ऐसी मशीनरी, उपकरणों और अन्य सामग्री भी लाएंगे एवं कार्य में प्रयोग करेंगे, जोकि इस कार्य को संतोषजनक ढंग से पूरा करने के लिए आवश्यक हैं।

The work shall be carried out strictly in accordance with the terms, conditions, specifications and drawings stipulated in the tender and also in best workmanlike manner. You shall employ and maintain qualified staff in the job at all times. You shall also bring to the site and employ such machinery and equipments and other materials as are necessary for the satisfactory completion of this work.

- 4) प्रारंभ तिथि से चौबीस (24) कैलेंडर माह के भीतर हर प्रकार से कार्य पूरा किया जाएगा। प्रारंभ होने की तारीख की गणना 21/10/2025 से की जाएगी। समय अनुबंध का सार होगी और कार्य अनुमोदित कार्यक्रम के अनुसार पूरा किया जाएगा।

The work shall be completed in all respects within **Twenty Four (24) Calendar Months** from the date of commencement. The date of commencement will be reckoned from **21/10/2025**. The time shall be essence of the contract and the work shall be completed as per approved program of work.

Handwritten signature

- 5) भुगतान में वृद्धि जैसा कि संविदा में इंगित किया गया है, भी देय होगी (यदि लागू हो)।

Escalation of payment as indicated in the Contract shall also be payable (if applicable).

- 6) आपसे अनुरोध है कि इस संविदा के सभी मामलों के पर्यवेक्षण हेतु अपने अधिकृत प्रतिनिधि का नाम सूचित करें और उचित मूल्य के स्टाम्प पेपर पर विधिवत निष्पादित मुख्तारनामा उनके पक्ष में प्रस्तुत करेंगे।

You are requested to inform the name of the authorized representative who will deal with all matters relating to the contract and the Power of Attorney in his favour duly executed on stamped paper of an appropriate value shall be furnished.

- 7) संविदा निष्पादन के दौरान और आपको कार्य समाप्ति प्रमाण पत्र जारी होने तक, आपकी वजह से तृतीय पक्ष को हुई हानि या क्षति सहित किसी भी कार्य, संरचना, संपत्ति आदि की हानि, क्षति या विनाश के लिए सभी संबंधितों को क्षतिपूर्ति करने के लिए आप पूरी तरह से उत्तरदायी होंगे और इसका निर्णय प्रभारी अभियंता द्वारा किया जाएगा और इस संदर्भ में उनका निर्णय अंतिम होगा।

During the execution of the contract and until completion certificate is issued you will be fully liable to compensate all concerned for any loss, damage or destruction of work, structure, property etc. including third party risk arising due to causes attributable to you which will be decided by the Engineer-in-Charge whose decision in this regard will be final.

- 8) अनुबंध की शर्तों के अनुसार आपको सभी लागू बीमा (एससीसी के 3.7.7 के अनुसार ईएसआई सहित) पॉलिसियाँ लेनी होंगी, एवं इससे संबंधित दस्तावेजों को कार्य शुरू होने से पहले प्रभारी-अभियंता को जमा किया जाना चाहिए।

You are required to take all applicable insurance (including ESI as per 3.7.7 of SCC) policies as per the conditions of the contract and documents in this required should be submitted to engineer-in-charge before start of work.

- 9) इस कार्य हेतु कार्य संविदा पर केंद्र अथवा राज्य सरकार द्वारा समय-समय पर यथा अधिसूचित आयकर और अन्य सांविधिक कर, यदि कोई हो, तो उसकी वसूली निर्धारित तरीके से आपके अंतरिम बिलों के अलावा अंतिम बिल से भी की जाएगी। आपसे अनुरोध है कि आप अपना स्थायी खाता संख्या (पैन नंबर) प्रभारी अभियंता सूचित करें।

Income Tax and statutory Levy, if any, on works contract as notified by Central/ State Govt. from time to time shall be recovered from your running bills as well as final bills for this work in the prescribed manner. You are requested to intimate your permanent Account number to Engineer-in-Charge.

- 10) श्री शशांक अग्रवाल वै.अधि./ई (सिविल), इस कार्य के प्रभारी अभियंता होंगे। आप प्रभारी अभियंता के साथ परामर्श करके तत्काल कार्य शुरू करने के लिए आवश्यक व्यवस्था करें।

Shri Shashank Agrawal, SO/E (Civil), will be the Engineer-in-Charge of this work. You may make necessary arrangements for commencing the work immediately in consultation with Engineer-in-charge.

- 11) कृपया आप ध्यान दें कि प्रतिभूति जमाराशि **रू० 23,35,298/-** (संविदा मूल्य के 10% की दर से) होगी। प्रारंभ में आपको **रू० 11,67,649/-** (प्रतिभूति जमाराशि का 50%) निष्पादन गारंटी के रूप में जमा करने होंगे। प्रतिभूति जमाराशि **रू०- 11,67,649/-** की शेष धनराशि प्रत्येक बिल राशि के 6% की दर से अंतरिम बिलों या अंतिम बिल से वसूल की जाएगी। प्रतिभूति जमाराशि पर कोई ब्याज देय नहीं होगा।

You may please note that Security Deposit will be **Rs. 23,35,298/-** (@10% of contract value). Initially you will have to submit a performance guarantee for **Rs. 11,67,649/-** (50% of Security Deposit). The remaining amount of Security Deposit of **Rs. 11,67,649/-** will be recovered from the RA bill/ Final bill at the rate of 6% of each bill amount. Security Deposit amount will not bear any interest.

- 12) आपको ठेका श्रमिक (विनियमन एवं उन्मूलन) अधिनियम-1970 के विभिन्न उपबंधों और उसके बाद समय - समय पर बनाए गए नियमों का अनुपालन करना होगा। यदि ठेका श्रमिक अधिनियम आपके प्रतिष्ठान पर लागू नहीं होता है, तो आप कार्य शुरू करने से पहले इस कार्य के प्रभारी अभियंता को तदनुसार सूचित करेंगे। इसके अलावा, आपके प्रतिष्ठान पर लागू अन्य कानूनों जैसे- कामगार क्षतिपूर्ति अधिनियम-1923, न्यूनतम मजदूरी अधिनियम-1948, कर्मचारी भविष्य निधि अधिनियम, उपदान अधिनियम और अन्य श्रम कानूनों का आप अनुपालन करेंगे। यदि एनपीसीआईएल को प्रधान नियोक्ता तौर पर विभिन्न कानूनी उपबंधों के अधीन कोई व्यय करना पड़ता है, तो एनपीसीआईएल उसे आपसे अथवा आपके बिलों से वसूल करने का हकदार होगा।

You shall comply with various provisions of the contract labour (Regulations & Abolition) Act 1970 and rules framed thereafter from time to time. In case, the Contract labour Act does not apply to your organisation you should intimate the Engineer-in-charge of this work accordingly before commencing the work. Further you shall also comply with the provisions of other laws such as Workmen's Compensation Act 1923, Minimum wages Act 1948, E.P.F. Act, Gratuity Act and other labour laws as applicable to your organisation. In case, NPCIL is required to incur any expenses as principal employer under the provisions of the various laws, NPCIL shall be entitled to recover the same from you/your bills.

- 13) आपके द्वारा इस कार्य पर लगाए जाने वाले प्रस्तावित कामगारों की अधिकतम संख्या के आधार पर श्रम लाइसेंस, यदि लागू हो, प्राप्त करने के लिए प्रधान नियोक्ता का प्रमाणपत्र आपकी माँग पर जारी किया जाएगा। कृपया ध्यान दें कि इस कार्यादेश के जारी होने की तारीख से 14 दिनों के भीतर, आपको इस कार्य पर लगाए जाने वाले अधिकतम कामगारों हेतु श्रम लाइसेंस के लिए क्षेत्र के सहायक श्रम आयुक्त (केन्द्रीय) के कार्यालय में आवेदन करना होगा। आवेदन की एक प्रति कार्य शुरू होने के एक सप्ताह के भीतर कार्य के प्रभारी अभियंता के समक्ष प्रस्तुत करनी होगी।

Principal Employer's certificate for obtaining labour license, **if applicable** based on the maximum number of workmen you propose to employ for this work will be issued upon requisition. You may please note that within 14 days from the date of issue of this work order, you will have to apply for a labour license to the Asstt. Labour Commissioner (Central), of the area, for the maximum number of workers you have to engage on the work. A copy of the application will have to be furnished to the Engineer-in-charge of the work within a week time from start of work.

Handwritten signature

- 14) प्रथम अंतरिम बिल का मुंगतान केवल श्रम लाइसेंस / श्रम लाइसेंस रसीद (यदि लागू हो) प्रस्तुत करने पर ही किया जाएगा।

The first running account bill will be paid only on production of labour license/ labour license receipt, **if applicable.**

- 15) आपसे अनुरोध है कि समझौते पर हस्ताक्षर करने के लिए आप कार्यालय में उपस्थित हों। औपचारिक अनुबंध होने तक प्रसंगाधीन पत्रों सहित मूल निविदा और यह कार्यदेश हमारे बीच बाध्यकारी संविदा होगा।

You are requested to attend the office for signing the agreement. Till a formal agreement is executed the original tender together with letters under reference and this work order shall form the binding contract between us.

कृपया इस कार्यदेश की प्राप्ति और स्वीकृति यथाशीघ्र दें।


Kindly acknowledge receipt of this Work Order & acceptance at the earliest.

धन्यवाद Thanking you,

टिप्पणी: किसी भी विवाद या निर्वचन की स्थिति में अंग्रेजी पाठ ही मान्य होगा।

Remark: In case of any inconsistency or discrepancy the English version shall prevail.

भवदीय
Yours faithfully


(अनंत कुमार सिंह Anant Kumar Singh)

अनुरक्षण अधीक्षक, एनएपीएस
Maintenance Superintendent, NAPS
एनपीसीआईएल के लिए एवं की ओर से
For and on behalf of N.P.C.I.L

- संलग्नक i) सामग्री आपूर्ति अनुसूची
Encl. (निविदा दस्तावेज के खंड-4 की अनुसूची-बी एवं सी तथा खंड-7)
Schedule of supply of material
(Section -VII and Schedule B & C of Section IV of tender document)
ii) मात्रा एवं दर अनुसूची
Schedule of Quantities & Rates

प्रतिलिपि CC:	i)	के.नि. SD / मु.अ. CS	सॉफ्ट प्राने का वितरण Distribution of soft copy
	ii)	संबंधित समूह प्रमुख Concerned Group Head	
	iii)	उप.म.प्र. (मा.सं.) DGM, HR	
	iv)	वरि. कमाण्डेण्ट, के.ओ.सु.ब., एनएपीएस स्थल Sr. Commandant, CISF, NAPS Site	

v)	कायोदेश हस्ताक्षर करने वाले प्राधिकारी WO signing authority	निविदा दस्तावेज एवं संलग्नकों सहित सॉफ्ट प्रति का वितरण
vi)	प्रभारी अभियंता Engineer In Charge	
vii)	वरि. अभियंता, क्यू.ए. Senior Engineer, QA	
viii)	सतर्कता अधिकारी, एनएपीएस Vigilance Officer, NAPS	Distribution of soft copy with enclosures & tender document
ix)	उप सतर्कता अधिकारी, एनएपीएस DVO, NAPS	
x)	वरि. प्र. (वि. एवं ले.) Sr. Mgr., F&A	संलग्नकों सहित मुद्रित प्रति का वितरण
xi)	ईएनसी, सीटीसी ENC, CTC	
xii)	फाइल प्रति File Copy	Distribution of hard copy with enclosures

Handwritten signature

अनुसूची 'बी' SCHEDULE 'B'

ठेकेदार को जारी की गई सामग्री
MATERIAL ISSUED TO THE CONTRACTOR

क्रसं S.No.	विवरण Particulars	यूनिट Unit	दर जिसपर सामग्री जारी की जाएगी Rate at which material will be issued	अधिकतम अदृश्य अपशिष्ट (गैर-वापसी योग्य) Max. invisible wastage (Non- Returnable) %	अधिकतम अनुज्ञेय अपशिष्ट (निःशुल्क जारी के स्थिति में लौटाने योग्य) Max. permissible wastage (Returnable in case of free issue) %	जारी की जाने वाली मात्रा (अनुमानित) Qty. to be issued (approx.)
1	2	3	4	5	6	7
1	Gypsum board/ metallic ceiling board	No	Free	0%	0%	100
2	Canvas Shoes	Pair	Free	0%	0%	80
3	Socks	Pair	Free	0%	0%	80
4	Underwear	No.	Free	0%	0%	80
5	Banyan	No.	Free	0%	0%	80

अनुसूची 'सी' SCHEDULE 'C'

ठेकेदार को किराए पर दिए जाने वाले उपकरण एवं यंत्र
TOOLS AND PLANT TO BE HIRED TO THE CONTRACTOR

क्रसं S.No.	विवरण Particulars	उपलब्ध संख्या Number available	प्रति दिन प्रति यूनिट किराया प्रभार Hire charges per Unit per working day Rs.	अनुरक्षण की आवृत्ति Frequency of Maintenance	प्रति यूनिट मूल्य Value Per Unit	जारी करने का स्थान Place of issue	ठेकेदार को आवश्यक संख्या Number required by the Contractor
1	2	3	4	5	6	7	8
-	NIL	-	NIL	-	NIL	-	NIL

Handwritten signature

SECTION-07

**SCHEDULE OF MATERIALS TO BE SUPPLIED BY THE
CORPORATION TO THE CONTRACTOR**

*Material will be issued as per Schedule B of General Conditions of
Contract, Section-04*

Shant

NUCLEAR POWER CORPORATION OF INDIA LIMITED
(A Government of India Enterprise)

Narora Site

Schedule Of Quantities And Rates



Print Date: 16-Sep-2025

CoManas		Name of Work: Miscellaneous Civil Maintenance Works at NAPS Plant Site. WO / SOQR Number : 8130		Agency Name : M/S TECHNICAL CONSTRUCTION CO.			
Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹
Schedule : CIVIL-NA							
1	Excavation of earth in all soil for footing, steps etc. in soil up to all depth, filling around foundation and in plinth with selected excavated soil in layers not exceeding 150mm in thickness watering, including dressing of sides and consolidation, ramming of bottom etc. disposing surplus earth with in a distance of 2 km.	CuM	500	180	-	-	90,000.00
				Rupees One Hundreds Eighty Only			
2	Providing of JCB machine for Excavation ,spreading and leveling of earth, waste, rubbish etc all purposes including fuel, operator etc all as per direction of EIC.	Per Hour	400	1000	-	-	4,00,000.00
				Rupees One Thousand Only			
3	Filling of available soil mix with cement including supply of cement @ 5% of weight of dry soil, mixing with Diesel Mixture, watering, consolidation etc. up to required depth in layers not exceeding 150mm in thickness.	CuM	10	1200	-	-	12,000.00
				Rupees One Thousand Two Hundreds Only			
4	Supplying and laying cement concrete 1:3:6 using graded stone aggregate of 20mm maximum size including, Scaffolding, formwork, consolidation, finishing, surface, needle vibrators and curing by hessian as per specification and drawing. (Cement content. 220 Kg/ M3).	CuM	50	4600	-	-	2,30,000.00
				Rupees Four Thousand Six Hundreds Only			
5	Supplying and laying cement concrete 1:2:4 using graded stone aggregate 20mm maximum size including mixing, Scaffolding, form-work, consolidation, finishing, surface, needle vibrators and curing by hessian complete for all works (Cement content 330 Kg/Cum) including repair and as per specification.	CuM	75	5500	-	-	4,12,500.00
				Rupees Five Thousand Five Hundreds Only			
6	Supplying and laying Reinforced cement concrete 1:1.5:3 using graded stone aggregate 20mm maximum size for different works (beam, slab, drain covers etc. wherever required.) including Scaffolding, formwork, mixing, consolidation, finishing, surface, needle vibrators and curing by hessian etc. complete as per specification and drawing etc. complete. (Including disposal of damaged pre cast cover and fixing new in position where necessary). (Cement content is 350 kg / M3). Note:-) Steel reinforcement will be paid separately in relevant items.	CuM	75	6600	-	-	4,95,000.00
				Rupees Six Thousand Six Hundreds Only			
7	Supplying delivery, and placing in position T.M.T bars of grade FE-500 or higher for all reinforced cement concrete work including cutting, bending, fabricating, fixing and tying in position with 16 gauge soft drawn annealed binding wire with chairs, supports etc. complete including cost of binding wire as per specifications and drawing (Binding wire will not be measured for payment).	MT	6	70000	-	-	4,20,000.00
				Rupees Seventy Thousand Only			

Handwritten signature

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹
				Rate in Words			
8	Supplying fabrication, bolting, welding, threading, handling erecting and embedding structural steel (Pipe, Angle, Flat, Plate, Tee, Hollow section) for misc. civil work as per requirement including anchoring with required size anchor bolt as per site requirement etc. with red oxide primer & two coat of Synthetic enamel paint complete. (Note - No separate payment will be made for providing anchor bolts for anchoring and their weight will not be considered for payment).	MT	1	80000	-	-	80,000.00
				Rupees Eighty Thousand Only			
9	Supplying and laying Bricks Masonry using locally available brick of uniform shape {average size- 225mmx105mmx65mm (± 5mm)} of Class designation 7.5 in cement mortar 1:6 at all elevation including, simultaneous pointing below plinth level and racking out joints above ground level, curing as per site requirement using hessian etc., Scaffolding and form work etc. complete.	CuM	150	4500	-	-	6,75,000.00
				Rupees Four Thousand Five Hundreds Only			
10	Laying of Bricks Masonry for pitching / soling/ brick work using old available brick in cement mortar 1:6 including, removing of brick, cleaning of old bricks simultaneous pointing below ground level, and racking out joints above ground levels curing scaffolding etc. complete as per specifications.	CuM	50	2000	-	-	1,00,000.00
				Rupees Two Thousand Only			
11	Providing and laying 115mm thick soling with brick of uniform shape {average size- 225mm x 105mm x 65mm (± 5mm)} including leveling and dressing the surface by cutting, transporting and filling the earth, complete to the required level and shape laying bricks with joints staggered and filling with earth and disposal of surplus earth upto a level of 2Km all as per specification.	SqM	2000	400	-	-	8,00,000.00
				Rupees Four Hundreds Only			
12	Breaking of brick work/ PCC (Plastered / unplastered) and stacking of all usable material in civil stores, disposal of all rubbish and brick bats up to a lead of 2 Km. by tractor, trolley along with driver & required manpower, required Scaffolding will be provided by the contractor at his own cost.	CuM	40	600	-	-	24,000.00
				Rupees Six Hundreds Only			
13	Breaking of RCC, cutting of reinforcement and disposal of all rubbish up to a lead of 2 Km. by tractor, trolley along with driver & required manpower, required Scaffolding will be provided by the contractor at his own cost.	CuM	10	1200	-	-	12,000.00
				Rupees One Thousand Two Hundreds Only			
14	Dismantling / removing existing Acid Alkali resistant tiled lining including mastic from walls, floors drain etc. complete in all respects cleaning and stracking of serviceable tiles for re-use under item No.-36 below, disposal of unserviceable materials, rubbish etc. within a lead of 2 Km. by tractor out side plant site in lowlying areas.	SqM	10	200	-	-	2,000.00
				Rupees Two Hundreds Only			
15	Providing & laying 15 mm thick cement plaster in cement mortar 1:4 to brick or concrete surface etc. including scaffolding, preparation of surface, hacking, removing of loose materials cleaning of joints, finishing curing complete all as per direction of EIC. including disposal of rubbish.	SqM	3000	200	-	-	6,00,000.00
				Rupees Two Hundreds Only			
16	Providing flush pointing on brick work, patch work on brick wall with cement mortar 1:3 including racking out joints, cleaning brick work, scaffolding and curing etc. complete.	SqM	3000	45	-	-	1,35,000.00
				Rupees Forty Five Only			
17	Removal of existing A.C / GI sheet and stacking of all usable material in civil stores, disposal of all rubbish and damaged sheet up to a lead of 2 Km. by suitable means & required manpower, Scaffolding as required will be provided by the contractor at his own cost.	SqM	200	65	-	-	13,000.00
				Rupees Sixty Five Only			

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹
				Rate in Words			
18	Supplying & fixing of 6 mm thick (Average) A.C. sheet of M/S Evrest / Uppal / Charminar / JP make for roofing with all accessories such as 'J' or 'U' Hooks, Nuts, GI and Bituminous washer etc over purline, rafter etc. including removal of existing damage sheets. Scaffolding as required will be provided by the contractor at his own cost all complete. Note: No Over-lapping will be paid.	SqM	200	425	-	-	85,000.00
			Rupees Four Hundreds Twenty Five Only				
19	Supplying and fixing 22 gauge corrugated / plain G.I. Sheet of M/S TATA, M/S JINDAL, M/S SAIL make, fixing over roofing including G.I. Plain Sheet for drain, G.I.'J' or 'U' bolts & nuts of required diameter with bitumen & G.I. washers to be fixing over existing purlins etc. including fixing of wind ties at all heights, Scaffolding as required will be provided by the contractor at his own cost all complete. Contractor will have to carry out repair of brick work / concrete at the ends of sheets by providing requisite materials (Cement, Aggregate etc.), manpower, scaffolding at his own cost. Also, contractor has to carry out two coats of synthetic enamel paint over one coat of red oxide primer over existing ties, trusses, purlins and all its components, etc. Cutting chases in brick work/ concrete for fixing of trusses, purlins & sheet and subsequent repairing at his own cost Note: No Over-lapping will be paid.	SqM	2500	1000	-	-	25,00,000.00
			Rupees One Thousand Only				
20	Replacement of Gypsum board, A.C. sheet, GI Sheet, Metallic false ceiling board with the material supplied by the department with necessary arrangement of supporting frame for which all material will be supplied by department at all height and location etc. complete.	SqM	200	100	-	-	20,000.00
			Rupees One Hundreds Only				
21	Providing and fixing door frame made out of M.S. angle 50x50x6mm with suitable rebate, four nos. 125mm long M.S. hinges, three Nos. 300 mm long M.S. hold fast of 35x5mm flat on each side including supplying and fixing minimum 35mm thick Flush shutter with two coats of synthetic enamel paint of make Berger / Asian / dulux over a coat of primer and putty.	SqM	10	3400	-	-	34,000.00
			Rupees Three Thousand Four Hundreds Only				
22	Fixing of door / window frame with shutter in position, line and plumbs with hold fast in cement concrete block complete.	SqM	50	400	-	-	20,000.00
			Rupees Four Hundreds Only				
23	Providing and fixing window shutter frame made out of seasoned sheeshum wood of size (75x30) mm, preparation of surface, painting two coat of S.E. paint make Berger / Asian / dulux over one coat of primer including removal / cutting of existing damaged frame matching.	RM	50	350	-	-	17,500.00
			Rupees Three Hundreds Fifty Only				
24	Applying Interior plastic emulsion paint in Two coats on walls and ceiling of T.B. S.B. etc. including preparation of surface removing of stains by rubbing the surface, applying putty, sand papering and including scaffolding provided by contractor for painting and as per Industrial Safety requirements. Note : Plastic emulsion paint will be supplied by the department.	SqM	1500	20	-	-	30,000.00
			Rupees Twenty Only				
25	Applying synthetic enamel paint in one coat including preparing the surfaces, filling with putty wherever required, scaffolding & cleaning etc. complete. Note: Synthetic enamel paint will be supplied by the department.	SqM	1500	20	-	-	30,000.00
			Rupees Twenty Only				

Paint

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹
		Rate in Words					
26	Applying of Epoxy paint as per specification including preparation of old painted surface by removing, grinding and loose sealing repairing of damage concrete and including full height scaffolding provided by contractor for painting and as per Industrial Safety requirements applying epoxy putty as per requirement and painting the surface with One coat to give smooth and even surface floor & wall by brush. (Epoxy paint and thinner will be supplied by the department). Note: (1) Work is to be carried out in the radiation area so TLD to be arranged by the contractor from HPU section (NAPS). (2) Baricating arrangement till drying of paint to be made by contractor. In T.B. and other area of zone I & II.	SqM	1500	20	-	-	30,000.00
				Rupees Twenty Only			
27	Applying of Epoxy paint as per specification including preparation of old painted surface by removing, grinding and loose sealing repairing of damage concrete and including full height scaffolding provided by contractor for painting and as per Industrial Safety requirements applying epoxy putty as per requirement and painting the surface with One coat to give smooth and even surface floor & wall by brush. (Epoxy paint and thinner will be supplied by the department). Note: (1) Work is to be carried out in the radiation area mostly, so TLD / DRD to be arranged by the contractor from HPU section (NAPS). (2) Baricating arrangement till dry of paint to be made by contractor. In Reactor building , Service building & other radiation area. Zone III & IV.	SqM	1500	25	-	-	37,500.00
				Rupees Twenty Five Only			
28	Applying Exterior Plastic Emulsion Paint in Two coats on walls and etc. of T.B, S.B., CWP/PH, RWPH etc. including preparation of surface removing of stains by rubbing the surface, applying putty, sand papering and including full height steel H-Frame scaffolding provided by contractor for painting and as per Industrial Safety requirements. Note : Plastic emulsion paint will be supplied by the department.	SqM	1500	20	-	-	30,000.00
				Rupees Twenty Only			
29	Supplying & applying one coat of coal tar epoxy of M/S Berger, Asian make on existing floor of cooling tower (NDCT & IDCT) clarifier, floor, wall, columns & any other areas as per requirement etc. Including cleaning and preparation of surface by grinding machine , emery paper , sand paper etc. as may be required and including full height scaffolding provided by the contractor for painting etc. complete at his own cost as per specifications.	SqM	65000	43	-	-	27,95,000.00
				Rupees Forty Three Only			
30	Applying Interior cement primer in one coat on walls and ceiling etc. including preparation of surface removing of stains by rubbing the surface, applying putty, sand papering and including full height scaffolding provided by contractor for painting and Industrial Safety requirements. Note : Interior cement primer will be supplied by the department.	SqM	500	15	-	-	7,500.00
				Rupees Fifteen Only			
31	Applying Exterior cement primer in one coat on walls etc. including preparation of surface removing of stains by rubbing the surface, applying putty, sand papering and including full height scaffolding provided by contractor for painting and Industrial Safety requirements shall be followed. Note : Exterior cement primer will be supplied by the department.	SqM	1500	10	-	-	15,000.00
				Rupees Ten Only			
32	Providing and attending the misc. nature of jobs in different building excluding material etc. Note :- works of one person in 8 hrs shall be deemed as one activity in Unit.						-
32.01	Jobs related to Skilled Manpower such as plumber/ mason/ carpenter/ painter/ Data recorder etc. for misc. civil maint. work. One activity consists of work of one skilled manpower in a day for 8 hours .	Activity	2700	915	-	-	24,70,500.00
				Rupees Nine Hundreds Fifteen Only			

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹
				Rate in Words			
32.02	Nature of jobs related to Semi skilled Manpower persons . for misc. civil maint. work.One activity consists of work of one semi- skilled manpower in a day for 8 hours .	Activity	650	760	-	-	4,94,000.00
			Rupees Seven Hundreds Sixty Only				
32.03	Nature of jobs related to Unskilled Manpower persons for misc. civil maint. work.One activity consists of work of one Unskilled manpower in a day for 8 hours .	Activity	3600	635	-	-	22,86,000.00
			Rupees Six Hundreds Thirty Five Only				
33	Providing and altering the misc. nature of jobs in different building excluding material etc. on overtime basis after normal duty as per item no. 10 Note :- (i) works of one person for 1 hrs shall be deemed as one activity in Unit. (ii) Deduction of 1 hour for duty done after 8 hours shall be done for determination of overtime period.				-	-	-
33.01	Execution of jobs mentioned in Item no. 32.1 (Skilled Manpower) above beyond 8 hour of duty in a day.	Activity	2050	140	-	-	2,87,000.00
			Rupees One Hundreds Forty Only				
33.02	Execution of jobs mentioned in Item no. 32.2 (Semi-Skilled Manpower) above beyond 8 hour of duty in a day.	Activity	530	120	-	-	63,600.00
			Rupees One Hundreds Twenty Only				
33.03	Execution of jobs mentioned in Item no. 32.3 (Unskilled Manpower) above beyond 8 hour of duty in a day.	Activity	2100	105	-	-	2,20,500.00
			Rupees One Hundreds Five Only				
34	Cleaning of NDCT basin and hot water ducts, and IDCT cold basin dewatering, making of concrete / brick wall water tight barrier for stopping of coming water after fixing gate and filling earth bags in between gate and jali, collection of all muck removable by water washing and other waste basin by using brooms, brush etc. Including dismantling of barrier and removal and disposal of all muck and other materials by providing tractor with driver & manpowers to average lead of 5km. All the materials such as aggregate, sand, cement bricks for work tools and plants empty bags etc. to be arranged by contractor (Pumps will be supplied departmentally for dewatering). Removal of Jali and refixing jali is also to be arranged by contractor. Note: Payment will be made on the basis of volume of muck removed from basin.	Cum	1500	400	-	-	6,00,000.00
			Rupees Four Hundreds Only				
35	Cleaning of hot water basin in IDCT after removal of A.C. Sheets rubbing the floor and wall etc with wire brush after removal of water, cleaning with bleaching powder etc. Complete. Note:- (a) During execution of above items the debris of any kind produced shall be disposed off to the areas directed by the engineer on daily basis at no extra cost and rate is inclusive of this work. It shall be ensure that no chocking or damage to lines and equipments while carrying out these work since the works shall be taken up in plant shut down and hence the contractor shall arrange to do the work accordingly. (b) AC sheets shall be supplied free of cost by the department for replacing or damaged A.C. Sheets. (c) Pucca area surrounding IDCT has to be cleaned of rubbish vegetation plants etc. work including this, no extra shall be payable. Note: Payment will be on the basis of number of operation carried out for one IDCT during shut down.	Nos	2	12000	-	-	24,000.00
			Rupees Twelve Thousand Only				

[Handwritten signature]

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹
				Rate in Words			
36	Laying of Acid / Alkali resistant tile lining on floor or walls in following sequence including supply of short tiles approximate 10% tiles may be required. (a) One coat of Prod. Dor lac spl. (b) Providing 20 mm Coromastic. (c) Tiles laid in cement prodor S.K. Bedding thickness 6mm. (d) Racking out the joint upto adepth of 18mm and width 6mm with grinding machine and pointing with furacin mortar all complete as per specification and as directed by of Engineer.(No material shall be issued by department. Contractor has to arrange at his own).	SqM	50	2200	-	-	1,10,000.00
			Rupees Two Thousand Two Hundreds Only				
37	Racking out the joints existing acid / alkali resistance tile lining on floors and walls, 6mm wide and depth of 12 mm with grinding / cutting machine. Repointing these joints with furacin or equivalent mortar. (No material shall be issued by department. Contractor has to arrange at his own.)	SqM	100	300	-	-	30,000.00
			Rupees Three Hundreds Only				
38	Providing and fixing premium quality mat finished Anti skid ceramic floor tiles of required size and 6mm thickness of H&R JOHNSON or KAJARIA or NITCO or SOMANY or equal range in price / quality as approved in required shade, laid on average 20 mm thick bed of cement mortar 1:4 (1 cement: 4 coarse sand) including cleaning and applying cement slurry @3.3 kg/ sqm grouting the joints including covering of floor tiles with PVC sheet protect the tile from painting stains and scratches during various finishing activities including finishing, curring and dismantling of existing floor / tiles and remove the debris etc, at all level etc. all complete. Note- Contractor may be required to provide extra mortar bed at various locations to provide adequate slope. Such extra mortar more than 20mm will have to be provided by the contractor at his own cost. No extra payment will be made for the extra mortar.	SqM	100	800	-	-	80,000.00
			Rupees Eight Hundreds Only				
39	Providing & laying of required size and 6mm thickness shade and series Glazed tile of H&R JOHNSON or KAJARIA or NITCO or SOMANY or equal range in price / quality for dado of WC bath and toilet with necessary specials etc. over average approx. 20 mm thick cement mortar 1:4 bedding to true plan & slope, close jointed & pointed with adhesive mortar, curing, cleaning and applying cement slurry @3.3 kg/ sqm including grouting the joints complete including removal / dismantling of existing or damaged tiles and disposal of debris at a designated place. Note- Contractor may be required to provide extra mortar bed at various locations to provide adequate slope. Such extra mortar more than 20mm will have to be provided by the contractor at his own cost. No extra payment will be made for the extra mortar.	SqM	100	800	-	-	80,000.00
			Rupees Eight Hundreds Only				
40	Providing and laying vitrified tiles (Double charge) of size 595mm x 595mm (Approx. thickness - 8 mm) of make in H&R JOHNSON or KAJARIA or NITCO or SOMANY or equal range in price / quality in as approved all colours & shade, in skirting & riser of steps, over average 12mm thick bed of cement mortar 1:3 jointing with grey cement slurry @3.3 kg / sqm including grouting the joints with required cement including finishing, curing and dismantling of existing floor / tiles and remove the debris etc, all complete as per specification. Note- Contractor may be required to provide extra mortar bed at various locations to provide adequate slope. Such extra mortar more than 20mm will have to be provided by the contractor at his own cost. No extra payment will be made for the extra mortar.	SqM	100	950	-	-	95,000.00
			Rupees Nine Hundreds Fifty Only				
41	Providing and laying of 15 mm thick (Approx.) approved GRANITE STONE flooring in glass finish gloss of approved shade in proper alignments over average 20mm thick bed with cement mortar 1:4 to give zero width of joints etc. complete for floor and skirting including removal of existing flooring and disposal of debris at a designated place all complete. Note- Contractor may be required to provide extra mortar bed at various locations to provide adequate slope. Such extra mortar more than 20mm will have to be provided by the contractor at his own cost. No extra payment will be made for the extra mortar.	SqM	100	2000	-	-	2,00,000.00
			Rupees Two Thousand Only				

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹
				Rate in Words			
42	Providing and laying machine cut double polished uniform colour best quality KOTA STONE slab minimum 18mm thick in required size laid over average 20mm thick bed with cement mortar 1:4 for floor, skirting and steps, joints with colour matching cement, rubbing, polishing, rounding of edge wherever required & curing etc. complete. Note- Contractor may be required to provide extra mortar bed at various locations to provide adequate slope. Such extra mortar more than 20mm will have to be provided by the contractor at his own cost. No extra payment will be made for the extra mortar.	SqM	100	1000	-	-	1,00,000.00
43	Grinding and polishing by machine of floors etc after plugging holes, repair of defects etc. complete upto the satisfaction of Engineer.	SqM	40	200	-	-	8,000.00
44	Carrying out injection grouting to all existing cracks to prevent water seepage etc. at a pressure of 2 to 3 kg/cm2 with low viscosity epoxy by providing non-returnable packers as per site conditions.	Kg	200	1200	-	-	2,40,000.00
45	Fixing of barbed wire in position to the existing poles / Y-post in horizontal row with G.I. wire/pins providing holes in the Y-Post etc. complete as per specification and as directed by the Engineer. Note:- Barbed wire shall be supplied by department free of cost.	RM	1000	2.5	-	-	2,500.00
46	Removal of existing damaged water proofing treatment of tarfeltment etc. transporting, unloading from roofs, and disposing the debris at the place upto lead of 2 km as per instruction of engineer including cutting of drain if required for drainage of rain water all complete.	SqM	2000	50	-	-	1,00,000.00
47	Providing and laying Heavy duty APP membrane of modified polymer of Pidilite / Texsa / S.T.P make reinforced with polyester mat in minimum 3mm. Thickness conforming to specification over one coat of primer of Berger, Asian, Nerolac make (oil based) jointing the strips and bottom by torch welding finish with super silver shield for roofs and parapet including testing of the treatment as per specification for water tightness as per instruction of engineer including repairing of expansion joint with polysulphide as per requirement at main plant buildings etc. Note- If leakage is observed from the APP membrane portion, contractor will have to remove and relay the APP membrane.	SqM	2000	500	-	-	10,00,000.00
48	Fabricating out of 22 gauge 800 mm wide G.I Sheet flashing as per site requirement, cutting chases in brick work/ concrete and fixing flashing with concrete etc. including removal of existing expansion joint treatment and prepared approximately (150 X 150) mm. Size concrete bund 1:1.5:3 both side after fixing the G.I Sheet over expansion joint and laying APP membrane as per directed by engineer-in-charge. APP membrane item will be paid in relevant item.	RM	100	800	-	-	80,000.00
49	Supplying & Laying 80mm thick (± 3 mm) cement concrete interlocking paver block of M-40 grade as per technical specification (minimum compressive strength 400Kg / cm2 & water absorption should not be more than 6% by mass) having smooth finish and of approved size and design/ shape laid in required colour and pattern over brick soling by providing 50mm thick compacted bed of Ganga Sand / Natural Sand / Other approved sand and filling the joints with same all complete as per the direction of Engineer - in - charge. Sample of paver block can be seen in the office of section head. Note- The manufacturer interlocking tiles should meet technical specifications requirements. Concrete testing lab facility is also required in manufacturer's factory. Each tile should be trade mark of manufacturer.	SqM	2000	700	-	-	14,00,000.00

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹
				Rate in Words			
50	Providing of smooth wheeled roller of 8 to 10 tonne capacity for compaction as per site requirement etc all purposes including fuel, operator etc all as per direction of EIC.	Per Hour	150	700	-	-	1,05,000.00
				Rupees Seven Hundreds Only			
51	Providing of motor Grader for grading Excavation, spreading and leveling of earth, waste, rubbish etc all purposes including fuel, operator etc all as per direction of EIC.	Per Hour	150	1000	-	-	1,50,000.00
				Rupees One Thousand Only			
52	Supplying and stacking of materials at site in phased manner as directed by engineer.				-	-	-
52.01	Natural sand (FM:- 2.3 to 3.2)	CuM	50	2100	-	-	1,05,000.00
				Rupees Two Thousand One Hundreds Only			
52.02	12.5mm Stone Aggregate for concrete etc.(40-85% passing from 10mm IS sieve)	CuM	25	2200	-	-	55,000.00
				Rupees Two Thousand Two Hundreds Only			
52.03	OPC- 43 / 53 Grade Confirming to IS: 269 (Make Birla uttam, J.K, Ultratech)	Bag	1000	400	-	-	4,00,000.00
				Rupees Four Hundreds Only			
52.04	White cement 5 kg of make Birla, JK white.	Bag	25	125	-	-	3,125.00
				Rupees One Hundreds Twenty Five Only			
52.05	White wall putty 20kg of make Birla, JK	Bag	10	425	-	-	4,250.00
				Rupees Four Hundreds Twenty Five Only			
52.06	Water proofing (101 pidiproof LW+) 1 Litre Pack make Dr. Fixit	Litre	50	150	-	-	7,500.00
				Rupees One Hundreds Fifty Only			
52.07	Ganga sand	CuM	10	1000	-	-	10,000.00
				Rupees One Thousand Only			
52.08	Clean coats, supreme & anabond make Two part Gun grade Poly sulphide sealant as per BS-4254-1983 in 04 Kg. packing.	Kg	600	650	-	-	3,90,000.00
				Rupees Six Hundreds Fifty Only			
52.09	Clean coats, supreme & anabond make Two part Gun grade Poly sulphide sealant as per BS-4254-1983 in 01 Kg. packing.	Kg	200	650	-	-	1,30,000.00
				Rupees Six Hundreds Fifty Only			

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹
		Rate in Words					
52.10	Araldite resin (Gy-250) in 30kg packing.	Kg	400	500	-	-	2,00,000.00
		Rupees Five Hundreds Only					
52.11	Hardner (Hy-840 /140) in 30kg packing.	Kg	200	650	-	-	1,30,000.00
		Rupees Six Hundreds Fifty Only					
52.12	Conbextra GP2 make fosroc 25kg bag.	Bag	75	500	-	-	37,500.00
		Rupees Five Hundreds Only					
52.13	Supplying of Bricks using locally available brick of uniform shape {average size-225mmx105mmx65mm (± 5mm)} of Class designation 7.5.	Nos	2000	6.5	-	-	13,000.00
		Rupees Six and Fifty Paisa Only					
52.14	Interior Acrylic Plastic emulsion paint of make Asian paint Apcolite Premium / Berger Rangoli Total Care.	Litre	100	210	-	-	21,000.00
		Rupees Two Hundreds Ten Only					
52.15	Exterior Plastic Emulsion Paint (water thinable) in 20-liter pack of M/S Asian Paints make Ace Exterior Emulsion, M/S Berger Paint make Walmasta, M/S Nerolac Suraxa Plastic, M/S ICI Dulux Super, M/S Snocem Paints make All Rounder.	Litre	100	140	-	-	14,000.00
		Rupees One Hundreds Forty Only					
52.16	Synthetic Enamel Paint of make Asian Paint Apcolite Gloss Enamel / Berger Luxol.	Litre	100	240	-	-	24,000.00
		Rupees Two Hundreds Forty Only					
52.17	Lime for white washing.	Kg	400	10	-	-	4,000.00
		Rupees Ten Only					
52.18	Epoxy paint in Vallum / Grey colour (In 20 litre packing) paint of Asian- Apcodur CF 641/ 641CS / Berger- protectomatic (Epoxy top coat) / Kansai Nerolac- Neromastic 400 NPK (Epoxy top coat).	Litre	900	400	-	-	3,60,000.00
		Rupees Four Hundreds Only					
52.19	Epoxy Thinner M/s Berger / M/s Asian / M/s Kansai Nerolac	Litre	160	220	-	-	35,200.00
		Rupees Two Hundreds Twenty Only					
52.20	General Purpose Thinner.	Litre	150	140	-	-	21,000.00
		Rupees One Hundreds Forty Only					
52.21	Epoxy paint for highly radiation area for FM vault FM service area in reactor building. Following make are required in white shade: make Asian- Apcodur CF 641/ 641CS / Berger- protectomatic (Epoxy top coat) / Kansai Nerolac- Neromastic 400 NPK (Epoxy top coat).	Litre	100	410	-	-	41,000.00
		Rupees Four Hundreds Ten Only					

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹
				Rate in Words			
52.22	Interior Cement primer Make Nerolac, Asian & Berger.	Litre	100	120	-	-	12,000.00
			Rupees One Hundreds Twenty Only				
52.23	Exterior Cement primer Make Nerolac, Asian & Berger.	Litre	100	100	-	-	10,000.00
			Rupees One Hundreds Only				
52.24	G.I. barbed wire having minimum weight 9.38 Kg /100 RM as per specifications.	Kg	200	85	-	-	17,000.00
			Rupees Eighty Five Only				
52.25	8'x4' x3mm Thick commercial ply.	Nos	20	750	-	-	15,000.00
			Rupees Seven Hundreds Fifty Only				
52.26	8'x4' x6mm Thick commercial ply.	Nos	20	1150	-	-	23,000.00
			Rupees One Thousand One Hundreds Fifty Only				
52.27	8'x4' x12mm Thick commercial ply.	Nos	20	1850	-	-	37,000.00
			Rupees One Thousand Eight Hundreds Fifty Only				
52.28	Heavy Duty Door Closer as per IS 3564 Size Type 3 for heavy steel door (Everite / Garnish / Godrej make).	Nos	100	2500	-	-	2,50,000.00
			Rupees Two Thousand Five Hundreds Only				
52.29	18 mm Thick Board.	SqM	20	850	-	-	17,000.00
			Rupees Eight Hundreds Fifty Only				
52.30	30 mm Thick Board.	SqM	20	1650	-	-	33,000.00
			Rupees One Thousand Six Hundreds Fifty Only				
52.31	MS Handle -125mm long.	Nos	100	40	-	-	4,000.00
			Rupees Forty Only				
52.32	MS Tower bolt-250mm long.	Nos	100	65	-	-	6,500.00
			Rupees Sixty Five Only				
52.33	MS Tower bolt-100mm long.	Nos	100	30	-	-	3,000.00
			Rupees Thirty Only				

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹
		Rate in Words					
52.34	MS Aldrops-300mm long.	Nos	100	130	-	-	13,000.00
		Rupees One Hundreds Thirty Only					
52.35	MS Hinges -150mm long.	Nos	100	60	-	-	6,000.00
		Rupees Sixty Only					
52.36	MS Hinges-125mm long.	Nos	500	40	-	-	20,000.00
		Rupees Forty Only					
52.37	M.S. Hinges 100mm long	Nos	300	30	-	-	9,000.00
		Rupees Thirty Only					
52.38	M.S. hinge 75mm long	Nos	300	25	-	-	7,500.00
		Rupees Twenty Five Only					
52.39	M.S. hinge 50mm long	Nos	100	20	-	-	2,000.00
		Rupees Twenty Only					
52.40	M.S. hinge 25mm long	Nos	100	12	-	-	1,200.00
		Rupees Twelve Only					
52.41	M.S. Chapka Kunda-100mm long	Nos	100	30	-	-	3,000.00
		Rupees Thirty Only					
52.42	M.S. Chapka Kunda-50mm long	Nos	200	20	-	-	4,000.00
		Rupees Twenty Only					
52.43	M.S. Chapka Kunda-75mm long	Nos	200	25	-	-	5,000.00
		Rupees Twenty Five Only					
52.44	Nails with head of size 1.5" X No. 12 (12SWG Thick).	Kg	10	100	-	-	1,000.00
		Rupees One Hundreds Only					
52.45	Nails 10 Nos. (10 SWG Thick) Size- 2"	Kg	10	100	-	-	1,000.00
		Rupees One Hundreds Only					

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹
Rate in Words							
52.46	Nails 14 Nos. (14 SWG Thick) Size- 1"	Kg	10	100	-	-	1,000.00
				Rupees One Hundreds Only			
52.47	Nails 14 Nos. (14 SWG Thick) Size- 1.5"	Kg	10	100	-	-	1,000.00
				Rupees One Hundreds Only			
52.48	Nails 14 Nos. (14 SWG Thick) Size- 3"	Kg	10	100	-	-	1,000.00
				Rupees One Hundreds Only			
52.49	Nails 17 Nos. (17 SWG Thick) Size- 1"	Kg	5	120	-	-	600.00
				Rupees One Hundreds Twenty Only			
52.50	Nails 10 Nos. (10 SWG Thick) Size- 1.5"	Kg	10	100	-	-	1,000.00
				Rupees One Hundreds Only			
52.51	Sheet metal screw (10 x 50mm) packing size 250 Nos. screw in one packet,	Pkt	10	400	-	-	4,000.00
				Rupees Four Hundreds Only			
52.52	Steel screw handed self tapping (10X16) packing size 1000 Nos. screw in one packet.	Pkt	5	600	-	-	3,000.00
				Rupees Six Hundreds Only			
52.53	Steel screw handed self tapping (8X19) packing size 1000 Nos. screw in one packet.	Pkt	5	600	-	-	3,000.00
				Rupees Six Hundreds Only			
52.54	Steel screw handed self tapping (8X16) packing size 1000 Nos. screw in one packet.	Pkt	10	550	-	-	5,500.00
				Rupees Five Hundreds Fifty Only			
52.55	Self Drilling Screw (3.9X25) packing size 1000 Nos. screw in one packet.	Pkt	5	600	-	-	3,000.00
				Rupees Six Hundreds Only			
52.56	Self Drilling Screw (3.9X19) packing size 1000 Nos. screw in one packet.	Pkt	15	600	-	-	9,000.00
				Rupees Six Hundreds Only			
52.57	Wooden Screw (35X8) packing size 1000 Nos. screw in one packet.	Pkt	5	700	-	-	3,500.00
				Rupees Seven Hundreds Only			

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹
				Rate in Words			
52.58	Drywall Screw (3.5X25) packing size 1000 Nos. screw in one packet.	Pkt	5	600	-	-	3,000.00
				Rupees Six Hundreds Only			
52.59	Plain Acrylic Sheet 5mm thick, Size (8x4) feet.	Nos	20	3500	-	-	70,000.00
				Rupees Three Thousand Five Hundreds Only			
52.60	Aluminium handle 100 mm size minimum weight 20gm	Nos	100	20	-	-	2,000.00
				Rupees Twenty Only			
52.61	Aluminum beading minimum weight 20gm per RM for window	RM	100	25	-	-	2,500.00
				Rupees Twenty Five Only			
52.62	Aluminum Tower bolt 4" size minimum weight 20gm per No.	Nos	100	30	-	-	3,000.00
				Rupees Thirty Only			
52.63	Pelmet strip Size minimum 1mm Thick & 115mm long & 19mm width.	Nos	100	10	-	-	1,000.00
				Rupees Ten Only			
52.64	Rubber Gasket U-type for aluminum door	RM	200	40	-	-	8,000.00
				Rupees Forty Only			
52.65	Beveled edge Mirror of superior glass (of approved quality).	SqM	20	1250	-	-	25,000.00
				Rupees One Thousand Two Hundreds Fifty Only			
52.66	Glass panes of 5mm thick of Sant Gobbins, Modi make.	SqM	50	800	-	-	40,000.00
				Rupees Eight Hundreds Only			
52.67	Wire mesh glass of 5mm thick of Sant Gobbins, Modi make.	SqM	20	800	-	-	16,000.00
				Rupees Eight Hundreds Only			
52.68	Stainless Steel wire mesh. mosquito proof jali having wire of 0.30 mm dia.	SqM	100	300	-	-	30,000.00
				Rupees Three Hundreds Only			
52.69	G.I. punched concertina wire of 450 mm dia coil with spring core wire of 2.6mm and having reinforced tape thickness of tape 0.5 mm of approved quality.	RM	300	190	-	-	57,000.00
				Rupees One Hundreds Ninety Only			

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹
		Rate in Words					
52.70	G.I. punched concertina wire of 730 mm dia coil with spring core wire of 2.6mm and having reinforced tape thickness of tape 0.5 mm of approved quality.	RM	300	230	-	-	69,000.00
		Rupees Two Hundreds Thirty Only					
52.71	G.I. punched RBT linear Wire having reinforced tape thickness of tape 0.5 mm, thickness.	RM	900	20	-	-	18,000.00
		Rupees Twenty Only					
52.72	A.C. sheet 6 mm thick (Approx.) of M/S Evrest / Uppal / Charminar / JP make.	SqM	100	300	-	-	30,000.00
		Rupees Three Hundreds Only					
52.73	Floor door stopper with twin rubber & stopper	Nos	100	70	-	-	7,000.00
		Rupees Seventy Only					
52.74	Supply of plastic Road reflectors M/S Avery / 3M / Stimsonite make and of size 100mm (minimum) x 90 mm (minimum) x 17 mm (minimum) of required colour and of bearing capacity 40MT (minimum) with Bituminous Adhesive & Anchoring material Note- Contractor has to submit test report of the road reflectors for compliance to above specification.	Nos	100	200	-	-	20,000.00
		Rupees Two Hundreds Only					
52.75	Supply of Anodised Aluminium sections (of all shapes and size etc.) as required .	Kg	50	380	-	-	19,000.00
		Rupees Three Hundreds Eighty Only					
52.76	Slim Taper with plastic handle-100mm long	Nos	20	50	-	-	1,000.00
		Rupees Fifty Only					
52.77	M.S. Nut with bolt 6mm dia -25mm long	kg	20	120	-	-	2,400.00
		Rupees One Hundreds Twenty Only					
52.78	M.S. Nut with bolt 6mm dia -50mm long	kg	30	120	-	-	3,600.00
		Rupees One Hundreds Twenty Only					
52.79	M.S. Nut with bolt 6mm dia -75mm long	kg	50	120	-	-	6,000.00
		Rupees One Hundreds Twenty Only					

Note: All Item Rates are considered to be in Indian Rupees unless otherwise explicitly specified and in which case shall be always converted appropriately to arrive at the amount in Indian Rupees.

Work Order Total	₹ 2,33,52,975.00
Overall Rebate (%)	0
Work Order Value After Overall Rebate in Figure	₹ 2,33,52,975.00
Work Order Value After Overall Rebate in Words	Rupees Two Crore Thirty Three Lakh Fifty Two Thousand Nine Hundreds Seventy Five Only



Signature

Signature Not Verified

Digitally signed by ARUN KUMAR TIWARI
Date: 2025.09.20 10:59:13 IST
Location: eProcurement System for Central PSUs