



न्यूक्लियर पावर कॉर्पोरेशन ऑफ इंडिया लिमिटेड Nuclear Power Corporation of India Ltd.

(भारत सरकार का उद्यम A Government of India Enterprise)


कुडनकुलम न्यूक्लियर पावर प्रोजेक्ट Kudankulam Nuclear Power Project

कुडनकुलम पोस्ट, राधापुरम तालुक, तिरुनेलवेली जिला, तमिलनाडु 627106-
Kudankulam P.O., Radhapuram Taluk, Tirunelveli District, Tamil Nadu – 627 106

वी.पी. विल्सन, मुख्य अभियंता (ईएंडयूस) V P WILSON, Chief Engineer (E&US)

☎ 04637- 282553/249801

ई-मेल E-mail: vpwilson@npcil.co.in



सं .No. एनपीसीआईएल NPCIL/केकेएनपीपी KKNPP/C&MM-WG/2025/एस S/ 988 November, 06, 2025

To

M/s. S.A.V. Constructions,
885, Radhapuram Main Road,
Vadakkankulam,
Tirunelveli District 627116.
Tamil Nadu.
Phone: 04637-232333
Mobile: 9443130652
E-mail: sav_constructions@yahoo.co.in;

Work Order No.	:	300506
Subledger Code	:	S10057
Account Code	:	78203
Charge Code	:	6185

Dear Sirs,

Subject : “WORK ORDER” – reg.

Name of work : Construction of Additional Class Room Buildings to Hindu Middle School, Sangnapuram and St Xavier Middle School, Perumanal at Radhapuram Taluk, Tirunelveli District.

- Ref. 1. E-Tender No. : NPCIL/KKNPP/AD/CSR ACTIVITIES/PT/2025/86
2. Our letter No. : NPCIL/KKNPP/ C&MM-WG/2025/S/846, dated: 09.10.2025 (Asking Rate Clarification reg.)
- 3 Your submission : dated: 13.10.2025 (Submission of Rate Clarification letter reg .)

Please refer to your above cited tender in response to e-TENDER NOTICE No:

NPCIL/KKNPP/AD/CSR ACTIVITIES/PT/2025/86 for the above work, Part-I and Part-II were opened on 09.07.2025 and 22.09.2025 respectively.

1. **BID ACCEPTANCE:**

This is to inform you that the tender submitted by you and modified in subsequent letters referred above has been accepted for and on behalf of Nuclear Power Corporation of India Limited, for the items of work shown in the schedule of quantities and rates covered by the tender for a total value of ₹ 1,57,34,220.00 (**Rupees One Crore Fifty Seven Lakhs Thirty Four Thousand Two Hundred and Twenty only**) inclusive of all applicable taxes, BOCW Cess including Goods and Services Tax (GST).

2. **RATES:**

The rates quoted by the contractor as given in Annexure- 'I' (Schedule of Quantities and rates) are for complete items of work including supply of all materials (unless otherwise specified), consumables, all temporary arrangements, all labours, all taxes (including GST) cess, duties, levies, BOCW cess applicable from time to time and incidental charges as per terms, conditions and specifications mentioned in the tender document will remain firm until the entire period of contract.

Further during execution of the contract due to variation in quantities, if tender structure changes you have agreed to give suitable discount to remain in L1 position as per Rate clarification letter dated 13.10.2025.

3. **EXECUTION OF WORK:**

The work shall be carried out strictly in accordance with the terms and conditions and specifications, drawings stipulated in the tender and also in best workmanlike manner. You shall employ and maintain qualified engineers/supervisors in the job at all times. You shall also bring to the site and employ such machinery and equipments and other materials as are necessary for the satisfactory completion of this work.


4. **CONTRACT PERIOD:**

The work shall be completed in all respects within **12 Months (including monsoon period)** from the date of commencement including Sunday, Holidays and rainy season/days, if any. The date of commencement will be reckoned within 14 days from the date of work order. The time shall be essence of the contract and the work shall be completed as per approved programme of work.

5. **CONTRACT PRICE ADJUSTMENT:**

Contract Price Adjustment is not applicable as per clause No.11.3.3 of Schedule: A of General Conditions of Contract.





6. AUTHORISED OFFICIALS:

You are requested to submit the name of the authorized Representative who will deal with all matters relating to the contract with the power of Attorney in his favour, duly executed on stamped paper of an appropriate value shall be furnished to Engineer-in-charge.

7. LIABILITY FOR DAMAGE AND INSURANCE: (As per clause No.2, Part-I of Special Instructions in Section-III of tender)

You shall provide the following insurance policies in the joint names of the Corporation and the Contractor with insurance cover from the date of commencement of work to the end of the Defects Liability Period. You will be fully responsible for any loss, damage or destruction of NPCIL plant & machineries, property, persons etc.,. Policies submitted should bear the Work Order (WO) number except Group Insurance for which WO number is not mandatory. You shall submit the copies of Insurance policies along with the original policy document to the Engineer-in-charge before the commencement of work.

7.1 Contractor's All Risk(CAR) Policy

You shall take Contractor's All Risk (CAR) Policy for the whole contract value (including GST) including Insurance for Third Party Liability for 10% of the work order value including applicable GST i.e, ₹ 15,73,422.00

7.2 Employees Compensation Policy:

You shall take the Employee's Compensation Policy for employees who are engaged in this work.

7.3 Group Insurance Policy:


In case the employees engaged on this work are already covered under the Group Insurance policy of the Contractor, same shall be acceptable in lieu of employee compensation policy. In such case the proof of employment shall be submitted.

8. TAXES

8.1 Income tax and statutory levy etc. if any, on this contract, as notified by Central/State Govt. from time to time shall be recovered from your running bills as well as final bill for this work in the prescribed manner. You are requested to submit copy of your GST No. & Permanent Account Number to Engineer-in-charge.

8.2 For GST related compliance (including TDS) refer Special Conditions of Contract (SCC) is attached in Section-IV of tender and clause no 11 of Part-2 of Section-I / NIT.





9. ENGINEER-IN-CHARGE:

Shri. G. Madasamy Scientific Officer-F(Civil) will be the Engineer-in-charge for this work. You may make necessary arrangements for commencing the work immediately in consultation with Engineer-in-charge.

10. SECURITY DEPOSIT:

You may please note that security deposit will be ₹ 15,73,422.00 (@ 10% of the contract value). Initially you will have to submit a performance guarantee for ₹ 7,86,711.00 (50% of security deposit) within 30 days after issue of work order. The remaining amount of security deposit of ₹ 7,86,711.00 will be recovered from the RA bill/ final bill at the rate of 6% of each bill amount. Security deposit amount will not bear any interest. Refer clause No.2, page-3 of Section – II for full details of Security deposit and its release. Defect liability period is 12 months from the certified date of completion of the contract as per Schedule: A Clause No.9.1.1 of General Conditions of Contract. Failure of furnishing the performance guarantee within 30 days as stated above shall constitute sufficient grounds for cancellation of the award of work.

11. APPLICABLE LAWS & ACTS:

You shall comply with various provisions of Contract Labour (Regulation & Abolition) Act 1970, and Rules framed there under from time to time. In case the Contract Labour Act does not apply to your organization the Contractor should intimate the Engineer-in-charge of this work accordingly before commencing the work. Further you shall also comply with the provisions of other laws such as Workmen's Compensation Act 1923, Minimum Wages Act 1948, E.P.F. Act, Bonus Act, Gratuity Act, BOCW cess Act and other Labour Laws as applicable to your organisation. In case NPCIL is required to incur any expenses as Principal Employer under the provisions of the various laws, NPCIL shall be entitled to recover the same from you from your bills.


12. LABOUR LICENSE :

If labour license is required to be obtained for the work as per the existing labour laws then the Principal Employer's Certificate required for obtaining Labour License for specified number of workmen proposed to be employed for the work and shall be issued on the request of the Contractor. A request for issue of Principal Employer's Certificate (Form – III) shall be submitted to the Engineer in charge of the work immediately after receipt of work order. You shall ensure the submission of labour license application within 07 days of issue of Form-III.

Ground Floor, Kudankulam Nuclear Power Project, Kudankulam P.O, Radhapuram Taluk, Tirunelveli District, Tamil Nadu and a copy to Engineer In-charge of this work.

Thanking you,

Yours faithfully,



वी.पी. विल्सन (V.P.Wilson)

मुख्य अभियंता (ईएंडयूस) Chief Engineer (E&US)

For and on behalf of
Nuclear Power Corporation of India Ltd

Encl: Schedule of Quantities and Rates – 'I'



NUCLEAR POWER CORPORATION OF INDIA LIMITED
(A Government of India Enterprise)
Kudankulam Nuclear Power Project
Schedule Of Quantities And Rates

Annexure -1

Name of Work: Construction of Additional Class Room Buildings to Hindu Middle School, Sanganapuram and St Xavier Middle School, Perumanal at Radhapuram Taluk, Tirunelveli district.							Agency Name : S.A.V.Constructions	
WO / SOQR Number : 300506							Tender No.:NPCIL/KKNPP/AD/CSR ACTIVITIES/PT/2025/86	
Item No	Item Description	Unit	Quantity	Rate in ₹	Rebate in %	Amount in ₹	Rate in Words	
Schedule : CSR Activities:A(CIVIL)								
1	Earth work excavation by mechanical means(hydraulic excavator) / manual means for foundation, trenches etc., in all types of soils below ground level including shoring, strutting, bailing / pumping of water, leveling, ramming the bottom of excavation, refilling with selected excavated materials in the sides of the foundation in layers, consolidating and disposing off the surplus earth at places as directed with in a lead of 2 Kms all as per drawings and specifications. - up to 1.5m ht	Cu.M	850	150	0.00	127,500.00	Rupees One Hundreds Fifty Only	
2	Providing and laying plain cement concrete 1:3:6, using 40 mm and down graded stone aggregate at all height including mechanical mixing, leveling, compaction, vibrating, finishing smooth the exposed surfaces of concrete, curing etc complete as per drawings and standard specifications.	Cu.M	45	3600	0.00	162,000.00	Rupees Three Thousand Six Hundreds Only	
3	Providing and laying plain cement concrete 1:2:4, using 20 mm and down graded stone aggregate at all height including mechanical mixing, leveling, compaction, vibrating, finishing smooth the exposed surfaces of concrete, curing etc complete as per drawings and standard specifications.	Cu.M	68	4200	0.00	285,600.00	Rupees Four Thousand Two Hundreds Only	
4	Filling in basement with selected earth in layers of not more than 150 mm thick, each layer well rammed, watered and consolidated as per specifications. Selected earth shall be brought from a maximum lead of 2 km with in the Site.	Cu.M	310	100	0.00	31,000.00	Rupees One Hundreds Only	
5	Providing Pre-construction anti-termite treatment using chlorpyrifos emulsifiable concentrate 20 % with 1 % concentration as per specifications. Note: The contractor shall furnish from the agency carrying out this work under this item a written guarantee in favour of NPCIL for the satisfactory performance of the treatment for a period of ten years.	SqM	400	100	0.00	40,000.00	Rupees One Hundreds Only	
6	Construction of granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by tippers to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge. With material conforming to Grade-I (size range 75 mm to 0.075 mm) having CBR Value-30, as per clause 401 of MORT & H specifications complete in all respects.	Cu.M	78	900	0.00	70,200.00	Rupees Nine Hundreds Only	

a. w. m. y

[Signature]

Name of Work: Construction of Additional Class Room Buildings to Hindu Middle School, Sanganapuram and St Xavier Middle School, Perumanal at Radhapuram Taluk, Tirunelveli district.

WO / SOQR Number : 300506

Tender No.:NPCIL/KKNPP/AD/CSR ACTIVITIES/PT/2025/86

Agency Name : S.A.V.Constructions

Item No	Item Description	Unit	Quantity	Rate in ₹	Rebate in %	Amount in ₹
		Rate in Words				
15	Supplying, manufacturing and Fixing frames and architraves for windows, ventilators, cupboards etc., with approved quality Malaysian Vengai wood of required sizes fixed in masonry/concrete with three numbers of MS holdfasts of size 40mm width x 5mm thick & 300 mm long on each side of the frame or providing fischer screws of required length for column portions wherever required all as directed, for the various sizes of structural openings including making necessary rebate/stopper for Fixing shutters as per drawings and specifications	Cu.M	4.4	100000	0.00	440,000.00
				Rupees One Lakh Only		
16	Supplying and fixing of Flush Doors of Solid core type conforming to IS : 2202, 35 mm thick single leaf manufactured from BORON based chemically treated and vacuum seasoned WOOD, core is framed in treated and seasoned wooden battens and strengthened by a layer of cross-bands, face veneers encompass both sides of the core, bonded with phenol formaldehyde resin and permanent type preservatives, under the cross-bonding process and internally lipped with treated wood for various structural openings including providing and fixing of fixtures and fittings as per relevant IS such as Aluminium D handles 150mm 2 Nos, 300mm long 16mm dia Aluminium Aldrop 1 No, 300mm long tower bolt 1 No, 150mm long tower bolt 1 No, Magnetic Catcher 1 No etc and fixing the Flush door with the hinges provided in the door frame all as per the drawings and specifications.	SqM	49	2200	0.00	107,800.00
				Rupees Two Thousand Two Hundreds Only		
17	Providing and Fixing window/ventilator shutters made of 70 x 30 mm size frames with approved quality Malaysian Vengai wood for shutter frame and shutters using 18mm thick approved quality Malaysian Vengai wood boards with required designs etc including cost of fixtures and fittings as per relevant IS etc., complete.(Aluminium tower bolts 100mm 2Nos., Aluminium Handle 75mm 1No,200 mm Aluminium peg stay 1No, SS hinges 100mm long-2 Nos per shutter are to be provided)	SqM	56	4000	0.00	224,000.00
				Rupees Four Thousand Only		
18	Providing, fabricating and erection of Structural steel members made out of M.S. angles, flats, plates, pipes, channels, tubes, rods etc conforming to relevant IS etc., including cost of welding, welding rods, drilling holes, bolts/nuts wherever required and providing and applying two or more coats of approved quality synthetic enamel paint over a coat of zinc chromate yellow primer etc., as per drawings and specifications	MT	2.95	85000	0.00	250,750.00
				Rupees Eighty Five Thousand Only		
19	Providing and applying Acrylic Emulsion paint of Asian paints (Premium Emulsion)/Lewis Berger (Rangoli) /ICI Dulux (Super smooth)/NIPPON (Matex Gold) make of approved shade in two or more coats over a coat of primer including preparation of surface with required coats of putty using Birla/ JK make, sand papering etc., to get good finish at all elevations etc all as per as per drawings and specifications	Sq.M	1720	175	0.00	301,000.00
				Rupees One Hundreds Seventy Five Only		
20	Providing and applying Exterior Emulsion Paint of Apex of Asian paints/Weather cote of Lewis Berger /Weather shield of ICI Dulux/NIPPON/NEROLAC make & shade in two or more coats to give an even shade over a coat of primer as per manufacturer's instructions to the external plastered surfaces including preparation of surfaces, scaffolding etc. at all elevations, complete as per drawings and specifications	Sq.M	2720	150	0.00	408,000.00
				Rupees One Hundreds Fifty Only		

[Handwritten Signature]

[Handwritten Signature]



Name of Work: Construction of Additional Class Room Buildings to Hindu Middle School, Sanganapuram and St Xavier Middle School, Perumanal at Radhapuram Taluk, Tirunelveli district.

WO / SOQR Number : 300506 Tender No.:NPCIL/KKNPP/AD/CSR ACTIVITIES/PT/2025/86 Agency Name : S.A.V.Constructions

Item No	Item Description	Unit	Quantity	Rate in ₹	Rebate in %	Amount in ₹
				Rate in Words		
21	Providing and applying two coats of First Quality synthetic enamel paint of Asian paints/ Lewis Berger/ ICI Dulux/NIPPON (Sumo Xtra) make of approved colour over a coat of primer on new wood / steel work, suitably prepared for receiving the paint by surface scraping, rubbing applying filler etc., including cost of filler primer, paint etc all complete as per drawings and specifications	Sq.M	503.635	150	0.00	75,545.25
			Rupees One Hundreds Fifty Only			
22	Providing, Fixing and testing PVC rain water pipes of 110 mm dia as per IS-13592 of Type A of "Prince/Jain/ Kitec/Finolex/Supreme" make with necessary fittings and fixtures, such as bottom shoe, PVC grating, GI clamps, screws/nails, wooden packing pieces at minimum 1 m spacing, cost inclusive of Fixing the shoes in brick masonry in CM 1:6 and plastering the same with CM 1:4 etc complete all as per drawings and specifications	RM	54	250	0.00	13,500.00
			Rupees Two Hundreds Fifty Only			
23	Providing and laying 20mm thick (+-2mm) polished Natural granite slab of approved colour as below, for platform/flooring/wall cladding and other surfaces as directed with all exposed surfaces buffed, making half/full round nosing, set over a base of cement mortar 1:4, 20 mm thick neatly pointed with white cement and colouring pigments to match the shade of the stone as per the requirement, curing, rubbing, polishing, etc complete as per drawings and specifications				0.00	
23.1	Granite Slab : Sadarhalli	SqM	750	2000	0.00	1,500,000.00
			Rupees Two Thousand Only			
24	Providing and laying 20mm thick (+-2mm) polished Natural granite slab of approved colour for name board including writing by engraving, painting etc. as per required etc., with all exposed surfaces buffed, set over a base of cement mortar 1:4, 20 mm thick neatly pointed with white cement/black oxide and colouring pigments to match the shade of the stone as per the requirement, curing, rubbing, polishing, etc complete as per specifications and as per drawings and specifications	SqM	5.5	10000	0.00	55,000.00
			Rupees Ten Thousand Only			
25	Providing and Fixing 20mm thick Exterior grade designer tiles of approved colour and design over 20mm thick base cement mortar 1:4 laid and pointed with white cement slurry mixed with pigments to match with the shade of the tile including rubbing, curing, in Staircases (both tread & riser), Walkway areas, Entrances etc., as per drawings and specifications	SqM	37	900	0.00	33,300.00
			Rupees Nine Hundreds Only			
26	Providing and making RCC roof mother slab/sunken slab water proof by injection grout with the approved compound of SIKABASF/OFF/FOSROC/ Dr.Fixit/ Bostic India make as per the manufacturers procedure/ specification by providing one water proofing membrane system by brush application as water proofing barrier for both slab and inner face of parapet/side wall including water testing by ponding for minimum 7 days and providing joint guarantee for water tightness for 10 years (This item may be got executed by specialized water proofing agents duly approved by NPCIL and 10 years joint guarantee for water proofing is required to be submitted).	SqM	425	400	0.00	170,000.00
			Rupees Four Hundreds Only			

G. V. m

Ch



Name of Work: Construction of Additional Class Room Buildings to Hindu Middle School, Sanganapuram and St Xavier Middle School, Perumanal at Radhapuram Taluk, Tirunelveli district.

WO / SOQR Number : 300506 Tender No.:NPCIL/KKNPP/AD/CSR ACTIVITIES/PT/2025/86 Agency Name : S.A.V.Constructions

Item No	Item Description	Unit	Quantity	Rate in ₹	Rebate in %	Amount in ₹
				Rate in Words		
27	Supply and laying one course of pressed cement tiles 20 mm thick of 250mmX250mm size as per IS:1237 of latest version, laid over the roof slab over a base of 20mm thick CM 1:4 and joints pointed neatly in cement mortar 1:3 mixed with water proofing admixture of approved make etc complete all as per drawings and specifications	SqM	400	650	0.00	260,000.00
			Rupees Six Hundreds Fifty Only			
28	Providing drip moulds of CM 1:4, 25mm thick on edges of sunshades including finishing, curing, scaffolding etc complete as per the standard specifications.	SqM	460	80	0.00	36,800.00
			Rupees Eighty Only			
29	Providing Rain water harvesting pit as per the drawing.	Cu.M	2	1700	0.00	3,400.00
			Rupees One Thousand Seven Hundreds Only			
30	Providing and fixing Terracotta jally of 75mm thick of approved size and pattern including chasing the masonry/concrete if required and fixing with CM 1:3 true to line and plumb & making good the surfaces, curing etc. at all elevations, complete all as per drawings and specifications	SqM	10	600	0.00	6,000.00
			Rupees Six Hundreds Only			
31	Providing and laying M30 grade 60 mm thick coloured interlocking precast concrete pavers blocks as per relevant IS of approved shape over a profiled layer to the required line, pattern etc., all as per drawings and specifications	SqM	1100	475	0.00	522,500.00
			Rupees Four Hundreds Seventy Five Only			
32	Providing and filling /spreading Crusher sand 30mm thick (compacted thickness) for preparation of base to lay interlocking precast concrete paver blocks including, leveling, placing, to the required slope, compacting with roller etc complete as per drawings and specifications. (Payment shall be made only for compacted thickness)	Cu.M	115	625	0.00	71,875.00
			Rupees Six Hundreds Twenty Five Only			
Schedule : CSR Activities:B(ELECT						
1	LDB : Supply and erection of 12 way single phase distribution board complete with interconnection Copper busbar, Neutral bar, Earth bar, top and bottom removable gland plates with knockout, and double door with the following 25A 2P RCCB (30 mA) - 1 no, 20A/16A/6A SP MCB - 10 Nos(Make:Legrand/havells) Scope includes construction of pedestal cubicle and supply of necessary electrical components, hardwares for fixing the panel etc. to complete the work in all respect.	SET	4	9000	0.00	36,000.00
			Rupees Nine Thousand Only			
2	PRIMARY WIRING:- For lighting, bulkhead fitting and exhaust fan points, supply and wiring for point with two + one (earth-green) runs of 1.5sq.mm (22/0.3)1100V grade FRLS insulated single core multi strand Copper conductor wire (without joint) drawn into the existing PVC conduit (inclusive of supplying and laying of PVC conduits while concreting), complete with angle / batten lamp holder or ceiling rose, 5 Amps modular type Legrand Mylinc/ MK India /Schneider make switch including pulling the wire from existing switch box to lighting point through the conduit and connecting at both ends.(The box, grid plate and the cover plate for the switch has been covered elsewhere.). All items such as 1.5sq.mm (22/0.3) Copper FRLS insulated wire(make:polycab/finolex,Havells), 6 Amps switch, 3 Plate ceiling rose, hylam sheet for JB's, necessary electrical components for wiring works (wherever applicable) shall be supplied by the contractor as per the requirement, specification	Point	45	1700	0.00	76,500.00
			Rupees One Thousand Seven Hundreds Only			


Name of Work: Construction of Additional Class Room Buildings to Hindu Middle School, Sanganapuram and St Xavier Middle School, Perumanal at Radhapuram Taluk, Tirunelveli district.

WO / SOQR Number : 300506
Tender No.:NPCIL/KKNPP/AD/CSR ACTIVITIES/PT/2025/86
Agency Name : S.A.V.Constructions

Item No	Item Description	Unit	Quantity	Rate in ₹	Rebate in %	Amount in ₹
				Rate in Words		
3	SECONDARY WIRING :- For lighting, 6A sockets supply and wiring for point with two + one (earth-green) runs of 1.5sq.mm (22/0.3)1100V grade FRLS insulated single core multi strand Copper conductor wire (without joint) drawn into the existing PVC conduit (inclusive of supplying and laying of PVC conduits while concreting), complete with angle / batten lamp holder or ceiling rose, 5 Amps modular type Legrand Mylinc/ MK India /Schneider make switch including pulling the wire from existing switch box to lighting point through the conduit and connecting at both ends.(The box, grid plate and the cover plate for the switch has been covered elsewhere.). All items such as 1.5sq.mm (22/0.3) Copper FRLS insulated wire(Make:Polycab/finolex/Havells), 6 Amps switch, 3 Plate ceiling rose, hylam sheet for JB's, necessary electrical components for wiring works (wherever applicable) shall be supplied by the contractor as per the site requirement.	Point	55	1400	0.00	77,000.00
			Rupees One Thousand Four Hundreds Only			
4	Fan control Primary point wiring: Primary point wiring for fan control including fixing of 6A switch,400W modular step type regulator,ceiling rose,wiring from switch to ceiling rose etc. (Make:Legrand Mylinc/ MK India /Schneider)	point	55	2200	0.00	121,000.00
			Rupees Two Thousand Two Hundreds Only			
5	Power point wiring : 16A Power switch & sockets (2 switches+2 sockets in switch board) in seprate switchboard: Supply, installation of 16A, 5 pin socket & switch outlet including supply of 16A 5 pin socket and SP switch modular type. Legrand Mylinc/ MK India /Schneider/Anchor panasonic/GM make (switch & socket separate type). One end of the earthing wire to be connected at the third pin of 16A socket and the another end to be connected at the earth bar in the Distribution Board. Scope includes supply of modular socket and switch, 4 module GI box with base ,cover plate and accessories with point wiring of 3 runs of 4 sq.mm copper wire for 16A-6A , 6 in 1 socket .	Nos	11	2700	0.00	29,700.00
			Rupees Two Thousand Seven Hundreds Only			
6	DB to Switch Board wiring :Supply, installation and wiring(Make:Polycab/finolex,Havells) of 3R x 4sqmm Cu for FRLS insulated each core multistrand with 1100V Copper wire, drawn into the existing PVC conduit (inclusive of supplying and laying of PVC conduits while concreting) from MCB DB to various switch boards as circuit mains and switch board to switch board looping. The termination shall be done by using crimping type Copper lugs of Dowells make, suitable modular type switch box supply by contractor scope.	RM	150	600	0.00	90,000.00
			Rupees Six Hundreds Only			
7	EARTH PIT :Supply and installation of Earthing with copper earth plate 600 mm X 3 mm thick, including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 metre long etc. with charcoal/ coke and salt as required.	Nos	3	12000	0.00	36,000.00
			Rupees Twelve Thousand Only			
8	EARTHING : Supplying, laying & Termination with suitable legs connector,clamp 25 mm X 5 mm copper strip at 0.50 metre below ground as strip earth electrode, including connection/ terminating with nut, bolt, spring, washer etc. as required. (Jointing shall be done by overlapping and with 2 sets of brass nut bolt & spring washer spaced at 50mm)	RM	30	650	0.00	19,500.00
			Rupees Six Hundreds Fifty Only			
9	Tube light LED: Supply and installation of LED tube light fitting 230V, 20W. (Make:Havells/Crompton/Philips)	Nos	66	700	0.00	46,200.00
			Rupees Seven Hundreds Only			

John L.

Q. W. T.



5. Wavy line



WO / SOQR Number : 300506

Agency Name : S.A.V.Constructions

Rupees Ten Thousand Five Hundreds Only

trans

Adhikari

Note:: All Item Rates are considered to be in Indian Rupees unless otherwise explicitly specified and in which case shall be always converted appropriately to arrive at the amount in Indian Rupees.

Work Order Total	₹15734220.25
Overall Rebate (%)	0
Work Order Value After Overall Rebate (in Figure)	₹15734220
Final Work Order Value (in Figure)	₹15734220
Final Work Order Value (in words)	Rupees One Crore Fifty Seven Lakh Thirty Four Thousand Two Hundreds Twenty Only

G.V. Vignesh
06/11/2025

(Signature)

Signature Not Verified

Digitally signed by RAJESHKUMAR
GANGADHARAN PILLAI
Date: 2025.11.07 12:48:07 IST
Location: eProcurement System for Central
PSUs