



न्यूक्लियर पावर कॉर्पोरेशन ऑफ इंडिया लिमिटेड



Nuclear Power Corporation of India Limited

(भारत सरकार का उद्यम Government of India Enterprise)

कैगा स्थल KAIGA SITE

C & MM-(WORKS GROUP) सी एंड एमएम (वर्क्स ग्रुप)

Corporate Identification No. U40104MH1987GOI149458

Phone: +91 8382 264002

Fax: +91 8382 264025

E-mail: sdileep@npcil.co.in

Website: www.npcil.nic.in

Ref: NPCIL/KAIGA/C&MM-WG/WO/2026/1239

Date: 24-01-2026.

Work Order

To:

M/S RAVI S HALAGATTI

Kadra Karwar

Pin-581396

Tq. Karwar

Dist. Uttar Kannada

Kind Atten: Shri Ravi S Halagatti

Mobile No.: 9448250384

E-mail: rshalagatti@gmail.com

Work Order Fais No.	:	600016
S.L. Code	:	R0065600016
Account Code	:	78205
Charge Code	:	9953
MSME Category	:	NA
MSME Reg. No.	:	NA

WORK ORDER NO.: 2025_NPCIL_254408_1/013/WO

Sub: Construction of Toilet blocks at Nage, Gotegali, Kurnipet, Nelapal and Vajaralli villages of Karwar and Yellapur Talukas.

Ref: 1) TENDER ID: 2025_NPCIL_254408_1

2) TENDER NO.: NPCIL/KGS/CTC/CSR/CPPP/2025/103

3) Last date of submission of tender is 27.11.2025.

Dear Sir,

1) Bid Acceptance:

This is to inform you that, the bid submitted by you as referred above has been accepted for and on behalf of NPCIL, for the items of work shown in the enclosed schedule of quantities and rates for a total value of Rs. 35,64,400.00 (Rupees Thirty Five Lakhs Sixty Four Thousand Four Hundred Only) inclusive of all applicable taxes and including 18% GST.

पंजीकृत कार्यालय 16 : वी तलसेंटर , -1, वर्ल्ड ट्रेड सेंटर. 400005-मुम्बई , कोलाबा , कफे पारेड ,

Registered Office: 16th Floor, Centre-1, World Trade Centre, Cuffe Parade, Colaba, Mumbai-400005.

Page 1 of 6

A. NP

WORK ORDER NO.: 2025_NPCIL_254408_1/013/WO

2) QUANTITIES & RATES:

You may note that the rates are for complete items of work including supply of all materials (unless otherwise specified), consumables, all temporary arrangements, all labours, all prevailing duties, taxes including GST.

3) CONTRACT PRICE ADJUSTMENT:

Escalation of payment shall be applicable as per GCC Clause no. 11.3, Sl. No. 21 of Schedule-A & Other conditions of this contract.

4) EXECUTION OF WORK:

The work shall be carried out strictly in accordance with the terms, conditions, specifications and drawings stipulated in the tender and also in best workmanlike manner. You shall employ and maintain qualified engineers / supervisors in the job at all times. You shall also bring to the site and employ such machinery and equipment and other materials as are necessary for the satisfactory completion of this work.

5) CONTRACT PERIOD:

5.1 Schedule completion Period:

The work shall be completed in all respect within **365 Calendar Days** (including monsoon period) from the date of commencement. **The date of commencement of work will be reckoned within seven (07) days from the date of issue of Work Order.** The time shall be essence of the contract and the work shall be completed as per approved program of work.

5.2 Defect Liability Period:

The Defect Liability Period as per Para 9.1.1 of Schedule-A of Tender is **12 Months**.

6) AUTHORISED OFFICIALS:

6.1 You are requested to inform the name of the authorized representative who will deal with all matter relating to the contract and the Power of Attorney in his favour duly executed on stamped paper of an appropriate value shall be furnished.

6.2 During the execution of the contract and until completion certificate is issued you will be fully liable to compensate all concerned for any loss, damage or destruction of work, structure, property etc. including third party risk arising due to causes



WORK ORDER NO.: 2025_NPCIL_254408_1/013/WO

attributable to you which will be decided by the Engineer-in-charge whose decision in this regard will be final.

7) INSURANCE:

You are required to take out following insurance policies applicable to this contract at your cost immediately after receipt of this work order from the date of commencement of work to the end of the Defect Liability Period for whole contract value Inclusive of GST.

- a) CAR policy for the whole contract value.
- b) The Insurance amount should cover THIRD PARTY LIABILITY to 10% of Contract value subject to a maximum of Rs. 50 lakhs.
- c) Employees State Insurances for contract workers.
- d) Wherever ESI Act not covers the contract worker based on monthly wage/ salary, contractor shall obtain the employees/ Workmen compensation for such workers.

You may note that all insurance policies taken under 7 (a), (b) & (d) are to be in Joint names of Corporation and the contractor and specific to work by mentioning the name of work and work order Number in the policies and all Policies in Original should be submitted to the Engineer-in-charge before the date of commencement of work. Copy of ESI registration certificate shall be submitted to EIC before commencement of the work.

8) TAXES & DUTIES:

For tax related compliance (including TDS) refer Contract document, GCC and Special Conditions of Contract (SCC).

9) ENGINEER-IN-CHARGE:

Shri Sainath G. Naik, SO/F (CSR), will be the Engineer-in-Charge of this work. You may make necessary arrangements for commencing the work immediately in consultation with Engineer-in-Charge.

10) SECURITY DEPOSIT:

Security Deposit shall be @ 10% of the contract value including GST will be **₹ 3,56,440/- (Rupees Three Lakh Fifty Six Thousand Four Hundred Forty Only)** and shall be governed as per clause no.4.2 of GCC and as per the relevant orders issued by Govt. of India.



WORK ORDER NO.: 2025_NPCIL_254408_1/013/WO

10.1 PERFORMANCE GUARANTEE:

As per clause No.4.2.3 of GCC you shall submit a performance guarantee for ₹ 1,78,220/- (50% of Security Deposit) to the Corporation within 30 days after issue of work order. It should cover the contract period plus defect liability period. In case bank guarantee is submitted it shall be as per the format given in the tender document.

10.2 RETENTION MONEY:

As per clause No.4.2.5 of GCC, the remaining amount (50% of Security Deposit) of Security Deposit of ₹ 1,78,220/- /- will be deducted as a Retention money from the RA bill/final bill at the rate of 6% of each bill amount. Security Deposit amount will not bear any interest.

10.3 REFUND OF SECURITY DEPOSIT:

Refund of Security deposit will be regularized as per clause no. 4.3 of General Condition of Contract.

11) APPLICABLE LAWS & ACTS:

11.1 You shall comply with various provisions of the contract labour (Regulations & Abolition) Act 1970 and rules framed thereafter from time to time. In case, the Contract Labour Act does not apply to your organization you should intimate the Engineer-In-Charge of this work accordingly before commencing the work. Further you shall also comply with the provisions of other laws such as Workmen's Compensation Act 1923, Minimum Wages Act 1948, E.P.F. Act, ESI Act, Gratuity Act and other labor laws as applicable to your organization. In case, NPCIL is required to incur any expenses as principal employer under the provisions of the various laws, NPC shall be entitled to recover the same from you/your bills.

11.2 You have to give request for the issue of Principal Employer's Certificate for obtaining labour license based on the maximum number of workmen you proposed to employ for this work. You may please note that within 14 days from the date of issue of this work order, you will have to apply for a labour license to the Asstt. Labour Commissioner, of the area, for the maximum number of workers you had indicated to engage on the work.

11.3 The contractor shall make the payment to all its labours on or before 7th of succeeding month and as defined in special condition of contract.

WORK ORDER NO.: 2025_NPCIL_254408_1/013/WO

11. 4 Labour License (if applicable),

12) PAYMENT TERMS:

12.1 The progressive monthly payment for the work completed and accepted by Engineer-In-Charge shall be made through Running Account bills once in a month as per clause No:12.2 of GCC on submission of measurement / bill by the contractor. Submission of bills on monthly basis shall be ensured by the Contractor.

12.2 Payment of bills will be processed on submission of GST Invoice duly supported with Annexure-8 (Declaration Form for GST).

12.3 In addition to above, first Running Account bill will be processed only on Intimation from Tender Section regarding Work order acceptance & agreement signed by the contractor and submission of Insurance Policies, Copy of PAN, GST Registration certificate and cancelled cheque for Bank Account details to the Engineer-In-Charge.

13) PENALTY & LIQUIDATED DAMAGES CLAUSE:

Penalties imposed by Engineer In-charge for non-compliance or violation of certain conditions of contract, Liquidated Damages for delay in execution and any other penalty in the nature of fine imposed during execution of work will be recovered along with applicable GST there on from bills of the contractor before release of payment.

14) SECURITY, SAFETY & HOUSEKEEPING:

You may have to comply all Security, Safety rules & regulations, Environmental measure as defined in the Contract.

15) TRANSPORT & ACCOMMODATION:

Contractor shall make his own arrangement for Accommodation & Transportation of manpower deployed for this work.



WORK ORDER NO.: 2025_NPCIL_254408_1/013/WO


16) AGREEMENT:

A formal agreement incorporating all the terms and conditions agreed between NPCIL and **M/S RAVI S HALAGATTI** will be executed as per Clause No 21.3 of Tender document and as defined in the special condition of contract from the date of issue of this work order. Till a formal agreement is executed the original tender together with letters under reference and this work order shall form the binding contract between NPCIL and **M/S RAVI S HALAGATTI**.

Kindly acknowledge receipt of this Work Order.

Thanking you,

Yours faithfully
For and on behalf of NPCIL


(Vishweshwar)
SO/F (CTC), Kaiga Site

Encl: Schedule of quantities and rates.



Print Date: 23-Jan-2026

Co Name of Work: Construction of Toilet blocks at Nage, Gotegali, Kurnipet, Nelapal and Vajaralli villages of Karwar and Yellapur Talukas
 WO / SOQR Number : 600016 Agency Name : M/s RAVI S HALAGATI

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹
Rate in Words							
Schedule : CSR:NA							
1	Earth work excavation for Foundation by mechanical means for all works & depth upto 3 m, as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, including dressing of excavated surfaces, disposing off or levelling the excavated earth or sorting & stacking the selected earth for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools, usage of machinery & other appurtenances required to complete the work. In all kinds of soils Depth upto 3 m	CuM	100	150	-	-	15,000.00
				Rupees One Hundreds Fifty Only			
2	Earth work excavation for Foundation by mechanical means for all works & depth upto 3 m, as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, including dressing of excavated surfaces, disposing off or levelling the excavated earth or sorting & stacking the selected earth for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools, usage of machinery & other appurtenances required to complete the work. soft rock without blasting upto 1.5 m depth	CuM	25	400	-	-	10,000.00
				Rupees Four Hundreds Only			
3	Providing and laying in position Cement Concrete for leveling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machinery, curing, and all the other appurtenances required to complete the work as per technical specifications. Mix 1:3:6 Using 20 mm and down size graded crushed coarse aggregates.	CuM	35	8000	-	-	2,80,000.00
				Rupees Eight Thousand Only			
4	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations and other similar works etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering as directed by Engineer-In-charge.	CuM	30	280	-	-	8,400.00
				Rupees Two Hundreds Eighty Only			
5	Filling approved earth (excluding rock) in trenches, plinth, sides of foundations and other similar works etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering and as directed by Engineer-In-charge.	CuM	30	480	-	-	14,400.00
				Rupees Four Hundreds Eighty Only			
6	Providing and laying 65 to 100mm size granite soling stones of approved quality & size for flooring base including preparation of base properly by leveling dressing & hand ramming using hand rammer with watering, providing & filling interstices using small sized stones / chips, providing & spreading binding materials such as murrum / gravel with proper watering, collecting & disposing the generated waste, from the place of work & cleaning the work area, etc. complete all as per standard technical specification, drawing and as directed by Engineer-in-charge at all locations & lifts.	CuM	15	3000	-	-	45,000.00
				Rupees Three Thousand Only			
7	Providing and constructing load bearing wall with Solid Concrete blocks of size 400x200x200mm having block density more than 1800kg/m3 and minimum compressive strength of 4.00 N/mm2 conforming to IS 2185 (Part - I) - 2005 and constructed with CM 1:4 as per IS 2572:2005 including cost of all materials, labour, scaffolding and curing, usage charges of machinery etc complete as per specifications.	CuM	85	8500	-	-	7,22,500.00
				Rupees Eight Thousand Five Hundreds Only			
8	Providing Brick work with common burnt clay Non Modular bricks of class designation 3.5 in superstructure above plinth level in all shapes and sizes in Cement mortar 1:6 (1 cement : 6 coarse sand) including cost of all materials, labour, scaffolding and usage charges of machinery & other incidental charges complete as per the direction of engineer incharge of work.	CuM	55	9800	-	-	5,39,000.00
				Rupees Nine Thousand Eight Hundreds Only			

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹
		Rate in Words					
9	Providing Half brick masonry with common burnt clay Non Modular bricks of class designation 3.5 in superstructure above plinth level up to floor 1 level cement mortar 1:4 (1 cement :4 coarse sand) including cost of all materials, labour, scaffolding and usage charges of machinery & other incidental charges complete as per the direction of engineer in-charge of work.	SqM	60	1500	-	-	90,000.00
			Rupees One Thousand Five Hundreds Only				
10	Providing 15 mm cement plaster on the rough side of single or half brick wall of mix 1:1:5 (1 cement: 5 fine sand) including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and as per directions of Engineer-in-charge.	SqM	425	350	-	-	1,48,750.00
			Rupees Three Hundreds Fifty Only				
11	Providing 18 mm cement plaster in two coats under layer 12 mm thick cement plaster with cement mortar 1:5 (1 cement : 5 coarse sand) finished with a top layer 6 mm thick cement plaster with cement mortar 1:4 (1 cement : 4 fine sand) to brick masonry including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and as per directions of Engineer-in-charge.	SqM	250	425	-	-	1,06,250.00
			Rupees Four Hundreds Twenty Five Only				
12	Providing and fixing Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Hot finished welded type tubes including cost of materials, labour, usage charges of machinery complete as per specifications and as per directions of the Engineer-in-Charge.	Kg	2500	150	-	-	3,75,000.00
			Rupees One Hundreds Fifty Only				
13	Providing and fixing Structural Steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete including cost of materials, labour, usage charges of machinery complete as per specifications and as per directions of the Engineer-in- Charge.	Kg	200	130	-	-	26,000.00
			Rupees One Hundreds Thirty Only				
14	Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer) of 1st quality conforming to IS : 15622 of approved make in colours such as White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick cement mortar 1:4 (1 Cement : 4 Coarse sand), Jointing with grey cement slurry @ 3.3 kg/m2 including pointing the joints with white cement and matching pigment etc., complete.	SqM	100	1500	-	-	1,50,000.00
			Rupees One Thousand Five Hundreds Only				
15	Applying priming coats with primer of approved brand and manufacture, having low VOC (Volatile Organic Compound) content. With water thinnable cement primer on wall surface having VOC content less than 50 g/L as per specifications and as per directions of Engineer in charge.	SqM	425	60	-	-	25,500.00
			Rupees Sixty Only				
16	Wall painting with acrylic emulsion paint, having VOC (Volatile Organic Compound) content less than 50 g/L, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour. Two coats as per specifications and as per directions of Engineer in charge.	SqM	425	110	-	-	46,750.00
			Rupees One Hundreds Ten Only				
17	Finishing walls with Premium Acrylic Smooth exterior paint with Silicone additives with pure Acrylic Resin, UV resistant, dirt & pick up resistant, Alkali & Water resistant of required shade. New work (Two coats applied @ 1.43 L/10 m² over and including priming coat of exterior primer applied @ 2.20 kg/10 m²) with paint of approved quality to give an even shade, after thoroughly brooming the surface to remove all dirt, dust, mortar drops and foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge.	SqM	250	190	-	-	47,500.00
			Rupees One Hundreds Ninety Only				

Handwritten signature/initials

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹
				Rate in Words			
18	Providing and fixing pre-coated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 g/m ² as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 m or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling/self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	Sqm	250	725	-	-	1,81,250.00
			Rupees Seven Hundredrs Twenty Five Only				
19	Providing and fixing mirror polished Inaugural board of Lacared granite stone of 18 to 20 mm thickness in approved size & shape and quality printed with Computerized Script & "NPCIL LOGO" etc., Inaugural board shall be fixed firmly on the surface of the structure as directed including preparation of base, providing; fixing & removing necessary staging / platform, collecting & disposing the generated waste from the place of work & cleaning the work area, etc. complete all as per standard technical specification, drawing, as per site requirement and as directed by Engineer-in-charge at all locations & heights.	Sqm	2	20000	-	-	40,000.00
			Rupees Twenty Thousand Only				
20	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require: White Vitreous China Flat back wash basin size 550x 400 mm with single 15 mm C.P. brass pillar tap	Each	10	3000	-	-	30,000.00
			Rupees Three Thousand Only				
21	Providing and fixing water closet squatting pan (Indian type W.C. pan) with 100 mm sand cast iron P or S trap, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required: White Vitreous china Orissa pattern W.C. pan of size 580x440 mm with integral type foot rests.	Each	15	6000	-	-	90,000.00
			Rupees Six Thousand Only				
22	Providing and fixing 15 NB, Brass, Clutch Head, Bib tap weight of each shall not be less than 600 grams with all its required accessories and ensuring smooth functioning including providing; fixing & removing necessary staging / platform, collecting and disposing the generated waste & cleaning the work area etc., complete all as per standard technical specification, manufacturer's technical specification and as directed by the Engineer-in-charge at all locations and at all lifts / heights.	Each	25	400	-	-	10,000.00
			Rupees Four Hundreds Only				
23	Providing and fixing 15 NB, "Stop Cock" weight of each shall not be less than 450 grams. with all its required accessories and ensuring smooth functioning including providing; fixing & removing necessary staging / platform, collecting and disposing the generated waste & cleaning the work area etc., complete all as per standard technical specification and as directed by the Engineer-in-charge at all locations and at all lifts / heights.	Each	25	400	-	-	10,000.00
			Rupees Four Hundreds Only				
24	Providing and fixing ball valve (brass) of approved quality, High or low pressure, with plastic floats complete : 25 mm dia Ball Valves	Each	5	450	-	-	2,250.00
			Rupees Four Hundredrs Fifty Only				
25	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, IS : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank.	Ltr	1000	13	-	-	13,000.00
			Rupees Thirteen Only				
26	Providing and fixing Unplasticised Polyvinyl Chloride (uPVC) pipes, for cold water supply including all uPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step uPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. External work						-
26.1	15 mm	RM	75	200	-	-	15,000.00
			Rupees Two Hundredrs Only				

ABC

C0

Name of Work: Construction of Toilet blocks at Nage, Gote gali, Kurnipet, Nelapal and Vajaralli villages of Karwar and Yellapur Talukas

Agency Name : M/s RAVI S HALAGATI

WO / SOQR Number : 600016

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹
		Rate in Words					
26.2	20 mm	RM	100	200	-	-	20,000.00
				Rupees Two Hundreds Only			
26.3	25 mm	RM	125	250	-	-	31,250.00
				Rupees Two Hundreds Fifty Only			
27	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. Concealed work, including cutting chases and making good the walls etc.			-	-	-	-
27.1	15 mm	RM	75	400	-	-	30,000.00
				Rupees Four Hundreds Only			
27.2	20 mm	RM	100	500	-	-	50,000.00
				Rupees Five Hundreds Only			
27.3	25 mm	RM	125	600	-	-	75,000.00
				Rupees Six Hundreds Only			
28	Providing and fixing Sewer PVC (SWR) pipes, including all fittings. This includes jointing of pipes & fittings with one step solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge.			-	-	-	-
28.1	75mm nominal dia pipes	RM	25	400	-	-	10,000.00
				Rupees Four Hundreds Only			
28.2	110mm nominal dia pipes	RM	25	500	-	-	12,500.00
				Rupees Five Hundreds Only			
29	Providing and fixing 600x450 mm beveled edge mirror of superior glass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete.	Each	10	1500	-	-	15,000.00
				Rupees One Thousand Five Hundreds Only			
30	Providing and fixing PVC (S.W.R) Nahani Trap 10cms x 10cms with all fitting arrangements & all necessary accessories complete	Each	10	300	-	-	3,000.00
				Rupees Three Hundreds Only			
31	Providing and fixing NP2 Class, Pre-Cast RCC, Septic Tank of size 2.50 meter long & 1.20 meter outer dia., including necessary excavation [Size of pit shall be 3.50 metre (L) X 2.20 meter (W) X 1.80 meter (D)] in all sorts of soil, including laying bed PCC 1:4:8 of 100 mm thick using 40 mm down size stone aggregates at bottom of Precast RCC Septic Tank including loading, carriage, unloading, lowering [without damaging the RCC Septic Tank] in the pit, aligning [to true line & level / slope etc.], finishing smooth, ensuring smooth functioning & back filling the sides [as directed] etc., providing, fixing & removing necessary staging / platform, collecting and disposing the generated waste & cleaning the work area etc., complete all as per standard technical specification, manufacturer's technical specification and as directed by the Engineer-in-charge at all locations and at all lifts.	Each	1	30000	-	-	30,000.00
				Rupees Thirty Thousand Only			

Ans

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹
				Rate in Words			
32	Supply and laying of O.D.20/25 mm of corrugated PVC rigid/ flexible conduits in concealed fashion at Ceiling, column and wall with necessary wire pulling or inspection JB, bends etc along with one run of steel wire. All civil works related to wiring installation such as chasing of walls for embedding PVC conduits and necessary rough plastering should be part of the laying work. The corrugated PVC conduit shall ISI approved make. The item sample shall be shown to engineer-in-charge and get approved before bulk All accessories and consumables required for installation are in the scope of contractor to complete the job in all respect.	RM	300	100	-	-	30,000.00
				Rupees One Hundreds Only			
33	Supply and pulling of wiring for light/ fan points: Supply and Pulling of concealed 20/25mm corrugated PVC rigid/flexible Conduit and wiring for light points. All civil works related to wiring installation such as chasing of walls for embedding PVC conduits and necessary rough plastering should be part of the wiring work. Every junction an inspection JB with cover must be provided. The 3 core X 0.75 sq.mm copper flexible cable for connection of LED fixtures and fans. The lighting accessories such as ceiling rose, angle /batten holders and required copper lugs are in contractors scope. All as instructed by the engineer in-charge. The switch, angle holder, adopter, ceiling rose shall BIS approved make.	Point	60	1600	-	-	96,000.00
				Rupees One Thousand Six Hundreds Only			
34	Supply, Installation and wiring for 6/16 amps twin socket and 10 amps SP way Modular switch with the connections. Switch board cover in item no 5.1 to 5.3. All as instructed by the engineer in charge.	No.	5	500	-	-	2,500.00
				Rupees Five Hundreds Only			
35	Supply and pulling of wiring for lighting/power circuits: Wire shall PVC insulated 650 / 1100V grade, copper conductor, multi stranded wire conforming to latest IS: 694. The colour code of wires for phase shall be red and black for neutral. The earth wire shall be of green colour to be laid in installed PVC concealed conduit. The required consumables to complete the job of pulling wires are in the scope of contractor.						
35.1	Supply & pulling of 2 run of Wire of (2 run of 2.5 sq mm for Phase and neutral) The wires shall be pulled from meter board to switch boards and looping.	RM	300	60	-	-	18,000.00
				Rupees Sixty Only			
35.2	Supply & pulling of 2 run of Wire of (2 run of 1.5 sq mm for Phase and neutral) The wires shall be pulled from Switch board to 10 A switch/socket looping and Lighting/Fan boards.	RM	500	50	-	-	25,000.00
				Rupees Fifty Only			
35.3	Supply & pulling of 1 run of 1.5 sq mm Wire for earth. The wires shall be pulled from meter board to main switch boards and from Switch board to 10 A switch socket looping/Fan points.	RM	200	40	-	-	8,000.00
				Rupees Forty Only			
36	Supply and installation of GI Metal box for concealed wiring for fixing modular switches including base frame and cover plate as per technical specification.. All civil works related to wiring installation such as chasing of walls for embedding PVC conduits and necessary rough plastering should be part of the wiring work.						
36.1	6 / 8 modules solid plate with base frame	No.	5	1000	-	-	5,000.00
				Rupees One Thousand Only			
36.2	3 / 4 modules solid plate with base frame	No.	5	600	-	-	3,000.00
				Rupees Six Hundreds Only			
36.3	2 modules solid plate with base frame	No	20	230	-	-	4,600.00
				Rupees Two Hundreds Thirty Only			

Agg

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹
		Rate in Words					
37	Supply and installation of Exhaust fan 300 mm dia/ sweep, 230 V, 1 Ph, 50 Hz, AC, and its accessories. Also supply of SS Wire mesh guard for back and opening. Installation work includes assembling, fixing at wall with anchor fasteners and making all the connections including earth connection. Make shall BIS approved. The item sample shall be shown to engineer in-charge and get approved before bulk supply.	No.	10	2500	-	-	25,000.00
		Rupees Two Thousand Five Hundreds Only					
38	Supply and installation of 7watt, LED (Light emitting Diode) lamp, cool day white. Base B22, Lumen 600, non dirmable, lifetime 15000 hrs.	No.	50	130	-	-	6,500.00
		Rupees One Hundreds Thirty Only					
39	Supply and installation of single phase MCB DB 6 Wa-1 No. The DB Consisting of 1 No RCCB, 2 numbers of 6 amps single pole MCB's with concealed mounting type metal enclosure DB and supply of cable end box 6 way (2 nos) concealed mounting type. The DB shall mount on concealed fashion and the required hardware's and wall chasing and finishing are in contractors scope. All Lighting/Power Circuit shall connect to MCB.	Set	5	4500	-	-	22,500.00
		Rupees Four Thousand Five Hundreds Only					
40	GENERAL NOTE FOR ABOVE ITEMS. 1] work shall be executed as specified in the each item description and as directed by the Engineer-in-charge. 2] Item Description shall be read in conjunction with the Technical specification and, drawing, General conditions of the contract and all other terms & conditions specified in the entire bid document.						-

Note: All Item Rates are considered to be in Indian Rupees unless otherwise explicitly specified and in which case shall be always converted appropriately to arrive at the amount in Indian Rupees.

Work Order Total	Rs. 35,64,400.00
Overall Rebate (%)	0
Work Order Value After Overall Rebate in Figure	Rs. 35,64,400.00
Work Order Value After Overall Rebate in Words	Rupees Thirty Five Lakh Sixty Four Thousand Four Hundreds Only

M. Vishweshwar 23-1-26
 M/s RAVI S HALAGATI
 DEPUTY GENERAL MANAGER
 C & MM (WORKS GROUP), KAIGA SITE