



ONGC

CAUVERY ASSET – KARAIKAL

Office of Engineering services, Neravy Complex, Karaikal- 609604

No.ONGC/KKL/CA/ES/GM(C)/T(VC1CC25005)/2025-26/NOA/PC

Date: 05.05.2025

To,

PREMIER CONSTRUCTIONS,
92, Venkatesa Gramani Street,
Chintadripet, Chennai – 600 002.
Mob: 98424 24490.
E-mail ID: premierkaraikal@yahoo.co.in

NOTIFICATION OF AWARD (NOA)

NAME OF WORK: "Recarpeting of internal roads & approach road to colony, widening of entrance of approach road to ONGC residential colony and providing paver block for four wheeler parking in ONGC Residential colony, Karaikal".

Dear Sir,

Your tender for the above mentioned work has been accepted on behalf of the ONGC at your quoted offer of **Rs. 1,01,49,669.11 (Rupees One crore one lakh forty nine thousand six hundred sixty nine and paise eleven only)** which is (-) 17.00% below the estimated cost of Rs.1,22,28,517.00.

You are requested to submit the Performance Guarantee in the form of NEFT/RTGS/Electronic fund transfer/ Electronic Bank Guarantee for the sum of **Rs.10,14,967.00 (Rupees Ten lakhs fourteen thousand nine hundred sixty seven only)** in the prescribed proforma vide Appendix- 1 of bid document from any Nationalized / Scheduled Bank which is valid up to 31.10.2026.

You may kindly confirm within 03 days of issue of the NOA that SD/PBG shall be submitted within 15 days from the date of NOA and also execute an agreement on non-judicial stamped paper worth Rs. 100/- (Rupees One Hundred only) as per standard Performa, which shall be signed within 15 days from receipt of an acceptable SD or PBG.

You are requested to obtain a PF Code number from the respective PF Commissioner (if not yet obtained, so far) and to submit proof of the same before submitting your bill.

You are requested to start the work immediately. However, the time Limit of **45 (Forty five) Days** shall be reckoned from the 15th day of this NOA or the handing over of the site, whichever is later.

[Signature]

[Signature]

GM (C)

For and on behalf of ONGC

Note: 1. The Nomenclatures, quantities, units and rates of the items provided in the original tender shall be considered for all purposes, in case of any dispute on account of Typographical error etc.

2. You are requested to contact GM (Civil) who shall remain in charge of the above work and shall arrange to hand over the work to you. All further correspondence in respect of this work should be addressed to him.

N.O.O.

Copy to:-


1. CGM – HES
2. CGM - HR
3. GM (F&A), Neravy -----do----- (PR. No. 2090063168)
4. GM (C) - With request:
To inform LEO through Form – VI-B for commencement & completion of the work.
To ensure the submission of proof of EPF Code by the Agency before processing his bill
5. Agreement Copy
6. Tender Cell.
7. File.

Encl: Schedule-B

Schedule-B

Sl. No	Description	Quantity	Unit	Rate Excl GST	Amount
1	Dismantling manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge : bituminous road	202.00	Sqm	437.58	88,391.16
2	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and for all lift, as directed by Engineer-in-charge. All kinds of soil	369.00	cum	181.26	66,884.94
3	Construction of granular sub-base by providing close graded Material conforming to Grade-I (size range 75 mm to 0.075mm) having CBR Value-30, mixing at site of work, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineerin-Charge.	230.00	cum	1,931.02	4,44,134.60
4	Supplying and stacking at site. 63 mm to 45 mm size stone aggregate	125.00	cum	1,670.71	2,08,838.75
5	Collection and supply of gravel of approved quality including loading, transporting, unloading at site of work and stacking properly for measurement all as directed by EIC.	319.00	cum	1,842.47	5,87,747.93
6	Laying, spreading and compacting stone aggregate of specified sizes to WBM specifications in uniform thickness, hand picking, rolling with 3 wheeled road/vibratory roller 8-10 tonne capacity in stages to proper grade and camber, applying and brooming requisite type of screening / binding material to fill up interstices of coarse aggregate, watering and compacting to the required density.	125.00	cum	1,069.13	1,33,641.25
7	Labour charges for laying gravel including labour charges for spreading, watering with all leads for water and consolidation by power roller of 8-10 tonnes capacity and all other T&P, cost of fuel etc., complete as directed by EIC (Mode of measurement for Payment is on the basis of loose volume, i.e. as per stack measurement quantity)	278.00	cum	30.05	8,353.90

 25/15


K. Ganesh
GM (Civil)
Page 2 | 6

Sl. No	Description	Quantity	Unit	Rate Excl GST	Amount
8	Providing and applying tack coat using hot straight run bitumen of grade VG - 10, including heating the bitumen, spraying the bitumen with mechanically operated spray unit fitted on bitumen boiler, cleaning and preparing the existing road surface as per specifications : On W.B.M. @ 0.75 Kg / sqm	712.00	Sqm	61.78	43,987.36
9	Providing and applying tack coat using hot straight run bitumen of grade VG - 10, including heating the bitumen, spraying the bitumen with mechanically operated spray unit fitted on bitumen boiler, cleaning and preparing the existing road surface as per specifications : On bituminous surface @ 0.50 Kg / sqm	15193.00	Sqm	49.22	7,47,799.46
10	Surface dressing on old surface with hot bitumen of grade VG-10 of approved quality using 1.95 kg of bitumen per sqm with 1.50 cum of stone chippings 11.2 mm nominal size per 100 sqm of road surface, including consolidation with road roller of 6 to 8 tonne capacity, etc. complete.	1381.00	Sqm	178.81	2,46,936.61
11	Providing and laying semi- dense Bituminous concrete using crushed stone aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site by tippers, laying with paver finisher equiped with electronic sensor to the required grade, level and alignment and rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction and density as per specification, complete and as per directions of Engineer-in-Charge. 25 mm compacted thickness with bitumen of grade VG-30 @ 5% (percentage by weight of total mix) and lime filler @ 2% (percentage by weight of Aggregate) prepared in Drum Type Hot Mix Plant of 60-90 TPH capacity.	14414.00	Sqm	281.13	40,52,207.82
12	Supplying, stacking and spreading 6mm thick river sand over WBM surface as directed by EIC.	14414.00	Sqm	16.50	2,37,831.00
13	Providing and applying 2.5 mm thick road marking strips (retro- reflective) of specified shade/ colour using hot thermoplastic material by fully/ semi automatic thermoplastic paint applicator machine fitted with profile shoe, glass beads dispenser, propane tank heater and profile shoe heater, driven by experienced operator on road surface including cost of material, labour, T&P, cleaning the road surface of all dirt, seals, oil, grease and foreign material etc. complete as per direction of Engineer-in-charge and accordance with applicable specifications.	629.00	Sqm	763.64	4,80,329.56

[Handwritten signature]

5/5/21
K. Ganesh
GM (Civil) 6

Sl. No	Description	Quantity	Unit	Rate Excl GST	Amount
14	Providing and fixing Glow studs of size 100x20 mm made of heavy duty body shall be moulded ASA (Acrylic styrene Acryloretite) or HIP (High impact polystyrene) or ABS having electronically welded micro- prismatic lens with abrasion resistant coating as approved by Engineer in charge. The glow stud shall support a load of 13635 kg tested in accordance with ASTM D4280. The slope of retro-reflective surface shall be 35 (+/- 5) degrees to base .The reflective panels on both sides with at least 12 cm of reflective area up each side. The luminance intensity should be as per the specification and shall be tested as described in ASTM I: 809 as recommended in BS: 873 part 4: 1973. The studs shall be fixed to the Road surface using the adhesive conforming to IS, as per procedure recommended by the manufacturer complete and as per direction of Engineer-in-charge.	811.00	Each	210.67	1,70,853.37
15	Demolishing brick work manually by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. In cement mortar	5.00	cum	2,103.85	10,519.25
16	Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete.	6.00	cum	2,168.74	13,012.44
17	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1:4:8 (1 Cement: 4 coarse sand (zone-III) derived from natural sources: 8 graded stone aggregate 40 mm nominal size derived from natural sources)	6.00	cum	6,956.32	41,737.92
18	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level: 1:1.5:3 (1 cement: 1.5 coarse sand (zone-III) derived from natural sources: 3 graded stone aggregate 20 mm nominal size derived from natural sources)	9.00	cum	9,237.40	83,136.60
19	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc, above plinth level up to floor five level, excluding cost of centering, shuttering, finishing and reinforcement : 1:1.5:3 (1 cement: 1.5 coarse sand (zone-III) derived from natural sources: 3 graded stone aggregate 20 mm nominal size derived from natural sources)	10.00	cum	11,082.89	1,10,828.90




K. Ganesh
GM (Civil) 4 | 6

Sl. No	Description	Quantity	Unit	Rate Excl GST	Amount
20	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 (1 cement: 1.5 coarse sand(zone-III) derived from natural sources: 3 graded stone aggregate 20 mm nominal size derived from natural sources).	8.00	cum	11,749.26	93,994.08
21	Centering and shuttering including strutting, propping etc, and removal of form for Foundations, footings, bases of columns, etc. for mass concrete	17.00	Sqm	400.46	6,807.82
22	Centering and shuttering including strutting, propping etc, and removal of form for Walls (any thickness) including attached pilasters, butteresses, plinth and string courses etc.	67.00	Sqm	860.35	57,643.45
23	Centering and shuttering including strutting, propping etc, and removal of form for Suspended floors, roofs, landings, balconies and access platform	29.00	Sqm	946.90	27,460.10
24	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	3240.00	Kg	110.13	3,56,821.20
25	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq.meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge. With cement mortar 1:4 (1 cement: 4 fine sand)	43.00	Sqm	559.00	24,037.00
26	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture	469.00	Sqm	231.04	1,08,357.76
27	Removing dry or oil bound distemper, water proffing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	426.00	Sqm	25.68	10,939.68

[Handwritten signature]

[Handwritten signature]
K. Ganesh
GM (Civil) 6

Sl. No	Description	Quantity	Unit	Rate Excl GST	Amount
28	Applying priming coats with primer of approved brand and manufacture, having low VOC (Volatile Organic Compound) content. With water thinnable cement primer on wall surface having VOC content less than 50 grams/litre	469.00	Sqm	75.52	35,418.88
29	Painting with synthetic enamel paint of approved brand and manufacturer of required colour to give an even shade: One or more coats on old work.	426.00	Sqm	104.98	44,721.48
30	Finishing walls with water proofing cement paint of required shade: New work (Two or more coats applied @ 1.67 ltr/10 sqm) over and including priming coat of exterior primer applied @ 0.90 litres/10 sqm	433.00	Sqm	164.00	71,012.00
31	Providing and laying at or near ground level factory made kerb stone of M-25 grade cement concrete in position to the required line, level and curvature, jointed with cement mortar 1:3 (1 cement: 3 coarse sand), including making joints with or without grooves (thickness of joints except at sharp curve shall not to more than 5 mm), including making drainage opening wherever required complete etc. as per direction of Engineer- in-charge (length of finished kerb edging shall be measured to calculate volume for payment). (Precast C.C. kerb stone shall be approved by Engineer-in-charge).	24.00	cum	10,331.96	2,47,967.04
32	Providing and laying 60 mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50 mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge.	1512.00	Sqm	992.59	15,00,796.08

Total Rs. 1,03,63,149.39

Deduct quoted offer @ (-) 17.00% below Rs. -17,61,735.40


Total Rs. 86,01,413.99

Add GST @ 18.00% Rs. 15,48,255.12

Awarded value Rs. 1,01,49,669.11

(Rupees One crore one lakh forty nine thousand six hundred sixty nine and paise eleven only)




K. Ganesh
GM (Civil)
Page 6/6