



OIL AND NATURAL GAS CORPORATION LIMITED
ASSAM ASSET, ENGINEERING SERVICES
Office of In-Charge Tender Cell, ES
O.T Complex, DBG, Sivasagar – 785640.

SIB/AA/SERVICES/ENGG-SERVICES/WORKS/2025/oldpipe/1437749/ 379

Date:-25/08/2025

NOTICE OF AWARD (NOA)

To,
M/s DIPANKAR DUTTA
VILL: DULIA, PO: KHONA KHOKORA,
GOURISAGAR, DIST.: SIVASAGAR (ASSAM).
VENDOR CODE - 830845
GePNIC Bid No. - 836927

OLA No- 9020003764

Name of work :- Replacement of old pipeline network at nonresidential area like CWS, DBG, WELL SERVICES, BOP YARD, AUTO WORKSHOP, RSJ YARD, CENTRAL STORE, FIRE ETC.

Reference: Tender no. RC5VC25003

Dear Sir,

Your tender for the above mentioned work has been accepted on behalf of Oil and Natural Gas Corporation Limited (ONGC) at your quoted percentage i.e. 38.95 % below w.r.t. estimated cost put to tender. The accepted value of the Work comes to Rs. 53,59,011.95 (**Rupees Fifty Three Lakh Fifty Nine Thousand Eleven and Paise Ninety Five Only**) Inclusive of 18% GST. The time period for completion of work shall be (12) Twelve Months from the date of commencement. The date of commencement of work shall be from 7th day of issuance of LOA/NOA or Handing over of site, whichever is later.

You are requested to furnish a Performance Security for a sum equivalent to 10.00% (Ten percent) of the contract value, i.e., Rs. 5,35,910.00 (**Rupees Five Lakh Thirty Five Thousand Nine Hundred Ten Only**), within 15 (fifteen) days from the date of this NOA. The Performance Security can be submitted either in the form of NEFT/RTGS/Electronic fund transfer to the designated account of ONGC or in the form of an Electronic Bank Guarantee, as per the prescribed format provided in the tender document. The validity of the Performance Bank Guarantee (e-BG) shall be initially up to the scheduled completion date for the work, plus the Security Period/Defect Liability Period (i.e. 12 months) plus Ninety (90) days, with a mandatory claim period of a minimum of 01 (One) month from the date of expiry of the Performance Bank Guarantee.

Please confirm within 3 days of the issue of this NOA that the Performance security shall be submitted within 15 days from the date of NOA. Non-submission of the Performance security within the stipulated period may lead to the annulment of the contract and actions as per the tender/NOA conditions.


Furthermore, please attend this office in person on any working day, along with a Non-judicial Stamp Paper of Rs.100/-, for executing the Agreement with ONGC within 30 (Thirty) days from the date of the issue of this letter. Non-compliance of above, will lead to forfeiture of EMD and cancellation/ termination of award of Work.

Please note that the "tender document with all supporting papers and documents" submitted by you along with this NOA will be treated as "Agreement", till such time the formal agreement is not executed by you. No payment will be made for work executed by you till PBG is submitted and formal agreement is executed.

Further you are requested to contact Engineer-in-Charge i.e. C.E (Civil) - Civil Maintenance (Sivasagar) for taking over site, for further instructions and correspondence regarding execution of the work. Kindly acknowledge receipt of this Notice of Award (NOA).

Enclosed: - Schedule-B

Yours faithfully


S. SENTHIL KUMAR
GM (Civil), ES
I/c Tender Cell
ONGC, Assam Asset

Schedule-B

Name of work :- Replacement of old pipeline network at non-residential area like CWS, DBG, WELL SERVICES, BOP YARD, AUTO WORKSHOP, RSJ YARD, CENTRAL STORE, FIRE ETC.

Sl No	Description Of Items	Qty	Unit	Rate	Amount
1	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth upto 30 cm measured at a height of 1m above ground level and removal of rubbish upto a distance of 50 m outside the periphery of the area cleared.	9210.00	M2	17.60	162096.00
2	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m: All kinds of soil.	385.92	M3	260.30	100454.98
3	Providing and laying in position specified grade of reinforced cement concrete of specified grade excluding the cost of centering and shuttering, finishing and reinforcement - All work up to plinth level :1:1.5:3 (1 Cement : 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 40 mm nominal size derived from natural sources	18.02	M3	9045.75	163031.55
4	Steel reinforcement for R.C.C. WORK including, straightening, cutting, bending, placing in position and binding all complete upto plinth level :- Thermo-Mechanically treated bars of grade FE-500D or more	1441.84	kg	107.85	155502.44
5	Centering and shuttering including strutting, propping etc. and removal of form for : Foundations, footings, bases of columns, etc. for mass concrete	198.32	M2	392.15	77771.19
6	Providing and fixing 3 layer PP-R (Poly propylene Random copolymer) pipes confirming to IS:15801 UV stabilized & anti - microbial fusion welded, having thermal stability for hot & cold water supply, including all PP - R plain & brass threaded polypropylene random fittings, including trenching, refilling & testing of joints complete as per direction of Engineer-in-Charge. External work. PN - 10 Pipe, 50 mm OD (SDR-11)	1255.00	RM	450.95	565942.25
7	Providing and fixing 3 layer PP-R (Poly propylene Random copolymer) pipes confirming to IS:15801 UV stabilized & anti - microbial fusion welded, having thermal stability for hot & cold	3350.00	RM	696.75	2334112.50

Tender no. RC5VC25003, Name of Work: - Replacement of old pipeline network at non-residential area like CWS, DBG, WELL SERVICES, BOP YARD, AUTO WORKSHOP, RSJ YARD, CENTRAL STORE, FIRE ETC.



S. SENTHIL KUMAR
 GM (Civil), ES
 I/c Tender Cell
 ONGC, Assam Asset

	water supply, including all PP - R plain & brass threaded polypropylene random fittings, including trenching, refilling & testing of joints complete as per direction of Engineer-in-Charge. External work. PN - 10 Pipe, 75 mm OD (SDR-11)				
8	Providing and fixing 3 layer PP-R (Poly propylene Random copolymer) pipes confirming to IS:15801 UV stabilized & anti - microbial fusion welded, having thermal stability for hot & cold water supply, including all PP - R plain & brass threaded polypropylene random fittings, including trenching, refilling & testing of joints complete as per direction of Engineer-in-Charge. External work. PN - 16 Pipe, 25 mm OD (SDR-7.4)	3130.00	RM	265.05	829606.50
9	Providing and fixing PPR Unions. PPR Union 25mm	63.00	EA	334	21042.00
10	Providing and fixing PPR Unions. PPR Union 75mm	25.00	EA	782.10	19552.50
11	Providing and fixing PPR Unions. PPR Union 75mm	67.00	EA	1684.05	112831.35
12	Providing and fixing gun metal gate valve with C.I. wheel of approved quality (screwed end) : 25mm	35.00	EA	622.40	21784.00
13	Providing and fixing gun metal gate valve with C.I. wheel of approved quality (screwed end) : 50mm	35.00	EA	1026.65	35932.75
14	Providing and fixing gun metal gate valve with C.I. wheel of approved quality (screwed end) : 80mm	100.00	EA	2604.55	260455.00
15	Providing flanged joints to double flanged C.I./ D.I. pipes and specials, including testing of joints :	200.00	EA	215.10	43020.00
16	Horizontal directional drilling (HDD) Complete work for crossing of RIVER/CANAL/HIGHWAY/RAILWAY TRACK etc. includes transportation of ONGC supplied bare pipe along with coating material / 3 LPE coated line pipes from ONGCs designated store to site, design, detailed Page - 59 - of 64 engineering of crossing, mobilization and demobilization of required manpower, material, machinery and other resources, supply of all consumables (except line pipe) and execution of the job. The work is to be executed in accordance with specification, drawings (if any), provisions of the contract and direction of Engineer-In-Charge (EIC). The item is also inclusive of string preparation of the pipes by welding as per API-1104, 100 % radiography of weld joints, tested of completed pipeline string, corrosion coating of bare pipes / field joints with supply and application of heat shrink sleeves compatible with 3 LPE as per specification, inspection of corrosion coating and repair of defects. Installation of pipeline string at minimum 3 mtrs below the lowest point of river bed .The item is to be carried out prior approval of I/C C&M . Agency has to produce as built drg. with profile after execution of work for payment. All activities for horizontal direction drilling shall be carried	120.00	M	8,063.22	967586.40

Tender no. RC5VC25003, Name of Work: - Replacement of old pipeline network at non-residential area like CWS, DBG, WELL SERVICES, BOP YARD, AUTO WORKSHOP, RSJ YARD, CENTRAL STORE, FIRE ETC.

 S. SENTHIL KUMAR
GM (Civil), ES
I/c Tender Cell
ONGC, Assam Asset

	out as per approved drawing, specification and direction of EIC. Item also includes hydro-testing of entire crossing pipe-length after installation, repair of leaks / defects found during testing and retesting to the satisfaction of EIC. Restoration and clean up and disposal of waste drilling fluid etc., preparation of as build drawings and other records. All other works not specifically listed herein but required to be executed in order to complete the crossing in all respect as per specification drawings provision of contract document and direction of EIC is in the scope of the contractor. 77.1 With casing pipe. 77.1.01 60.3 mm OD L/P (up to 7.90 mm WT) with 150ND cased pipe				
17	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	24.30	M3	7878.50	191447.55
18	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	18612.20	kg	133.70	2488450.87
19	Providing and fixing gun metal non- return valve of approved quality (screwed end) :				
a	80 mm nominal bore (horizontal)	10.00	Each	3664.75	36647.50
b	50 mm nominal bore (horizontal)	5.00	Each	1371.20	6856.00
c	25 mm nominal bore (horizontal)	20.00	Each	591.40	11828.00
20	Design engineering and consultancy services complete in all aspect as per the scope and direction of EIC.	1	Each	172119.03	172119.03
Total(Rs.)=					8778070.36
Less quoted percentage @ (-) 38.95 % below the Estimated Cost put to Tender (Rs.)=					3419058.41
Total Amount Quoted Including GST(Rs.)=					53,59,011.95


 25/8/2025
 GM (Civil), ES
S. SENTHIL KUMAR
 GM (Civil), ES
 I/c Tender Cell
 ONGC, Assam Asset

Tender no. RC5VC25003, Name of Work: - Replacement of old pipeline network at non-residential area like CWS, DBG, WELL SERVICES, BOP YARD, AUTO WORKSHOP, RSJ YARD, CENTRAL STORE, FIRE ETC.