

India's
energy
anchor



ऑयल एंड नैचुरल गैस कॉर्पोरेशन लिमिटेड, पश्चिमी अपतटीय इकाई
Oil and Natural Gas Corporation Limited, Western Offshore Unit

बसीन एवं सैटेलाइट सम्पत्ति, दूसरी मंज़िल -बी खण्ड, वसूधरा भवन, बान्द्रा(पूर्व)मुम्बई -
400051

B&S ASSET, B Wing, 2nd Floor, Vasudhara Bhavan, Bandra (East), Mumbai: 400051
Tel No.# 022 2656 2201/2656 3180

Registered Office: Pandit Deendayal Upadhyaya Urja Bhavan 5, Nelson Mandela
Marg, Vasant Kunj, New Delhi-110070

dated 21.07.2025

NOA no MUM/OFS/BSA/ST/2025/cable/1434403/9030013278

NOTIFICATION OF AWARD (NOA)

To:

M/s. M/s. Ctech Engineering Consulting supply and Project Company (V. Code- 894512)
203, A-Wing, 2nd Floor, Crystal Plaza, Opp Railway Station Mira Road, (E) Thane- 401107
Email Id: ctech9784@yahoo.co.in


SUB: Notification of Award (NOA) for "Revamping of damaged heat tracing system at BPA and Fuel gas system at BCPB1 and BCPB2 of BPB Platform of B&S Asset" against ONGC e-tender No. QY1SC25004

Dear Sir,

Please refer your bid submitted against GePNIC Tender No. 2025_ONGC_231863_2 (e-tender No. QY1SC25004), ONGC hereby places firm order (NOA) on you for "Revamping of damaged heat tracing system at BPA and Fuel gas system at BCPB1 and BCPB2 of BPB Platform of B&S Asset" against the tender No. QY1SC25004 at following rates, terms and conditions:


1. **Description:** "Revamping of damaged heat tracing system at BPA and Fuel gas system at BCPB1 and BCPB2 of BPB Platform of B&S Asset" as per scope of work at Annexure-II of tender documents.
2. **Price Schedule:** As per attached Annexure-A.
3. **Completion Time:** 06 months including monsoon period from the date of issue of Notification of Award (NOA) i.e. up to 17.01.2026.
4. **Liquidated Damages:** As per tender conditions
5. **Total Contract Value:** INR 13496249.76/- (Including GST@12% on Material & Services).
6. **Performance Security:** Contractor to submit security deposit of Rs. 1349625/- in the form of Bank guarantee/NEFT/RTGS/Electronic fund transfer to designated account of ONGC. The security deposit is to be submitted within 15 days from the date of acceptance of NOA. If security deposit is to be submitted in the form of bank guarantee then it should be valid beyond 60 days from post commissioning warranty period considering contract completion only after warranty period i.e. up to 17.03.2027.
7. **Payment Terms and Conditions:** As per payment terms of SCC.
8. **Contract price schedule and breakup of price:** At appendix-I.
9. **Formal Contract** will be signed within 30 days from the date of issue of this NOA. Till formal contract is signed, this NOA shall be binding on both ONGC and contractor.

Kindly acknowledge the receipt & Confirm acceptance of this Notification of Award within 03 days of issue of this NOA.


(Gurmeet Singh Makkar)
CGM (P)-I/C SPM,
B&S Asset, Mumbai
Gurmeet Singh Makkar
CGM (P), I/c (SPM)
B & S Asset,
ONGC, Mumbai

Contract price schedule and breakup of price:

Sl. No.	Item Description	Quantity	Units	Quoted Currency in INR / Other Currency	BASIC RATE In Figures To be entered by the Bidder Rs. P	GST (%)	TOTAL AMOUNT Without Taxes	Total GST amount in INR Rs. P	TOTAL AMOUNT With Taxes
1	Item description								
1.1	Self-Regulating Heat tracing cable, 230Vac, 20W/ft	548.64	meter	INR	2600	12	1426464	171175.68	1597639.68
1.2	Thermal insulation (compatible with heat tracing) 1200 X 6 ft*ft	7200	ft*ft	INR	110	12	792000.00	95040.00	887040.00
1.3	Line sensing control thermostat with flameproof JB, (10-110Deg.C), contactor (20Amp) and thermostat relay & sensor – 10ft steel capillary	60	no	INR	25300	12	1518000.00	182160.00	1700160.00
1.4	End Seal kit of heat tracing system (tolerance 150 degC)	50	no	INR	200	12	10000.00	1200.00	11200.00
1.5	Thermal conductive paste (100gm)	30	tubes	INR	500	12	15000.00	1800.00	16800.00
1.6	Adhesive Aluminum tape (2.5" wide, 50m roll)	50	no	INR	700	12	35000.00	4200.00	39200.00
1.7	Adhesive Rubber tape (2" wide, 20m)	75	roll	INR	700	12	52500.00	6300.00	58800.00
1.8	Dismantling of existing material at BPA	1	Lump sum	INR	375000	12	375000.00	45000.00	420000.00
1.9	Installation and commissioning of new material at BPA	1	Lump sum	INR	650000	12	650000.00	78000.00	728000.00
2.1	Heat tracing cable Self regulating heat tracing cable 240Vac, 9W/m, with termination kit	300	meter	INR	900	12	270000.00	32400.00	302400.00
2.2	Heat tracing cable Self regulating heat tracing	650	meter	INR	900	12	585000.00	70200.00	655200.00



	cable 240Vac, 32W/m, with termination kit								
2.3	Heat tracing cableSelf regulating heat tracing cable 240Vac, 24W/m, with termination kit	50	meter	INR	900	12	45000.00	5400.00	50400.00
2.4	Heat tracing cable Self regulating EL. Heating cable, 240Vac, 50Hz, 36W/m, with termination kit	125	meter	INR	1100	12	137500.00	16500.00	154000.00
2.5	Thermostat Voltage: 120-270Vac, 30A Temperature range: 0 to 250OF Bulb dimensions-1/4" x 6-3/8" (6.4 x 162 mm) Bulb material -nickel-plated copper Capillary length-6' (1.8 m) Capillary material-nickel-plated copper Capillary armor -flexible stainless steel	25	nos	INR	1100	12	27500.00	3300.00	30800.00
2.6	Thermostat Voltage: 250Vac, 30A Temperature range: 0 to 250OF Bulb dimensions-1/4" x 6-3/8" (6.4 x 162 mm) Bulb material -nickel-plated copper Capillary length-6' (1.8 m) Capillary material-nickel-plated copper Capillary armor -flexible stainless steel	4	nos	INR	1100	12	4400.00	528.00	4928.00
2.7	LCS with selector switch Ex-d zone-1, IP-66, 3 position 'Hand-Off-Auto' switch, 3 nos of ¾ ET cable entry Material: SS 304/ SS 316 Area classification: Gas Group IIA & IIB	47	nos	INR	16800	12	789600.00	94752.00	884352.00
2.8	Junction box Ex-d zone-I, Gas group IIA & IIB, IP-66, 2 nos ¾" ET (F) and 1 nos 1" ET (F) cable entry. Material: SS 304/ SS 316	63	nos	INR	3500	12	220500.00	26460.00	246960.00

2.9	Main Distribution board for BCP-B2 Incoming feeder, outgoing feeder consisting of MCCB, MCB, RCBO, Indication lamps, CT, Ammeters, Voltmeters, Selector Switches Material: SS 304/ SS 316 Type of enclosure: Ex-d, Zone-I Area Classification: Gas Group IIA & IIB	2	lot	INR	170000 0	12	3400000. 00	4080 00.00	3808000.00
3	Glands (M20, M25, ¾" ET, 1" ET, ½" NPT, ¾" NPT etc) Gas group IIA & IIB, Armoured cable Material: SS	1	Lum p sum	INR	80000	12	80000.00	9600. 00	89600.00
3.1	Heat tracing cable glands (PG 16 Raychem C1629 or equivalent is acceptable)	1	Lum p sum	INR	75000	12	75000.00	9000. 00	84000.00
3.2	Thermal insulation (compatible with heat tracing)	2798	sq ft	INR	120	12	335760.0 0	4029 1.20	376051.20
3.3	Thermal conductive paste (100gm)	1	lum p sum	INR	15000	12	15000.00	1800. 00	16800.00
3.4	Adhesive Aluminum tape (2.5" wide, 50m roll)	1	lum p sum	INR	10000	12	10000.00	1200. 00	11200.00
3.5	Adhesive Rubber tape (2" wide, 20m)	1	lum p sum	INR	5999	12	5999.00	719.8 8	6718.88
3.6	Dismantling of existing material BPB	1	Lum p sum	INR	37500	12	375000.0 0	4500 0.00	420000.00
3.7	Installtion and commisioning of new material BPB	1	Lum p sum	INR	80000	12	800000.0 0	9600 0.00	896000.00
Total in Rs (INCL all taxes and GST)									13496249.76

Pg-4


21/7/25