



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA

मदुरै हवाई अड्डा, मदुरै - 625 022.

MADURAI AIRPORT, MADURAI - 625 022.

(ISO 9001 - 2015 & 14001 - 2015 प्रमाणित / CERTIFIED)

भा.भा.वि.प्रा./मदुरै/इ(वि)/MDU-479/25-26

दि:/Date: 22.04.2026

Ref: AAI/MDU/E-E/MDU-479/25-26

सेवा में /To

M/s.Balaji Engineering,

No 28, 6th street, Bakthavatchalam Nagar,

Palavanthangal, Chennai - 600 114.

विषय/Sub: Grading of runway basic strip 140M from centreline of runway i/c construction of perimeter road, Emergency access road & RCC precast drain at Madurai Airport. SH: Replacement of faulty cables and other associated works.

संदर्भ/Ref:Your e-tender (Financial bid-2026 AAI 264891 1) Opened on30.03.2026

महोदय/Dear sir(s),

- 1) Your e-tender for the work mentioned above is hereby accepted on behalf of Chairman, Airports Authority of India, at the item rates quoted by you totaling to **Rs. 88,57,605.00** (Rupees Eighty Eight Lakhs Fifty Seven Thousand Six Hundred and Five Only) plus applicable GST which is 10.01% below the estimated cost put to tender of Rs. 98,52,685.00 plus applicable GST.
- 2) Asst. General Manager (Engg-Elect.), Airports Authority of India, Madurai Airport, Madurai- 625 022, shall be the Engineer-in-charge of the work. You are requested to attend the office of the Asst. General Manager (Engg-Elect.), AAI, Madurai Airport by 06.05.2026 to sign and complete the contract agreement. The contract Agreement shall be executed on a non-judicial stamp paper of value Rs. 100/- (Rupees One Hundred only). The tender document shall be down loaded and signed in each page which shall form part of the agreement. The entire cost towards stamp paper, down loading and printing tender document shall be borne by the contractor.
- 3) As per relevant clause of GCC-2017, which is a part of the contract agreement, security deposit @ 10% (Ten Percent) of gross amount of each running bill will be deducted from your R/A bills which shall released after successful completion of Defects Liability Period which shall be one year from the certified date of completion of contract.

Contd....2

विमानपत्तन निदेशक का कार्यालय, मदुरै हवाई अड्डा, मदुरै - 625 022.

O/o The Airport Director, Madurai Airport, Madurai - 625 022.

दूरभाष / Tel : 0452-2690717 / फ़ैक्स / Fax : 0452 - 2690151, 2690305 E-mail : apdmadurai@aai.aero



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA

मदुरै हवाई अड्डा, मदुरै - 625 022.


MADURAI AIRPORT, MADURAI - 625 022.

(ISO 9001 - 2015 & 14001 - 2015 प्रमाणित / CERTIFIED)

- 4) You are requested to comply with the provision of Contract Labour (Regulation and Abolition) Act 1970 and Contract Labour (Regulation and Abolition) Central rules 1971 Child Labour (Prohibition & Regulation) Act 1986, Construction Workers (Regulation of Employment and condition of Service) Act 1996, Building and other construction Workers Welfare Cess Act 1996 as specified in Clause 19 on page no.50 of GCC of tender and rules of Central and State Governments.
- 5) You are also directed to contact Manager (Engg-Elect)-II, AAI, Madurai Airport immediately who will arrange to hand over the site to you.
- 6) Please note that the time allowed for carrying out the work which shall be **04 Months** and the same shall be reckoned from 06.05.2026
- 7) Any further correspondence in connection with the contract should normally be addressed to the Engineer-in-charge.
- 8) Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith to the undersigned within (15) fifteen days as a token of acceptance from the date of issue of this award letter.
- 9) This work order is allotted the number MDU-479 which shall be quoted by you future correspondence in connection with this work Contract.
- 10) All other terms & Condition shall be as per Tender Document.

Encl: Schedule of Work

Yours faithfully,


Asst. General Manager (E-E)
For and on behalf of the Chairman
Airports Authority of India,
Madurai Airport.

विमानपत्तन निदेशक का कार्यालय, मदुरै हवाई अड्डा, मदुरै - 625 022.

O/o The Airport Director, Madurai Airport, Madurai - 625 022.

दूरभाष / Tel : 0452-2690717 / फैक्स / Fax : 0452 - 2690151, 2690305 E-mail : apdmadurai@aai.aero

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: AIRPORTS AUTHORITY OF INDIA

Name of Work: Grading of runway basic strip 140M from centreline of runway i/c construction of perimeter road, Emergency access road & RCC precast drain at Madurai Airport. SH: Replacement of faulty cables and other associated works.

Contract No: AAI/MDU/E-E/MDU-479/NIT-17/2025-26 Tender ID No.2026_AAI_204891_1

Name of the Bidder/ Bidding Firm / Company : M/s. Balaji Engineering

PRICE SCHEDULE

(DOMESTIC TENDERS - RATES ARE TO GIVEN IN RUPEES (INR) ONLY)
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Please Note: 1) Tenderer should quote the rates Excluding of GST.

2) GST shall be paid to bidder for taxable services/supply against a valid tax invoice.

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
1	Supply of 3.5C X 185 Sq.mm XLPE insulated PVC sheathed, armoured Aluminium conductor power cable of 1.1 KV grade as per IS 7098 part I 1988 with upto date amendments etc complete as required.	1100	Mtr	1500.00	1650000.00	INR Sixteen Lakh Fifty Thousand Only
2	Supply of 4C X 25 Sq.mm XLPE insulated PVC sheathed, armoured Aluminium conductor power cable of 1.1 KV grade as per IS 7098 part I 1988 with upto date amendments etc complete as required.	200	Mtr	300.00	60000.00	INR Sixty Thousand Only
3	Supply of 4C X 16 Sq.mm XLPE insulated PVC sheathed, armoured Aluminium conductor power cable of 1.1 KV grade as per IS 7098 part I 1988 with upto date amendments etc complete as required.	1100	Mtr	300.00	330000.00	INR Three Lakh Thirty Thousand Only

4	Supply of 2C X 16 sq.mm, 5KV grade, stranded copper conductor, PVC insulated and PVC sheathed, unarmoured, underground unscreened, Anti-rodent & Anti-termite treated Airfield Lighting cable generally conforming to IS 1554 Part II with upto date amendments as required.	660	Mtr	800.00	528000.00	INR Five Lakh Twenty Eight Thousand Only
5	Supply of following size DWC HDPE pipe ISI marked along with all accessories like socket, bend, couplers etc. conforming to IS 6205, part 24 with up-to-date amendments complete with fitting and cutting, jointing etc. complete as required. 110 mm dia (outer dia)	1760	Mtr	130.00	228800.00	INR Two Lakh Twenty Eight Thousand Eight Hundred Only
6	Supply of following size DWC HDPE pipe ISI marked along with all accessories like socket, bend, couplers etc. conforming to IS 6205, part 24 complete with fitting and cutting, jointing etc. complete as required. 63 mm dia (outer dia)	1960	Mtr	100.00	196000.00	INR One Lakh Ninety Six Thousand Only
7	Supply of following size DWC HDPE pipe ISI marked along with all accessories like socket, bend, couplers etc. conforming to IS 6205, part 24 complete with fitting and cutting, jointing etc. complete as required. 50 mm dia (outer dia)	3619	Mtr	80.00	289520.00	INR Two Lakh Eighty Nine Thousand Five Hundred & Twenty Only
8	Supply of 25W LED roadway luminaire with high power LED as Light source, inbuilt driver with aluminium/suitable alloy housing etc. as per tender specification for the proposed extension of perimeter wall etc. as required.	75	Nos	2000.00	150000.00	INR One Lakh Fifty Thousand Only
9	Supply of 1X18W LED tube light fitting (4ft) with all accessories including LED tube lamp as per tender specification for the CISF watch tower etc. as required.	4	Nos	750.00	3000.00	INR Three Thousand Only

10	SITC of 1.5 KVA / 24V single phase inverter conforming relevant IEC codes with up-to-date amendments, suitable to operate on DC Input from the lead acid 2X12V battery and able to tap from main supply as independent Input and to deliver the AC output of 230 V on 1 Phase, 50 Hz, 2 wire system including connection, interconnections, provision for earthing with GI wire etc. as required having protection against over current, DC reverse polarity, AC & DC short circuit AC & DC under / over voltage protection etc. complete as per site requirement.	4	Nos	50000.00	200000.00	INR Two Lakh Only
11	SITC of 2 X 12V, 150AH @ C10 rating, tall tubular battery suitable to connect with the above mentioned 1.5KVA inverter for power storage including connection, interconnections, etc. as required and comprising MS structures to accommodate battery and inverter, provision for earthing of structures with GI wire etc. as per site requirements.	4	Nos	65000.00	260000.00	INR Two Lakh Sixty Thousand Only
12	Supply of 50W, 3 blades, aero dynamically balanced leaf wall mount fan complete with bearing, motor, blades, capacitor etc. complete as required. Size 400mm	3	Nos	4500.00	13500.00	INR Thirteen Thousand Five Hundred Only
13	Supply of Astronomical timer switch capable of following output in feeder pillars / Lighting DBs for automatic switching On & Off of street lights at sun set & sun rise or twilight(Auto ON, Auto OFF) with manual override facility with 12/24 hour display format with suitable battery and indication for relay status shall be provided for the timer switch etc. complete as required. 2 output per phase and suitable for single phase supply	3	Nos	9000.00	27000.00	INR Twenty Seven Thousand Only
14	Supply of 3Pole 32A contactor capable of feeding Lighting DBs for automatic switching On & Off of street lights from timer output etc. complete as required.	3	Nos	3000.00	9000.00	INR Nine Thousand Only
15	Supply of 32A rating Three pole, 415 volts, miniature circuit breaker (MCB) matching with the existing enclosure complete with connections etc. as required.	3	Nos	1500.00	4500.00	INR Four Thousand Five Hundred Only
16	Supply of poly carbonate enclosures with hinges, protection IP54 or better & in accordance to fix in the surface/recess having size minimum of 240 mm X 130mm X 95mm suitable to mount 1 no. of TP, 2 nos. of TP MCBs, 1 no. of timer and 02 nos. of TP contactors, suitable fixing arrangement shall be provided etc. complete as required.	25	Nos	20000.00	500000.00	INR Five Lakh Only

17	Supply & Installation street light pole GI double arm bracket up to 750mm and 1000mm length each and 40mm dia arm fixing assembly shall be matching with the 70mm top diameter of the existing 3M, bajaj make octogonal pole already available at site.etc Complete as required.	30	Job	7000.00	210000.00	INR Two Lakh Ten Thousand Only
18	Installation, testing & commissioning of 3 Mtr. Height Octagonal Street Light Pole with all accessories in RCC foundation with 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm nominal size) foundation of size 45x45x110 cm (90 cm below the ground and 20 cm above the ground) (or as per OEM's Standard which ever is better) including excavation and refilling, positioning of template and foundation bolts (supplied with pole to match with pole base plate) and providing and fixing of PE 63, PN 6, HDPE pipe of size 50 mm dia (2 pieces of each minimum 0.75 Mtr length) in the foundation for loop-out of the cable, numbering the pole etc., complete as required. Including mesh to cover the bottom of the pole	30	Job	3500.00	105000.00	INR One Lakh Five Thousand Only
19	ITC of 25W LED roadway luminaire with high power LED as Light source with suitable mounting arrangement, wiring connections with 3C X 1.5sq.mm flexible cable etc. complete as required as per site requirement for the proposed extension of perimeter wall.	62	Job	500.00	31000.00	INR Thirty One Thousand Only
20	Installation, testing and commissioning of prewired LED indoor fittings of all types complete with all accessories and LED tubes etc. directly on ceiling /wall including connection with 1.5 sq.mm PVC insulated copper conductor single core cable and earthing etc. as required.	3	Job	500.00	1500.00	INR One Thousand Five Hundred Only
21	Installation, testing and commissioning of wall mount fan, including suitable bracket arrangements, modification work if required etc. as per site conditions.	3	Job	500.00	1500.00	INR One Thousand Five Hundred Only
22	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in recessed steel conduit, with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sq.mm. FRLS PVC insulated copper conductor single core cable etc. as required. Group C (the work includes supply and fixing of suitable size of MS conduits in recessed or wall surface)	6	Point	1500.00	9000.00	INR Nine Thousand Only

23	Wiring for light/power plug with 4 x 4 sq.mm FRLS PVC insulated copper conductor single core cable in recessed steel conduit along with 2 Nos. 4 sq.mm FRLS PVC insulated copper conductor single core cable for loop earthing as required. (The work includes supply and fixing of suitable size of MS conduits in recessed or wall surface)	35	Mtrs	350.00	12250.00	INR Twelve Thousand Two Hundred & Fifty Only
24	Wiring for circuit/submain wiring along with earth wire with the following sizes FRLS PVC insulated copper conductor, single core cable in recess steel conduit as required. a) 2x1.5sq.mm+ 1x1.5 sq.mm earth wire (The work includes supply and fixing of suitable size of MS conduits in recessed or wall surface)	30	Mtrs	250.00	7500.00	INR Seven Thousand Five Hundred Only
25	Wiring for circuit/submain wiring along with earth wire with the following sizes FRLS PVC insulated copper conductor, single core cable in recess steel conduit as required. a) 2x4sq.mm+ 1x4 sq.mm earth wire (The work includes supply and fixing of suitable size of MS conduits in recessed or wall surface)	35	Mtrs	350.00	12250.00	INR Twelve Thousand Two Hundred & Fifty Only
26	Supplying and fixing suitable size GI box with modular plate and cover in front on in recess, including providing and fixing 6 pin 15/16 amps modular socket outlets and 15/16 amps modular switches, connection etc. as required.	6	Job	500.00	3000.00	INR Three Thousand Only
27	Laying of 63mm dia (Outer dia) DWC pipe direct in ground (75 cm below ground level) in all types of soil including excavation and refilling the trench but excluding sand cushioning and protective covering etc. Complete as required	1960	Mtrs	125.00	245000.00	INR Two Lakh Forty Five Thousand Only
28	Laying of 50mm dia (Outer dia) DWC pipe direct in ground (75 cm below ground level) in all types of soil including excavation and refilling the trench but excluding sand cushioning and protective covering etc. Complete as required	3619	Mtrs	30.00	108570.00	INR One Lakh Eight Thousand Five Hundred & Seventy Only
29	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size in the existing RCC/DWC/ HUME/HDPE/ METAL pipe as required. Upto 35 sq. mm	5579	Mtrs	30.00	167370.00	INR One Lakh Sixty Seven Thousand Three Hundred & Seventy Only
30	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size in the existing RCC/DWC/HUME/HDPE/METAL pipe as required. Above 95 sq. mm and upto 185 sq. mm	1760	Mtrs	30.00	52800.00	INR Fifty Two Thousand Eight Hundred Only

31	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size in the existing masonry open duct as required. Above 95 sq. mm and upto 185 sq. mm	40	Mtrs	30.00	1200.00	INR One Thousand Two Hundred Only
32	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required. 4C X 25 sq.mm	6	Job	500.00	3000.00	INR Three Thousand Only
33	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required. 4C X 16 sq.mm	6	Job	500.00	3000.00	INR Three Thousand Only
34	Supplying and making end termination with aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required. 4C X 16 sq.mm	60	Job	500.00	30000.00	INR Thirty Thousand Only
35	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required. 3.5C X 185 sq.mm	4	Job	1000.00	4000.00	INR Four Thousand Only
36	Providing, laying 150mm dia G.I. pipe (medium class) in ground complete with G.I. fittings including trenching (75 cm deep) and re-filling etc complete as required.	18	Mtrs	2000.00	36000.00	INR Thirty Six Thousand Only
37	Kerf cutting with machine in bituminous/ cement concrete paved area of runway for cables/ pipes of bore not exceeding 50 mm upto a depth of 0.12 meter including filling back/ sealing the cutting using cement concrete/ compound / bitumen and restoring the surface to normal condition etc complete as required but excluding pipe laying.	18	Mtrs	600.00	10800.00	INR Ten Thousand Eight Hundred Only
38	Earthing with G.I. earth pipe 4.5 metre long, 40 mm dia including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe with charcoal/coke and salt etc. as required.	45	Job	8000.00	360000.00	INR Three Lakh Sixty Thousand Only

39	Providing and fixing of 25mm X 5mm G.I strip in 40 mm dia G.I pipe from earth electrode including connection with G.I Nut, bolt spring, washer excavation and re-filling etc. as required.	60	Mtrs	500.00	30000.00	INR Thirty Thousand Only
40	Providing of 6 SWG dia G.I. wire on existing cable trench for loop earthing as required.	7422	Mtrs	30.00	222660.00	INR Two Lakh Twenty Two Thousand Six Hundred & Sixty Only
41	Fixing of 6 SWG dia G.I. wire on existing cable trench for loop earthing as required.	7422	Mtrs	30.00	222660.00	INR Two Lakh Twenty Two Thousand Six Hundred & Sixty Only
42	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan including getting out, refilling up to ground level and disposal of remaining excavated earth lead upto 50 m and for all lift, as directed by Engineer-In-Charge.	12	Cum	500.00	6000.00	INR Six Thousand Only
43	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer-In-Charge. Nominal Concrete 1:3:6 or richer mix (including equivalent mix)	3	Cum	750.00	2250.00	INR Two Thousand Two Hundred & Fifty Only
44	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, welding, fixing in position and applying a priming coat of approved steel primer all complete.	20	Kg	120.00	2400.00	INR Two Thousand Four Hundred Only
45	Supplying and fixing following way, single pole and neutral, sheet steel, MCB distribution board, 240 volts, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator) 6 way, Double Door	2	Job	9000.00	18000.00	INR Eighteen Thousand Only

46	Supplying and fixing 5 amps to 32 amps rating, 240/415 volts, 10 kA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required. Single Pole	8	Job	250.00	2000.00	INR Two Thousand Only
47	Supplying and fixing 5 amps to 32 amps rating, 240/415 volts, 10 kA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required. Double Pole	2	Job	400.00	800.00	INR Eight Hundred Only
48	Supply and fixing following rating and breaking capacity (Icu = Ics) and four pole MCCB with thermal magnetic release in the existing LT Panel complete with connections and other accessories etc. as required. a) 250Amps, 50KA, Four Pole MCCB	6	Job	50000.00	300000.00	INR Three Lakh Only
49	Dismantling, lifting, transportation, transinstallation, testing & Commissioning of 2 X 100KVA UPS, Model: MHT100-2No's, UPS sl.no.2305 PMHT 0002655, sl.no.2304 PMHT0002650 along with associated accessories from new CCR Hall at Madurai Airport complete as required as per technical specification & site requirement according to direction of EIC.	1	Job	25000.00	25000.00	INR Twenty Five Thousand Only
50	Dismantling, lifting, transportation, transinstallation, testing & Commissioning of LT Panel along with associated accessories from new CCR Hall at Madurai Airport complete as required as per technical specification & site requirement according to direction of EIC.	1	Job	10000.00	10000.00	INR Ten Thousand Only
51	Shifting of CCRs from existing CCR hall to new CCR hall at service block including transportation, installation & commissioning of the same at the new location complete as required as per technical specification & tender document.	1	Job	10000.00	10000.00	INR Ten Thousand Only
52	Drilling suitable horizontal bore across runway/taxiway/road/pavement and supplying & inserting 120mm dia HDPE pipe in the bore along with required fittings including providing pulling rope through the pipe.	103	Mtrs	1000.00	103000.00	INR One Lakh Three Thousand Only
53	Supply of PE 80 HDPE Pipe (PN-6) of 120 mm dia with all necessary accessories including testing of joints laying in the pipe at >0.75 mtrs below the ground trenching & refilling etc. complete as per direction of EIC.	103	Mtrs	350.00	36050.00	INR Thirty Six Thousand & Fifty Only

54	Supply of 3.5C X 120 Sq.mm XLPE insulated PVC sheathed, armoured Aluminium conductor power cable of 1.1 KV grade as per IS 7098 part I 1988 with upto date amendments etc complete as required.	700	Mtrs	900.00	6300000.00	INR Six Lakh Thirty Thousand Only
55	Supply of 3.5C X 70 Sq.mm XLPE insulated PVC sheathed, armoured Aluminium conductor power cable of 1.1 KV grade as per IS 7098 part I 1988 with upto date amendments etc complete as required.	940	Mtrs	600.00	5640000.00	INR Five Lakh Sixty Four Thousand Only
56	Supply of following size DWC HDPE pipe ISI marked along with all accessories like socket, bend, couplers etc. conforming to IS 6205, part 24 with up-to-date ammennments complete with fitting and cutting, jointing etc. complete as required. 90 mm dia (outer dia)	905	Mtrs	120.00	1086000.00	INR One Lakh Eight Thousand Six Hundred Only
57	Laying of 110mm dia (Outer dia) DWC pipe direct in ground (75 cm below ground level) in all types of soil including excavation and refilling the trench but excluding sand cushioning and protective covering etc. Complete as required	1760	Mtrs	125.00	2200000.00	INR Two Lakh Twenty Thousand Only
58	Laying of 90mm dia (Outer dia) DWC pipe direct in ground (75 cm below ground level) in all types of soil including excavation and refilling the trench but excluding sand cushioning and protective covering etc. Complete as required	905	Mtrs	125.00	113125.00	INR One Lakh Thirteen Thousand One Hundred & Twenty Five Only
59	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size in the existing RCC/DWC/HUME/HDPE/METAL pipe as required. Above 35 sq. mm and upto 95 sq. mm	905	Mtrs	30.00	27150.00	INR Twenty Seven Thousand One Hundred & Fifty Only
60	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size in the existing masonry open duct as required. Above 35 sq. mm and upto 95 sq. mm	25	Mtrs	30.00	750.00	INR Seven Hundred & Fifty Only

61	Laying and fixing of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size on wall surface as required. Above 35 sq. mm and upto 95 sq. mm (clamped with 25x3mm MS flat clamp)	10	Mtrs	30.00	300.00	INR Three Hundred Only
62	Supply of omni-directional inset type LED taxiway Light fittings complete with LEDs capable of working at 6.6A, transmitting light beams in blue colour, all required electronic circuit, maximum protrusion of 13mm above ground level, double water tight barrier, 2pole plug with leads, supply of 8inch high pressure injection shallow base to fix light fittings in concrete pavement with cable entry hole in the side and M10 bolts for fixing, approximately 13watts etc. as per the technical specification meeting ICAO and FAA standards .(Item includes 2 sets of lamps with drivers as spare). A)Blue	4	Each	55000.00	220000.00	INR Two Lakh Twenty Thousand Only
63	ITC of inset light fittings in straight line on concrete after core cutting to the required level and fixing the shallow base can in Döbelfil/ equivalent compound complete with lamps, with necessary slit cutting for GI pipe for the insertion of cable, connectors and making field connections with lamp and esna connector connections and cable etc. as required.	4	Job	7500.00	30000.00	INR Thirty Thousand Only
64	Laying and fixing of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size on wall surface as required. Above 95 sq. mm and upto 185 sq. mm (clamped with 25/40x3mm MS flat clamp)	9	Mtrs	100.00	900.00	INR Nine Hundred Only
65	Supplying and making cable route marker with cement concrete 1:2:4 (1 cement: 2coarse sand: 4 graded stone aggregate 20 mm nominal size) of size 60 cm X 30 cm X 15 cm including inscription duly engraved as required.	97	Job	700.00	67900.00	INR Sixty Seven Thousand Nine Hundred Only
66	Supply & Installation of following size of exhaust fan complete with all accessories such as motor, blade, louvers, capacitors etc. suitable for operation on single phase 240V, 50HZ AC supply etc as required. 450mm dia, 1400RPM (Heavy Duty)	4	Job	5000.00	20000.00	INR Twenty Thousand Only
Total in Figures					8857605.00	INR Eighty Eight Lakh Fifty Seven Thousand Six Hundred & Five Only
Quoted Rate in Figures					0.0000	Zero Only
Quoted Rate in Words					INR Eighty Eight Lakh Fifty Seven Thousand Six Hundred & Five Only	