



भारतीय विमानपत्तन प्राधिकरण

AIRPORTS AUTHORITY OF INDIA

सं. :- भाविप्रा/किशनगढ़/अभि.(वि.)/अवार्ड लैटर-02/2026-27/598

दिनांक :- 14.05.2026

सेवामें,

मैसर्स के बी कॉन्ट्रैक्ट (प्रा.) लिमिटेड.,
311, टी. सी. जैना टावर -11, प्लॉट नंबर 6,
डिस्ट्रिक्ट सेंटर, जनकपुरी,
पश्चिम दिल्ली, दिल्ली, 110058
ई-मेल- kbcontractspvtltd@gmail.com

M/s K B Contract (P) Ltd.,
311, T C Jaina Tower -11, Plot No 6,
District Centre, Janak Puri,
West Delhi, Delhi, 110058
E-mail- kbcontractspvtltd@gmail.com

विषय:- प्रोविजन ऑफ आईएलएस एट किशनगढ़ एयरपोर्ट, अजमेर। सबहेड :- इलेक्ट्रिकल वर्क।

Subject :- Provision of ILS at Kishangarh Airport, Ajmer. SH:- Electrical Work.

सन्दर्भ:- दिनांक 09.04.2026 को खोली गई आपकी बिड नं. 2026_AAI_267335_1 (वित्तीय बिड)।

Ref:- Your Tender ID: 2026_AAI_267335_1 (Financial Bid) opened on dated -09.04.2026.

महोदय,

- उल्लेखित कार्य हेतु आपकी ई-निविदा आपके द्वारा उद्धृत कुल रु. **Rs. 1,92,18,807/-** (अक्षरे एक करोड़ बानवे लाख अठारह हजार आठ सौ सात रूपये मात्र) (जीएसटी रहित) की नियत मद दर पर अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से एतद् द्वारा स्वीकृत की जाती है, जो कि ई-निविदा की अनुमानित/जस्टीफाइड लागत रु. **Rs. 2,58,22,388/-** (जीएसटी रहित) से **25.57%** नीचे है।

Your E-Tender for the work mentioned above is hereby accepted on behalf of Chairman, Airports Authority of India at the item rates quoted by you totalling to **Rs. 1,92,18,807/-** (Rupees One Crore Ninety Two Lacs Eighteen Thousand Eight Hundred Seven only) (**excluding GST**) which is **25.57% Below** the estimated/Justified cost of **Rs. 2,58,22,388/-** (**excluding GST**).

- सहायक महाप्रबंधक (अभियांत्रिकी-विद्युत), भाविप्रा, किशनगढ़ हवाई अड्डा, अजमेर इस कार्य के इंजिनियर-इन-चार्ज होंगे। आपसे अनुरोध है कि आप संविदा करार पर हस्ताक्षर करने एवं उसे पूरा करने हेतु **25/05/2026** तक सहायक महाप्रबंधक (अभियांत्रिकी-विद्युत), भाविप्रा, किशनगढ़ हवाई अड्डा, अजमेर के कार्यालय में उपस्थित हो। संविदा करार रु. 100/- (मात्र सौ रूपये) के न्यायिकेतर (नॉन-ज्युडिशियल) स्टाम्प पेपर पर बनाया जायेगा तथा स्टाम्प पेपर की लागत आपके द्वारा वहन की जाएगी।

Assistant General Manager (Engg-E), AAI, Kishangarh Airport, Ajmer shall be the Engineer-In-Charge of the work. You are requested to attend the office of the Assistant General Manager (Engg-E) AAI, Kishangarh Airport, Ajmer by **25/05/2026** to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value of Rs. 100/- (Rupees One Hundred only) and the cost of the stamp paper shall be borne by you.

- सुरक्षा जमा राशि रु. **19,21,881.00** (अक्षरे उन्नीस लाख इक्कीस हजार आठ सौ इक्कासी रूपये मात्र) को 10 दिन के भीतर जमा करें अन्यथा इस राशि की कटौती संविदा कागजात के पृष्ठ 41 पर खण्ड-1 ए के अनुसार आपके चालु बिलों में से की जाएगी।

Security deposit **Rs.19,21,881.00** (Rupees Nineteen Lakh Twenty One Thousand Eight Hundred Eighty One Only) within 10 days from the date of issue of this letter, failing which, the same will be deducted as per clause no.- 1A, page no. -41 of tender/contract document.

- आप से अनुरोध है की आप संविदा श्रम, 1970 अधिनियम (विनिमय एवं उन्मूलन) संविदा श्रम (विनिमय एवं उन्मूलन), 1971 केंद्रीय नियमबाल श्रम, 1986 अधिनियम (निषेध एवं उन्मूलन) निर्माण श्रमिकों सेवा के शर्त और) नियमन (सी.सी.जे. कि निविदा दस्तावेज के जी 1996 और अन्य निर्माण श्रमिक कल्याण उपकर अधिनियम 1986 अधिनियम के प्रावधानों का और केंद्रीय व राज्य सरकारों के तदसंबंधी नियमों का अनुपालन करें।

You are requested to comply with the provision of Contract Labour (Regulation & Abolition) Act of 1970, Contract Labour (Regulation & Abolition) Central Rules 1971, Child Labour (Prohibition & Regulation) Act 1986, Construction Workers (Regulation of Employment & Condition of Service) Act 1996, Building & Other Construction Workers Welfare Cess Act 1996 as specified in GCC of tender Document and Rules of Central and state Govt.




भारतीय विमानपत्तन प्राधिकरण

AIRPORTS AUTHORITY OF INDIA

5. आपको प्रबंधक (अभियांत्रिकी-विद्युत), भाविप्रा, किशनगढ़ हवाई अड्डा, अजमेर से तत्काल संपर्क करने का भी निर्देश दिया जाता है जो आपको कार्यस्थल सौंपने (साइट) की व्यवस्था करेंगे।
You are also directed to contact Manager (Engg-E), AAI, Kishangarh Airport, Ajmer immediately who will arrange to hand over the site to you.
6. कृपया नोट करें की कार्य पूरा करने के लिए आपको 04 (चार) माह का समय प्रदान किया जाता है जो कि इस पत्र के जारी होने की तिथि से 10दिन बाद से प्रभावी होंगी।
Please note that the time allowed for carrying out the work shall be 04 (Four) Months & shall be reckoned from 10th day after the date of issue this letter.
7. दोष दायित्व अवधि **एक (01) वर्ष** होगी जो इस कार्य के पूर्ण होने की वास्तविक दर्ज तिथि से प्रभावी होगी।
The defects liability period shall be **One (01) Year**, which will be effective from the actual recorded date of completion of the work.
8. संविदा के संबंध में भविष्य में किसी भी प्रकार का पत्र व्यवहार सामान्यतः इंजीनियरिंग-इन-चार्ज के नाम से किया जायेगा।
Any further correspondence in connection with the contract should normally be addressed to the Engineer-In-Charge.
9. कृपया पत्र की पावती भेजे।
Please acknowledge the receipt.
10. यदि कोई विसंगति पाई जाती है तो अंग्रेजी भाषा ही मान्य होगी।
In case any discrepancy is found, then English version will be taken as correct.

Enclosure:- BOQ (05Pages)

भवदीय/ Yours Faithfully,


सहायक महाप्रबंधक (अभि.-वि.)/Asstt. Gen. Mgr. (Engg.-E)
कृते तथा ओर से अध्यक्ष भा.वि.प्रा./For and on behalf of Chairman, AAI

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority:-Asstt. Gen. Manager (Engg-E), Kishangarh Airport, Ajmer-305801

Name of Work:-Provision of ILS at Kishangarh Airport, Ajmer. SH:- Electrical Work.

Contract No:-2026_AAI_267335_1

Name of the Bidder/
Bidding Firm /
Company :

K B CONTRACT (P) LTD

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be updated after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P (Excluding GST)	TOTAL AMOUNT (Excluding GST) in Rs. P (Excluding GST)	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
1	Supply of 3.5C x 185 Sq.mm size 1.1 KV grade, XLPE insulated and PVC sheathed, FRLS at outer sheath, Aluminium conductor armoured power cable conforming to IS: 7098(Part-1) 1988 with up to date amendments etc. complete as required.	11460	Mtr	855.00	9798300.00	INR Ninety Seven Lakh Ninety Eight Thousand Three Hundred Only
2	Supply of 4C x 50 Sqmm, 1.1 KV grade, XLPE insulated and PVC sheathed, FRLS at outer sheath, Aluminium conductor armoured power cable conforming to IS: 7098(Part-1) 1988 with up to date amendments etc. complete as required.	60	Mtr	90.00	5400.00	INR Five Thousand Four Hundred Only
3	Supply of 4C x 16 Sqmm, 1.1 KV grade, Armoured, XLPE insulated, PVC sheathed, FRLS at outer sheath, Multicore, Copper conductor cable conforming to IS: 7098 (Part -1) 1988 amended upto date.	84	Mtr	90.00	7560.00	INR Seven Thousand Five Hundred & Sixty Only
4	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade upto 185 sq. mm in the existing masonry open duct as required.	120	Mtr	90.00	10800.00	INR Ten Thousand Eight Hundred Only
5	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade size of above 95 Sqmm and up to 185 Sqmm cable in the existing RCC/ HUME/ STONEWARE/ METAL/ HDPE/DWC pipe as required.	11410	Mtr	90.00	1026900.00	INR Ten Lakh Twenty Six Thousand Nine Hundred Only
6	Laying and fixing of one number PVC insulated and PVC sheathed /XLPE power cable of 1.1 KV grade of Upto 50 sq. mm cable in the existing RCC/ HUME/ STONEWARE/ METAL/ HDPE/DWC pipe as required.	40	Mtr	90.00	3600.00	INR Three Thousand Six Hundred Only
7	Laying and fixing of one number PVC insulated and PVC sheathed /XLPE power cable of 1.1 KV grade of Upto 50 sq. mm (clamped with 1mm thick saddle) size on wall surface as required.	44	Mtr	180.00	7920.00	INR Seven Thousand Nine Hundred & Twenty Only
8	Supplying and making straight through joint with heat shrinkable kit including ferrules and other jointing materials for size of 3.5 x 185 Sqmm of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required.	20	Each	4500.00	90000.00	INR Ninety Thousand Only
9	Supplying and making end termination with brass compression gland and aluminium lugs for 3.5 C x 185 sq.mm size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 kV grade as required.	10	Each	720.00	7200.00	INR Seven Thousand Two Hundred Only
10	Supplying and making end termination with brass compression gland and aluminium lugs for 4 C x 50 sq.mm size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 kV grade as required.	8	Each	360.00	2880.00	INR Two Thousand Eight Hundred & Eighty Only
11	Supplying and making end termination with brass compression gland and copper lugs for 4 X 16 sq. mm (28mm) size of PVC insulated and PVC sheathed / XLPE copper conductor cable of 1.1 KV grade as required.	8	Each	90.00	720.00	INR Seven Hundred & Twenty Only
12	Supplying and laying of following size DWC HDPE pipe ISI marked along with all accessories like socket, bend, couplers etc. conforming to IS 16205, Part 24 complete with fitting and cutting, jointing etc. direct in ground (75 cm below ground level) including excavation and refilling the trench but excluding sand cushioning and protective covering etc., complete as required. 63 mm dia (OD-63 mm & ID-51 mm nominal)	40	Mtr	153.00	6120.00	INR Six Thousand One Hundred & Twenty Only
13	Supplying and laying of following size DWC HDPE pipe ISI marked along with all accessories like socket, bend, couplers etc. conforming to IS 16205, Part 24 complete with fitting and cutting, jointing etc. direct in ground (75 cm below ground level) including excavation and refilling the trench but excluding sand cushioning and protective covering etc. , complete as required. 120 mm dia (OD-120 mm & ID-103 mm nominal)	6790	Mtr	252.00	1711080.00	INR Seventeen Lakh Eleven Thousand & Eighty Only

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P (Excluding GST)	TOTAL AMOUNT (Excluding GST) in Rs. P (Excluding GST)	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
14	Supply of 110 mm high density polyethylene HDPE pipe (PE- 80, PN-6) as per IS - 4984 with up to date amendment along with accessories like socket, bend, couplers etc. complete as required.	4620	Mtr	342.00	1580040.00	INR Fifteen Lakh Eighty Thousand & Forty Only
15	Laying of HDPE pipe (PE- 80, PN-6) of size of 110 mm (OD) in suitable depth by trenchless horizontal directional drilling (HDD) method by deploying HDD machines with necessary arrangements complete as required as per the site requirements. (Excluding the cost of HDPE Pipe)	4620	Mtr	450.00	2079000.00	INR Twenty Lakh Seventy Nine Thousand Only
16	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLSH PVC insulated copper conductor single core cable in surface / recessed steel conduit, with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sq.mm. FRLSH PVC insulated copper conductor single core cable etc as required.	44	Each	1800.00	79200.00	INR Seventy Nine Thousand Two Hundred Only
17	Supplying and fixing of 20mm size of steel conduit along with accessories in surface/recess including painting in case of surface conduit, or cutting the wall and making good the same in case of recessed conduit as required.	162	Mtr	135.00	21870.00	INR Twenty One Thousand Eight Hundred & Seventy Only
18	Supplying and fixing of 25mm size of steel conduit along with accessories in surface/recess including painting in case of surface conduit, or cutting the wall and making good the same in case of recessed conduit as required.	238	Mtr	180.00	42840.00	INR Forty Two Thousand Eight Hundred & Forty Only
19	Supplying and drawing 3 x 2.5 sq.mm sizes of FRLSH PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required.	27	Mtr	135.00	3645.00	INR Three Thousand Six Hundred & Forty Five Only
20	Supplying and drawing 6 x 2.5 sq.mm sizes of FRLSH PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required.	14	Mtr	270.00	3780.00	INR Three Thousand Seven Hundred & Eighty Only
21	Supplying and drawing 3 x 4 sq.mm sizes of FRLSH PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required.	64	Mtr	207.00	13248.00	INR Thirteen Thousand Two Hundred & Forty Eight Only
22	Supplying and drawing 6 x 4 sq.mm sizes of FRLSH PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required.	224	Mtr	405.00	90720.00	INR Ninety Thousand Seven Hundred & Twenty Only
23	Supplying and fixing suitable size GI box with modular plate and cover in front on surface or in recess, including providing and fixing 6 pin 5/6 & 15/16 amps modular socket outlet and 15/16 amps modular switch, connection etc. as required.	68	Each	900.00	61200.00	INR Sixty One Thousand Two Hundred Only
24	Installation, testing and commissioning of pre-wired, fluorescent fitting / compact fluorescent/LED fitting of all types, complete with all accessories and tube etc. directly on ceiling/ wall, including connection with 1.5 sq. mm FRLSH PVC insulated, copper conductor, single core cable and earthing etc. as required.	34	Each	450.00	15300.00	INR Fifteen Thousand Three Hundred Only
25	Supplying and drawing 2 pair 0.5 mm dia FRLS PVC insulated annealed copper conductor, unarmored telephone cable in the existing surface/ recessed steel/ PVC conduit as required.	128	Mtr	27.00	3456.00	INR Three Thousand Four Hundred & Fifty Six Only
26	Supplying and fixing of modular Telephone socket outlet on the existing modular plate & switch box including connections but excluding modular plate etc. as required.	16	Each	135.00	2160.00	INR Two Thousand One Hundred & Sixty Only
27	Supplying and fixing of 2 Module (75mmX75mm) GI box alongwith modular base & cover plate for modular switches in recess etc as required.	8	Each	90.00	720.00	INR Seven Hundred & Twenty Only
28	Brush Less Direct Current (BLDC) Fan without Remote, Supply, Installation, Testing and Commissioning of ceiling fan with Brush Less Direct Current (BLDC) Motor, class of insulation: B, 3 nos. metal(Aluminium alloy) blades, 30 cm long down rod, 2 nos. canopies, shackle kit, safety rope, copper winding, steel/Al body Power Factor not less than 0.9, Service Value (CM/M/W) minimum as below, 350 RPM (tolerance as per IS: 374-2019), THD (Total Harmonic Distortion) less than 10%, suitable for operation with regulator for speed control and all remaining accessories including safety pin, nut bolts, washers, temperature rise=75 °C (max.), insulation resistance more than 2 mega ohm, suitable for 230 V, 50 Hz, single phase AC supply, Ceiling Fan compliant to IS 374:2019 fan i/c external connections with 1.5 sq.mm FRLSH, PVC insulated copper conductor single core cable and earthing etc. as required. 1200mm, service value ≥ 6.0 CM/Min/Watt, air delivery 210 CM/Min (Minimum)	2	Each	4500.00	9000.00	INR Nine Thousand Only
29	Supplying and fixing two module stepped type electronic fan regulator on the existing modular plate switch box including connections but excluding modular plate etc. as required.	2	Each	450.00	900.00	INR Nine Hundred Only
30	Supply of 300 mm fresh air/ventilation fan with metal body suitable for operation on 240 volt, AC supply with all accessories.	2	Each	4500.00	9000.00	INR Nine Thousand Only

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P (Excluding GST)	TOTAL AMOUNT (Excluding GST) in Rs. P (Excluding GST)	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
31	Installation of 300mm sweep exhaust fan in the existing opening, including making good the damage, connection, testing, commissioning etc. as required.	2	Each	450.00	900.00	INR Nine Hundred Only
32	Supplying and fixing 6 A to 32 As rating, 240/415 volts, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required. Single Pole	50	Each	270.00	13500.00	INR Thirteen Thousand Five Hundred Only
33	Supplying and fixing 6 A to 32 A rating, 240/415 volts, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required. Double Pole	30	Each	810.00	24300.00	INR Twenty Four Thousand Three Hundred Only
34	Supplying and fixing Double Pole 63 A rating, 240/415 volts, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.	2	Each	1350.00	2700.00	INR Two Thousand Seven Hundred Only
35	Supplying and fixing 63A four pole, 240/415 volts, "C" curve, 10kA breaking capacity miniature circuit breaker (MCB) suitable for inductive load in the existing MCB DB complete with connections, testing and commissioning etc. as required.	2	Each	2340.00	4680.00	INR Four Thousand Six Hundred & Eighty Only
36	Supplying and fixing of 230 V single-phase (1PH+N), Type 2 + 3 AC Surge Protector Device (SPD), 40KA, Uc-275V AC with (MOV+GSG) technology including connections, testing and commissioning and providing suitable mounting box for fixing the SPD on the wall etc. complete as required. Make:- CITEL, Model-DAC50VG-11-275 or equivalent.	30	Each	810.00	24300.00	INR Twenty Four Thousand Three Hundred Only
37	Supply, Installation, Testing and Commissioning of 8 way (8 + 24), Double door, horizontal type three pole and neutral, sheet steel, IP-43, MCB distribution board, 415 volts, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator)	4	Each	12600.00	50400.00	INR Fifty Thousand Four Hundred Only
38	Supplying and fixing 6 way, 6 module, Double door single pole and neutral, sheet steel, MCB distribution board, 240 volts, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator)	4	Each	4500.00	18000.00	INR Eighteen Thousand Only
39	Supply of 20 watt LED batten type tube light (4 ft.) ultra slim with CRCA or Aluminium housing, IP-65, PC diffuser, durable industrial lighting Suitable for 230V, 50Hz, AC Supply with all accessories etc. Complete as required.	32	Each	540.00	17280.00	INR Seventeen Thousand Two Hundred & Eighty Only
40	Supply, installation, testing & commissioning of 200 Watt LED type out door lighting luminaire (flood light) ,with high pressure die cast aluminium/standard alloy housing, having uniform lighting distribution with luminaire efficiency of more than 110 lumen per watt, CRI more than 70, THD less than 10%, IP 66 protection, with 5 Year warranty on complete luminaire including driver/control gear & LED, more than 50,000 burning hours, suitable size GI pipe bracket of length 01 mtr including bending & clamps as per technical specifications complete as required. Make/Model:- Bajaj/ZELA P 144L WH PO TG SD or Make/Model:- Havells/ ENDURASUNDOWNSL120WLED765PASY BO PC or equivalent.	10	Each	8100.00	81000.00	INR Eighty One Thousand Only
41	Supply and fixing of Rechargeable Emergency light providing through suitable watt rating Twin High Intensity LED fitted Lamps with Adjustable Swivel Type Beam Lights fitted upon Powder Coated CRCA/MS Sheet Sleek Electronic Cabinet fitted with 12V, 7AH SMF Battery giving Battery Backup of Upto 3 Hours provided with feature of Trickle Charging facilitating Overcharging and Low Battery Protection, suitable for 230V 50Hz etc. complete as required.	8	Each	3600.00	28800.00	INR Twenty Eight Thousand Eight Hundred Only
42	Supply of portable waterproof handheld type rechargeable Emergency torch Light suitable for Fast recharge on 230V AC, minimum 6-8 Hour battery backup, Minimum 20000 mAh battery, suitable for outdoor work, Long Range upto 800 meter, with USB Cable etc. complete as required	6	Each	2430.00	14580.00	INR Fourteen Thousand Five Hundred & Eighty Only

[Handwritten Signature]

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P (Excluding GST)	TOTAL AMOUNT (Excluding GST) in Rs. P (Excluding GST)	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
43	SITC of High Wall single phase, 5-Star inverter type 1.5 TR capacity, minimum 16500 BTU/Hr rated Cooling capacity (100 % load), split type air conditioner fitted with hermetically sealed rotary compressor operating on green refrigerant suitable for single phase, 230V, 50Hz, including standard length of copper refrigerant pipe, copper cable and all other accessories as per OEM specifications capable of performing the functions as cooling, dehumidifying, air circulating and filtering, the units shall be supplied with standard length of copper refrigerant pipes, thermal insulation, interconnecting PVC Copper power cable, UPVC Drain pipe, LCD cordless remote, providing & fixing of suitable voltage stabilizer (operating voltage from 170 V to 250 V, auto cut, overload & short circuit protection) including civil work such as drilling for hole, painting, finish with the same and connection of refrigerant pipelines, Pipe Insulation and control cables including first charge of refrigerant etc. complete as required.	12	Each	54000.00	648000.00	INR Six Lakh Forty Eight Thousand Only
44	Supply and fixing of MS angle stand made by 50x50x6 mm MS angle for fixing 1.5 TR split AC outdoor unit or condensing units along with necessary anchor fastener/bolt & nuts etc with concrete, including painting etc. complete as required.	12	Each	1350.00	16200.00	INR Sixteen Thousand Two Hundred Only
45	Supplying and fixing 20 amps, 240 volts, SPN industrial type, socket outlet, with 2 pole and earth, metal enclosed plug top alongwith 20 amps "C" curve, SP, MCB, in sheet steel enclosure, on surface or in recess, with chained metal cover for the socket out let and complete with connections, testing and commissioning etc. as required.	12	Each	1530.00	18360.00	INR Eighteen Thousand Three Hundred & Sixty Only
46	Supply, installation, testing and commissioning of 1-Phase Auto time changeover switch, time cycle of 04 hours for operation of 2 nos 1.5TR Inverter Split type AC Units with all accessories complete as required.	6	Each	900.00	5400.00	INR Five Thousand Four Hundred Only
47	Supply and fixing of extra copper refrigerant pipe of suitable size with nitrile rubber pipe insulation for installation of 1.5 TR Split AC units including jointing/brazing, all accessories for fixing the pipe etc. complete as required.	36	Mtr	450.00	16200.00	INR Sixteen Thousand Two Hundred Only
48	Supply & fixing of PVC drain piping of proper dia for installation of 1.5 TR Split AC units as required at site beyond company provided standard length.	24	Mtr	90.00	2160.00	INR Two Thousand One Hundred & Sixty Only
49	Design, Fabrication, Supply, installation, testing and commissioning of vermin proof, dust proof, front operated, cubicle type, floor/surface mounted, double door, outdoor LT feeder panel PTTA type made out of 2 mm thick CRCA sheet duly rust inhibited, powder coated paint, fully compartmentalized complete with double hinged front door with lockable arrangement etc. including necessary iron channel stand of size 50X50X5, depth of leg 3 feet (minimum), CC all around of the panel upto 1 Meter, control wiring, with mechanical interlocking etc. and having following accessories. INCOMER 2 Nos. 160 A 4P MCCB (Ics=Icu=36KA) thermal magnetic release with rotary operating mechanism including terminal extension. Each Incomer shall have one set of the following items: Digital Multifunction Meter, suitable for measure Voltage, Current, Energy, frequency, power factor etc. with CT ratio programmable and auto ranging along with suitable range CTs. 1 Set of Indication Lamps, LED type, R,Y,B and MCCB 'ON' lamps. BUS COUPLER 1 Nos. 160 A 4P MCCB (Ics=Icu=36 KA) thermal magnetic release with rotary operating mechanism including terminal extension. Bus coupler shall have indication 'ON' indication lamp. BUS BAR 1 Set of 200 A TPN Busbars of aluminium alloy. OUTGOING 02 Nos. 125 A TPN MCCB (Ics=Icu=25 KA) with thermal magnetic release. 02 Nos. 63 A TPN MCCB (Ics=Icu=25 KA) with thermal magnetic release. 04 Nos. 32 A TPN MCCB (Ics=Icu=25 KA) with thermal magnetic release also with Timer and suitable contactor etc. 08 Sets (1 Set for each outgoing) LED type 'ON' Indication Lamps.	2	Job	315000.00	630000.00	INR Six Lakh Thirty Thousand Only

[Handwritten signature]

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P (Excluding GST)	TOTAL AMOUNT (Excluding GST) in Rs. P (Excluding GST)	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
50	Design, Fabrication, Supply, installation, testing and commissioning of vermin proof, dust proof, front operated, cubicle type, floor/surface mounted, double door, outdoor LT distribution panel PTTA type made out of 2 mm thick CRCA sheet duly rust inhibited, powder coated paint, fully compartmentalized complete with double hinged front door with lockable arrangement etc. including necessary iron channel stand of size 50X50X5, control wiring, with mechanical interlocking etc. and having following accessories. (i) INCOMER 2 Nos. 63 A 4P MCCB (Ics=Icu=25KA) thermal magnetic release with rotary operating mechanism including terminal extension. Each Incomer shall have one set of the following items: Digital Multifunction Meter, suitable for measure Voltage, Current, Energy, frequency, power factor etc. with CT ratio programmable and auto ranging along with suitable range CTs. 1 Set of Indication Lamps, LED type, R,Y,B and MCCB 'ON' lamps. (ii) 01 No 63A, 4P, 16KA, ATS (Automatic Transfer Switch) at Incomers having following arrangements at outgoing of ATS. 01 set of 63A HRC fuse. 01 No 0-500V range Voltmeter with voltage selector switch and 2A protection MCB. 01 No 63A, 4P MCCB (Ics=Icu=16KA) thermal magnetic release with Overload, short circuit and earth fault protection, with rotary operating mechanism including terminal extension. 01 no T2, 50KA, SPD with suitable rating TPN MCB. (iii) BUS BAR 1 Set of 100 A TPN, 415V, aluminium alloy Busbars, short-circuit withstand capacity 16KA for 01 Sec. (iv) OUTGOINGS 03 Nos. 32 A, DP, RCBO (100 mA). 02 Nos. 63 A, TPN MCCB (Ics=Icu=25 KA) with thermal magnetic release and 01 no T2, 50KA, SPD with suitable rating TPN MCB. 01 No 40A, TPN MCB. 01 No 32A, DP, RCBO (100 mA) 01 No 20A, DP, MCB. 08 Sets (1 Set for each outgoing) LED type 'ON' Indication Lamps.	2	Job	360000.00	720000.00	INR Seven Lakh Twenty Thousand Only
51	Earthing with G.I. earth pipe 4.5 meter long, 40 mm dia including accessories, and providing masonry enclosure with cover plate having locking arrangement etc. with charcoal/ coke and salt complete as required.	8	Job	5400.00	43200.00	INR Forty Three Thousand Two Hundred Only
52	Providing and laying earth connection from earth electrode with 6 SWG dia G.I. Wire in 15 mm dia G.I. pipe from earth electrode including connection with G.I. thimble excavation and re-filling as required.	140	Mtr	180.00	25200.00	INR Twenty Five Thousand Two Hundred Only
53	Providing and fixing 6 SWG dia G.I. wire on surface or in recess for loop earthing as required.	28	Mtr	36.00	1008.00	INR One Thousand & Eight Only
54	Supplying and making cable route marker with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) of size 60 cm X 60 cm at the bottom and 50 cm X 50 cm at the top with a thickness of 10cm including inscription duly engraved as required.	114	Each	720.00	82080.00	INR Eighty Two Thousand & Eighty Only
55	Supply of nominal 2.0 mm thick (Size of each piece 1Mtr x 10 Mtr) electric insulated synthetic mats conforming to IS:15652-2006, (3.3 KV) Class A, in dotted surface texture etc complete as required.	20	Mtr	1800.00	36000.00	INR Thirty Six Thousand Only
Total in Figures					19218807.00	INR One Crore Ninety Two Lakh Eighteen Thousand
Quoted Rate in Words		INR One Crore Ninety Two Lakh Eighteen Thousand Eight Hundred & Seven Only				

14/05/26
AGM (E-E)

Signature Not Verified

Digitally signed by TANSUKH
Date: 2026.06.20 12:28:53 IST
Location: eProcurement System for
Central PSUs