



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA

संख्या : भा.वि.प्रा./अभि.-सि./जोधपुर/एन.टी.बी./स्टोन/2026-27/
Ref: AAI/ENGG (C)/Jodhpur/NTB/Stone/2026-27/

By: Speed Post/E-mail/Hand
दिनांक : 24/03/2026
Date : 24/03/2026

सेवा में,
मैसर्स एम एल ब्रदर,
एफ22/117 सेक्टर 3,
रोहिणी 110085, दिल्ली
ई-मेल -ankurmadaan88@gmail.com

To,
M/s M L Brother,
F22/117 Setor 3,
Rohini 110085, Delhi
E-mail Id: ankurmadaan88@gmail.com

कार्य का नाम : जोधपुर हवाई अड्डे के नए टर्मिनल भवन में पत्थर के साइनबोर्ड का निर्माण और अन्य विविध कार्य
Name of work: Construction of Stone Signage and Other Miscellaneous works at New
Terminal Building Jodhpur Airport
संदर्भ/Ref. : Tender ID: 2026_AAI_268742_1, Financial bid opened on 11/03/2026 at 12:00 hrs.

महोदय/Sir,

1. उपर्युक्त कार्य हेतु आपकी निविदा, भारतीय विमानपत्तन प्राधिकरण के अध्यक्ष की ओर से, उद्धृत मद दरों पर आपकी कुल राशि **86,89,519.00** रुपये (छियासी लाख नवासी हजार पाँच सौ उन्नीस रुपये मात्र) जी.एस.टी. को छोड़कर, स्वीकार की जाती है, जो कि टेंडर की अनुमानित लागत राशि रुपये **1,02,26,796.00** (जी.एस.टी. छोड़कर) से **(-) 15.03 %** कम है।

Your tender for the work mentioned above is here by accepted on behalf of the Chairman Airports Authority of India at the item rates quoted for a sum totaling to **Rs. 86,89,519.00 (Rupees Eighty Six Lacs Eighty nine thousand five hundred nineteen only) Excl. GST** which is **(-) 15.03 % below the estimated cost put to tender of Rs. 1,02,26,796.00 (Excl. GST).**

2. सहायक महाप्रबंधक (अभियान्त्रिकी-सि.) भारतीय विमानपत्तन प्राधिकरण, जोधपुर हवाई अड्डा, जोधपुर इस कार्य के प्रभारी अभियंता होंगे। आपसे निवेदन है आप अपनी ओर से एक विश्वसनीय प्रतिनिधि नियुक्त करें जो करारनामे पर हस्ताक्षर करने के लिए अधिकृत हो तथा वह दिनांक **04/04/2026** तक सहायक महाप्रबंधक (अभियान्त्रिकी-सि.), भारतीय विमानपत्तन प्राधिकरण, जोधपुर हवाई अड्डा, जोधपुर के कार्यालय में उपस्थित हो तथा करारनामे को पूरा करें। ठेके का करारनामा 500/-रु के नोन ज्युडिशियल स्टैम्प पेपर पर निष्पादित किया जाएगा जिसका खर्चा आपके द्वारा उठाया जाएगा।

Asst. General Manager (Engg.-Civil) Airports Authority of India, Civil Enclave, Jodhpur will be Engineer-in-Charge of the work. You are requested to depute your accredited representative empowered to sign the contract agreement on your behalf & present in the office of the Asst. General Manager (Engg.- Civil) Airports Authority of India, Civil Enclave, Jodhpur to sign & complete the agreement on or before **04/04/2026**. The contract agreement shall be executed on a non-judicial stamp paper of value of Rs. 500/- and the cost of the stamp paper shall be borne by you.

3. कृपया इस पत्र के जारी होने की तिथि से **30 दिनों के भीतर सुरक्षा जमा राशि के रु. 8,68,951.90/-** (आठ लाख अड़सठ हजार नौ सौ इक्यावन रुपये और नब्बे पैसे मात्र) जमा करायें, अन्यथा सुरक्षा जमा राशि पर जमा करने की देरी की अवधि के लिए 12 प्रतिशत प्रति वर्ष की दर ब्याज लगाया जाएगा (वापसी नहीं होगी) तथा अनुबंध दस्तावेज की शर्तों के अनुसार आपके रनिंग बिल से ब्याज सहित काट लिया जाएगा।

Please deposit **Rs. 8,68,951.90/- (Rs. Eight lakh sixty-eight thousand nine hundred fifty-one and ninety paise Only)** towards Security Deposit within 30 days from the date of issue of this letter, failing which, interest at 12% per annum on Security Deposit amount would be levied (non-refundable) for delayed period of submission the same shall be deducted from your running bill as per conditions of the contract document.

24/03/2026



4. आपसे निवेदन है कि आप केन्द्रीय और राज्य सरकारों के 1970 के अधिनियम अनुबन्ध श्रम नियम 1971 के केन्द्रीय नियम (नियमन तथा उन्मूलन) एवं केन्द्र तथा राज्य सरकार के न्यूनतम वेतन अधिनियम और नियमों का अद्यतन संशोधनों के साथ अनुपालन करें।

You are requested to comply with the Provision of Contract labour (Regulation and Abolition) Act of 1970 and Contract Labour (Regulation and Abolition) Central Rules 1971 & minimum Wages Act & Rules there of Central & State Governments with up to date amendments.

5. श्रम लाइसेंस के उपबंधों के अनुसार प्राप्त ठेका श्रम (विनियम एवं उन्मूलन) अधिनियम 1970 सहित विभिन्न श्रम कानूनों के अन्तर्गत सभी आवश्यक प्राधिकारियों/अनुमतियों संबंधित प्राधिकारियों से प्राप्त करने एवं मानने का सम्पूर्ण दायित्व ठेकेदार का होगा।

It shall be the sole liability of the contractor to obtain and to abide by all necessary licenses/permissions from the authorities concerned as provided under the various labour legislations including the labour license obtained as per the provisions of the Contract Labour (Regulation & Abolition) Act, 1970.

6. ठेकेदार नियमित तथा प्रभावी पर्यवेक्षण को सुनिश्चित करेगा और उनके द्वारा तैनात किये गये कार्मिक पर नियंत्रण एवं ठेके के दायित्वों को पूरा करने के लिए उपयुक्त निर्देश देगा।

The contractor shall ensure regular and effective supervision and control of the personnel deployed by him and gives suitable direction for undertaking the contractual obligations.

7. आपको निर्देश दिया जाता है कि **प्रबंधक (अभि.-सिविल)** भारतीय विमानपत्तन प्राधिकरण, जोधपुर हवाईअड्डा, जोधपुर से मिले वह आपको साइट सौंपने की व्यवस्था करेंगे। कृपया नोट कर ले कि काम करने का निर्धारित समय **पैंतालीस (45) दिवस** है जो कि जो कि इस पत्र के जारी होने की तिथि से 10 दिन बाद सेवा साइट सौंपने की तिथि में से जो भी पहले हो प्रभावी होगा।

You are directed to contact **Manager (Engg.-Civil)**, Airports Authority of India, Civil Enclave, Jodhpur immediately, who will arrange to hand over the site to you. Please note that the time allowed for carrying out the work is **Forty Five (45) Days**, which shall be reckoned from 10th day after issue of this letter or from the date of handover of site which ever is earlier.

8. इस ठेके के संबन्ध में आगे का कोई भी पत्राचार सहायक महाप्रबंधक (अभि.-सिविल), भारतीय विमानपत्तन प्राधिकरण, जोधपुर हवाई अड्डा, जोधपुर के पते पर किया जाए।

Any further correspondence in connection with this contract should normally be addressed to Asst. General Manager (Engg.-Civil), Airports Authority of India, Civil Enclave, Jodhpur.

9. ठेके की **त्रुटि दायित्व अवधि चौबीस (24) महीने** है जो कि कार्य समाप्ति की तिथि से गिना जाएगा।

The defect liability period is **Twenty Four (24) Months** after the actual date of completion.

कृपया पावती भेजें /Please acknowledge the receipt.

संलग्न/ Encl : मात्रा की अनुसूची/ Schedule of Quantity

धन्यवाद /Thanking you

नोट : हिंदी तथा अंग्रेजी संस्करण में अंतर पाए जाने पर अंग्रेजी संस्करण मान्य होगा।

Note: If there any discrepancy is observed in Hindi and English version, the English version will be considered.

संलग्न— यथोपरि।

भवदीय/Yours Faithfully


(Ashok Choudhary)

सहायक महाप्रबंधक (अभि.-सिविल)/Asst.General Manger (Engg.-Civil)

भारतीय विमानपत्तन प्राधिकरण/Airports Authority of India

सिविल एन्क्लेव जोधपुर/Civil Enclave Jodhpur



प्रतिलिपि :-

1. कार्यकारी निदेशक (अभि.), उ.क्षे निगमित मुख्यालय न्यु एटीएस कॉम्प्लेक्स, राजीव गांधी भवन नई दिल्ली
2. क्षेत्रीय कार्यकारी निदेशक उ.क्षे, क्षेत्रीय मुख्यालय, नया ATS कॉम्प्लेक्स IGI हवाई अड्डा, नई दिल्ली ।
3. महाप्रबन्धक (अभि.-परियोजना), भारतीय विमानपत्तन प्राधिकरण, एमपी हवाई अड्डा, उदयपुर ।
4. विमानपत्तन निदेशक, भारतीय विमानपत्तन प्राधिकरण, सिविल एन्क्लेव जोधपुर ।
5. उप महाप्रबन्धक (अभि.-सिविल), भारतीय विमानपत्तन प्राधिकरण, सिविल एन्क्लेव जोधपुर ।
6. उप महाप्रबन्धक (अभि.-वि.), भारतीय विमानपत्तन प्राधिकरण, सिविल एन्क्लेव जोधपुर ।
7. सहायक महाप्रबन्धक (वित्त), भारतीय विमानपत्तन प्राधिकरण, सिविल एन्क्लेव जोधपुर ।
8. प्रबन्धक (अभि.-सिविल), भारतीय विमानपत्तन प्राधिकरण, सिविल एन्क्लेव जोधपुर ।
9. सहायक श्रम आयुक्त, ऑफिसर मैस के सामने, जोधपुर ।
10. करारनामा प्रति ।

भवदीय / Yours Faithfully

B
24/03/2024

(Ashok Choudhary)

सहायक महाप्रबन्धक (अभि.-सिविल)/Asst.General Manger (Engg.-Civil)
भारतीय विमानपत्तन प्राधिकरण/Airports Authority of India
सिविल एन्क्लेव जोधपुर/Civil Enclave Jodhpur

Item Rate Boq

Tender Inviting Authority: Asstt. General Manager (Engg.-Civil), AAJ Civil Enclave, Jodhpur.

Name of Work: Construction of Stone Signage and Other Miscellaneous works at New Terminal Building Jodhpur Airport.

Tender ID: 2025_AAJ_288742_1

Name of the Bidder/ Building Firm/ Company:

M/S M. L. BROTHAR

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be updated after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only.)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Quoted Currency in INR / Other Currency	RATE (excluding GST) in Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT	TOTAL AMOUNT In Words		
1	2	4	5	12	13	54	55		
1.00	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, for all lifts, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.	129.00	Cum	INR	200.00	25800.00	INR Twenty Five Thousand Eight Hundred Only		
2.00	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering. Lead up to 50 and for all lift	102.00	Cum	INR	200.00	20400.00	INR Twenty Thousand Four Hundred Only		
3.00	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering. All work up to plinth level: 1:4:8 (1 Cement : 4 coarse sand (zone-III) derived from natural sources : 8 graded stone aggregate 40 mm nominal size derived from natural sources)	17.00	Cum	INR	5000.00	85000.00	INR Eighty Five Thousand Only		
4.00	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement. All work up to plinth level : 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	35.10	Cum	INR	6500.00	98150.00	INR Ninety Eight Thousand One Hundred & Fifty Only		
5.00	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. above plinth level up to floor five level, excluding cost of centering, shuttering, finishing and reinforcement : 1:1.5:3 (1 cement : 1.5 coarse sand/zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	10.00	Cum	INR	7000.00	70000.00	INR Seventy Thousand Only		
6.00	Centering and shuttering including strutting, propping etc. and removal of form for Foundations, footings, bases of columns, etc. for mass concrete	61.00	Sqm	INR	400.00	24400.00	INR Twenty Four Thousand Four Hundred Only		
7.00	Centering and shuttering including strutting, propping etc. and removal of form for lintels, beams, plinth beams, girders, bressumers and cantilevers	86.00	Sqm	INR	400.00	34400.00	INR Thirty Four Thousand Four Hundred Only		
8.00	Centering and shuttering including strutting, propping etc. and removal of form for Columns, Pillars, Piers, Abutments, Posts and Struts	29.00	Sqm	INR	400.00	11600.00	INR Eleven Thousand Six Hundred Only		
9.00	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-5000 or more.	1812.00	kg	INR	100.00	181200.00	INR One Lakh Eighty One Thousand Two Hundred Only		
10.00	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. Thermo-Mechanically Treated bars of grade Fe-5000 or more.	1200.00	kg	INR	100.00	120000.00	INR One Lakh Twenty Thousand Only		
11.00	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement Mortar 1:6 (1 cement : 6 coarse sand)	36.18	cum	INR	7000.00	253260.00	INR Two Lakh Fifty Three Thousand Two Hundred Only		
12.00	Brick work with common burnt clay modular bricks of class designation 7.5 in foundation and plinth in: Cement Mortar 1:6 (1 cement : 6 coarse sand).	11.32	cum	INR	7000.00	79240.00	INR Seven Thousand Nine Hundred Twenty Four Only		
13.00	Stone work in plain ashlar in superstructure upto floor five level in cement mortar 1:6 (1 cement : 6 coarse sand) including pointing with cement mortar 1:2 (1 white cement : 2 stone dust) with an admixture of pigment matching the stone shade. Both face dressed White sand stone	13.38	cum	INR	9000.00	120420.00	INR One Lakh Twenty Four Thousand Two Hundred & Twenty Only		
14.00	Stone work plain ashlar in arches in super structure upto floor V level in cement mortar 1:3 (1 cement : 3 coarse sand) including centering, shuttering and pointing with white cement mortar 1:2 (1 white cement : 2 stone dust) with an admixture of pigment matching the stone shade. Both face dressed White sand stone	4.68	cum	INR	10000.00	46800.00	INR Forty Six Thousand Eight Hundred Only		
15.00	Stone work plain in copings, cornices, string courses and plinth courses, upto 75 mm thick in Cement mortar 1:6 (1 cement : 6 coarse sand), including pointing with white cement mortar 1:2 (1 white cement : 2 stone dust) with an admixture of pigment matching the stone shade. Red sand stone	0.70	cum	INR	10000.00	7000.00	INR Seven Thousand Only		
16.00	Providing and fixing stone jali 40 mm thick throughout in cement mortar 1:3 (1 cement : 3 coarse sand), including pointing in white cement mortar 1:2 (1 white cement : 2 stone dust) with an admixture of pigment, matching the stone shade. jali slab without any chamfers etc. Red sand stone	55.96	sqm	INR	8000.00	447680.00	INR Four Lakh Seven Thousand Eight Hundred & Eighty Only		
17.00	Stone work (machine cut edges) for wall lining etc. (veneer work) upto 10 metre height, backing filled with a grout of average 12 mm thick cement mortar 1:3 (1 cement : 3 coarse sand) including pointing in white cement mortar 1:2 (1 white cement : 2 stone dust) with an admixture of pigment matching the stone shade. (To be secured to the backing and the sides by means of cramps and pins which shall be paid for separately) : Red sand stone - exposed face fine dressed with rough backing. 40 mm thick	45.00	sqm	INR	8000.00	360000.00	INR Three Lakh Sixty Thousand Only		
18.00	Providing and fixing stainless steel cramps of required size and shape for anchoring stone wall lining to the backing or securing adjacent stones in stone wall lining in cement mortar 1:2 (1 cement : 2 coarse sand), including making the necessary chases in stone and holes in walls wherever required	75.00	kg	INR	860.00	64500.00	INR Sixty Four Thousand Five Hundred Only		

BS
DGM/ey

Sl. No.	Item Description	Quantity	Units	Quoted Currency in INR / Other Currency	RATE (excluding GST) in Figures To be entered by the Bidder Rs. p	TOTAL AMOUNT	TOTAL AMOUNT In Words
19.00	Providing and fixing partition upto ceiling height consisting of G.I. frame and required board, including providing and fixing of frame work made of special section power pressed/ roll form G.I. sheet with zinc coating of 120 gms/sqm(both side inclusive), consisting of floor and ceiling channel 50 mm wide having equal flanges of 32 mm and 0.50 mm thick, fixed to the floor and ceiling at the spacing of 610 mm centre to centre with dash fastener of 12.5 mm dia meter/ 50 mm length or suitable anchor fastener/or metal screws with nylon plugs and the studs 48 mm wide having one flange of 34 mm and other flange 36 mm and 0.50 mm thick fixed vertically within flanges of floor and ceiling channel and plated at a spacing of 610 mm centre to centre by 6 mm dia bolts and nuts, including fixing of studs along both ends of partition fixed flush to wall with suitable anchor fastener or metal screws with nylon plugs at spacing of 450 mm centre to centre, and fixing of boards to both side of frame work by 25 mm long dry wall screws on studs, floor and ceiling channels at the spacing of 300 mm centre to centre. The boards are to be fixed to the frame work with joints staggered to avoid through cracks. M.S. fixing channel of 90 mm width (0.9 mm thick having two flanges of 9.5 mm each) to be provided at the horizontal joints of two boards, fixed to the studs using metal to metal flat head screws, including jointing and finishing to a flush finish with recommended jointing compound/jointing tape, angle beads at corners (125 mm x 25 mm x 0.5 mm), joint finisher and two coats of primer suitable for board as per manufacturer's specification and direction of engineer in charge all complete. 75 mm overall thickness partition with 12.5 mm thick double skin fire rated glass Reinforced Gypsum (GRG) plaster board conforming to IS: 2095; part 3 (Board with BIS certification marks)	248.50	sqm	INR	3000.00	745800.00	INR Seven Lakh Forty Five Thousand Five Hundred Only
20.00	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	629.00	kg	INR	140.00	88060.00	INR Eighty Eight Thousand Eighty Only
21.00	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolting with special shaped washers etc. complete. Hot finished welded type tubes	5164.00	kg	INR	140.00	722860.00	INR Seven Lakh Twenty Two Thousand Nine
22.00	Providing and fixing stainless steel (Grade 304) railing made of hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fixing the same with necessary stainless steel nuts and bolts complete, (i/c fixing the railing with necessary accessories & stainless steel dash fasteners, stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-in-Charge, (for payment purpose only) weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.).	2453.00	kg	INR	700.00	1717100.00	INR Seventeen Lakh Seventeen Thousand One Hundred Only
23.00	Providing and fixing precast/aluminized iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-Charge) of total coated thickness 0.50 mm (base metal of minimum 0.45 mm thickness with total coating thickness of 0.05mm) with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling/self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of putties, rollers and trusses and including cutting to size and shape wherever required.	27.00	sqm	INR	1000.00	27000.00	INR Twenty Seven Thousand Only
24.00	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade. Two or more coats on new work	200.66	Sqm	INR	150.00	30099.00	INR Thirty Thousand Nine Hundred Nine
25.00	Wall painting with acrylic emulsion paint, having VOC (Volatile Organic Compound) content less than 50 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour. Two coats	497.00	sqm	INR	200.00	99400.00	INR Ninety Four Thousand Five Hundred Only
26.00	Supplying at site - Welded steel wire fabric of required width having rectangular mesh painted with two or more coats of enamel paint of approved shade over a coat of primer (Priming & Painting to be paid for separately).	284.00	kg	INR	200.00	56800.00	INR Fifty Six Thousand Eight Hundred Only
27.00	Welded steel wire fabric fencing with posts of specified material and of standard design placed and embedded in cement concrete blocks 45x45x 60 cm of mix: 1:1.5:10 (1 cement:5 fine sand : 10 graded concrete blocks 70x45x50 cm of the same mix, last but one end post and corner post shall be struted at both sides and end post on one side only and struts embedded in cement concrete blocks 70x45x50 cm of the same mix, provided with welded steel wire fabric fixed between the posts fitted and fixed with G.I. staples on wooden plugs or tied to 6 mm bar ribs with G.I. binding wire (cost of posts, welded steel wire fabric, painting, earth work in excavation and concrete to be paid for separately).	81.00	sqm	INR	550.00	44550.00	INR Forty Four Thousand Five Hundred & Fifty Only
28.00	Providing and fixing G.I. chain link fabric fencing of required width in mesh size 50x50 mm including strengthening with 2 mm dia wire or nuts, bolts and washers as required complete as per the direction of Engineer-in-charge. Made of G.I. wire of dia 4 mm	216.00	sqm	INR	600.00	129600.00	INR Twelve Thousand Nine Hundred Six
29.00	12 mm cement plaster of mix : 1:6 (1 cement: 6 fine sand)	75.00	Sqm	INR	220.00	16500.00	INR Sixteen Thousand Five
30.00	15 mm cement plaster on the rough side of single or half brick wall of mix :: 1:6 (1 cement: 6 fine sand)	75.00	Sqm	INR	300.00	22500.00	INR Twenty Two Thousand Five
31.00	Providing & Fixing Corro Steel Signage Fabricated from sheets and welded to create a hollow 3D form, usually 2 inches deep. This material develops a protective, rustic patina over time when exposed to the elements. Backer Panel: A clear or translucent acrylic sheet is installed at the back of the letter to diffuse the LED light evenly and protect the internal components and lighting LED module. Waterproof, low-voltage LED lights are mounted inside the hollow return, facing the backer panel. They are chosen for their longevity and energy efficiency. The LED's connect via wiring that typically exits through the back of each letter to an external power supply (transformer), converting standard line voltage (110V-230V) to low voltage, and Wiring is typically routed through pre-drilled holes in the mounting wall or via a gusset for a clean finish as per the direction of the Engineer-in-charge. The signage consists of bilingual Hindi & English letters as " विद्यया ढातुः सत्यं & ज्ञानमपि अमृतम् and AAI logo. The body of each letter should be of minimum 600 mm height. The signage of AAI logo should be of base 2.0 meter and height as 1.07 meter as per direction of EIC. The reference drawings is attached in tender document.	2.00	Job	INR	300000.00	600000.00	INR Six Lakh Only
32.00	Providing and fixing 12 mm thick clear toughened glass with holes and cutouts, shape cutting as require, as per approved pattern fixed with necessary stainless steel stud fixing welded to SS pipe necessary screw, gaskets etc. complete in all types of railing system in required shapes & size as per particular specification, design drawing and directions of Engineer-in- Charge.	243.00	sqm	INR	3000.00	729000.00	INR Seven Lakh Twenty Nine Thousand Only
33.00	Providing and fixing glass film of design Digital graphics of brand 3M or equivalent as per directions of Engineer-in-Charge.	1100.00	sqm	INR	1190.00	1309000.00	INR Thirteen Lakh Nine Thousand
34.00	Making of frames for movable airfirt & partitions, cabinetry box etc with providing and fixing 19 mm thick ply veneering on both side (BWR) of approve make in required size with necessary screws, and nuts wherever necessary etc. complete as per direction of Engineer-in-charge.	53.00	Sqm	INR	1500.00	79500.00	INR Seventy Nine Thousand Five Hundred Only
35.00	Providing and fixing vertical blinds of 100mm louver width made of dust and stain repellent fabric with matching valances of required colour and shade (make Visa, MAC Decor Ltd. Aeroluxor equivalent including self adjusting runners, bottom weights, link chain and tilt chain, installation brackets etc. as per manufacturers specifications required for smooth functioning of blinds in all respect & satisfaction of Engineer-in-charge. (Area of measurement will be extreme dimensions of fully opened blind only.)	45.00	Sqm	INR	800.00	36000.00	INR Thirty Six Thousand Only
36.00	Supply of 4c x 10 sqmm XLPE insulated, PVC sheathed aluminium multi stranded conductor armoured power cable of 1.1 KV grade conforming to IS 7308 (part I) with upto date amendments etc as required.	100.00	Meter	INR	500.00	50000.00	INR Fifty Thousand Only

ACM (E-4)

Sl. No.	Item Description	Quantity	Units	Quoted Currency in INR / Other Currency	RATE (excluding GST) in Figures To be entered by the Bidder Rs. / P	TOTAL AMOUNT	TOTAL AMOUNT In Words
37.00	Supply of 63 mm (OD), PN-6, PE 80 size ISI marked, HDPE pipe conforming to IS-4984-1995 with up to date amendments and conforming to tender's technical specifications, terms & conditions i/c loading, unloading etc. complete as required.	100.00	Meter	INR	350.00	35000.00	INR Thirty Five Thousand Only
38.00	Laying of 63 mm Dia HDPE pipe in ground including trenching (80 cm deep & 30 cm Wide), refilling & making good the same as required.	100.00	Meter	INR	100.00	10000.00	INR Ten Thousand Only
39.00	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size in the existing RCC/ HUIHE/ METAL/HDPE pipe/on surface as required. Up to 35 sq.mm	100.00	Meter	INR	100.00	10000.00	INR Ten Thousand Only
40.00	Supplying and making end termination with brass compression gland and copper/aluminum lugs according to the cable for 4 x 10 sqmm (25mm) aluminum cable. size for PVC/XLPE insulated and PVC sheathed armoured copper/ aluminum conductor cable of 1.1 KV grade as required.	2.00	Set	INR	550.00	1100.00	INR One Thousand One Hundred Only
41.00	STC of outdoor type Cable termination / looping pole box of minimum size 276mm x 186mm x 186mm suitable for termination of 4X10sq. mm Al. Armoured Cables made of thermoplastic polycarbonate having minimum IP65 protection alongwith clamp, 4 pole isolator (01 No.), single pole MCBS (Min. 03 Nos.), connectors, DIN rail channel etc. including making suitable fring arrangements etc. complete as required.	1.00	Each	INR	40000.00	40000.00	INR Forty Thousand Only
42.00	Facade lighting of the stone signage including supply of light fixtures, wiring, mounting arrangement, and all required accessories to make fully functional the system of facade lighting, all accessories, all inclusive as per concept approved by EIC.	1.00	Job	INR	40000.00	40000.00	INR Forty Thousand Only
Total in Figures						8689519.00	INR Eighty SIX Lakh Eighty Nine Thousand Five Hundred & Nineteen Only
Quoted Rate in Words		INR Eighty Six Lakh Eighty Nine Thousand Five Hundred & Nineteen Only					

3
BAGMEE-1

संख्या: भा.वि.प्रा./अभि.-सि./जोधपुर/एन.टी.बी./स्टोन/2026-27/

दिनांक: 27.03.2026

Ref. No: AAI/ENGG (C)/Jodhpur/NTB/Stone/2026-27/

Date: 27.03.2026

सेवा मे,
मैसर्स एम एल ब्रदर,
एफ 22/117 सेक्टर 3,
रोहिणी 110085, दिल्ली
ई-मेल —ankurmadaan88@gmail.com

To,
M/s M L Brother,
F22/117 Setor 3,
Rohini 110085, Delhi

कार्य का नाम : जोधपुर हवाई अड्डे के नए टर्मिनल भवन में पत्थर के साइनबोर्ड का निर्माण और अन्य विविध कार्य

Name of Work: Construction of Stone Signage and Other Miscellaneous works at New Terminal Building
Jodhpur Airport.

Dear Sir,


Reference may please be made to above mention work for which work order was issued vide letter no AAI/ENGG(C)/Jodhpur/NTB/Stone/2026-27/3903-3913 dated 24.03.2026. In this regard following is submitted,

Sl No	Para no 3 on page no 1 mentioned as	Para no 3 on page no 1 to be read as
1	कृपया इस पत्र के जारी होने की तिथि से 30 दिनों के भीतर सुरक्षा जमा राशि के रु. 8,68,951.90/- (आठ लाख अड़सठ हजार नौ सौ इक्यावन रुपये और नब्बे पैसे मात्र) जमा कराये, अन्यथा सुरक्षा जमा राशि पर जमा करने की देरी की अवधि के लिए 12 प्रतिशत प्रति वर्ष की दर ब्याज लगाया जाएगा (वापसी नहीं होगी) तथा अनुबंध दस्तावेज की शर्तों के अनुसार आपके रनिंग बिल से ब्याज सहित काट लिया जाएगा। Please deposit Rs. 8,68,951.90/- (Rs. Eight lakh sixty-eight thousand nine hundred fifty-one and ninety paise Only) towards Security Deposit within 30 days from the date of issue of this letter, failing which, interest at 12% per annum on Security Deposit amount would be levied (non-refundable) for delayed period of submission the same shall be deducted from your running bill as per conditions of the contract document.	कृपया इस पत्र के जारी होने की तिथि से 30 दिनों के भीतर सुरक्षा जमा राशि के रु. 8,68,951.90/- (आठ लाख अड़सठ हजार नौ सौ इक्यावन रुपये और नब्बे पैसे मात्र) जमा कराये, अन्यथा सुरक्षा जमा राशि अनुबंध दस्तावेज की शर्तों के अनुसार आपके रनिंग बिल से ब्याज सहित काट लिया जाएगा। Please deposit Rs. 8,68,951.90/- (Rs. Eight lakh sixty-eight thousand nine hundred fifty-one and ninety paise Only) towards Security Deposit within 30 days from the date of issue of this letter, failing which shall be deducted from your running bill as per conditions of the contract document.

Note :- 1. All other terms and condition of work order will remains same.
2. This will be part of contract agreement.

Thanking you,

भवदीय/Your Sincerely


(अशोक चौधरी / Ashok Choudhary)

सहायक महाप्रबंधक (अभि.-सिविल.) / AGM (Engg.-C)

प्रतिलिपि :-

1. कार्यकारी निदेशक (अभि.), उ.क्षे निगमित मुख्यालय न्यु एटीएस कॉम्प्लेक्स, राजीव गांधी भवन नई दिल्ली
2. क्षेत्रीय कार्यकारी निदेशक उ.क्षे, क्षेत्रीय मुख्यालय, नया ATS कॉम्प्लेक्स IGI हवाई अड्डा , नई दिल्ली ।
3. महाप्रबंधक (अभि.-परियोजना), भारतीय विमानपत्तन प्राधिकरण, एमपी हवाईअड्डा, उदयपुर ।
4. विमानपत्तन निदेशक, भारतीय विमानपत्तन प्राधिकरण, सिविल एन्क्लेव जोधपुर ।
5. उप महाप्रबंधक (अभि.-सिविल), भारतीय विमानपत्तन प्राधिकरण, सिविल एन्क्लेव जोधपुर ।
6. उप महाप्रबंधक (अभि.-वि.), भारतीय विमानपत्तन प्राधिकरण, सिविल एन्क्लेव जोधपुर ।
7. सहायक महाप्रबंधक (वित्त), भारतीय विमानपत्तन प्राधिकरण, सिविल एन्क्लेव जोधपुर ।
8. प्रबंधक (अभि.-सिविल), भारतीय विमानपत्तन प्राधिकरण, सिविल एन्क्लेव जोधपुर ।
9. सहायक श्रम आयुक्त, ऑफिसर मैस के सामने, जोधपुर ।
10. करारनामा प्रति ।

Signature Not Verified

Digitally signed by ASHOK

CHOUDHARY

Date: 2023.05.08 12:09:24 IST

Location: eProcurement System for
Central PSUs

कार्यालय प्रभारी अभियंता (परियोजना), सिविल एन्क्लेव, जोधपुर – 342011 E-Mail - proj.cto@aaai.aero
O/o Engineer-in-Charge (Project), Civil Enclave, Jodhpur -342011, E-Mail - proj.cto@aaai.aero

“हिन्दी पत्रों का स्वागत है।”