



संदर्भ सं.: भाविप्रा/पक्षे/मुंबई/समप्र(अभि-वि.)-एटीएस/सीडब्ल्यू/काआ-01/2026-27/58  
Ref.No.: AAI/WR/MUM/AGM(E-E)-ATS/CW/WO-01/2026-27/58

दिनांक : 12.06.2026  
Date: 12.06.2026

**रजिस्टर्ड डाक /स्वीकृति**

प्रति / To,  
मेसर्स.एआरसी सर्विसेस, / M/s. ARC Services,  
ए-123/3, जैतपुर एक्सटेंशन, / A-123/3, Jaitpur Extn.,  
कालिंदी कुंज रोड, / Kalindi Kunj Road,  
बदरपुर, नई दिल्ली - 110044 / Badarpur, New Delhi - 110044.

विषय/Sub : "मुंबई के एटीएस कॉम्प्लेक्स में फायर पंप सेट और फायर हाइड्रेंट सिस्टम के इलेक्ट्रिकल कंट्रोल पैनल का प्रतिस्थापन और पोर्टा केबिन में फायर हाइड्रेंट सिस्टम की व्यवस्था करना।" / "Replacement of Fire pump sets along with Electrical Control panel of fire hydrant system and at ATS complex, Mumbai and provision of fire hydrant system at Porta cabin."

संदर्भ : 1. आपका वित्तीय बोली द्वारा निविदा आईडी : निविदा आई.डी. : 2026\_भाविप्रा\_270008\_1 दिनांक 07.05.2026 को खुला।

Ref.: 1. Your Financial Bid vide Tender ID.: 2026\_AAI\_270008\_1 opened on 07.05.2026.

महोदय / Dear Sir,

- उपरोक्त कार्य के लिए आपकी निविदा अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से आपके द्वारा उद्धृत मद दरों पर स्वीकार की जाती है जो कुल **रु. 31,97,250.00 (रुपये इकतीस लाख सत्तानवे हजार दो सौ पचास मात्र) (जीएसटी रहित)**, जो निविदा में रखी गई अनुमानित लागत **रु. 38,42,543.00 (जीएसटी रहित)** से **16.79% नीचे** है। वैध टैक्स चालान के खिलाफ जीएसटी का भुगतान किया जाएगा। कृपया कर चालान में महाराष्ट्र राज्य के लिए **AAI GST no. 27AAACA6412D1Z8** उद्धृत करें।
- Your tender for the work mentioned above is hereby accepted on behalf of the Chairman, Airports Authority of India at the item rates quoted by you totaling to **Rs. 31,97,250.00 (Rupees Thirty One Lakhs Ninety Seven Thousand Two Hundred Fifty only) (Excluding GST)** which is **16.79% below** the estimated cost put to tender of **Rs. 38,42,543.00 (Excluding GST)**. GST will be paid against Valid Tax invoice. Please quote **AAI GST no.27AAACA6412D1Z8** for Maharashtra State in Tax Invoice.
- सहायक महाप्रबंधक (अभि. विद्युत), भाविप्रा, एटीएस कॉम्प्लेक्स, मुंबई कार्य के प्रभारी अभियंता होंगे। आपसे अनुरोध है कि आप सहायक महाप्रबंधक (अभि. विद्युत), भाविप्रा, एटीएस कॉम्प्लेक्स, मुंबई के कार्यालय में दिनांक **26.06.2026** तक उपस्थित रहकर हस्ताक्षर करने तथा करार की कार्यवाही पूर्ण करने का कष्ट करें। ठेका करार का निष्पादन 100/- रुपये (केवल एक सौ रुपये) के गैर-न्यायिक स्टैम्प पेपर पर किया जाएगा तथा स्टैम्प पेपर का खर्च आपके द्वारा वहन किया जाएगा।
- Asstt.General Manager (Engg.-E.), AAI, ATS Complex, Mumbai shall be the Engineer-In-Charge of the work. You are requested to attend the office of the Asstt.General Manager (Engg.-E.), AAI, ATS Complex, Mumbai by **26.06.2026** to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs.100/- (Rupees One hundred only) and the cost of the stamp paper shall be borne by you.
- आपसे अनुरोध है कि इस पत्र के जारी होने की तिथि से 15 दिनों के भीतर निष्पादन गारंटी जो टेंडर राशि के 5% है को प्रस्तुत करें अथवा इस पत्र के जारी होने की तिथि से 10 दिनों के भीतर सुरक्षा राशि जो टेंडर राशि के 10 % है को प्रस्तुत करें, अन्यथा अनुबंध के पृष्ठ 58 पर शर्त के अनुसार आपके बिल से काटा जाएगा।
- You are requested to furnish performance guarantee @ 5% of tendered amount within 15 days from the date of issue of this letter or furnish security deposit @ 10% of tendered amount within 10 days from the date of issue of this letter, failing which the same will be deducted from your bill as per condition on page 58 of the contract document.

CONTD. 2/-

:: 2 ::

4. आपसे अनुरोध है कि ठेका श्रम (विनियमन और उन्मूलन) अधिनियम 1970 और ठेका श्रम (विनियमन और उन्मूलन) केंद्रीय नियमावली 1971 और केंद्रीय एवम राज्य सरकारों के न्यूनतम वेतन तथा उससे संबंधित अन्य नियमों के प्रावधानों का पालन करें।
4. You are requested to comply with the provisions of contract labour (Regulation and abolition) Act of 1970 and contract labour (Regulation & abolition) Central rules 1971 and minimum wages Act & rules of central and state Governments with its upto date amendments thereof.
5. आपको यह भी निर्देश दिया जाता है कि आप तुरंत प्रबंधक (अभि.वि.), भाविप्रा, एटीएस कॉम्प्लेक्स, मुंबई से संपर्क करें जो आपको साइट सौंपने की व्यवस्था करेंगे।
5. You are also directed to contact Manager (Engg.-E.), AAI, ATS Complex, Mumbai immediately who will arrange to hand over the site to you.
6. कृपया यह भी नोट कर ले कि निविदा के अनुसार कार्य निष्पादन हेतु अनुमत समय **04 (चार) माह** है, जिसकी गणना **22.06.2026** से **21.10.2026** तक की जाएगी।
6. Please note that the time allowed for carrying out the work is **04 (Four) months**, which shall be reckoned from **22.06.2026** to **21.10.2026**.
7. इस ठेके के संबंध में कोई और पत्राचार सामान्य रूप से सहायक महाप्रबंधक (अभि.विद्युत), भाविप्रा, एटीएस कॉम्प्लेक्स, मुंबई को संबोधित किया जाना चाहिए।
7. Any further correspondence in connection with the contract should normally be addressed to the Asstt.General Manager (Engg.-E.), AAI, ATS Complex, Mumbai.
8. ऊपर उल्लिखित सभी पत्र अनुबंध का हिस्सा होंगे।
8. All the letters referred above shall form part of contract.
9. कृपया इस पत्र की प्राप्ति सूचना दें तथा इसके साथ संलग्न अनुप्रति पर हस्ताक्षर करके टोकन के प्रतिग्रहण के रूप में अधोहस्ताक्षरी को वापस भेजे।
9. Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.
10. कार्य आदेश के संबंध में किसी प्रकार की टंकनीय त्रुटी/विसंगति होने पर अंग्रेजी संस्करण मान्य होगा।
10. With reference to this work order, if in case of any typographical mistake / discrepancy arise, the English version shall prevail.

धन्यवाद, / Thanking You,

भवदीय / Yours faithfully,

सहायक महाप्रबंधक (अभि.-विद्युत),  
Asstt.General Manager (Engg.-E.),

कृते तथा ओर से, अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण  
For and on behalf of Chairman, Airports Authority of India

संलग्न/Encl.: 1. मात्रा का बिल ( बी.ओ.क्यू.) / Bill of Quantities (B.o.Q.)

सहायक महाप्रबंधक (अभि.-विद्युत)  
Asstt. Gen. Manager (Engg.-E.)  
भारतीय विमानपत्तन प्राधिकरण, ए.टी.एस. कॉम्प्लेक्स  
Airports Authority of India, A.T.S. Complex,  
मुंबई/Mumbai - 400 099.

| <p style="text-align: center;"><b>AIRPORTS AUTHORITY OF INDIA</b><br/>ENGINEERING ELECTRICAL WING, ATS COMPLEX, MUMBAI - 400 099.</p> <p style="text-align: center;"><b>Name of Work : Replacement of Fire pump sets along with Electrical Control panel of fire hydrant system and at ATS complex, Mumbai and provision of fire hydrant system at Porta cabin.</b></p> <p style="text-align: center;">Tender ID: 2026_AAI_270008_1</p> <p style="text-align: center;"><b>Bill of Quantities (B.o.Q.)</b></p> |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |       |      |                      |                        |
|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|------|----------------------|------------------------|
| Sr. No.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | Description of items                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | Qty.  | Unit | Rate (Excl. GST) Rs. | Amount (Excl. GST) Rs. |
| 1                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | <p><b>Subhead-1: Replacement of fire pumps and panel</b></p> <p>Fabrication, supply, installation testing &amp; commissioning of Electrical control panel of cubical construction, floor mounted type, fabricated out of 2 mm. thick CRCA sheet, compartmentalised with hinged lockable doors, dust and vermin proof, powder coated of approved shade after 7 tank treatment process, cable alley, inter- connection with suitable size copper conductor cable/solid copper strip, having switchgears and accessories, mountings and internal wiring, earth terminals, numbering etc. complete in all respect, suitable for main fire pump, pressurisation pump &amp; diesel pump set complete as per CPWD specification with following in coming connect with suitable rating bus coupler and Outgoings: suitable for operation on 415V, 3 phase, 50Hz Ac Supply with enclosure protection class IP 42 as required:</p> <p><b>Incomer-1</b></p> <p>400A, 50KA 4 Pole MCCB, Ics=100% Icu rating</p> <p>Digital Voltmeter 0-500V with selector switch Ammeter (0-400 A) with selector switch &amp; CTs, etc.</p> <p>LED Type RYB phase indicating lamps, ON, OFF, trip indicating lamps</p> <p>Set of Copper Bus Bar 500A</p> <p><b>Incomer-2</b></p> <p>400A, 50KA 4 Pole MCCB, Ics=100% Icu rating</p> <p>Digital Voltmeter 0-500V with selector switch Ammeter (0-400 A) with selector switch &amp; CTs, etc.</p> <p>LED Type RYB phase indicating lamps, ON, OFF, trip indicating lamps</p> <p>Set of Copper Bus Bar 500A</p> <p><b>Outgoings</b></p> <p>(Note : All outgoing feeders for pumps should have digital Ammeter with selector switches, and LED type ON, OFF, trip indicating lamps)</p> <p>1. Main Fire Pump</p> <p>250 A, 50KA TPN MCCB, Ics=100% Icu, with fully automatic Star / Delta starter suitable for 100 hp pump with overload protection, current sensing type single phase preventor complete with all accessories and internal wiring required for automatic operation, selector switch for local / remote auto / manual / OFF operation.</p> <p>2. Jockey Pump</p> <p>100 A, 50KA TPN MCCB, Ics=100% Icu, with suitable HP fully automatic Star/Delta starter with overload protection, current sensing type single phase preventor complete with all accessories and internal wiring required for automatic operation, selector switch for local/remote, auto/manual/OFF operation.</p> <p>3. Diesel Engine Control</p> <p>Control for diesel engine comprising - Automatic/Manual selector switch &amp; 3 attempt starting device, timers and relays as required, push buttons, start/stop in manual mode Indicating lamp for high / Low Lub. Oil pressure, High Water Pump and Engine on indication Battery charger suitable for 12V/24 V DC with boost and trickle selector switch, 0-30 V DC volt meter, and 0-20 A DC Ammeter</p> <p>All standard relays and accessories for automatic operation of diesel engine System Controller.</p> <p>4. 03 Nos. of Spares having 100A, 50KA TPN MCCB</p> | 1 Set | Set  | 400000.00            | 400000.00              |
| 2                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | <p>Supplying, installation, testing and commissioning of Electric driven Main Fire Pump suitable for 1620 lpm flow rate and 70m head, automatic operation and consisting of following, complete in all respects, as required :</p> <p>(a) Horizontal type, multistage, centrifugal, split casing pump of cast iron body &amp; bronze impeller with stainless steel shaft, mechanical seal conforming to IS 1520.</p> <p>(b) 60 HP Squirrel cage induction motor, TEFC, synchronous speed 1500 RPM, suitable for operation on 415 volts, 3 phase 50 Hz, AC supply with IP 55 protection for enclosure, horizontal foot mounted type with Class-F insulation, conforming to IS-325.</p> <p>(c) M.S. fabricated Common base plate, coupling, coupling guard, foundation bolts, etc. as required.</p> <p>(d) Suitable cement concrete foundation duly plastered with anti vibration pads.</p>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | 1 Set | Set  | 750000.00            | 750000.00              |
| 3                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | <p>Supply, installation, testing and commissioning of diesel engine driven main fire pump suitable for 1620 lpm flow rate and 70m head, automatic operation and consisting of following, complete in all respects, as required :</p> <p>(a) Diesel Driven Pump - Horizontal type, multistage, centrifugal pump of cast of iron body and bronze impeller with stainless steel shaft, mechanical seal conforming to IS 1520.</p> <p>(b) 1105 BHP, 1500 RPM water cooled with radiator, diesel engine conforming to relevant IS standard complete with auto starting mechanism, 12 /24 volts electric starting equipment, diesel tank, exhaust pipe extended upto 10 m outside pump house duly insulated with 50 mm thick glass wool with 1.0 mm thick aluminium sheet ladding residential silencer, instruments and protection as per standard specification, stop solenoid for auto stop in the event of fault with audio indications, painted with post office red colour etc. as required.</p> <p>(c) M.S fabricated, common base plate, coupling, coupling guard, foundation bolts etc. as required.</p> <p>(d) Suitable cement concrete foundation duly plastered and with anti vibration pads.</p>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | 1 Set | Set  | 825000.00            | 825000.00              |

  
 आरपीएच महानगर (अभ. विद्युत)  
 Asst. Gen. Manager (Engg-E)  
 आरपीएच महानगर, ए.टी.एस. कॉम्प्लेक्स,  
 भारतीय विमानपत्तन प्राधिकरण, A.T.S. Complex,  
 Authority of India, 400 099

| Sr. No. | Description of Items                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | Qty.        | Unit  | Rate (Excl. GST) Rs. | Amount (Excl. GST) Rs. |
|---------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------|-------|----------------------|------------------------|
| 4       | Supplying, installation, testing and commissioning of electric driven pressurisation pump suitable for 180 lpm flow rate and 70 m. head, automatic operation and consisting of following, complete in all respects, as required: (Jockey Pump)<br>(a) Horizontal type, multistage, centrifugal pump of cast iron body and bronze impeller with stainless steel shaft, mechanical seal conforming to IS : 1520.<br>(b) 20 HP squirrel cage induction motor TEFC type suitable for operation on 415 volts, 3 phase 50 Hz, AC supply with IP 55 class of protection for enclosure, horizontal foot mounted type with Class-'F' insulation, conforming to IS : 325.<br>(c) M.S. fabricated Common base plate, coupling, coupling guard, foundation bolts etc. as required.<br>(d) Suitable cement concrete foundation duly plastered and with anti vibration pads | 1 Set       | Set   | 295000.00            | 295000.00              |
| 5       | Supplying of following size cable of 1.1 KV grade multicore copper conductor XLPE insulated and PVC sheathed armoured cable as per IS-1554 (Part-I) 1968/IS-7098 (Part-I) 1985 respectively with upto date amendments.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |             |       |                      |                        |
| 5.1     | 3.5C x 16 sq.mm. Copper armoured cable                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | 50 Metres.  | Meter | 125.00               | 6250.00                |
| 5.2     | 3C x 150 sq.mm. Copper armoured cable                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | 50 Metres.  | Meter | 200.00               | 10000.00               |
| 5.3     | 3C x 25 sq.mm. Copper armoured cable                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | 50 Metres.  | Meter | 350.00               | 17500.00               |
| 5.4     | 2C x 1.5 sq.mm. Copper armoured cable                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | 60 Metres.  | Meter | 100.00               | 6000.00                |
| 5.5     | 4C x 1.5 sq.mm. copper armoured cable                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | 10 Metres.  | Meter | 125.00               | 1250.00                |
| 6       | Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size in the existing RCC / HUME / METAL pipe as required.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |             |       |                      |                        |
| 6.1     | Upto 35 sq.mm.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |             |       |                      |                        |
| 6.2     | Above 95 sq. mm. and upto 185 sq. mm.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | 50 Metres.  | Meter | 125.00               | 6250.00                |
| 7       | Laying and fixing of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size on cable tray as required.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | 30 Metres.  | Meter | 200.00               | 6000.00                |
| 7.1     | Upto 35 sq.mm. (clamped with 1mm thick saddle)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |             |       |                      |                        |
| 7.2     | Above 95 sq. mm and upto 185 sq. mm. (clamped with 25/40 x 3 mm. MS flat clamp)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | 120 Metres. | Meter | 125.00               | 15000.00               |
| 8       | Supplying and laying 25 mm. X 5 mm. G.I strip at 0.50 metre below ground as strip earth electrode, including connection/ terminating with G.I. nut, bolt, spring, washer etc. as required. (Joining shall be done by overlapping and with 2 sets of G.I. nut bolt & spring washer spaced at 50mm)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | 20 Metres.  | Meter | 200.00               | 4000.00                |
| 9       | Providing and fixing 25 mm. X 5 mm. copper strip in 40 mm dia G.I. pipe from earth electrode including connection with brass nut, bolt, spring, washer excavation and re-filling etc. as required.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            | 30 Metres.  | Meter | 12000.00             | 360000.00              |
| 10      | Supplying and making end termination with brass compression gland and copper lugs for size of 3 X 150 sq. mm. (50 mm.) PVC insulated and PVC sheathed / XLPE copper conductor cable of 1.1 KV grade as required.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | 20 Metres.  | Meter | 1200.00              | 24000.00               |
| 11      | Dismantling of following existing Fire pumps and Panel, packing and transporting it to nearby store location or at suitable location as per direction of E-I-C<br>a. Main Fire pump<br>b. Diesel Drive Pump<br>c. Jockey Pump<br>d. Fire Panel                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | 4 Sets      | Set   | 1000.00              | 4000.00                |
| 12      | Subhead-II: Provision of Fire hydrant system at Porta Cabin, ATS Complex<br>Providing, laying, testing & commissioning of 'C' class heavy duty MS pipe conforming to IS 3589/IS 1239 including Welding, fittings like elbows, tees, flanges, tapers, nuts bolts, gaskets etc. and fixing the pipe on the wall/ ceiling with suitable clamp/ support frame and painting with two or more coats of synthetic enamel paint of required shade complete as required.                                                                                                                                                                                                                                                                                                                                                                                               | 1 Job       | Job   | 25000.00             | 25000.00               |
| 12.1    | 150 mm. dia.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | 30 Metres.  | Meter | 3000.00              | 90000.00               |
| 12.2    | 100 mm. dia.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | 10 Metres.  | Meter | 2500.00              | 25000.00               |
| 12.3    | 80 mm. dia.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | 20 Metres.  | Meter | 2000.00              | 40000.00               |
| 13      | Supplying and fixing single headed gunmetal internal hydrant valve with instantaneous gunmetal coupling of 63 mm. dia. with cast iron wheel ISI marked conforming to IS 5290 (Type-A) with blank Gunmetal/ Stainless Steel cap and chain as required.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | 2 Nos.      | No.   | 7000.00              | 14000.00               |

19/10/26

प्रमुख प्रशासक (अति-विशेष)

आस. प्र. प्रशासक (एन्ग-ई)

आस. प्र. प्रशासक (एन्ग-ई)

आस. प्र. प्रशासक (एन्ग-ई)

आस. प्र. प्रशासक (एन्ग-ई)

आस. प्र. प्रशासक (एन्ग-ई)

आस. प्र. प्रशासक (एन्ग-ई)

आस. प्र. प्रशासक (एन्ग-ई)

आस. प्र. प्रशासक (एन्ग-ई)

आस. प्र. प्रशासक (एन्ग-ई)

आस. प्र. प्रशासक (एन्ग-ई)

आस. प्र. प्रशासक (एन्ग-ई)

आस. प्र. प्रशासक (एन्ग-ई)

आस. प्र. प्रशासक (एन्ग-ई)

आस. प्र. प्रशासक (एन्ग-ई)

आस. प्र. प्रशासक (एन्ग-ई)

| Sr. No.   | Description of Items                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | Qty.   | Unit | Rate (Excl. GST) Rs. | Amount (Excl. GST) Rs. |
|-----------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|------|----------------------|------------------------|
| 14        | Providing and fixing internal fire hose cabinet fabricated from 2mm thick MS sheet with single or double glazed front door and locking arrangement, vinyl tape 50% front side, "Fire Hose" with stove enamelled paint, written on front, including necessary supports of approximate size 2100 x 900 x 715 mm, deep to house two lengths of canvas hose with couplings, branch pipe, fire hose reel, nozzle, fireman axe, single outlet landing valve and first-aid hose reel, complete in all respects. | 4 Nos. | No.  | 10000.00             | 40000.00               |
| 15        | Supply of fire Canvas hose pipe of suitable diameter and 15m length alongwith ISI marked SS male and female coupling conforming to industrial standards as required.                                                                                                                                                                                                                                                                                                                                     | 4 Nos. | No.  | 4000.00              | 16000.00               |
| 16        | Supplying, fixing, testing and commissioning of 80 mm. dia. butterfly valve of PN 1.6 rating with bronze / gunmetal seat duly ISI marked complete with nuts, bolts, washers, gaskets conforming to IS 13095 as required.                                                                                                                                                                                                                                                                                 | 9 Nos. | No.  | 7000.00              | 63000.00               |
| 17        | Supplying and fixing first-aid Hose Reel with MS construction spray painted in post office red, conforming to IS 884 complete with the following as required.<br>20 mm nominal internal dia 30 m. water hose thermoplastic ("textile reinforced") type -2 as per IS: 12585 20 mm nominal internal dia gun metal globe valve & nozzle.<br>Drum and brackets for fixing the equipments on wall.<br>Connections from riser with 25 mm. dia. stop gun metal valve & M.S. Pipe and socket.                    | 9 Nos. | No.  | 12500.00             | 112500.00              |
| 18        | Supplying and fixing air vessel made of 250 mm. dia., 8 mm. thick MS sheet, 1200 mm. in height with air release valve on top and flanged connection to riser, drain arrangement with 25 mm. dia. gun metal wheel valve with required accessories, pressure gauge and painting with synthetic enamel paint of approved shade as required.                                                                                                                                                                 | 1 Nos. | No.  | 25000.00             | 25000.00               |
| 19        | Supplying & fixing 63 mm. dia. gun metal short branch pipe with 20 mm. nominal internal diameter size nozzle conforming to IS 903 suitable for instantaneous connection to interconnect hose pipe coupling as required                                                                                                                                                                                                                                                                                   | 2 Nos. | No.  | 1500.00              | 3000.00                |
| 20        | Providing, Fixing, Testing & Commissioning of full way lever operated forged brass ball valve of brass body with forged brass hard chrome plated steel ball tested to a pressure rating of PN 1.6 with threaded / flanged joints complete with nuts, bolts, gaskets, washers union etc. all complete as per specifications and direction of Engineer-In-Charge                                                                                                                                           | 9 Nos. | No.  | 1500.00              | 13500.00               |
| Total Rs. |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |                      | 3197250.00             |

(Total Rupees : Thirty One Lakhs Ninety Seven Thousand Two Hundred Fifty only) Exclusive of GST

12/6/26

Asstt. General Manager (Engg.-Elect.)  
A.A.I.ATS Complex, Mumbai.

महाराष्ट्र मंत्रालय (अभि. विद्युत)  
Asslt. Gen. Manager (Engg.-E)  
भारतीय विमानपत्तन प्राधिकरण, इ.टी.एच. कॉम्प्लेक्स  
Airports Authority of India, A.T.S. Complex,  
मुंबई/Mumbai - 400 099.

Signature Not Verified

Digitally signed by MUKESH MEENA  
Date: 2026.06.15 17:19:33 IST  
Location: eProcurement System for Central PSUs