

CENTRAL WAREHOUSING CORPORATION
(A NAVRATNA CPSE)

Work Order

Doc. Number : 3500001644

Vendor Code : 10503537 Vendor Name : JOSMAR CONSULTING ENGINEERS Vendor Address : No 9, OFFICERS COLONY, AYYA DWARAGA, 100 FEET ROAD, VELACHERY, CHENNAI-42 Vendor Contact : 9445111089 Vendor Email : JOSMAR.CONSULTANTS@GMAIL.COM Vendor GSTIN : 33AAGFJ0418F2ZV Vendor PAN : AAGFJ0418F	Order No : 3500001644 PO Validity : 26-03-2026 to 16-04-2026 Contact Person : Maravarman Sundaram Contact No : Contact Email : Currency : INR Plant : RO Chennai GSTIN : 33AAACC1206D1ZN						
Name Of Work : Geotechnical investigation and topography survey for proposed construction of warehouse for CWC at SIPCOT Industrial Park, phase-II, Gangaikondan (Tirunelveli Dt.)							
Refrence : 1. SNIQ No. 11Q/2025-26 Dt. 10-03-2026 [EMD - Rs.12,100/-] 2. Date of opening 17-03-2026 E-file no.118122							
Dear Sir/Madam, Central Warehousing Corporation (CWC) is pleased to issue this Work Order to you, for the following work.							
Sr. No.	Description	Schedule Rate	Quoted %	Total Amount	Additional Cost	Total Amount Including Tax	Remarks on Positon / L1 Rates
10	GEOTECHNICAL INVESTIGATION	258,750	-4	0	0	293,112	
20	TOPOGRAPHY SURVEY	250,406.64	-4	0	0	283,660.63	
Grand Total : 576,772.63							
Amount In Words : FIVE LAKH SEVENTY SIX THOUSAND SEVEN HUNDRED SEVENTY TWO RUPEES SIXTY THREE PAISE ONLY /-							

CENTRAL WAREHOUSING CORPORATION
(A NAVRATNA CPSE)

Work Order

Doc. Number : 3500001644

Anexure

SL No.	DSR No.	Description Item Of Works	Total Quantity	Unit	Rate (INR)	Amount (INR)
		GEOTECHNICAL INVESTIGATION				
10	MR-48.	Soil investigation by boring up to 15.00 mtr depth in all type of soil /rock strata at various locations, performing SPT at 1.5 m interval as per IS 2131-1981. Collection of disturbed /undisturbed soil samples of different strata of soil as per direction of Engineer-in-Charge. including standard penetration test, Laboratory testing (as per below list), bearing capacity calculation, foundation recommendation, report preparation, & submission. The rate is inclusive of Mobilization & demobilization of tools tackles, manpower etc. to the site, vegetation clearance, all complete, as per directions of Engineer-in- charge. The rates are inclusive of GST. 1) Laboratory testing on soil samples (for determining S.B.C. & foundation Properties) a) Atterberg Limit b) Free Swell test c) Dry Density, bulk Density and Natural moisture content d) Specific gravity e) Engineering soil classification i/c Grain size analysis f) Direct shear test or triaxial test g) Consolidation Test h) Modules of elasticity of soil i) Swell Pressure test 2) Tests on Rock samples (if any) (For Determining S.B.C. & Foundation properties) a) Determination of Core Recovery b) Determination of RQD c) Compressive Strength d) Density e) Water Absorption. Total no. of boreholes - 5 Nos.	5.00	NOS (Numbers)	51750.00	258750.00
		TOPOGRAPHY SURVEY				

CENTRAL WAREHOUSING CORPORATION
(A NAVRATNA CPSE)

Work Order

Doc. Number : 3500001644

SL No.	DSR No.	Description Item Of Works	Total Quantity	Unit	Rate (INR)	Amount (INR)
10	MR-81.	Digitalized Topographical Survey of site showing all existing features such as boundaries, drain, adjacent roads (finished top), top & inverted levels of adjoining National/State Highways, SIPCOT internal road, nearest storm water drain, trees or area covered under trees (where marking of individual tree is not possible), electric and telephone poles, Nala, height of H.T. Lines, Pylons, etc., if any, taking levels at grid 3m x 3m, using total electronic station by assumed northing and easting including preparation of contour plan at 1 m contour interval and fixing temporary benchmark and making them on ground with paint as required, calculation of ; (i) area with standard surveying software program and (ii) cutting and filling quantity, plotting on Auto CAD to the suitable scale and supplying of TWO (02) sets colored drawings along with CAD dwg in digital means. Rate is inclusive of mobilizing/de-mobilizing machinery, labour, to site, all complete. The rates are inclusive of GST Total Area - 39.60 Acres	39.60	ACR (Acre)	6323.40	250406.64

Digitally signed by
MARAVARMAN SUNDARAM
Date: 2026.03.25 12:05:48
+05'30'

Signature