

CENTRAL WAREHOUSING CORPORATION
(A NAVRATNA CPSE)

Work Order

Doc. Number : 3500001645

Vendor Code : 10503537 Vedor Name : JOSMAR CONSULTING ENGINEERS Vendor Address : No 9, OFFICERS COLONY, AYYA DWARAGA, 100 FEET ROAD, VELACHERY, CHENNAI-42 Vendor Contact : 9445111089 Vendor Email : JOSMAR.CONSULTANTS@GMAIL.COM Vendor GSTIN : 33AAGFJ0418F2ZV Vendor PAN : AAGFJ0418F	Order No : 3500001645 PO Validity : 26-03-2026 to 16-04-2026 Contact Person : Maravarman Sundaram Contact No : Contact Email : Currency : INR Plant : RO Chennai GSTIN : 33AAACC1206D1ZN						
Name Of Work : Geotechnical investigation for proposed construction of warehouse for CWC at SIPCOT Multi Park, Theni							
Refrence : 1. SNIQ No. 12Q/2025-26 Dt. 10-03-2026 [EMD - Rs.6,200/-] 2. Date of opening 17-03-2026 E-file no.118122							
Dear Sir/Madam, Central Warehousing Corporation (CWC) is pleased to issue this Work Order to you, for the following work.							
Sr. No.	Description	Schedule Rate	Quoted %	Total Amount	Additional Cost	Total Amount Including Tax	Remarks on Positon / L1 Rates
10	GEOTECHNICAL INVESTIGATION	258,750	-3	0	0	296,165.26	
Grand Total : 296,165.26							
Amount In Words : TWO LAKH NINETY SIX THOUSAND ONE HUNDRED SIXTY FIVE RUPEES TWENTY SIX PAISE ONLY /-							

CENTRAL WAREHOUSING CORPORATION
(A NAVRATNA CPSE)

Work Order

Doc. Number : 3500001645

Anexure

SL No.	DSR No.	Description Item Of Works	Total Quantity	Unit	Rate (INR)	Amount (INR)
		GEOTECHNICAL INVESTIGATION				
10	MR-48.	Soil investigation by boring up to 15.00 mtr depth in all type of soil /rock strata at various locations, performing SPT at 1.5 m interval as per IS 2131-1981. Collection of disturbed /undisturbed soil samples of different strata of soil as per direction of Engineer-in-Charge. including standard penetration test, Laboratory testing (as per below list), bearing capacity calculation, foundation recommendation, report preparation, & submission. The rate is inclusive of Mobilization & demobilization of tools tackles, manpower etc. to the site, vegetation clearance, all complete, as per directions of Engineer-in- charge. The rates are inclusive of GST. 1) Laboratory testing on soil samples (for determining S.B.C. & foundation Properties) a) Atterberg Limit b) Free Swell test c) Dry Density, bulk Density and Natural moisture content d) Specific gravity e) Engineering soil classification i/c Grain size analysis f) Direct shear test or triaxial test g) Consolidation Test h) Modules of elasticity of soil i) Swell Pressure test 2) Tests on Rock samples (if any) (For Determining S.B.C. & Foundation properties) a) Determination of Core Recovery b) Determination of RQD c) Compressive Strength d) Density e) Water Absorption. Total no. of boreholes - 5 Nos.	5.00	NOS (Numbers)	51750.00	258750.00

Digitally signed by
MARAVARMAN SUNDARAM
Date: 2026.03.25 12:06:15
+05'30'

Signature