

केन्द्रीय भण्डारण निगम
(एक नवरत्न सीपीएसई)

CENTRAL WAREHOUSING CORPORATION
(A NAVRATNA CPSE)

Work Order

Doc. Number : 3500001664

Vendor Code : 10400711 Vedor Name : AKM Infrastructure and Design Vendor Address : No.5/1149-C 636705 DHARMAPURI Vendor Contact : 9698730833 Vendor Email : info.akminfra@gmail.com Vendor GSTIN : 33ABUFA7355D1ZB Vendor PAN : ABUFA7355D	Order No : 3500001664 PO Validity : 01-04-2026 to 15-04-2026 Contact Person : Maravarman Sundaram Contact No : Contact Email : Currency : INR Plant : RO Chennai GSTIN : 33AAACC1206D1ZN						
Name Of Work : Geotechnical investigation and topography survey for proposed construction of warehouse for CWC at Moolapalayam, Erode							
Reference : 1. SNIQ No.13Q/2025-26 dt 10.03.2026 : 2. Your quotation opened on 17.03.2026 E-file no.118122							
Dear Sir/Madam, Central Warehousing Corporation (CWC) is pleased to issue this Work Order to you, for the following work.							
Sr. No.	Description	Schedule Rate	Quoted %	Total Amount	Additional Cost	Total Amount Including Tax	Remarks on Positon / L1 Rates
10	GEOTECHNICAL INVESTIGATION	103,500	-16	0	0	102,589.2	
20	TOPOGRAPHY SURVEY	31,941.25	-11	0	0	33,544.69	
Grand Total : 136,133.89							
Amount In Words : ONE LAKH THIRTY SIX THOUSAND ONE HUNDRED THIRTY THREE RUPEES EIGHTY NINE PAISE ONLY /-							

CENTRAL WAREHOUSING CORPORATION
(A NAVRATNA CPSE)

Work Order

Doc. Number : 3500001664

Anexure

SL No.	DSR No.	Description Item Of Works	Total Quantity	Unit	Rate (INR)	Amount (INR)
		GEOTECHNICAL INVESTIGATION				
10	MR-48.	Soil investigation by boring up to 15.00 mtr depth in all type of soil /rock strata at various locations, performing SPT at 1.5 m interval as per IS 2131-1981. Collection of disturbed /undisturbed soil samples of different strata of soil as per direction of Engineer-in-Charge. including standard penetration test, Laboratory testing (as per below list), bearing capacity calculation, foundation recommendation, report preparation, & submission. The rate is inclusive of Mobilization & demobilization of tools tackles, manpower etc. to the site, vegetation clearance, all complete, as per directions of Engineer-in- charge. The rates are inclusive of GST. 1) Laboratory testing on soil samples (for determining S.B.C. & foundation Properties) a) Atterberg Limit b) Free Swell test c) Dry Density, bulk Density and Natural moisture content d) Specific gravity e) Engineering soil classification i/c Grain size analysis f) Direct shear test or triaxial test g) Consolidation Test h) Modules of elasticity of soil i) Swell Pressure test 2) Tests on Rock samples (if any) (For Determining S.B.C. & Foundation properties) a) Determination of Core Recovery b) Determination of RQD c) Compressive Strength d) Density e) Water Absorption	2.00	NOS (Numbers)	51750.00	103500.00
		TOPOGRAPHY SURVEY				

CENTRAL WAREHOUSING CORPORATION
(A NAVRATNA CPSE)

Work Order

Doc. Number : 3500001664

SL No.	DSR No.	Description Item Of Works	Total Quantity	Unit	Rate (INR)	Amount (INR)
10	MR-81.	Digitalized Topographical Survey of site showing all existing features such as boundaries, drain, adjacent roads (finished top), top & inverted levels of adjoining National/State Highways, existing boundary wall, approach/internal road, nearest storm water drain, trees or area covered under trees (where marking of individual tree is not possible), electric and telephone poles, Nala, height of H.T. Lines, Pylons, etc., if any, taking levels at grid 3m x 3m, using total electronic station by assumed northing and easting including preparation of contour plan at 1 m contour interval and fixing temporary benchmark and making them on ground with paint as required, calculation of ; (i) area with standard surveying software program and (ii) cutting and filling quantity, plotting on Auto CAD to the suitable scale and supplying of TWO (02) sets colored drawings along with CAD dwg in digital means. Rate is inclusive of mobilizing/demobilizing machinery, labour, to site, all complete. The rates are inclusive of GST	5.05	ACR (Acre)	6325.00	31941.25

Digitally signed by
MARAVARMAN
SUNDARAM
Date: 2026.03.26
18:47:58 +05'30'

Signature

Signature Not Verified