

Annexure-I

Release of Electric Power for Works/Maintenance contractor at Metro Station {To be made part of SCC, wherever provision of electricity is mentioned}

1. Electric power required by Contractor while carrying out the awarded Works/maintenance by DMRC is required to be sourced from existing available source of DMRC at station. The disbursement of power at different stations shall be dealt with metered connections. The power fed shall be from normal source without backup. The electricity supplied during the period shall be billed as per the prevalent DISCOM tariff for charges pertaining to temporary supply as per the metered consumption.
2. DMRC shall nominate source within the station premises and thereafter, work required for the extension to the required work location including provision of energy meter shall be done by the contractor without any cost to DMRC.
3. The Contractor is required to undertake electrical work for extension of power from nominated source by Electrical O&M. The work of Supply provision shall comply to all electrical and codal provisions as per DMRC Rating of Electrical Items and specifications. The contractor shall request for the required ratings of the electrical items from the line in-charge and accordingly, before release of the power supply, the station supervisor shall verify the temporary installation done by the contractor for electrical supply extension.
4. DMRC provides temporary power supply subject to work completion by contractor such as supply and laying of suitable cable, calibrated energy meter, electrical switchgear with all necessary electrical safety ratings and power requirements. Contractor is also required to comply with all necessary provision for electrical and fire safety especially the ratings of MCCB/MCB and ELCB in accordance to electrical codes while carrying out the works.
5. The Billed consumption shall be verified by each Station In-charge through energy meter on monthly basis and respective amount in lieu of Energy billing would be sent to concerned executive.

Release of Water Supply for Infrastructure construction works contractors of Civil/O&M

{To be made part of SCC, wherever provision of water is mentioned}

To streamline the process of providing water for works to be carried out under the contract, following procedure is hereby prescribed for releasing temporary water connections to contractors:

1. Application Procedure

- **Request:** The contractor shall submit a formal application to the Engineer citing the Work Order details.
- **Availability and Point of Supply:** The supervisor of executive department, in consultation with supervisor of civil and E&M department, will conduct a technical feasibility visit to finalize the availability of water and location of the tapping point. DMRC will provide only tapping point on the nearest existing water main.
- **Infrastructure:** All further piping, storage tanks, pumping arrangements, and plumbing fixtures shall be installed and maintained by the contractor at their own cost.

2. Supervision

The work will be supervised by the supervisor from the executive department who shall ensure that the installation follows the approved scheme. Also, amount as per the applicable rates shall be adjusted from the running bills of the contractor by the executive department.

3. Metering

Calibrated Water meter will be installed by the Civil department of DMRC. If meter is not available with DMRC, the contractor may be asked to procure a meter from an approved vendor list and submit testing / calibration certificate before installation.

4. Water Consumption Charges: ₹[Amount]* per kilolitre or part thereof (on the basis of a water meter).

* [Amount], i.e., rate for water consumed will be as prescribed by DMRC from time to time.

5. Terms and Conditions

- **Misuse:** Water shall be used strictly for the specified construction work. Unauthorized use will lead to immediate disconnection and a penalty of 3x the standard rate.
- **Leakage:** The contractor is responsible for preventing wastage. Any damage to the department's main line during tapping will be repaired at the contractor's expense.
- **Duration:** The connection will be valid only for the sanctioned period plus any extensions.