



न्यूक्लियर पावर कॉर्पोरेशन ऑफ इंडिया लिमिटेड
Nuclear Power Corporation of India Limited
(भारत सरकार का उद्यम Government of India Enterprise)



कैगा स्थल KAIGA SITE

C & MM- (WORKS GROUP) सी एंड एमएम (वर्क्स ग्रुप)

Corporate Identification No. U40104MH1987GOI149458

Phone: +91 8382 264002

Fax: +91 8382 264025

E-mail: cmmworks.kaiga@npcil.co.in

Website: www.npcil.nic.in

Ref: NPCIL/KAIGA/C&MM-WG/WO/2026/1235

Date: 25-06-2026.

Work Order

To:

M/S INDECOR SLIDES (INDIA) PRIVATE LIMITED
404, Hill View Industrial Estate, Amrut Nagar,
LBS Road, Ghatkopar West
Mumbai-400086

Kind Atten: Shri Sachin K

Mobile No.: 9082871170

E-mail: indecorslides@gmail.com

Work Order Fais No.	:	500102 ✓
S.L. Code	:	I0049500102 ✓
Account Code	:	14600 ✓
Charge Code	:	6353
MSME Category	:	NA
MSME Reg. No.	:	NA

WORK ORDER NO.: 2026_NPCIL_266778_1/81210.01/WO

Sub: Acoustic, Interior, Furniture, Audio Visual and General Lighting & Fixtures works for Quality Assurance (QA) Complex Building at Kaiga-5&6

Ref: 1) TENDER ID: 2026_NPCIL_266778_1

2) TENDER NO.: NPCIL/KAIGA-5&6/C&MM(WG)/CIVIL INFRA/CPPP/2026/112 ✓

3) Last date of submission of tender is 27.03.2026. ✓

Dear Sir,

1) Bid Acceptance:

This is to inform you that, the bid submitted by you as referred above has been accepted for and on behalf of NPCIL, for the items of work shown in the enclosed schedule of quantities and rates for a total value of Rs. 4,69,04,880.00 (Rupees Four Crore Sixty-Nine Lakh Four Thousand Eight Hundred Eighty Only) inclusive of all applicable taxes and including 18% GST.

पंजीकृत कार्यालय 16 : वी तलसेंटर, -1, वर्ल्ड ट्रेड सेंटर, 400005-मुम्बई, कोलाबा, कफे परेड,

Registered Office: 16th Floor, Centre-1, World Trade Centre, Cuffe Parade, Colaba, Mumbai-400005.

2) **QUANTITIES & RATES:**

You may note that the rates are for complete items of work including supply of all materials (unless otherwise specified), consumables, all temporary arrangements, all labours, all prevailing duties, taxes including GST.

3) **CONTRACT PRICE ADJUSTMENT:**

Escalation of payment shall be applicable as per GCC Clause no. 11.3, Sl. No. 21 of Schedule-A & Other conditions of this contract.

4) **EXECUTION OF WORK:**

The work shall be carried out strictly in accordance with the terms, conditions, specifications and drawings stipulated in the tender and also in best workmanlike manner. You shall employ and maintain qualified engineers / supervisors in the job at all times. You shall also bring to the site and employ such machinery and equipment and other materials as are necessary for the satisfactory completion of this work.

5) **CONTRACT PERIOD:**

5.1 **Schedule completion Period:**

The work shall be completed in all respect within **243 Calendar Days (including monsoon period)** from the date of commencement. **The date of commencement of work will be reckoned within seven (07) days from the date of issue of Work Order.** The time shall be essence of the contract and the work shall be completed as per approved program of work.

5.2 **Defect Liability Period:**

The Defect Liability Period as per Para 9.1.1 of Schedule-A of Tender is **12 Months**.

6) **AUTHORISED OFFICIALS:**

6.1 You are requested to inform the name of the authorized representative who will deal with all matter relating to the contract and the Power of Attorney in his favour duly executed on stamped paper of an appropriate value shall be furnished.

6.2 During the execution of the contract and until completion certificate is issued you will be fully liable to compensate all concerned for any loss, damage or destruction of work, structure, property etc. including third party risk arising due to causes

attributable to you which will be decided by the Engineer-in-charge whose decision in this regard will be final.

7) INSURANCE:

You are required to take out following insurance policies applicable to this contract at your cost immediately after receipt of this work order from the date of commencement of work to the end of the Defect Liability Period for whole contract value Inclusive of GST.

- a) CAR policy for the whole contract value.
- b) The Insurance amount should cover THIRD PARTY LIABILITY to 10% of Contract value subject to a maximum of Rs. 50 lakhs.
- c) Employees State Insurances for contract workers.
- d) Wherever ESI Act not covers the contract worker based on monthly wage/ salary, contractor shall obtain the employees/ Workmen compensation for such workers.

You may note that all insurance policies taken under 7 (a), (b) & (d) are to be in Joint names of Corporation and the contractor and specific to work by mentioning the name of work and work order Number in the policies and all Policies in Original should be submitted to the Engineer-in-charge before the date of commencement of work. Copy of ESI registration certificate shall be submitted to EIC before commencement of the work.

8) TAXES & DUTIES:


For tax related compliance (including TDS) refer Contract document, GCC and Special Conditions of Contract (SCC).

9) ENGINEER-IN-CHARGE:

Shri Arvind Kumar, SO/D (Civil), Kaiga 5&6, will be the Engineer-in-Charge of this work. You may make necessary arrangements for commencing the work immediately in consultation with Engineer-in-Charge.

10) SECURITY DEPOSIT:

Security Deposit shall be @ 10% of the contract value including GST will be **₹ 46,90,488.00/- (Rupees Fourty Six Lakh Ninety Thousand Four Hundred Eighty Eight Only)** and shall be governed as per clause no.4.2 of GCC and as per the relevant orders issued by Govt. of India.



10.1 PERFORMANCE GUARANTEE:

As per clause No.4.2.3 of GCC you shall submit a performance guarantee for ₹ 23,45,244.00/- (50% of Security Deposit) to the Corporation within 30 days after issue of work order. It should cover the contract period plus defect liability period. In case bank guarantee is submitted it shall be as per the format given in the tender document.

10.2 RETENTION MONEY:

As per clause No.4.2.5 of GCC, the remaining amount (50% of Security Deposit) of Security Deposit of ₹ 23,45,244.00/- will be deducted as a Retention money from the RA bill/final bill at the rate of 6% of each bill amount. Security Deposit amount will not bear any interest.

10.3 REFUND OF SECURITY DEPOSIT:

Refund of Security deposit will be regularized as per clause no. 4.3 of General Condition of Contract.

11) APPLICABLE LAWS & ACTS:

11.1 You shall comply with various provisions of the contract labour (Regulations & Abolition) Act 1970 and rules framed thereafter from time to time. In case, the Contract Labour Act does not apply to your organization you should intimate the Engineer-In-Charge of this work accordingly before commencing the work. Further you shall also comply with the provisions of other laws such as Workmen's Compensation Act 1923, Minimum Wages Act 1948, E.P.F. Act, ESI Act, Gratuity Act and other labor laws as applicable to your organization. In case, NPCIL is required to incur any expenses as principal employer under the provisions of the various laws, NPC shall be entitled to recover the same from you/your bills.

11.2 You have to give request for the issue of Principal Employer's Certificate for obtaining labour license based on the maximum number of workmen you proposed to employ for this work. You may please note that within 14 days from the date of issue of this work order, you will have to apply for a labour license to the Asstt. Labour Commissioner, of the area, for the maximum number of workers you had indicated to engage on the work.

11.3 The contractor shall make the payment to all its labours on or before 7th of succeeding month and as defined in special condition of contract.



11.4 Labour License (if applicable),

12) PAYMENT TERMS:

12.1 The progressive monthly payment for the work completed and accepted by Engineer-In-Charge shall be made through Running Account bills once in a month as per clause No:12.2 of GCC on submission of measurement / bill by the contractor. Submission of bills on monthly basis shall be ensured by the Contractor.

12.2 Payment of bills will be processed on submission of GST Invoice duly supported with Annexure-8 (Declaration Form for GST).

12.3 In addition to above, first Running Account bill will be processed only on Intimation from Tender Section regarding Work order acceptance & agreement signed by the contractor and submission of Insurance Policies, Copy of PAN, GST Registration certificate and cancelled cheque for Bank Account details to the Engineer-In-Charge.

13) PENALTY & LIQUIDATED DAMAGES CLAUSE:


Penalties imposed by Engineer In-charge for non-compliance or violation of certain conditions of contract, Liquidated Damages for delay in execution and any other penalty in the nature of fine imposed during execution of work will be recovered along with applicable GST there on from bills of the contractor before release of payment.

14) SECURITY, SAFETY & HOUSEKEEPING:

You may have to comply all Security, Safety rules & regulations, Environmental measure as defined in the Contract.

15) TRANSPORT & ACCOMMODATION:

Contractor shall make his own arrangement for Accommodation & Transportation of manpower deployed for this work.



16) **AGREEMENT:**

A formal agreement incorporating all the terms and conditions agreed between NPCIL and **M/S INDECOR SLIDES (INDIA) PRIVATE LIMITED** will be executed as per Clause No 21.3 of Tender document and as defined in the special condition of contract from the date of issue of this work order. Till a formal agreement is executed the original tender together with letters under reference and this work order shall form the binding contract between NPCIL and **M/S INDECOR SLIDES (INDIA) PRIVATE LIMITED**.

Kindly acknowledge receipt of this Work Order.

Thanking you,

Yours faithfully
For and on behalf of NPCIL



(BATHAL KUMAR)

Sr. Manager, C&MM-Works Group, Kaiga Site

Encl: Schedule of quantities and rates.

NUCLEAR POWER CORPORATION OF INDIA LIMITED
(A Government of India Enterprise)
Kaiga Generating Station
Schedule Of Quantities And Rates



Print Date: 24-Jun-2026

Name of Work: Acoustic, Interior, Furniture, Audio Visual and General Lighting & Fixtures works for Quality Assurance(QA) Complex Building at Kaiga-5&6 WO / SOQR Number : 500102								Agency Name : M/s Indecor Slides (India) Private Limited	
Co									
Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹		
Rate in Words									
Schedule : CIVIL:A									
1	Supply and fixing of suspended acoustical GI metal Hanging Baffles based of wooden finished texture having NRC Value up-to 0.70 NRC. The baffle shall be of sizes 50mm thick and 100mm height. The baffles with end caps will be installed using all hardware's and accessories including runners, suspended wires, etc. The interspacing distance between the Baffles will be 100mm. The Baffles to be suspended individually using the runners tied by 6mm Threaded rod, including all other hardware's and accessories, etc., including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of make Indosonic/Hunter Douglas/Durlum or approved make.	sqft	850	500	-	-	4,25,000.00		
Rupees Five Hundreds Only									
2	Providing, placing and fixing 12.5mm Moisture Resistant Gypsum based false ceiling at all height, including providing and fixing of frame work made of special sections, power pressed from MS. sheets and galvanized with zinc coating of 120 gms/sqm (both sides inclusive) as per IS : 277 and consisting of angle cleats of size 25 mm wide x 1.6 mm thick with flanges of 27 mm and 37mm, at 1200 mm centre to centre, one flange fixed to the ceiling with dash fastener 12.5 mm dia x 50mm long with 6mm dia bolts, other flange of cleat fixed to the angle hangers of 25x10x0.50 mm of required length with nuts & bolts of required size and other end of angle hanger fixed with intermediate G.I. channels 45x15x0.9 mm running at the spacing of 1200 mm centre to centre, to which the ceiling section 0.5 mm thick bottom wedge of 80 mm with tapered flanges of 26 mm each having lips of 10.5 mm, at 450 mm centre to centre, shall be fixed in a direction perpendicular to G.I. intermediate channel with connecting clips made out of 2.64 mm dia x 230 mm long G.I. wire at every junction, including fixing perimeter channels 0.5 mm thick 27 mm high having flanges of 20mm and 30 mm long including jointing and finishing to a flush finish of tapered and square edges of the board with recommended jointing compound , jointing tapes , finishing with jointing compound in 3 layers covering up-to 150 mm on both sides of joint and two coats of primer suitable for board, all as per manufacturer's specification and also including the cost of making openings for light fittings, grills, diffusers, cutouts made with frame of perimeter channels suitably fixed, including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of make India Gypsum / Gyproc/ Knauf or approved make.	sqft	2150	150	-	-	3,22,500.00		
Rupees One Hundreds Fifty Only									

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹
		Rate in Words					
3	Providing & Fixing of Aluminium metal tiles in horizontal level suspended ceiling comprising of Lay-in 6mm to 8mm Perforated metal ceiling consisting of 600x600mm (Nominal Size) Lay-in tiles suitable for architectural finishes in 0.7 mm thickness in wooden finished colour powder coating (ranging from 60-80 microns) with Square Regular edge. The Back side of the tile will have 1mm acoustic Freudenberg fleece to achieve NRC up to 0.7 as per ASTM C-423 and Fire Performance of Class 0/1 as per BS 476 Part 6 & 7 in module size of 600x600mm. The installation will be done on interlocking T-Grid of hot dipped all round galvanized iron section of 0.33 mm thick (galvanized @120 gsm) comprising of main T runners of 15x32 mm of length 3000 mm, cross T of size 15x32mm of length 1200mm and secondary intermediate cross T of size 15x32 mm of length 600 mm to form grid module of size 600x600 mm suspended from ceiling using galvanized mild steel item (galvanized@80gsm) 50 mm long 8mm outer diameter M-6 dash fasteners, 6 mm diameter fully threaded hanger rod up to 1000 mm length and L-shape level adjuster of size 85x25x2 mm, spaced at 1200 mm centre to centre along main 'T'. The system should rest on periphery walls /partitions with the help of GI perimeter wall angle of size 15x15x3000 mm made of 0.40 mm thick sheet, to be fixed to the wall with help of plastic rawl plug at 450 mm centre to centre & 40 mm long dry wall S.S. screws. The exposed bottom portion of all T-sections used in false ceiling support system shall be pre-painted with polyester baked paint, for all heights. The work shall be carried out as per specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of make Indosonic/Armstrong/Hunter Douglas or approved make.	sqft	2000	265	-	-	5,30,000.00
		Rupees Two Hundreds Sixty Five Only					
4	Providing & Fixing of 4' X 2' aluminium based glossy wooden finished metal tiles of thickness 0.7mm. The installation will be done on the frame work shall consist of G.I. 'T' Sections of 25 micron hot dipped galvanized iron section of 0.40mm thick on Silhouette profile, rotary stitched double webbed wooden finish with 6mm reveal profile (white/black) comprising of Main runners 15x42x3000mm length, Cross runners of 15x42x1200mm & 15x42x600mm size to form grid module of size 1200x600mm. Galvanized iron perimeter wall angle of size 15x19x0.4mm of length 3000mm to be fixed on periphery wall/partition with the help of plastic rawl plugs at 450mm C/C and 40mm long dry wall SS screws. The work shall be carried out as per specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of make Indosonic/Armstrong/Hunter Douglas or approved make.	sqft	800	300	-	-	2,40,000.00
		Rupees Three Hundreds Only					

Handwritten signature

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹
		Rate in Words					
5	Providing, placing & Fixing of SS 304 grade plain metal tiles in horizontal level suspended ceiling comprising of Lay-in metal tiles consisting of 600x600mm (Nominal Size) Lay-in tiles suitable for architectural finishes in 0.5/0.7 mm thickness with Square Regular edge. The installation will be done on an interlocking T-Grid of hot dipped all round galvanized iron section of 0.33 mm thick (galvanized @120-gsm) comprising of main T runners of 15x32 mm of length 3000 mm, cross T of size 15x32mm of length 1200mm and secondary intermediate cross T of size 15x32 mm of length 600 mm to form grid module of size 600x600 mm suspended from ceiling using galvanized mild steel item (galvanized@80gsm) 50 mm long 8mm outer diameter M-6 dash fasteners, 6 mm diameter fully threaded hanger rod up to 1000 mm length and L-shape level adjuster of size 85x25x2 mm, spaced at 1200 mm centre to centre along main 'T'. The system should rest on periphery walls /partitions with the help of GI perimeter wall angle of size24x24X3000 mm made of 0.40 mm thick sheet, to be fixed to the wall with help of plastic rawl plug at 450 mm centre to centre & 40 mm long dry wall S.S. screws. The exposed bottom portion of all T-sections used in false ceiling support system shall be of SS clad Layer, for all heights. The work shall be carried out as per specifications (if any) and as per directed by Engineer-in-charge, including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of make Armstrong/Anutone /Indosonic or approved make	sqft	350	350	-	-	1,22,500.00
		Rupees Three Hundreds Fifty Only					
6	Providing and Fixing of Wooden 12mm Moisture Resistant Plywood, finished with a 4mm Veneer Board facing as per the approved shade/ species & polished with a melamine polish. The panels shall be mounted on the Aluminium framework consisting of 50x25mm size, that shall be fixed with suitable isolator (as per recommended by manufacturer) in-filled with polysynth (50mm) of 1000 GSM. The framework shall be placed at 600mm x 600mm c/c both ways and 12mm marine Ply shall be fixed on the frame. Construction, adhesives and accessories shall be as per the instructions laid down by the manufacturer, including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. (Basic Rate of Veneer Board shall not be less than Rs. 350/sqft). Note: Product shall be of make Anutone/Indosonic/Armstrong.	sqft	950	900	-	-	8,55,000.00
		Rupees Nine Hundreds Only					

[Signature]

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹
		Rate in Words					
7	Providing and Fixing of real wood Fluted panels of width 128/192mm, thickness of 18mm and length 2440 mm, made of Oakwood with a melamine polished finish. The panels shall have a Fluted design on the front side as per the Architects/Consultants requirement. The edges of the panel shall be tongue-grooved pattern for fixing and getting a seamless surface finish. The panels shall be mounted and fixed on the Z-Bar/Strut channel with clipping system. The vapour barrier membrane (recommended by manufacturer) shall be mounted on the vertical surface of the wall before the installation of the Aluminium framework. The Aluminium framework of 50x50mmx2.0mm shall be fixed with suitable Isolator (as per recommended by manufacturer) in-filled with polywad (50mm) of 1000 GSM/25mm RGB of Density 96 kg/m3. The framework shall be placed at 600mm x 600mm c/c both ways and 10mm marine Ply with Helmholtz perforations shall be fixed on the frame. The product should have an acoustical performance of 0.70 NRC. Construction, adhesives and accessories shall be as per the instructions laid down by the manufacturer, including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc. away from work premises & cleaning the work area etc. complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of make Indosonic/Anutone/Armstrong or approved make	sqft	600	1050	-	-	6,30,000.00
		Rupees One Thousand Fifty Only					
8	Providing, placing and fixing in position Acoustical Polyethylene Terephthalate PET tech-panel of size 2400mm x 1200mm, made up from compressed polyester Fibre of 10mm thickness, 1600 GSM Density in CNC made groove/cut/3D design panels. The Tech-Panel should be Highly resistance to humidity (RH:99%), water vapour diffusion resistance (as per ISO-12572-2016 standards), zero mold growth (as per EN-15101-1 standards), Highly versatile and (Class A) flame retardant (as per BS-3119 standards, IS-15061 standards) and Thermal conductivity (as per EN12667 standards). The product should have an acoustical performance of 0.60 NRC. The Sheet Panel should be applied on a 50X25mm Aluminium framework with 8mm MR ply backing and 50 mm Polysynth (1000 GSM). The panelling shall be finished as per the grooves/cuts design, sizes, colour, and joints including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc. away from work premises & cleaning the work area etc. complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of make Anutone/Indosonic/Polysonic or approved make	sqft	3300	575	-	-	18,97,500.00
		Rupees Five Hundreds Seventy Five Only					

hmy

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹
		Rate in Words					
9	Providing, placing and Fixing of Acoustical Fabric Wall Paneling of 25mm Thickness placed and tucked on stretch vinyl tracks. The fabric panel shall have RGB infill of 25mm thickness with Density of 96 Kg/m ³ , having recycle content of 85%, with Freudenberg acoustic fleece and wrapped on the front side with an acoustically transparent and breathable fabric Fire Retardant grade as per BS EN1021 and IS-1561-2002 and should have Hydro-guard property for water & stain repellent and Abrasion value of around 90000 cycles, with an option of colours, size, dimensions, etc – as per the design and choice of the Engineer-in-charge, giving an average sound absorption level of 0.85 NRC. (Basic Rate of the Acoustic Fabric shall not be less than Rs. 2600/mtr) INSTALLATION: The vapour barrier membrane (recommended by manufacturer) shall be mounted on the vertical surface of the wall before the installation of the Aluminium framework. The Anodised Aluminium framework of 50x25mmx1.5mm shall be fixed with suitable isolator, with an air gap of 50mm (as per recommended by manufacturer). Anodised Aluminium hollow space section should be filled with Polyurethane sound resistance chemical. The Framework will be in-filled with poly-synth (50mm thickness) of 1000 GSM and on the inner side with chicken wire mesh/2mm Hazen Cloth. The framework shall be placed at 600mm x 600mm c/c both ways and 8mm marine Ply with Helmholtz perforation shall be fixed on the frame, including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of make Anutone/Indosonic/Armstrong or approved make	sqft	2700	800	-	-	21,60,000.00
		Rupees Eight Hundreds Only					
10	Providing, placing and Fixing of real wood grooved panels of width 128/192mm, thickness of 18mm and length 2440 mm, made of Oakwood & with a melamine polished finish. The panels shall have a grooves design on the front side as per the Engineer-in-charge direction. The edges of the panel shall be tongue-grooved pattern for fixing and getting a seamless surface finish. The panels shall be mounted and fixed on the Z-Bar/Strut channel with clipping system. The vapour barrier membrane (recommended by manufacturer) shall be mounted on the vertical surface of the wall before the installation of the Aluminium framework. The Aluminium framework of 50x50mmx2.0mm shall be fixed with suitable isolator (as per recommended by manufacturer) in-filled with polywad (50mm) of 1000 GSM/25mm RGB of Density 96 kg/m ³ . The framework shall be placed at 600mm x 600mm c/c both ways and 10mm marine Ply with Helmholtz perforations shall be fixed on the frame. Construction, adhesives and accessories shall be as per the instructions laid down by the Engineer-in-charge, including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. The product should have an acoustical performance of 0.70 NRC. Note: Product shall be of make Anutone/Indosonic/Armstrong or approved make	sqft	750	1050	-	-	7,87,500.00
		Rupees One Thousand Fifty Only					

[Signature]



Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹
		Rate in Words					
11	Designing, fabricating, testing, installing and fixing in position 60 mm thick acoustic door, with seasoned Hardwood frame of size 100x75mm with rebate of required size (door should have a 6mm thick glass vision panel) as directed by Engineer-in-charge. Shutter to be made using frame of 34x100mm section of chemically treated seasoned wood. All wood work shall be treated as termite free. 12 mm thick M/R plywood of Approved make with 1 mm thick lamination with suitable adhesive of approved make and shade shall be fixed over and cavity shall be filled with acoustic insulation material of 2mm thick Sound arrestor sheet and infill of polysynth (1000GSM). Periphery of shutter to be covered with 12mm thick teak wood lipping matching to shade of door shutter. Acoustic seal to be fixed on frame of door to fill the gap of shutter and wooden frame. Drop-down seal to be fixed in shutter to block gap with floor when door is closed having STC of 30dBA. The cost shall include all Hardware fittings like Heavy duty SS hinges ball bearing type (Magnum 6x4 inch) of suitable size, Handles, Tower bolts, door closers, locking arrangement and panic bar of Approved brand including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of make Polysonic/Gordon/Indosonic/Sonicguard or approved make	sqft	390	4200	-	-	16,38,000.00
		Rupees Four Thousand Two Hundreds Only					
12	Providing and fixing U-Shape Pelmet including SS Rods of overall size 75' length x 6" height x 12" projection fabricated from 19 mm thick BWP grade Marine Plywood (IS:710), finished with 1.0 mm thick decorative white laminate of approved make and shade, complete in all respects including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height.	ft	220	550	-	-	1,21,000.00
		Rupees Five Hundreds Fifty Only					
13	Acoustic heavy duty curtains: Provisioning, installing, testing & Commissioning of Motorised Curtain System with sensor-based automation, comprising motorised track with silent drive, SS rods, sheer fabric (basic fabric rate Rs. 950/mtr), American pleats, PIR/motion sensor, lux-based light sensor, safety stop sensor, RF remote, app integration, and all accessories, including labour, hardware, wiring and Commissioning of, complete as per manufacturer's specifications, including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Technical Specifications: • Curtain Fabric: Sheer fabric, minimum basic rate 7950/- per running meter, stitched with American pleats, double hem and finished edges. • Curtain Track & Motor: Motorised curtain track of approved make smooth and noiseless operation, compatible with sensor-based automation. Minimum load capacity 50 kg. Motor power Providing 100-240V AC, 50/60 Hz. • Control System: Remote control, manual override, etc. • Hardware: SS rods (304 grade), end caps, brackets, runners, hooks, pleat tapes, etc. • Installation: Complete with wiring, accessories, calibration, testing and Commissioning of. • Warranty: Minimum 1 year on motor. Note: Product shall be of make IKEA/MMT Acoustix/D Decor or approved make	sqft	2200	550	-	-	12,10,000.00
		Rupees Five Hundreds Fifty Only					

Wing

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹
		Rate in Words					
14	Providing, installing, testing & Commissioning of Motorised Non-reflective Curtain System with sensor-based automation, comprising motorised track with silent drive, SS rods, sheer fabric (basic fabric rate Rs. 1050/mtr), American pleats, PIR/motion sensor, lux-based light sensor, safety stop sensor, RF remote, app integration, and all accessories, including labour, hardware, wiring and Commissioning of , complete as per manufacturer's specifications, including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Technical Specifications: • Curtain Fabric: Sheer fabric, minimum basic rate ₹1050/- per running meter, stitched with American pleats, double hem and finished edges. • Curtain Track & Motor: Motorised curtain track of approved make smooth and noiseless operation, compatible with sensor-based automation. Minimum load capacity 50 kg. Motor power Providing 100-240V AC, 50/60 Hz. • Control System: Remote control, manual override, etc • Hardware: SS rods (304 grade), end caps, brackets, runners, hooks, pleat tapes, etc. • Installation: Complete with wiring, accessories, calibration, testing and Commissioning of . • Warranty: Minimum 1 year on motor. Note: Product shall be of make IKEA/MMT Acoustix/D'Decor or approved make	sqft	2200	550	-	-	12,10,000.00
		Rupees Five Hundred\$ Fifty Only					
15	Providing and Fixing of Acoustic Wooden Sound Trap Slats of width 128/192mm, thickness of 18mm and length 2440 mm, made of HDMR (high density moisture resistant) board substrate of FR grade, with a laminated facing as per the approved shade/ species & finish and a melamine balancing layer on the reverse side. The boards shall have a special Helmholtz perforation pattern on the reverse side of the panel and the pitch, grooves design on the front side will be as per the Architects/Consultants requirement. The edges of the panel shall be tongue-grooved pattern for fixing and getting a seamless surface finish. The back surface of the panel should be provided with high quality acoustic fleece. The panels shall be mounted and fixed on the Z-Bar/Strut channel with clipping system. The Aluminium framework of 50x50mmx2.0mm shall be fixed with suitable isolator (as per recommended by manufacturer) in-filled with polywad (50mm) of 1000 GSM/25mm RGB of Density 96 kg/m3. The framework shall be placed at 600mm x 600mm c/c both ways and 10mm marine Ply with Helmholtz perforations shall be fixed on the frame. The Final finish slat panel shall be fixed on the framework. Construction, adhesives and accessories including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. The product should have an acoustical performance of 0.85 NRC. Note: Product shall be of make Indosonic/Anutone/Armstrong or approved make	sqft	350	800	-	-	2,80,000.00
		Rupees Eight Hundreds Only					
16	Providing & installation of wall to wall Nylon Printed Carpet 1000 GSM with PP Mesh Backing, wool/x (100% Dull Nylon) Roll width - 14 feet over a underlay of rubberised foam 4-6mm glued to under surface as per direction of Engineer-in-charge, including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of make Flotex/Indosonic/Kane/Shaw or approved make	sqft	2950	350	-	-	10,32,500.00
		Rupees Three Hundreds Fifty Only					

Handwritten signature

Item No	Description	Unit Quantity Rate in ₹ Rebate Rebated Amount in ₹			
		Rate in Words			
17	Providing and laying 20mm thick Real wood Flooring of approved make, shade, and pattern over a 10mm thick underlay backing. Flooring shall be laid in proper line and level using proprietary adhesive, ensuring full surface contact, stability, and uniform finish. Joints shall be tight and aligned, with necessary expansion gaps provided as per manufacturer's recommendation. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. . Note: Product shall be of make Flotex/Indosonic/Kane/Shaw or approved make	sqft	850	650	5,52,500.00
				Rupees Six Hundreds Fifty Only	
18	Providing and fixing Single OR Double leaf flush door shutter of 30mm thick both side commercial (Veneer/laminates), made out of boiled water proof solid core block board type with 30*20mm external teak wood lipping all-round, well seasoned with cross bonded wooden sheets (core veneer) hot pressed and fastened on both sides of the door using liquid phenol formaldehyde resin, including veneer polishing on both surface of the door, including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per IS specifications 2202 (part-I) 1991, technical specification & manufacturer's specification, drawing (if any) and as directed by Engineer-in-Charge at all locations and at all lifts & height. Note: Material shall be of make DURO, MERINO, GREEN PLY, CENTURY, ARCHID or equivalent.	sqft	750	2750	20,62,500.00
				Rupees Two Thousand Seven Hundreds Fifty Only	
19	Providing and fixing Stainless Steel Door Fixtures conforming to 304 graded steel on door shutter with necessary screws, fixtures etc., as directed by Engineer-in-charge including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard, technical specification & manufacturer's specification, drawing (if any) and as directed by Engineer-in-Charge at all locations and at all lifts & height. Note: Product shall be of make GODREJ, EVERITE, SIGMA, OPEL, DOORSET, PALLADIUM or equivalent.			-	-
19.1	300 mm SS Handle	Nos	75	3500	2,62,500.00
				Rupees Three Thousand Five Hundreds Only	
19.2	SS Aldrop 16mm dia, 300mm	Nos	40	1100	44,000.00
				Rupees One Thousand One Hundreds Only	
19.3	SS Tower Bolts 200x10mm	Nos	40	350	14,000.00
				Rupees Three Hundreds Fifty Only	
19.4	SS Door stopper 75mm with rubber cushion at bottom	Nos	40	750	30,000.00
				Rupees Seven Hundreds Fifty Only	

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹
		Rate in Words					
19.5	SS Door hinges 125mm	Nos	150	850	-	-	1,27,500.00
Rupees Eight Hundreds Fifty Only							
Schedule : CIVIL:B							
20	Meeting Room Central Rectangular Table in ground floor meeting room & first floor meeting room: Providing & placing in position 14 seater meeting table, made out of marine plywood (BWP 710), base structure made up of Teak wood framing, of desired size, placed vertically at 600 mm centre to centre in both directions as per design, covered with two layers of 6 mm thick flexible marine plywood from outside, finished with 1 mm thick approved laminate and matt finish 1 mm thick Stainless Steel (304 grade) skirting of 50 mm height externally. It also includes 2 openable bend shutters in 19 mm thick flexible marine plywood finished with 1 mm thick laminate on both sides including necessary Teak wood framing all around the shutters covered with 1 mm thick approved laminate, hinges 2 Nos. for each shutter, 2 Nos. of ball catch, concealed Teak wood handles at top level of shutters & shutter lock etc. as per design. Size of each shutter to be 400 mm wide x 690 mm high. The top of table to be in 25 mm thick marine plywood finished with 1 mm thick approved laminate. Thickness of exposed part of table top will be 60 mm, made up of 25 mm thick marine plywood top + Teak wood framing 27 mm thick + 6 mm thick bottom marine plywood finished with 1 mm thick laminate. The edge of table top to be in BTC wood, 60 mm x 75 mm, finished with matt PU polish to match the colour of laminate. POP UP wire manager system (8/12 module for Power/Data/USB etc. to be provided as required on table top at the centre of table at around 1200 mm centre to centre distance. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc. away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. 1. Size : 14Ft X 5Ft 2. Product shall be of make Featherlite/HNI/Amber or approved make. 3. All hardware shall be of reputed make as per sample finally approved by the Engineer. Product should be BIFMA gold rated SCS global certified for in-house air quality and with 10 years warranty.	Nos	2	141000	-	-	2,82,000.00
Rupees One Lakh Forty One Thousand Only							



Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹
		Rate in Words					
21	Medium Back Chairs: Providing and Placing Medium Back Visitor Chair with Half Leather Finish . Chair Shall have size of 690*740*1025(h)mm. Medium Back Chair shall be upholstered with half leather without headrest. Chair shall have Class-3 Gas Lift. Sponge: Density>50KG/M3 stereotyped sponge, healthy and odourless, with a resilience of more than 40%, and a thickness of more than 10 cm, to ensure that the buttocks have enough sink depth, and the HD test will never deform. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc . complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Chassis: Synchronous tilting chassis ("DONATI" brand), four-speed adjustment, manual back tension adjustment system. Pneumatic rod: air rod lifting stroke 8cm, 120,000 lifting and rotating tests, 2.0mm thick-walled pipe, Chair foot: aluminium die-casting chair foot, radius 350mm, surface finish polished, one-piece moulding, Chair wheel: R60mm PU wheel shockproof and silent wheel, normal use, can go back and forth 100,000 times on a smooth hard surface without losing any function. Note: Product shall be of make Featherlite/HNI/Amber or approved make. All hardware shall be of reputed make as per sample finally approved by the Engineer. Product should be BIFMA gold rated SCS global certified for in-house air quality and with 10 years warranty.	Nos	88	42300	-	-	37,22,400.00
Rupees Forty Two Thousand Three Hundreds Only							
22	High Back Chairs : Providing and Placing High Back Chair with Half Leather Finish . Chair Shall have size of 650*740*1205(h)mm. High Back Chair shall be upholstered with half leather with headrest. Chair shall have Class-3 Gas Lift. Sponge: Density>50KG/M3 stereotyped sponge, healthy and odourless, with a resilience of more than 40%, and a thickness of more than 10 cm, to ensure that the buttocks have enough sink depth, and the HD test will never deform. Chassis: Synchronous tilting chassis ("DONATI" brand), four-speed adjustment, manual back tension adjustment system. Pneumatic rod: air rod lifting stroke 8cm, 120,000 lifting and rotating tests, 2.0mm thick-walled pipe, Chair foot: aluminium die-casting chair foot, radius 350mm, surface finish polished, one-piece moulding, Chair wheel: R60mm PU wheel shockproof and silent wheel, normal use, can go back and forth 100,000 times on a smooth hard surface without losing any function. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of make Featherlite/HNI/Amber or approved make. All hardware shall be of reputed make as per sample finally approved by the Engineer. Product should be BIFMA gold rated SCS global certified for in-house air quality and with 10 years warranty.	Nos	12	47000	-	-	5,64,000.00
Rupees Forty Seven Thousand Only							

kmj

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹
		Rate in Words					
23	Big Conference Room Table in ground floor conference room: Providing & placing in position 60 seater meeting table, made out of marine plywood (BWP 710), base structure made up of Teak wood framing , of desired size, placed vertically at 600 mm centre to centre in both directions as per design, covered with two layers of 6 mm thick flexible marine plywood from outside, finished with 1 mm thick approved laminate and matt finish 1 mm thick Stainless Steel (304 grade) skirting of 50 mm height externally. It also includes 2 openable bend shutters in 19 mm thick flexible marine plywood finished with 1 mm thick laminate on both sides including necessary Teak wood framing all around the shutters covered with 1 mm thick approved laminate, hinges 2 Nos. for each shutter, 2 Nos. of ball catch, concealed Teak wood handles at top level of shutters & shutter lock etc. as per design. Size of each shutter to be 400 mm wide x 690 mm high. The top of table to be in 25 mm thick marine plywood finished with 1 mm thick approved laminate. Thickness of exposed part of table top will be 60 mm, made up of 25 mm thick marine plywood top + Teak wood framing 27 mm thick + 6 mm thick bottom marine plywood finished with 1 mm thick laminate. The edge of table top to be in BTC wood, 60 mm x 75 mm, finished with matt PU polish to match the colour of laminate. POP UP wire manager system (8/12 module for Power/Data/USB etc. to be provided as required on table top at the centre of table at around 1200 mm centre to centre distance. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc. complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Size : 36' X 10' Note: Product shall be of make Featherlite/HNI/Amber or approved make. All hardware shall be of reputed make as per sample finally approved by the Engineer. Product should be BIFMA gold rated SCS global certified for in-house air quality and with 10 years warranty.	Nos	1	752000	-	-	7,52,000.00
		Rupees Seven Lakh Fifty Two Thousand Only					

[Handwritten Signature]

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹
24	PD room Table, CCE room table Providing & Placing Chairman Table of approved Size and L Shaped Executive Table with Unique Design Curved Modesty Panel & Fixed Side Storage. Table top will be 60mm thick with bevelled edge. Table top shall have PU Leather pad. Modesty panel is attached to a laser cut design on metal to enhance design. Including Electric Rotatable Wire-box with Wireless Charger Smart Lock, Blum Damping Slide Rail, Blum Hinge. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. 1. Substrate: medium fibreboard and particleboard; E1 grade medium fibreboard, density of 0.79g/cm³, moisture content of 5%; static bending strength of 37.4MPa, formaldehyde emissions of 0.2mg/L; particleboard using E0 grade substrate standard, static bending strength of 13.7MPa, moisture content of 6.8%, density of 0.67g/cm³, formaldehyde emissions of 0.047mg/m³; 2. Surface material: natural solid wood veneer veneer, natural and smooth appearance; 3. Veneer: the plate is made of finish paper, which is wear-resistant and not easy to change colour; 4. Edge sealing: the use of high-quality MDF substrate and solid wood veneer edge sealing, effectively preventing water intrusion; 5. Edge sealing: using high-quality solid wood particle board as the substrate and PVC edge, with hot melt adhesive, by 200 ° high temperature suppression in the edge, effectively prevent moisture intrusion; 6. Surface: the surface is bright and smooth, glossy, clear wood grain, good overall effect; All works shall be complete as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of make Featherite/HNI/Amber or approved make. All hardware shall be of reputed make as per sample finally approved by the Engineer. Product should be BIFMA gold rated SCS global certified for in-house air quality and with 10 years warranty.	Nos	2	188000	-	-	3,76,000.00
25	Providing & Placing Chair for PD room & CCE room of approved Size, High Back Executive Chair with Half Leather Finish Donati Synchronized Tilting Mechanism with 4-Position Locking, Class-3 Gas Lift, aluminium Alloy 5-Star Base with Reinforced PU Mute Castors. Leather: head layer cowhide, thickness > 2mm. Sponge: Density 30KG/m³ native sponge cushion, healthy and odourless, 6cm thickness, to ensure that the buttocks have enough sinking depth. Chassis: synchronized tilt chassis ("DONATI" brand), four gear adjustment, hand-cranked back tension adjustment system. Pneumatic bar: gas bar lifting stroke 8cm, 120,000 times lifting and rotating test, 2.0mm thick-walled tube, genuine steel seal certification. Chair feet: aluminium alloy die-casting chair feet, radius 345mm, surface fine polishing treatment, one-piece moulding, Chair wheel: R60mm PU wheel anti-vibration mute wheel, normal use, can be in smooth hard surface back and forth 100,000 times without losing any function. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of make Featherite/HNI/Amber or approved make. All hardware shall be of reputed make as per sample finally approved by the Engineer. Product should be BIFMA gold rated SCS global certified for in-house air quality and with 10 years warranty.	Nos	2	47000	-	-	94,000.00

Rupees Forty Seven Thousand Only

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹
		Rate in Words					
26	Providing & Placing Visitor Chair of approved Size, Medium Back Executive Chair with Half Leather Finish Donati Synchronized Tilting Mechanism with 4-Position Locking, Class-3 Gas Lift, aluminium Alloy 5-Star Base with Reinforced PU Mute Castors. Leather: head layer cowhide, thickness > 2mm. Sponge: Density 30KG/m ³ native sponge cushion, healthy and odourless, 6cm thickness, to ensure that the buttocks have enough sinking depth. Chassis: synchronized tilt STG chassis, single file lock. Pneumatic bar: gas bar lifting stroke 8cm, 120,000 times lifting and rotating test, 2.0mm thick-walled tube Chair feet: electroplated steel feet, radius 350mm, 1 Chair Wheel: R60mm PU wheel anti-shock mute wheel, normal use, can go back and forth on the smooth hard surface 100,000 times without losing any function. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all lifts & height. Note: Product shall be of make Featherlite/HNI/Amber or approved make. All hardware shall be of reputed make as per sample finally approved by the Engineer. Product should be BIFMA gold rated SCS global certified for in-house air quality and with 10 years warranty.	Nos	36	42300	-	-	15,22,800.00
		Rupees Forty Two Thousand Three Hundreds Only					
27	Providing & Placing 3 Seater Sofa of approved Size, High Quality PU leather is used. Executive sofa may have curve design with PU Leather finish. Inner frame made up of solid wood and particle board. Sofa shall have black plastic base. 1.Frame: high-quality solid wood frame, moisture content =< 9%, no rotten wood, no insect erosion, hard material, strong load-bearing capacity; 2.sponge: density > 50KG / M3 shaped sponge, healthy and odourless, resilience of more than 40%, HD test lasting deformation; 3.PU leather: soft and elastic texture and beautiful appearance and other advantages; 4.sitting height 420mm, armrest height 660mm, foot height 70mm. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of make Featherlite/HNI/Amber or approved make. All hardware shall be of reputed make as per sample finally approved by the Engineer. Product should be BIFMA gold rated SCS global certified for in-house air quality and with 10 years warranty.	Nos	14	70500	-	-	9,87,000.00
		Rupees Seventy Thousand Five Hundreds Only					
28	Providing & Placing 2 Seater Sofa of approved Size, High Quality PU leather is used. Executive sofa may have curve design with PU Leather finish. Inner frame made up of solid wood and particle board. Sofa shall have black plastic base. 1.Frame: high-quality solid wood frame, moisture content =< 9%, no rotten wood, no insect erosion, hard material, strong load-bearing capacity; 2.sponge: density > 50KG / M3 shaped sponge, healthy and odourless, resilience of more than 40%, HD test lasting deformation; 3.PU leather: soft and elastic texture and beautiful appearance and other advantages; 4.sitting height 420mm, armrest height 660mm, foot height 70mm. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of make Featherlite/HNI/Amber or approved make. All hardware shall be of reputed make as per sample finally approved by the Engineer. Product should be BIFMA gold rated SCS global certified for in-house air quality and with 10 years warranty.	Nos	6	47000	-	-	2,82,000.00
		Rupees Forty Seven Thousand Only					

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹
		Rate in Words					
29	Providing & Placing Coffee table of approved Size, Tea/Coffee Table top will be made up of Artificial Marble and understructure is made up of Titanium Coated Stainless Steel Legs. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc. away from work premises & cleaning the work area etc. complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all lifts & height. Note: Product shall be of make Featherlite/HNI/Amber or approved make. All hardware shall be of reputed make as per sample finally approved by the Engineer. Product should be BIFMA gold rated SCS global certified for in-house air quality and with 10 years warranty.	Nos	8	23500	-	-	1,88,000.00
		Rupees Twenty Three Thousand Five Hundreds Only					
30	Providing & Placing Corner Coffee table of approved Size, Coffee Table is having irregular shape with black tempered glass top, coffee table shall have understructure with PVC body. 1. Frame: using high-quality solid wood frame, moisture content = < 10%, no rotten wood, no erosion, hard material, strong load-bearing capacity 2. PVC Leather: gray water-based PVC leather, with comfortable and breathable, solid wear-resistant, with anti-static, imitation slip, anti-ageing and other effects 3. Sponge: the use of high-density high rebound sponge, seat sponge density of >=30.0 or more, rebound performance >= 40% or more, not easy to deformation 4. Glass: black tempered glass is used. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc. away from work premises & cleaning the work area etc. complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of make Featherlite/HNI/Amber or approved make. All hardware shall be of reputed make as per sample finally approved by the Engineer. Product should be BIFMA gold rated SCS global certified for in-house air quality and with 10 years warranty.	Nos	2	23500	-	-	47,000.00
		Rupees Twenty Three Thousand Five Hundreds Only					
31	Supply and installation of 8 seater Dining Table with 12mm Korean top Finish approved size for specified dimensions and design. Size : 7.5' x 3'. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc. away from work premises & cleaning the work area etc. complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of make Featherlite/HNI/Amber or approved make. All hardware shall be of reputed make as per sample finally approved by the Engineer. Product should be BIFMA gold rated SCS global certified for in-house air quality and with 10 years warranty.	Nos	2	164500	-	-	3,29,000.00
		Rupees One Lakh Sixty Four Thousand Five Hundreds Only					

my

Name of Work: Acoustic, Interior, Furniture, Audio Visual and General Lighting & Fixtures works for Quality Assurance(QA) Complex Building at Kaiga-5&6 Agency Name : M/s Indecor Slides (India) Private Lim										
WO / SOQR Number : 500102										
Co										
Item No	Description				Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹
Rate in Words										
32	PA room table Providing & Placing L Shape Table of Size: 1500X950X750 (Ht). L Shaped Manager Table with Fixed Side Storage, Table top shall have 50mm thickness. Table top shall have PU Leather pad. Flip Wire Box on the Tabletop with 2 Power and 2 Data Socket. Sliding Door at Side Storage with Soft Closing Function and Number Lock. Substrate: E1 grade medium density fibreboard and E0 grade particleboard are used. The water content of MDF is controlled within the range of 3.0- 13.0%, and the density of the boards is controlled within the range of 0.65- 0.8g/c?, which is in line with the national standards and technical requirements; the formaldehyde emission rate is less than 0.124mg/m³ and the , and the formaldehyde and better than the national standards. Particleboard is E0 grade base material standard, formaldehyde emission is less than 0.025mg/m³. Banding: using high-quality PVC edging, with hot melt adhesive by 200 ? high temperature suppression in the edge, cracking resistance is greater than 2 levels, hot and cold cycling test no bulging, no discolouration, no wrinkles, and effectively prevent the intrusion of moisture, formaldehyde emission is less than 1.5mg / L (desiccator method), better than the national standard. Hardware: hinges. 1. Anti-fatigue test: 40,000 times. 2.Vertical static load: 15kg. 3. Water calming load: 20kg. 4.Corrosion resistance: 100h. 5.Salt spray resistance: 18h. Product features: the product emphasizes simple lines, calm and modern. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of make Featherlite/HNI/Amber or approved make. All hardware shall be of reputed make as per sample finally approved by the Engineer. Product should be BIFMA gold rated SCS global certified for in-house air quality and with 10 years warranty.				Nos	2	70500	-	-	1,41,000.00
Rupees Seventy Thousand Five Hundreds Only										
33	Providing & Placing Manager Back Credenza of Size: 2000*400*750 (Ht). Substrate: E0 grade boards, using E0 grade substrate standards, formaldehyde emissions less than 0.025mg/m³ Banding: the use of high-quality PVC edging, with hot melt adhesive by 200? high temperature suppression in the edge, cracking resistance is greater than 2 levels, hot and cold cycling test no bulging, no discolouration, no wrinkles, and effectively prevent the intrusion of moisture, formaldehyde emission is less than 1.5mg / L (desiccator method), better than the national standard Hardware: DTC powerless hinge: 1. Durability: more than 80,000 times. 2.Vertical static load can be overloaded 30kg. 3. Water calming load can be overloaded 70kg. 4. Corrosion resistance: 18h All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of make Featherlite/HNI/Amber or approved make. All hardware shall be of reputed make as per sample finally approved by the Engineer. Product should be BIFMA gold rated SCS global certified for in-house air quality and with 10 years warranty.				Nos	6	51700	-	-	3,10,200.00
Rupees Fifty One Thousand Seven Hundreds Only										

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹
		Rate in Words					
34	Providing and Placing Executive Back Cabinet with Wood Doors & Shelves. Back Cabinet shall have a size of 3320(W) x 450(D) x 2035(H)mm. Back Storage shall have Full size aluminium alloy handle. LED light strip in display area. Sliding cloth hanger in Side storage with openable shutter. Push and open drawers. Cabinet shall be made of E1 MDF with density of 0.75g/cm ³ , moisture content of 5%, static bending strength of 37.4MPa, formaldehyde emission of 0.2mg/L. Edge banding: using density fibreboard base material and solid wood veneer edge banding, prevent water vapour invasion. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc. away from work premises & cleaning the work area etc. complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Paint: waterborne wood environmental protection paint, benzene series content (benzene, toluene, ethyl benzene, xylene sum) is 50mg/kg, free formaldehyde content is 5mg/kg. Drawers shall be push and open type, without handle. Static load: 30kg extra load when the drawer is fully opened. Side load: 20kg (to ensure that the panel can withstand excessive load). Blum hinge: 1. Fatigue test: 200000 open and close. 2. Static load: load 30kg at 45° opening Angle. 3. Dynamic load: 20kg in the vertical direction. Blum Damping Slide Rail, Blum Hinge, LED Light. Cabinet shall have LED light in display area with remote operation. the direction of EIC Note: Product shall be of make Featherite/HNI/Amber or approved make. All hardware shall be of reputed make as per sample finally approved by the Engineer. Product should be BIFMA gold rated SCS global certified for in-house air quality and with 10 years warranty.	Nos	2	70500	-	-	1,41,000.00
Rupees Seventy Thousand Five Hundreds Only							
35	Providing, supplying, and installing Executive Recliner Chair for Project Director Room & CCE room, size approx. 950-1050 W x 950-1050 D x 1050-1150 H mm, SWL =150 kg, with kiln-dried hardwood/steel internal frame, dual-motor low-noise reclining mechanism with independent back & leg rest, side-mounted control with Home/child-lock and USB charging, cold-cure HD foam (seat 45-50 kg/m ³), integrated lumbar & headrest, premium upholstery (top-grain leather or PU leatherette) meeting BS 5852/TB117, EN 16139/BIFMA X5.11 durability, complete with glides, wiring, SMPS (220-240 V), packing, delivery, installation, testing and Commissioning of, all as per specification and directions of Engineer-in-Charge. Warranty: 5 years frame/mechanism & 2 years upholstery/electricals. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc. away from work premises & cleaning the work area etc. complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of make Featherite/HNI/Amber or approved make. All hardware shall be of reputed make as per sample finally approved by the Engineer. Product should be BIFMA gold rated SCS global certified for in-house air quality.	Nos	2	51700	-	-	1,03,400.00
Rupees Fifty One Thousand Seven Hundreds Only							

Amr

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹
		Rate in Words					
36	LOW HEIGHT STORAGE : Providing, fabricating, supplying & installing low-height credenza storage of height 730-760 mm, depth 450-550 mm, modular carcass in 18/19 mm HDHMR/BWP IS:710 (else E1 MDF/particleboard where approved), finished externally with 1.0 mm HPL / veneer with PU matt and internally with 0.7-1.0 mm laminate; 25 mm finished top; soft-close clip-on hinges, soft-close drawer slides (45 kg), cam locks, SS/Al handles, 32-mm adjustable shelves (=30 kg UDL), cable grommets and AV bay with ventilation, 75 mm MR plinth/SS 304 skirting with levellers, complete with all hardware, fasteners, cleaning and making good, as per directions of Engineer-in-Charge. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc; complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of make Featherlite/HNI/Amber or approved make. All hardware shall be of reputed make as per sample finally approved by the Engineer. Product should be BIFMA gold rated SCS global certified for in-house air quality and with 10 years warranty.	Sqft	240	1175	-	-	2,82,000.00
		Rupees One Thousand One Hundreds Seventy Five Only					
37	FULL HEIGHT STORAGE : Providing, fabricating, supplying & installing full-height storage up to 2400 mm, depth 450-600 mm, modular carcass in 18/19 mm HDHMR/BWP (else E1 MDF/particleboard), finished externally with 1.0 mm HPL / veneer with PU matt and internally with 0.7-1.0 mm laminate; tall shutters with 3 soft-close hinges each (or glass 6 mm toughened as shown), adjustable shelves on 32-mm system (=30 kg UDL), file frames/pull-outs/coat-rod where indicated, 3-point espagnolette locks, SS/Al handles, 75 mm MR plinth/SS 304 skirting with levellers, all complete including hardware, accessories, delivery, installation and making good, as per directions of Engineer-in-Charge. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of make Featherlite/HNI/Amber or approved make. All hardware shall be of reputed make as per sample finally approved by the Engineer. Product should be BIFMA gold rated SCS global certified for in-house air quality and with 10 years warranty.	Sqft	240	1175	-	-	2,82,000.00
		Rupees One Thousand One Hundreds Seventy Five Only					

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹
		Rate in Words					
38	Providing & Placing CE Cabin Table of Size: 1800*1670*760 (Ht) . L Shaped Executive Table with Fixed Side Storage, Including Multi-Functional Socket with 2 Power, 1 VGA, 1 Data, 1 Phone, Artificial Leather Pad at the Tabletop and Lock at Side Storage. Table top thickness is 52mm with bevelled edge. Table shall have leg in 60mm thickness with aluminium alloy profile on the edges of 60mm width. Side storage shall have aluminium alloy handle in full length. Substrate: E1 grade medium density fibreboard and E0 grade particleboard. The water content of MDF is controlled within the range of 3.0~13.0%, and the density of the boards is controlled within the range of 0.65~0.8g/cm ³ , which is in line with the national standards and technical requirements; the formaldehyde emission rate is less than 0.124mg/m ³ . Edge: using high-quality PVC edging, with hot melt adhesive by 200 ? high temperature suppression in the edge, cracking resistance is greater than 2 levels, hot and cold cycling test no bulging, no discolouration, no wrinkles, and effectively prevent the intrusion of moisture, formaldehyde emission is less than 1.5mg / L (desiccator method), better than the national standard; Surface: bright and smooth surface, glossy, clear wood grain, good overall effect. Hardware: Colcano damping hinge. 1. Anti-fatigue test: 40,000 times 2. Vertical static load: 15kg. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of make Featherlite/HNI/Amber or approved make. All hardware shall be of reputed make as per sample finally approved by the Engineer. Product should be BIFMA gold rated SCS global certified for in-house air quality and with 10 years warranty.	Nos	4	70500	-	-	2,82,000.00
							Rupees Seventy Thousand Five Hundreds Only
39	Supply and installation of 10 seater Dining Table in first floor dining room with 12mm Korean top of Size :10' x 5'. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of make Featherlite/HNI/Amber or approved make. All hardware shall be of reputed make as per sample finally approved by the Engineer. Product should be BIFMA gold rated SCS global certified for in-house air quality and with 10 years warranty.	Nos	3	164500	-	-	4,93,500.00
							Rupees One Lakh Sixty Four Thousand Five Hundreds Only
40	Providing and placing Dining Chair with cushioned back and seat, overall approx. W 480 x D 540 x H 900 mm, seat height 465 mm, frame in MS 30x30x1.6 mm powder-coated (or seasoned hardwood, MC =10%), seat base 12 mm ply/HDHMR, HR foam seat 40-45 kg/m ³ & back 28-35 kg/m ³ , upholstered in stain-resistant fabric/PU (=100,000 Martindale) meeting BS 5852/TB117, non-marring adjustable glides, all joints firmly fixed, SWL =150 kg, finish as approved, complete with delivery, installation, cleaning and making good, all as directed by Engineer-in-charge. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of make Featherlite/HNI/Amber or approved make. All hardware shall be of reputed make as per sample finally approved by the Engineer. Product should be BIFMA gold rated SCS global certified for in-house air quality and with 10 years warranty.	Nos	46	12220	-	-	5,62,120.00
							Rupees Twelve Thousand Two Hundreds Twenty Only

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹
							Rate in Words
41	Providing and Placing Round Meeting Room table of size . D1200*750(Ht)mm. Round Table 18mm treated Real wood/Rubber wood with polish works table top . All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of make Featherlite/HNI/Amber or approved make.. All hardware shall be of reputed make as per sample finally approved by the Engineer. Product should be BIFMA gold rated SCS global certified for in-house air quality and with 10 years warranty.	Nos	4	15040	-	-	60,160.00 Rupees Fifteen Thousand Forty Only
42	Providing & placing Cafe Chair of size 530*520*860. Seat back: Plastic back is made of high strength modified PP material, 4 colours are optional. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Bow frame: 13mm steel frame, load-bearing 102KG under drop test. Note: Product shall be of make Featherlite/HNI/Amber or approved make.. All hardware shall be of reputed make as per sample finally approved by the Engineer. Product should be BIFMA gold rated SCS global certified for in-house air quality and with 10 years warranty.	Nos	16	5405	-	-	86,480.00 Rupees Five Thousand Four Hundreds Five Only
43	Providing & Placing single Seater Sofa of size 870*830*830(Ht) with Inner side of sofa Fabric Finish and Outside PU Leather Finish. Sofa Inner structure is made up of Solid Wood & Particle Board Inner Frame with Steel Legs. Frame: high-quality solid wood frame, moisture content =9%, no rotten wood, no insect erosion; hard material, strong bearing capacity. Sponge: high-density high rebound sponge, seat surface sponge density of =35.0 above, rebound performance = 40% above, not easy to deform; All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of make Featherlite/HNI/Amber or approved make.. All hardware shall be of reputed make as per sample finally approved by the Engineer. Product should be BIFMA gold rated SCS global certified for in-house air quality and with 10 years warranty.	Nos	4	23500	-	-	94,000.00 Rupees Twenty Three Thousand Five Hundreds Only
Schedule : CIVIL:C							

hmg

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹
		Rate in Words					
44	CCE Room, PD Room, First Floor Conference Room: Supply, Installation, Testing & Commissioning of 75" 4K Interactive Led Display with OPS-Touch Point-40 IR Nos, Panel Type:-TFT LCD Module with DLED Backlight, IPS, Aspect Ratio:-16:9, Resolution:-4K UHD with 3840x2160, Colour Processor-10 Bit, Brightness-350 Nits, Contrast Ratio:-1200:1, Response Time:-8ms, Viewing Angles:-178H*178V, Backlight Life:-50,000 hours, Orientation-Landscape, PLATFORM Processor-ARM Cortex-A73*4 + Cortex-A53*4, Ram/Storage-4GB/32GB, Touch Point-Windows: 40 points of touch, Android : 20 points of touch, HDMI Inputs-2.0 x 3 (3840x2160 @60Hz, HDCP2.2, HDMI1 with CEC/ARC), RS232 Control-1 No., OPS Slot-required, Following Output Required-HDMI, Audio, Optical, LAN Connectivity Required, Following Type USB Required-USB2.0 x 2 Nos, USB3.0 x 4 Nos, Type B x 2 Nos, Type C x 1 no. Inbuilt speaker of 2 x 12 watts with 1 x 16watts subwoofer. display should be Android version 13.0 upgradable, Wireless Presentation:- chromecast and airplay. with required accessories like Keyboard and Mouse. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of approved make.	Nos	4	208152	-	-	8,32,608.00
		Rupees Two Lakh Eight Thousand One Hundreds Fifty Two Only					
45	CCE Room, PD Room Supply, Installation, Testing & Commissioning of Trolley for the 75" Interactive Display and Video Conferencing, Slim-lift Motorized Height Adjustable Heavy-Duty TV Cart, Height Range: 1307~1607mm (51.5"-63.3"), Material:-Steel and Plastic, Metal Sheet Thickness:-Bracket Arm THK=2mm cold-rolled sheet (Bracket Arm THK=0.079" cold-rolled sheet), Shelf Weight Capacity:3kg (6.6lbs) or more, Base Type:-Caster, Fit Screen Size:55"-90", Controller Type:-Radio Frequency(RF) Remote. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of approved make.	Nos	2	115640	-	-	2,31,280.00
		Rupees One Lakh Fifteen Thousand Six Hundreds Forty Only					
46	CCE Room, PD Room, First Floor Conference Room: Supply, Installation, Testing & Commissioning of HDMI Cable@3Mtr, HDMI Cable should support - up to 4K@60Hz (4:4:4), Lip Sync, 7.1 Pcm, Dolby TrueHD, DTS-HD, CEC. Should have 24K gold-plated connectors resist corrosion, HDMI cable should have lock, Conductor Material should have - Tinned Copper/Bare Copper. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of approved make.	Nos	6	2725.8	-	-	16,354.80
		Rupees Two Thousand Seven Hundreds Twenty Five and Eighty Paise Only					
47	CCE Room, PD Room, First Floor Conference Room: Supply, Installation, Testing & Commissioning of HDMI Cable@10Mtr, HDMI Cable should support - up to 4K@60Hz (4:4:4), Lip Sync, 7.1 Pcm, Dolby TrueHD, DTS-HD, CEC. Should have 24K gold-plated connectors resist corrosion, HDMI cable should have lock, Conductor Material should have - Tinned Copper/Bare Copper. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of approved make.	Nos	6	18006.8	-	-	1,08,040.80
		Rupees Eighteen Thousand Six and Eighty Paise Only					

hmy

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹
		Rate in Words					
48	CCE Room, PD Room, First Floor Conference Room: Supply, Installation, Testing & Commissioning of USB Cable C-type to Type-A @ 3 mtr, MAX. DATA RATE: 480Mbps, POWER RATING: 100W max, CONNECTOR A: USB Type-C male, CONNECTOR B: C-USB/CC — USB Type-C male, CONDUCTORS: 28AWG, CABLE SHIELD TYPE: aluminium-Mylar foil with braid. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc; away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. . Note: Product shall be of approved make.	Nos	3	25110.4	-	-	75,331.20
		Rupees Twenty Five Thousand One Hundreds Ten and Forty Paise Only					
49	CCE Room, PD Room, First Floor Conference Room(60 Seater): Supply, Installation, Testing & Commissioning of 4K Wireless Presentation Device for the Window and Mac, Supports Windows™ and Mac™ laptops, Chromebooks™, iOS™ and Android™ mobile operating systems, minimum Four participants can present simultaneously, Should Have minimum 1 HDMI Output Port, Minimum 3 USB3.0 should have, Video, Max Resolution: Up to 4K Output, Processor: Intel® N100 Main Memory: 16GB DDR4 or better Storage: 128GB SSD or better Networking: 1 x Gigabit LAN Wi-Fi 802.11 ac/b/g/n dual band & Bluetooth Operating System: Linux. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. . Note: Product shall be of approved make.	Nos	4	79296	-	-	3,17,184.00
		Rupees Seventy Nine Thousand Two Hundreds Ninety Six Only					
50	CCE Room, PD Room, First Floor Conference Room: Supply, Installation, Testing & Commissioning of Video Conferencing All-in-one 4K Video, Conf/Collaboration/Wireless Presentation Sys: Touch Cntrl, 4K 5x, EPTZ auto-track 120-deg FOV Cam, Codec, IP Stereo Spkrphone, Wall Mount, 2 HDMI 1.83m, 1 CAT5E LAN 4.57m; NTSC/PAL; Pwr: India BIS, (Require POE data point for Touch panel by client), Camera should have the resolution-Dual lens, 2160p, 4K UHD (3840 x 2160), Camera should have the Horizontal and vertical Field of View (HFOV)-120° (wide); 70° (narrow) and 140° (wide); 78° (narrow), Camera Sensor Resolution should be 2 x 20 megapixel, and zoom should be 7.3x digital, Camera should have Smart Technology-DirectorAI with speaker framing, people framing, and group framing, inbuilt Microphone pickup range should be Up to 25 ft (7.62 m), video conferencing should have inbuilt 2 way stereo speakers, it should have NoiseBlockAI and Acoustic Fence, should support the USB Mode, Should have the following I/O- HDMI Input*1 for the Device Mode and content sharing, Output- 2 * HDMI, Audio I/O- 1 * 3.5mm Jack for the Audio input and Audio output, Unit should have connection for the Expansion Microphone, Unit should have the following USB Ports- 2*USB Type-A, 1*USB Type-C, 2 * RJ 45 Connection for the LAN And Local monitor, Touch panel Controller- Touch Panel should have the dialler with the camera control(Pan, Tilt, Zoom Etc), Touch panel should have the feature of preset Recalling, Should have the aspect ratio of 16:10, brightness-300Nits, Dynamic Contrast Ratio-1000:1, Native resolution: WXGA (1280 x 800), Panel technology: IPS, touch Panel Display Size should be -10" Diagonal, Touch panel should have POE Port(LAN-Power over Ethernet (PoE), compatible with IEEE 802.3at class 0), VC System should have all required accessories included for installation. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. . Note: Product shall be of approved make.	Nos	3	925120	-	-	27,75,360.00
		Rupees Nine Lakh Twenty Five Thousand One Hundreds Twenty Only					

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹
		Rate in Words					
51	CCE Room, PD Room, First Floor Conference Room: Supply, Installation, Testing & Commissioning of IP conference phone for Video conferencing WITHOUT RADIO support. PoE. Includes 7.6m/25ft Ethernet cable and Setup Sheet. The Conference phone should have the 5" Touch Screen, Native resolution: 720 x 1280, Panel technology: Colour LCD, should have wireless as well wired connectivity, Conference phone should have the following Ports- 1 USB 2.0 Type-A for charging, 1 * USB 2.0 Micro-B for the Audio Interface, 2 * RJ-45 (10/100/1000BASE-TX Mbps), LAN IN-Built-in auto-sensing IEEE 802.3at, PoE Device (Class 4), LAN OUT: Built-in auto-sensing IEEE 802.3af power sourcing equipment, IP Conference should have-Three cardoid microphones, frequency response-100 Hz to 22 kHz, Sensitivity (speaker): 92 dB, Should have support the following Audio Codec-G.711 (A-law and u-law) G.722, G.722.1, G.722.1C, G.729AB, G.719, Polycorn™ 7, Siren™ 14, ILBC, OPUS. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of approved make.	Nos	3	85904	-	-	2,57,712.00
		Rupees Eighty Five Thousand Nine Hundreds Four Only					
52	CCE Room, PD Room, First Floor Conference Room: Supply, Installation, Testing & Commissioning of Polycorn Studio / Studio X / G7500 USB cable to computing platform. For use with Studio USB, Device Mode on G7500, Studio X30 and Studio X50. USB 2.0, connector type A to C, 5m. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of approved make.	Nos	3	13216	-	-	39,648.00
		Rupees Thirteen Thousand Two Hundreds Sixteen Only					
53	CCE Room, PD Room, First Floor Conference Room: Supply, Installation, Testing & Commissioning of PoE network Switch for the IP Conference Phone, PoE Adaptor should have Class 4 PoE adaptor 8-Port Gigabit Ethernet High-Power PoE+ Smart Switch with 2 Dedicated SFP Ports (190W), ProSAFE® 8-Port 10/100/1000 PoE+ Smart Switch with 2 Gigabit SFP Ports, Gigabit ports : 8, SFP ports : 2, Number of PoE ports : 8, PoE+ (802.3at) : 8, Total PoE Power budget (Watts) : 190W, Max MAC entries : 16K Buffer size : 1.5MB, VLAN (Number Supported) : 256, VLAN routing : Yes, Dynamic VLAN assignment : Yes All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of approved make.	Nos	3	22302	-	-	66,906.00
		Rupees Twenty Two Thousand Three Hundreds Two Only					
54	CCE Room, PD Room, First Floor Conference Room: Supply, Installation, Testing & Commissioning of Partner Premium Service Plus, Three Year for the Video Conferencing Unit and Touch Controller. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of approved make.	Nos	3	105728	-	-	3,17,184.00
		Rupees One Lakh Five Thousand Seven Hundreds Twenty Eight Only					

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹
		Rate in Words					
55	CCE Room, PD Room, First Floor Conference Room: Supply, Installation, Testing & Commissioning of Partner Premium Service Plus, Three Year, IP Conference Phone. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc. away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. . Note: Product shall be of approved make.	Nos	3	14868	-	-	44,604.00
		Rupees Fourteen Thousand Eight Hundreds Sixty Eight Only					
56	CCE Room, PD Room, First Floor Conference Room(60 Seater): : Supply, Installation, Testing & Commissioning of Zoom Room Perpetual License Required. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of approved make.	Nos	4	113280	-	-	4,53,120.00
		Rupees One Lakh Thirteen Thousand Two Hundreds Eighty Only					
57	First floor meeting room: Supply, Installation, Testing & Commissioning of Push-pull Wall Mount for the 75" Display. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of approved make.	Nos	2	12390	-	-	24,780.00
		Rupees Twelve Thousand Three Hundreds Ninety Only					
58	First floor meeting room: Supply, Installation, Testing & Commissioning of 4 x 4 HDMI Matrix Switcher-4x4 4K HDR HDMI HDCP 2.2 Matrix Switcher with Audio De-embedding, Switcher should have following AV I/O- Inputs-4 nos HDMI with 18G 4K@60Hz (4:4:4) HDR, output-4 nos HDMI with 18G 4K@60Hz (4:4:4) HDR,, 4 x S/PDIF: On female RCA connectors, 4 x Balanced Stereo Audio,switched should have following pots- 1 x usb port for the firmware upgrade, 1 x RS232 Port, 1 x LAN Port, and power on/off switch on front or back, Switch should have content Protection:- Supports HDCP 2.2/1.4, HDMI Port should support the following- HDMI Support: HDR10, xvYCC colour, Dolby TrueHD/DTS-HD Master Audio, 3D Video as specified in 'HDMI 2.0. Switcher should have the front Panel Button for the I/O Selection with the Front Panel Lock option, Switcher Should have the cooling fan with the 19" rack mounting kit. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of approved make.	Nos	1	327096	-	-	3,27,096.00
		Rupees Three Lakh Twenty Seven Thousand Ninety Six Only					
59	First Floor Conference Room, Ground Floor Conference Room(60 Seater): Supply, Installation, Testing & Commissioning of Cable Cubby With 1x HDMI Connectivity, 1x LAN and 2x Power, 1x USB charging. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of approved make.	Nos	5	20650	-	-	1,03,250.00
		Rupees Twenty Thousand Six Hundreds Fifty Only					

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹
		Rate in Words					
60	First Floor Conference Room, Ground Floor Conference Room(60 Seater): Supply, Installation, Testing & Commissioning of HD BaseT Transmitter and receiver Set(Extender), Extender should have HDCP2.2, Should send 1080p signal up to 70 Mtr. and 4K@60Hz (4:2:0) HDMI signal up to 40 mtr should have ir and rs232 extension with the HDMI ,bandwidth of the signal should be 10.2Gbps bandwidth (3.4Gbps per graphic channel)Up to 4K UHD @60Hz (4:2:0) 24bpp resolution, extender should support -Supports deep colour, lip sync, HDMI uncompressed audio channels, Dolby TrueHD, DTS-HD, 2K, 4K, and 3D as specified in HDMI 2.0, RS 232 port in extender should support the baud rate of 9600 to 115200, should support poe if not then power adaptor should supply with extender. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of approved make.	Nos	12	66740.8	-	-	8,00,889.60
		Rupees Sixty Six Thousand Seven Hundreds Forty and Eighty Paise Only					
61	First Floor Conference Room, Ground Floor Conference Room(60 Seater):: Supply, Installation, Testing & Commissioning of HDMI Cable@5Mtr, HDMI Cable should support - up to 4K@60Hz (4:4:4), Lip Sync, 7.1 Pcm, Dolby TrueHD, DTS-HD, CEC, Should have 24K gold-plated connectors resist corrosion, HDMI cable should have lock Conductor Material should have -Tinned Copper/Bare Copper. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of approved make.	Nos	2	3270.96	-	-	6,541.92
		Rupees Three Thousand Two Hundreds Seventy and Ninety Six Paise Only					
62	First Floor Conference Room, Ground Floor Conference Room(60 Seater): Supply, Installation, Testing & Commissioning of Control Processor:- Controller should have the following control Port- 1 x LAN(100/1000 Mbps, auto-switching, auto-negotiating, auto-discovery, full/half duplex, industry-standard TCP/IP stack, UDP/IP, CIP, DHCP, SSL, TLS, SSH, SFTP (SSH File Transfer Protocol), 1x Master Control bus, 1 * USB Type-B for the Host, 1x USB Type-A for the Mass Storage, RS 232 and RS422,RS485 Bidirectional Communication Port- 3 Nos, Controller should have minimum 08 nos of uni-direction IIR/RS232 Ports, and 8 nos of digital IO Ports, Should have 2 GB SDRAM and 8GB Flash, and should have minimum 08 nos of relay port, Controller should have the Power Indicator LED ,Net Bus Indicator LED, MSG Indicator LED , LAN Indicator LED, Should support-SNMP, BACnet™ and IP1, IPv4 or IPv6, Active. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of approved make.	Nos	2	234584	-	-	4,69,168.00
		Rupees Two Lakh Thirty Four Thousand Five Hundreds Eighty Four Only					

Amey

Co Name of Work: Acoustic, Interior, Furniture, Audio Visual and General Lighting & Fixtures works for Quality Assurance(QA) Complex Building at Kaiga-5&6 WO / SOQR Number : 500102 Agency Name : M/s Indecor Slides (India) Private Lim						
Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate
						Amount in ₹
					Rate in Words	
63	First Floor Conference Room, Ground Floor Conference Room(60 Seater): Supply, Installation, Testing & Commissioning of 64 GB Wi-Fi Ipad for the Remote Control-Display size should be 9.7-inch (diagonal) with LED-backlit glossy widescreen Multi-Touch display with IPS technology.Resolution should be 1024-by-768-pixel resolution at 132 pixels per inch (ppi). Should have Fingerprint-resistant oleophobic coating and Support for display of multiple languages and characters simultaneously.Should have Wi-Fi (802.11a/b/g/n) and Bluetooth 2.1 + EDR technology. should support the controller Application. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of approved make.	Nos	2	54516	-	1,09,032.00
					Rupees Fifty Four Thousand Five Hundreds Sixteen Only	
64	First Floor Conference Room, Ground Floor Conference Room(60 Seater): Supply, Installation, Testing & Commissioning of Application for the remote Control , Application should be installed in Touch panel and programmed with the controller. Application along with required software and drivers shall be of perpetual. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of approved make.	Nos	2	16354.8	-	32,709.60
					Rupees Sixteen Thousand Three Hundreds Fifty Four and Eighty Paise Only	
65	First Floor Conference Room, Ground Floor Conference Room(60 Seater): Supply, Installation, Testing & Commissioning of Wi-Fi Router, should have Ethernet Ports: 4 10/100/1000Mbps LAN Ports, 1 10/100/1000Mbps WAN Port, USB Ports: 1 USB 2.0 Port,Buttons: WPS/Wi-Fi On/Off Button, Power On/Off Button, Reset Button, Antennas: 3 External Antennas, Wifi router should have Wireless Standards: IEEE 802.11ac/n/a 5GHz, IEEE 802.11b/g/n 2.4GHz Frequency: 2.4GHz and 5GHz, Signal Rate: 867Mbps at 5GHz, 300Mbps at 2.4GHz. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of approved make.	Nos	2	4047.4	-	8,094.80
					Rupees Four Thousand Forty Seven and Forty Paise Only	
66	First floor CE cabin: Supply, Installation, Testing & Commissioning of Push-Pull Wall Mount for the above 55" Display. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of approved make.	Nos	1	12390	-	12,390.00
					Rupees Twelve Thousand Three Hundreds Ninety Only	

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹
		Rate in Words					
67	Ground floor canteen & visitor room: Supply, Installation, Testing & Commissioning of 55" display LED 4K LED Display,, Resolution : 3,840 x 2,160 (4K UHD), Brightness should have 500Nits or more, Display should have the feature to install in Landscape or portrait format, operation Hour should be 24/7, Should have following input Port Display Port*1 and HDMI Port*2 Nos. Should have USB Media Port with the Audio Output Port. Should Have LAN and RS 232 Control port input and Output. Should have 10w *2 Stereo Speaker , Display should have Wi-Fi (2.4/5.0GHz dual) and BT. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of approved make.	Nos	1	80948	-	-	80,948.00
		Rupees Eighty Thousand Nine Hundreds Forty Eight Only					
68	Ground floor canteen: Supply, Installation, Testing & Commissioning of Ceiling Hung Mount for the above 55" Display. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of approved make.	Nos	1	14042	-	-	14,042.00
		Rupees Fourteen Thousand Forty Two Only					
69	Ground floor lounge area: Supply, Installation, Testing & Commissioning of 85" LED 4k Display, Display Type-Panel Type-Slim Direct LED,Resolution-3,840 x 2,160,Brightness (Typical)-500Nits or better,Contrast Ratio 3,000 : 1 or better,Response time-8 ms or better,HDMI Input should be 2 or more,Display Port should have atleast one,Dvi Port should one,USB Port *2 minimum required, Display should have audio in and Audio Out, Should have RS-232 in and Out, Should have Wired LAN Port and also wireless network Connectivity. Operation Conditions-Temperature- 0 to 40 deg Celsius,Humidity-10 ~ 80%, non-condensing?. TV shall be supplied with mounting assemblies. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of approved make.	Nos	1	280840	-	-	2,80,840.00
		Rupees Two Lakh Eighty Thousand Eight Hundreds Forty Only					

Amey

Name of Work: Acoustic, Interior, Furniture, Audio Visual and General Lighting & Fixtures works for Quality Assurance(QA) Complex Building at Kaiga-5&6 WO / SOQR Number : 500102							
Agency Name : M/s Indecor Slides (India) Private Lim							
Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹
		Rate in Words					
70	Ground floor conference room: Supply, Installation, Testing & Commissioning of 1.5 mm Pixel Pitch or better, 136" All-in-One Direct View LED Display-Screen Size: 136" or more, Display Area (mm): 3000 (H) x 1687.5 (V) or more, Native Resolution: 1920x1080 or better, Panel Technology: Direct view LED, LED Package Type: SMD 3 in 1 (GOB), Pixel Pitch (mm): 1.56 or better, Brightness (max.): 600 nits (100 levels adjustable) or better, Contrast Ratio (typ.): 6500:1 or better, Viewing Angles (typ.): H = 170, V = 170 or better, LED Lifetime (typ.): 100,000 Hours or better, Local Storage: Total 32GB or more, Embedded OS: Minimum Android 9.0, Resolution Support: VGA(640 x 480) to 4K(3840 x 2160@60hz), HDTV Compatibility: 480p, 576p, 720p, 1080p, 2160p, HDMI Input-HDMI: 4 or more (HDMI 2.0/HDCP 2.2) (internal x3, external x1). Should have minimum USB Type A: 3 (USB3.0 x1, USB2.0 x2), should have RJ45 Input (Internet): 3 (Internet x2, control x1), IR in (3.5mm): 1, Wi-Fi Input: 2, 4G/5G Hz, USB Type C: 1, should have HDMI out: 1 (HDMI 1.4/HDCP 1.4) (internal x1), Speaker output-Speaker: 30Wx2 or better, Audio out (3.5mm): 2, S/PDIF: 1, Power Supply Voltage: 100-120V/20A ~ 50/60Hz or 220-240V/10A ~ 50Hz, Power Consumption: 609W (typ), 1740W (max), Operating Temperature: 0~40°C, Ingress Protection Rating: IP54 (Front), Impact Protection Rating: IK06 (Front), mounting kit and required accessories are included. All work shall be completed in accordance with the specifications including fixing & removing Staging / platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of approved make.	Nos	1	2388320	-	-	23,88,320.00
		Rupees Twenty Three Lakh Eighty Eight Thousand Three Hundreds Twenty Only					
71	Ground floor conference room: Supply, Installation, Testing & Commissioning of 55" Interactive display LED 4K LED Display, Resolution : 3,840 x 2,160 (4K UHD), B/ViewBoard@ 55" 4K Interactive Display, Panel Type. IPS,, with OPS, Panel Type: TFT LCD Module with DLED Backlight. Aspect Ratio: 16:9, Resolution: UHD 3840x2160, Colours: 1.07B colours (8bit+FRC) or better, Brightness: 450 nits (typ.) or better, Contrast Ratio: 1200:1 (typ.) 5000:1 (DCR) or better, Response Time: 8ms or better, Viewing Angles: H = 178, V = 178 typ. or better Backlight Life: 50,000 hours (Min) or better, Surface Treatment: Hardness: 9H, Anti-glare coating, Processor: ARM Cortex-A73*4 + Cortex-A53*4, RAM: 4GB, Storage: 32GB, Type/ Tech: Ultra Fine Touch Technology (IR Recognition), Touch Point: Windows: 40 points of touch, Android : 20 points of touch, minimum following input should have the Display-HDMI: 2.0 x 3 (3840x2160 @60Hz, HDCP2.2, HDMI1 with CEC/ARC), RS232: x1 OPS: x1, Wi-Fi: x1 module slot (Module included for the Wi-Fi connectivity), Display Should have following output-HDMI: x1 (4K@60Hz), Audio: x1 (Earphone out), SPDIF: x1 (optical), LAN-RJ45: x2, Display should have following input-Type A: 2.0 x 2, 3.0 x 4, Type B: x2, for touch, Type C: x1 (DP 1.2, USB2.0, PD65W, Ethernet 100M), SPEAKERS 12W x 2 + 16W x 1 subwoofer, display should have included following software-Basic Annotation Software, Pro Annotation Software, Wireless Presentation, Temperature (°C): 0°C to 40°C, Humidity: 10% ~ 90% RH non-condensing. All work shall be completed in accordance with the specifications including fixing & removing Staging / platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of approved make.	Nos	1	103250	-	-	1,03,250.00
		Rupees One Lakh Three Thousand Two Hundreds Fifty Only					

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹
		Rate in Words					
72	Ground floor conference room: Supply, Installation, Testing & Commissioning of Trolley for the 55" Interactive Display. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc. away from work premises & cleaning the work area etc. complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of approved make.	Nos	1	14042	-	-	14,042.00
				Rupees Fourteen Thousand Forty Two Only			
73	Ground floor conference room: Supply, Installation, Testing & Commissioning of 22" Interactive Display with the Tiltable Mount on Conference Table-Panel Type: IPS Technology Resolution: 1920 x 1080 or better,,Resolution Type: FHD (Full HD) or better,Static Contrast Ratio: 1,000:1 (typ) or better,Dynamic Contrast Ratio: 50M:1 or better,Light Source: LED,Brightness: 200 cd/m² (typ) or better,Colours: 16.7M or better,Colour Space Support: 8 bit (6 bit + Hi-FRC) or better,Aspect Ratio: 16:9,Response Time (Typical GTG): 5ms or better,Response Time (GTG w/OD): 5ms or better,Viewing Angles: 178° horizontal, 178° vertical Backlight Life (Hours): 30000 Hrs (Min) or better,Refresh Rate (Hz): 60, Flicker-Free: Yes, Colour Gamut: NTSC: 77% size (Typ), Touch Screen: Projected Capacitive, 10-point multi-touch, Surface Treatment: Glossy, Hard Coating (7H) should have the compatibility PC Resolution (max): 1920x1080,Mac@ Resolution (max): 1920x1080 PC Operating System: Windows 7/8.8, 1/10/11 certified: macOS tested,Mac@ Resolution (min): 1920x1080, should have following connectivity-VGA: 1,USB 3.2 Type A Down Stream: 2,USB 3.2 Type B Up Stream: 1,3.5mm Audio In: 1,3.5mm Audio Out: 1,HDMI 1.4: 1,Display-Port: 1,Power in: DC Socket (Center Positive) All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc. away from work premises & cleaning the work area etc. complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of approved make.	Nos	2	46256	-	-	92,512.00
				Rupees Forty Six Thousand Two Hundreds Fifty Six Only			
74	Ground floor conference room: Supply, Installation, Testing & Commissioning of Mini PC with the Wireless Keyboard and Mouse for conference ground floor. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc. away from work premises & cleaning the work area etc. complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of approved make.	Nos	1	109150	-	-	1,09,150.00
				Rupees One Lakh Nine Thousand One Hundreds Fifty Only			

hmy

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹
		Rate in Words					
75	Ground floor conference room: Supply, Installation, Testing & Commissioning of 8 x 8 HDMI Matrix Switcher-8x8 4K HDR HDMI HDCP 2.2 Matrix Switcher with Audio De-embedding. Switcher should have following AV I/O-Inputs-8 nos HDMI with 18G 4K@60Hz (4:4:4) HDR, output-8 nos HDMI with 18G 4K@60Hz (4:4:4) HDR,, 4 x S/PDIF: On female RCA connectors, 4 x Balanced Stereo Audio, switched should have following pots- 1 x usb port for the firmware upgrade, 1 x RS232 Port, 1 x LAN Port, and power on/off switch on front or back, Switch should have content Protection:- Supports HDCP 2.2/1.4, HDMI Port should support the following-HDMI Support: HDR10, xvYCC colour, Dolby TrueHD/DTS-HD Master Audio, 3D Video as specified in HDMI 2.0, Switcher should have the front Panel Button for the I/O Selection with the Front Panel Lock option, Switcher Should have the cooling fan with the 19" rack mounting kit. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of approved make.	Nos	1	636020	-	-	6,36,020.00
		Rupees Six Lakh Thirty Six Thousand Twenty Only					
76	Ground floor conference room: Supply, Installation, Testing & Commissioning of Mini PC with the Wireless KVM for the Software Based Video Conferencing. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of approved make.	Nos	1	109150	-	-	1,09,150.00
		Rupees One Lakh Nine Thousand One Hundreds Fifty Only					
77	Ground floor conference room: Supply, Installation, Testing & Commissioning of Constant Beamwidth Technology™ Line Array Column Loudspeaker-Speaker type- column, Peak power handling-480 W or better, Program power handling-240 W or better, Continuous power (AES)-120 W or better Impedance-12 ? or better, Sensitivity (1W/1m)-92 dB or better, Sound Pressure (Max. W/1m)-113 dB or better, Frequency Range (-10 dB) -120 Hz - 20 kHz, Frequency Response (± 3 dB) 150 Hz - 20 kHz, Drivers-12"x2", speaker should have Line Transformer Tapping-70V, Temperature Operating: -20 - +50 °C. Speaker shall be provided with mounting accessories. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of approved make.	Nos	4	87556	-	-	3,50,224.00
		Rupees Eighty Seven Thousand Five Hundreds Fifty Six Only					
78	Ground floor conference room: Supply, Installation, Testing & Commissioning of 4 Channel Amplifier for the Above Speakers-Continuous power (AES)@ 4 ? Stereo 4 x 250 W, @ 8 ? Stereo 4 x 130 W, @ 8 ? Bridge 2 x 500 W or better, Frequency Response (± 3 dB) 20 Hz - 20 kHz, Signal / Noise > 90 dB or better, THD+N (@ 1 kHz) < 0.1% or better, Crosstalk (@ 1 kHz) > 70 dB or better, Amplifier should have Class-D, Sensitivity-0 dB (1V RMS) or better, Impedance-12 k? balanced or better, should have following protection-DC Short circuit, Over heating, Over load, Signal limiting, Operating temperature 0° ~ 40° @ 95% Humidity. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of approved make.	Nos	1	118944	-	-	1,18,944.00
		Rupees One Lakh Eighteen Thousand Nine Hundreds Forty Four Only					

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹
		Rate in Words					
79	Ground floor conference room: Supply, Installation, Testing & Commissioning of Ceiling Speakers- Background/ Foreground Ceiling Loudspeakers- Rimless speaker system featuring a 134mm (5.25") polypropylene cone with a rubber surround for low frequency and a 19mm (0.75") silk dome tweeter optimized for speech intelligibility in high frequency. The system will be powered by a single Ethernet connection and includes an integrated mounting for the amplifier at the rear of the back-can. Audio input and output are via RJ45, CatX, and amplified audio over Category cable. The frequency range is from 50Hz to 20kHz (-10dB), with a coverage angle of 180 degrees (-6dB at 2kHz) and 107 degrees (-6dB at 10kHz). The speaker has a sensitivity of >91dB (at 1m) and complies with CE and RoHS standards. The system will be provided with all necessary components for installation and integration. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all lifts & height.	Nos	12	28084	-	-	3,37,008.00
		Rupees Twenty Eight Thousand Eighty Four Only					
80	Ground floor conference room: Supply, Installation, Testing & Commissioning of 4 Channel Amplifier for the Above Speakers-Four-channel PoE amplifier with integrated Dante networking, capable of powering in-ceiling loudspeakers. The amplifier shall include an additional network port to support Dante networking and shall be powered via Power-over-Ethernet (PoE). All necessary accessories and components shall be included for complete functionality and installation. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of approved make.	Nos	3	117292	-	-	3,51,876.00
		Rupees One Lakh Seventeen Thousand Two Hundreds Ninety Two Only					
81	Ground floor conference room: Supply, Installation, Testing & Commissioning of Boundary Layer Table Microphone-microphone shall be a cardioid pre-polarized condenser. The frequency response shall be 40 Hz - 20,000 Hz and sensitivity shall be 10 mV/Pa. Nominal impedance at 1 kHz shall be 200 Ω. Equivalent noise level shall be 26 dB(A) or 39 dB weighted as per CCIR 468-3. Dynamic range shall be 111 dB (A). Maximum SPL shall be 140 dB on-table boundary layer microphone. The microphone shall provide a tiny 3-pin XLR. The microphone shall operate on 48 V phantom power. Current consumption shall be 1.5 mA. The microphone shall have a rugged housing; dimensions shall be 85 x 100 x 25 mm (3.35" x 3.94" x 0.98"). Weight shall be 291 grams (10.27oz). Operating temperature shall range from -10 °C to +50°C (+14 °F to +122 °F). All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Product shall be of approved make.	Nos	22	51212	-	-	11,26,664.00
		Rupees Fifty One Thousand Two Hundreds Twelve Only					

Amr

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹
		Rate in Words					
82	Ground floor conference room: Supply, Installation, Testing & Commissioning of Digital Signal Processor with 16 nos AEC Input and 6 Nos of Analog Output with Dante and USB Card-Full rack 19" 1RU processor mainframe with sixteen user-configurable card slots (16 blank cards included). The mainframe supports selectable 48 kHz and 96 kHz sampling rates and features integrated, license-activated Acoustic Echo Cancellation (AEC) with dual-core 40-bit floating DSP processing. It includes a front panel OLED display with a jog wheel and a rear panel with an Ethernet module (RJ45 connector) and internal power supply connection. The MOD-Dante-ETH module is pre-installed to provide 64x64 I/O channels of Dante network audio, with dual RJ45 Dante and a single RJ45 Ethernet connector. It offers 6-channel mic/line inputs with selectable mic, line, mic gain, and phantom power, using 32-bit analog-to-digital converters, and 6-channel line outputs using 32-bit digital-to-analog converters. The system also features software-activated AEC, supporting 8 channels at 250 ms delay or 16 channels at 100 ms delay, and includes a USB 2.0 to Dante network endpoint with PoE-powered functionality. The setup shall be designed to be mounted under a table or behind a display and shall include UC mute synchronization, along with all necessary accessories. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of approved make.	Nos	2	525336	-	-	10,50,672.00
		Rupees Five Lakh Twenty Five Thousand Three Hundreds Thirty Six Only					
83	Ground floor conference room: Supply, Installation, Testing & Commissioning of Wireless handheld Microphone-Should have Audio frequency response 20 Hz - 20 kHz (-3 dB)@ 3 dBfs,Audio THD = -60 dB for 1 kHz@ -3 dBfs input level,Dynamic range 134 dB or better, System latency 1.9 ms or better,Operating temperature -10 °C - +55 °C(14 °F - 131 °F),Relative humidity 5 - 95 % (non-condensing), Receiver-Input voltage 11 - 13 V,Input current = 300 mA,Audio output power 18 dBu max.,Handheld Transmitter-Input voltage 2.0 - 4.35 V,Input current < 300 mA,Power supply 2 AA batteries 1.5 V,Sensitivity 2.1 mV/Pa,Sound pressure level 154 dB SPL,Pick-up pattern cardioid. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of approved make.	Nos	2	73160	-	-	1,46,320.00
		Rupees Seventy Three Thousand One Hundreds Sixty Only					
84	Ground floor conference room: Supply, Installation, Testing & Commissioning of 4K AI(4K Dual Video Outputs with a panoramic camera) Auto-Tracking 30x Zoom PTZ Camera-4K 60 Dual output, Video Output (HD) Interface HDMI / Ethernet / 3G-SDI / USB, USB output,Sensor-1/1.8" 8.48M,Video Format 2160p : 60 / 50,2160p : 30 / 25,1080p : 60 / 50 / 30 / 25,720p : 60 / 50 / 30 / 25,1080i : 60 / 50 ,Digital Zoom-8x,Horizontal Viewing Angle-59.2°, Vertical Viewing Angle-33.3°,Aperture-F1.6 ~ F5.4,Focal Length-7.1 ~ 213 mm or better,Minimum Object Distance-Tele:1.5m Wide:1m,Video S/N Ratio-> 50dB,Minimum Illumination-1Lux (F1.6, AGC ON),Focus System-Auto, manual,White Balance-Auto, manual,WDR-Yes,PIP-Yes, Camera should have Auto Tracking and Auto Framing. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of approved make.	Nos	1	289100	-	-	2,89,100.00
		Rupees Two Lakh Eighty Nine Thousand One Hundreds Only					



Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹
		Rate in Words					
85	Ground floor conference room: Supply, Installation, Testing & Commissioning of Capture-vision System 4-Channel Recorder and Streaming Media Processor with UltraHD and NDI-Recorder/streamer with multi-view capability supporting up to 4 video input channels (HDMI, 3G-SDI, IP, NDI) and 7 audio input channels (line in, combo XLR/TRS, IP audio). The system shall include 2 x HDMI outputs, 1 x HDMI loop-through, 1 x UVC output, and audio outputs including XLR, 3.5mm, and USB. The device shall support video compression (HEVC/H.264), support resolutions up to 4K@60fps, and provide scalable frame rates (60/50/30/25 fps). It shall have 4TB internal storage, USB external storage, and a 21-inch colour LCD monitor. Dual Ethernet ports for WAN/LAN integration and RS-232 serial control shall be included. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of approved make.	Nos	1	632480	-	-	6,32,480.00
		Rupees Six Lakh Thirty Two Thousand Four Hundreds Eighty Only.					
86	Ground floor conference room: Supply, Installation, Testing & Commissioning of Modular room video conferencing system-Video Input 3 x IP or USB based HP Poly Cameras,, Video Output 2 x HDMI, 3 x HDMI (Zoom Mode with optional adapter), Touch Display Compatible,Audio Input USB (UAC), 1 x HDMI, 1 x 3.5 mm stereo line-in, up to 3 IP Microphones, 8 HP A2 Microphones with Studio A2 Audio Bridge, Audio Output 1 x HDMI, USB (UAC), 1 x 3.5 mm stereo line-out, People Video Resolution 4K, 30 fps (TX and RX) from 2048 Kbps, 1080p, 60 fps from 1740 Kbps, 1080p, 30 fps from 1024 Kbps, 720p, 60 fps from 832 Kbps, 720p, 30 fps from 512 Kbps, Video Output Resolutions UHD (3840 x 2160), HD (1920 x 1080), HD (1280 x 720), Certifications Microsoft Teams TEAMS, Zoom, Tencent, Security AES 128 bits encryption, AES 256 bits encryption, H.235,6 support, Authenticated access to admin menus, web interface, and APIs, local account password policy configuration. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of approved make.	Nos	1	305620	-	-	3,05,620.00
		Rupees Three Lakh Five Thousand Six Hundreds Twenty Only					
87	Ground floor conference room: Supply, Installation, Testing & Commissioning of Partner Poly Plus, Three Year, Video Conferencing System . All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of approved make.	Nos	1	99120	-	-	99,120.00
		Rupees Ninety Nine Thousand One Hundreds Twenty Only					

Amey

Name of Work: Acoustic, Interior, Furniture, Audio Visual and General Lighting & Fixtures works for Quality Assurance(QA) Complex Building at Kaiga-5&6 WO / SOQR Number : 500102 Agency Name : M/s Indecor Slides (India) Private Limited							
Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹
		Rate in Words					
88	Ground floor conference room: Supply, Installation, Testing & Commissioning of Touch Panel Controller compatible with the Video Conferencing with calling(Dialling), preset recall, Navigation etc-Aspect ratio: 16:10,Brightness (typical): 300 nits,Display Contrast Ratio (Static): 1000:1 Native resolution: WXGA (1280 x 800),Panel technology: IPS,Display size (diagonal): 25.7 cm (10.1"),Horizontal viewing angle: 75° Vertical viewing angle: 75°,Connectivity and communications External I/O ports:1 RJ-45,Other features Special features: Air Quality Sensor; Proximity sensor;Scheduler; Wall mountable; Standalone mode,Power supply,Power features:Power over Ethernet (PoE), compatible with IEEE 802.3at class 0,Certifications:Certified collaboration software: Zoom and team. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of approved make.	Nos	1	127204	-	-	1,27,204.00
		Rupees One Lakh Twenty Seven Thousand Two Hundreds Four Only					
89	Ground floor conference room: Supply, Installation, Testing & Commissioning of Wired Ethernet Module with 2 COM Ports-100 Mbps, auto-switching, auto-negotiating, auto-discovery, full/half duplex, DHCP, SSL, TLS, IEEE 802.3af and 802.3at Type 1 compliant,For 2-way device control and monitoring, supports RS-232 up to 115.2k baud with hardware and software handshaking,LAN PoE (1) 8-pin RJ45 connector, female;100Base-TX Ethernet port; PoE (Power over Ethernet) PD (Powered Device) port;COM (2) 5-pin 3.5 mm detachable terminal blocks; Bidirectional RS-232 port; Up to 115.2k baud, hardware and software handshaking support,PoE (Power over Ethernet)-IEEE 802.3at Type 1 (802.af compatible) Class 0 (12.95 Watts) PoE Powered Device. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of approved make.	Nos	2	44604	-	-	89,208.00
		Rupees Forty Four Thousand Six Hundreds Four Only					
90	Ground floor conference room: Supply, Installation, Testing & Commissioning of Universal Keypad Interface, should have 4-pin 3.5mm detachable terminal block for the Bus,Inputs comprised of (2) GND references and 10-pin 0.1" IDC connector, includes (10) single conductor 22 AWG 3" flying leads (8) digital inputs, 0-pin 0.1" IDC connector, includes (10) single conductor 22 AWG 3" flying leads Outputs comprised of (1) 24VDC, (1) 5VDC, and (8) digital outputs (referenced to GND) Inputs rated for 0-24 Volts DC, includes 10K ohm pull-up to 5VDC, Logic Low Threshold: =1 Volt Logic High Threshold: =3.7 Volts. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of approved make.	Nos	3	28910	-	-	86,730.00
		Rupees Twenty Eight Thousand Nine Hundreds Ten Only					

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹
91	Ground floor conference room: Supply, Installation, Testing & Commissioning of Poe network Switch, POE Adopter should have Class 4 POE adopter, 24-Port Gigabit Ethernet High-Power PoE+ Smart Switch with 2 Dedicated SFP Ports (190W), ProSAFE@ 24-Port 10/100/1000 PoE+ Smart Switch with 2 Gigabit SFP Ports, Gigabit ports : 8, SFP ports : 2, Number of PoE ports : 8, PoE+ (802.3at) : 8, Total PoE Power budget (Watts) : 190W or better, Max MAC entries : 16K Buffer size : 1.5MB, VLAN (Number Supported) : 256, VLAN routing : Yes, Dynamic VLAN assignment : Yes All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of approved make.	Nos.	1	257712	-	-	2,57,712.00
							Rupees Two Lakh Fifty Seven Thousand Seven Hundreds Twelve Only
92	Ground floor conference room: Supply, Installation, Testing & Commissioning of 8 Channel dimming module- Analog dimming system 0-10V, PWM, DALI Broadcast with relay interface, Dimming of lamps fitted with Analog 1-10V dimmable drivers, Dimming of lamps fitted with Analog 0-10V dimmable drivers, Dimming of lamps fitted with PWM dimmable drivers, Dimming of lamps fitted with DALI drivers in broadcast mode, Relay controls for switching mains supply of all drivers mentioned above, POWER SUPPLY 230 VA 50 Hz Single Phase Max 40A, OUTPUTS 8 x 16A Switched Loads, Max total load to not exceed 40A 8 x 0-10V / PWM / DALI BC 25 ma per channel, POWER CONTROL 8 x Analog outputs selectable for 0-10V / 1-10V 8 x Analog outputs selectable for PWM signals, 8 x Analog outputs selectable for Dali broadcast mode 8 x Relays for driver power control of above driver types, Over-voltage protection, 60 non-volatile scene memory, Individual scene fade time, Create up to 16 areas, Last scene and channel level recall on power up, Front panel channel controls, Internal webserver for setup, Status LEDs. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of approved make.	Nos	6	30066.4	-	-	1,80,398.40
							Rupees Thirty Thousand Sixty Six and Forty Paise Only
93	Ground floor conference room: Supply, Installation, Testing & Commissioning of 6 Button Keypad compatible with the Dimming system(Dimmer), All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Note: Product shall be of approved make.	Nos	2	13216	-	-	26,432.00
							Rupees Thirteen Thousand Two Hundreds Sixteen Only
94	Ground floor conference room: Supply, Installation, Testing & Commissioning of Speaker Cable-4 Sq-mm, 2.5 Sq-mm, 1.5 Sq-mm: Supply, laying, termination, testing, and Commissioning of high-quality multi-strand copper speaker cables for audio signal transmission between amplifiers and loudspeakers, complete with proper ferrules, terminations, and identification labels along with Supply, Installation, Testing & Commissioning of Audio Line-Level Cable with Connectors and microphone cable and Supply, Installation, Testing & Commissioning of Audio Line-Level Cable with Connectors. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height.	Lot	1	483800	-	-	4,83,800.00
							Rupees Four Lakh Eighty Three Thousand Eight Hundreds Only

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹
							Rate in Words
95	Ground floor conference room: Supply, Installation, Testing & Commissioning of Connectors-XLR-Male, XLR-Female, XLR Panel Mount Male, XLR Female Panel Mount, EP Male and Female, RCA Male And Female, Spoon Connectors, XLR Wall Plate for Connecting Microphone. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height.	Lot	1	206500	-	-	2,06,500.00 Rupees Two Lakh Six Thousand Five Hundreds Only
96	Ground floor conference room: Supply, installation, testing, and Commissioning of an AV equipment rack with integrated climate control system, suitable for housing AV processors, amplifiers, servers, and networking equipment. The rack shall include all necessary cooling, cable management, power distribution, and safety features to ensure optimum performance and equipment longevity. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height.	Nos	1	66670	-	-	66,670.00 Rupees Sixty Six Thousand Six Hundreds Seventy Only
Schedule : CIVIL:D							
97	Conference room(60 seater): Ground floor Providing, Supplying, Installation, Testing & Commissioning of 30 Watt INSTARAY Slim LED Magnetic Fixed Linear Light suitable for 48V magnetic track lighting system, with high efficiency LED module, system efficacy =100 lm/W, luminous flux =3000 lumens, CCT 3000K / 4000K as specified, CRI =80, glare-controlled diffuser, precision-engineered aluminium housing with matte finish, snap-fit magnetic mounting compatible with slim magnetic track, complete with all required connectors, fixing accessories, alignment, electrical connection to 48V magnetic track, proper earthing, making good damages and testing complete as per direction of Engineer-in-Charge. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Model: LINRSD1F30XN or approved equivalent. Make: Jaquar/ Hybec/GM	Nos	40	4025	-	-	1,61,000.00 Rupees Four Thousand Twenty Five Only
98	Conference room(60 seater): Ground floor Providing, Supplying, Installation, Testing & Commissioning of Magnetic Track Slim System – 1 Meter Length, Recess Mounted, made of high-grade extruded aluminium profile suitable for 48V magnetic track lighting system, with integrated copper conductors, precision-engineered for snap-fit magnetic luminaires, powder-coated / anodised black or white finish as specified, complete with end caps, connectors, joiners, mounting accessories, cutting, alignment, recessed installation in false ceiling / gypsum / metal ceiling, making good the surface, proper earthing and testing complete as per direction of Engineer-in-Charge. Model: LTRKSM1MTRXX or approved equivalent. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Make: Jaquar/ Hybec/GM	Nos	3	2796	-	-	8,388.00 Rupees Two Thousand Seven Hundreds Ninety Six Only

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹
		Rate in Words					
99	Conference room(60 seater): Ground floor Providing, Supplying, Installation, Testing & Commissioning of Magnetic Track Slim System – 2 Meter Length, Recess Mounted, made of high-grade extruded aluminium profile suitable for 48V magnetic track lighting system, with integrated copper conductors, precision-engineered for snap-fit magnetic luminaires, powder-coated / anodised black or white finish as specified, complete with end caps, connectors, joiners, mounting accessories, cutting, alignment, recessed installation in false ceiling / gypsum / metal ceiling, making good the surface, proper earthing and testing complete as per direction of Engineer-in-Charge. Model: LTRKSM2MTRXX or approved equivalent. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Make: Jaquar/ Hybec/GM	Nos	20	5600	-	-	1,12,000.00
				Rupees Five Thousand Six Hundreds Only			
100	Conference room(60 seater): Ground floor Providing, Supplying, Installation, Testing & Commissioning of Magnetic Track Connector – L Shape (Horizontal), Recess Mounted, suitable for 48V magnetic track slim system, made of high-grade aluminium / engineered polymer with integrated electrical conductors, enabling right-angle horizontal connection between recessed magnetic tracks, complete with fixing accessories, electrical continuity connectors, alignment, concealed recessed installation, making good the surface, proper earthing and testing complete as per direction of Engineer-in-Charge. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Model: LTRCMLSHPHXX or approved equivalent. Preferred Make: Jaquar/ Hybec/GM	Nos	5	1276	-	-	6,380.00
				Rupees One Thousand Two Hundreds Seventy Six Only			
101	Conference room(60 seater): Ground floor Providing, Supplying, Installation, Testing & Commissioning of Magnetic Track Channel Fixed Joiner, suitable for 48V magnetic track slim system, made of high-grade aluminium / engineered polymer with integrated electrical continuity conductors, used for straight inline joining of magnetic track channels ensuring mechanical rigidity and uninterrupted electrical connection, complete with fixing accessories, alignment, concealed / recessed installation as applicable, making good the surface, proper earthing and testing complete as per direction of Engineer-in-Charge. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Model: LTRCMFJOINTR or approved equivalent. Preferred Make: Jaquar/ Hybec/GM	Nos	17	820	-	-	13,940.00
				Rupees Eight Hundreds Twenty Only			

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹
		Rate in Words					
102	Conference room(60 seater): Ground floor Providing, Supplying, Installation, Testing & Commissioning of Magnetic Track Bendable Loop-In Joiner, suitable for 48V magnetic track slim system, made of high-grade insulated flexible conductors with protective outer sheath, enabling bendable / curved or offset continuity between magnetic track channels while maintaining electrical and mechanical integrity, complete with fixing accessories, concealed / recessed installation as applicable, proper electrical continuity, earthing, making good the surface and testing complete as per direction of Engineer-in-Charge. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Model: LTRCMBLOOPIN or approved equivalent. Preferred Make: Jaquar/ Hybec/GM	Nos	5	1195	-	-	5,975.00
		Rupees One Thousand One Hundreds Ninety Five Only					
103	Conference room(60 seater): Ground floor Providing, Supplying, Installation, Testing & Commissioning of Magnetic Track I-Shape Connector, suitable for 48V magnetic track slim system, made of high-grade aluminium / engineered polymer with integrated electrical continuity conductors, used for straight inline (I-type) connection between magnetic track channels ensuring mechanical alignment and uninterrupted electrical continuity, complete with fixing accessories, concealed / recessed installation as applicable, proper earthing, making good the surface and testing complete as per direction of Engineer-in-Charge. Model: LTRCMISHPXXX or approved equivalent. Preferred Make: Jaquar/ Hybec/GM	Nos	27	210	-	-	5,670.00
		Rupees Two Hundreds Ten Only					
104	Conference room(60 seater): Ground floor Providing, Supplying, Installation, Testing & Commissioning of LED Magnetic Track Driver, 48V DC, 200 Watt suitable for powering magnetic track lighting system, with high efficiency SMPS, input voltage 220-240V AC, power factor =0.95, efficiency =90%, protections against short-circuit, over-voltage, overload & thermal faults, complete with all necessary wiring, connectors, fixing accessories, proper earthing, mounting arrangement (concealed / accessible as specified), making good damages and testing complete as per direction of Engineer-in-Charge. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Model: LDRVM48V200W or approved equivalent. Make: Jaquar/ Hybec/GM	Nos	8	6820	-	-	54,560.00
		Rupees Six Thousand Eight Hundreds Twenty Only					
105	Project Director room : First floor, Conference room(60 seater): Ground floor, CCE room : First floor Providing, Supplying, Installation, Testing & Commissioning of 96 Watt LED Indoor Strip Driver (SMPS) suitable for powering LED strip / COB strip lighting system, with high efficiency electronic power supply, input voltage 220-240V AC, output voltage as required (12V / 24V DC), power factor =0.90, efficiency =88%, protections against short-circuit, overload, over-voltage & thermal faults, slim compact metal housing suitable for concealed installation, complete with all necessary wiring, connectors, fixing accessories, proper earthing, making good damages and testing complete as per direction of Engineer-in-Charge. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Model: LDRVSL01S096 or approved equivalent.	Nos	25	1295	-	-	32,375.00
		Rupees One Thousand Two Hundreds Ninety Five Only					

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹
		Rate in Words					
106	Project Director room : First floor, CCE room : First floor Providing, Supplying, Installation, Testing & Commissioning of 8 Watt per metre Indoor COB LED Strip Light with uniform dot-free illumination, suitable for cove / profile / concealed lighting, system efficacy =90 lm/W, CCT 3000K / 4000K / 6500K as specified, CRI =80, operating on 24V DC, complete with matching electronic LED driver (SMPs) of adequate capacity, aluminium mounting profile with diffuser (wherever required), connectors, fixing accessories, wiring using FRLS copper flexible wire from driver to strip, proper earthing, making good damages and testing complete as per direction of Engineer-in-Charge. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc. away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Model: LSTPCOB008XN or approved equivalent. Preferred Make: Jaquar/ Hybec/GM	Nos	40	2215	-	-	88,600.00
		Rupees Two Thousand Two Hundreds Fifteen Only					
107	Project Director room : First floor, Conference room(60 seater): Ground floor, CCE room : First floor Providing, Supplying, Installation, Testing & Commissioning of Corner Bare Aluminium Profile 16 x 16 mm made of extruded aluminium section, suitable for corner mounting of LED strip / linear lighting applications, anodised / powder-coated finish as specified, complete with end caps, mounting clips / brackets, fixing accessories, cutting, alignment, and installation on wall / ceiling / joinery surfaces, including making good damages and testing complete as per direction of Engineer-in-Charge. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Model: CP1616BAREXX or approved equivalent. Preferred Make: Jaquar/ Hybec/GM	Nos	66	595	-	-	39,270.00
		Rupees Five Hundreds Ninety Five Only					
108	CCE room : First floor, Project Director room : First floor Providing, Supplying, Installation, Testing & Commissioning of 12 Watt NERO Surface Mounted Round LED Downlight with high efficiency LED module, system efficacy =90 lm/W, luminous flux =1080 lumens, CCT 3000K / 4000K / 6500K as specified, CRI =80, power factor =0.95, input voltage 220-240V AC, glare-controlled diffuser, powder-coated aluminium housing suitable for surface mounting on ceiling, complete with electronic constant current LED driver with protections, mounting accessories, FRLS copper flexible wiring, proper earthing, making good damages and testing complete as per direction of Engineer-in-Charge. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Model: LNRO02R012SC or approved equivalent. -Make: Jaquar/ Hybec/GM	Nos	77	868	-	-	66,836.00
		Rupees Eight Hundreds Sixty Eight Only					

Item No	Description	Unit	Quantity	Rate in ₹	Rebate In %	Rebated Rate	Amount in ₹
							Rate in Words
109	Dining room : First floor Providing, Supplying, Installation, Testing & Commissioning of 36 Watt Recessed Linear Profile LED Light (Cool White) made of extruded aluminium powder-coated white housing with glare-free opal / micro-prismatic diffuser, system efficacy =100 lm/W, luminous flux =3600 lumens, CCT 4000K ±300K, CRI =80, power factor =0.95, input voltage 220-240V AC, suitable for recessed mounting in false ceiling / gypsum / metal ceiling, complete with electronic constant current LED driver with inbuilt protections, all fixing accessories, supports, clamps, FRLS copper flexible wiring, proper earthing, making good damages and testing complete as per direction of Engineer-in-Charge. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Model: FPF-WHT-PRLR36CS08004FED or approved equivalent. Make: Jaquar/ Hybec/GM	Nos	27	6175	-	-	1,66,725.00
							Rupees Six Thousand One Hundreds Seventy Five Only
110	Dining room : First floor Providing, Supplying, Installation, Testing & Commissioning of 36 Watt ULTIMA SLIM 2' x 2' Recessed LED Panel Light (Cool White) with high efficiency LED modules, system efficacy =100 lm/W, luminous flux =3600 lumens, CCT 4000K ±300K, CRI =80, power factor =0.95, input voltage 220-240V AC, glare-free opal diffuser, slim powder-coated CRCA / aluminium housing suitable for recessed mounting in 600 x 600 mm T-grid / false ceiling, complete with electronic constant current LED driver with inbuilt protections, all fixing accessories, clamps, supports, wiring using FRLS copper flexible wire, proper earthing, making good damages and testing complete as per direction of Engineer-in-Charge. All work shall be completed in accordance with the specifications including fixing & removing Staging /platform / ladder wherever required, collecting & disposing the generated waste & construction waste etc, away from work premises & cleaning the work area etc, complete all as per standard & manufacturer's specification and as directed by Engineer-in-charge at all locations and at all lifts & height. Model: LULTSLS036XC or approved equivalent. Make: Jaquar/ Hybec/GM	Nos	8	1795	-	-	14,360.00
							Rupees One Thousand Seven Hundreds Ninety Five Only

Note: All Item Rates are considered to be in Indian Rupees unless otherwise explicitly specified and in which case shall be always converted appropriately to arrive at the amount in Indian Rupees.

Work Order Total	Rs. 4,69,04,880.12
Overall Rebate (%)	0
Work Order Value After Overall Rebate in Figure	Rs. 4,69,04,880.00
Work Order Value After Overall Rebate in Words	Rupees Four Crore Sixty Nine Lakh Four Thousand Eight Hundreds Eighty Only

[Signature]

Signature Not Verified

Digitally signed by BATHAL KUMAR
Date: 2026.06.25 16:40:27 IST
Location: eProcurement System for
Central PSUs