

सं. No. RR Site /C&MM-WG /CPT-A2957/2026/M/ 54

दिनांक Date: 18.07.2026

कायदेशि WORK ORDER

प्रति To,
मैसर्स. खान कांटेक्टर
M/s KHAN CONTRACTOR
बिहाइंड अजमेरा इलेक्ट्रिकल न्यू मार्केट
Behind Ajmera Electricals, New Market,
रावतभाटा, राज. -323307
Rawatbhata (Raj.) 323307
मोबाइल न. 9414331638
ई-मेल - mahmood.khancontractor@gmail.com

W.O. No.	64820
SL CODE	WOS 64820
A/C CODE	74231
USI NO.	90000
CHARGE CODE	9802
CC CODE	644
MSME Registration	Yes
PAN NO.	ALOPK3084D
NAME	Mahmood Khan
GSTIN	08ALOPK3084D1Z0
GST Rate	18%
SAC Code	995419
Bank Account No.	17920200001386
Bank & Branch	Bank of Baroda, Rawatbhata
IFSC Code	BARB0RAWATB

कृपया ध्यान दें Kind Attention (Mahmood Khan महमूद खान)

विषय Subject	:	“आर आर साइट में अणुकिरण और अणुछाया कालोनियों में भवन और बाहरी सिविल अवसंरचना कार्य की मरम्मत-रखरखाव के लिए द्विवार्षिक अनुबंध” के लिए कार्य आदेश। Work Order for the work of “Biennial Contract for Repair-Maintenance of Building and External Civil Infrastructure work in AnuKiran and AnuChhaya colonies at R.R. Site.”
संदर्भ Reference	:	1. निविदा सं. Tender No. :- NPC/RRS/90/2026/CPT-A2957
	:	2. आपका ई-निविदा प्रस्ताव सं. : 1001118 दिनांक 30/03/2026 Your e-Tender Offer no. : 1001118 Dtd. 30/03/2026
	:	3. Our Letter No. NPCIL/RRS/C&MM-WG/2026/M/44 dtd. 30/06/2026 regarding submission of notarized photocopies of documents.

प्रिय महोदय Dear Sir,

1.0 आपको सूचित किया जाता है कि (अनुलग्नक-1) उपरोक्त संदर्भनुसार आपके द्वारा उत्तरवर्ती पत्रों के साथ प्रस्तुत की गई बोली को एनपीसीआईएल के लिए एवं की ओर से मात्राओं एवं दरों की अनुसूची में दर्शाई गई मदों की दरें तथा कुल सभी करों सहित 4,45,89,331/- (रु चार करोड़ पैतालीस लाख नेवासी हजार तीन सौ इकतीस मात्र) के मूल्य के लिए निविदा में सम्मिलित दरों को स्वीकार कर लिया गया है।

This is to inform you that the bid submitted by you along with subsequent letters as referred above has been accepted for and on behalf of NPCIL for the item rates as shown in the Schedule of Quantities and Rates (Annexure-1) covered by the tender for a total value of ₹ 4,45,89,331/- (Rupees Four Crore Forty Five Lakh Eighty Nine Thousand Three Hundred Thirty One Only) inclusive of all taxes

- 1.1 संविदा के प्रचलन के दौरान वस्तु एवं सेवा कर की दर में कोई भी परिवर्तन होने पर दस्तावेजी साक्ष्य प्रस्तुत करने पर निगम द्वारा उसकी प्रतिपूर्ति/वसूली प्रयोज्य नियमों के अनुसार की जाएगी। Any variation in the rate of Goods & Service Tax during the currency of the contract shall be reimbursed/ recovered by the Corporation as per applicability on submission of documentary evidence.

2.0 मात्रा एवं दरें Quantities & Rates (AHR): Not Applicable

3.0 पूर्णता अवधि Completion Period:

- 3.1 यह कार्य सभी अर्थों में कार्य आरंभ होने की तारीख से 24 (चौबीस) कैलेंडर माह के भीतर पूर्ण कर लिया जाएगा। कार्य आरंभ होने की तारीख की गणना कार्य आदेश जारी होने की 05 दिनों के बाद.

The work shall be completed in all respect within **24 (Twenty Four) Calendar Month** from the date of commencement. The date of commencement will be reckoned from **05 days after issued of Work order**

- 3.2 वास्तविक कार्य प्रारम्भ होने की तारीख से ईएसआई/बीमा पॉलिसी ली जानी है। कार्य प्रारम्भ किए जाने की वास्तविक तारीख एवं विधिमान्य बीमा योजना के प्रभावी होने की तारीख के बीच के समय को बीमा योजना की अननुपलना माना जाएगा तथा तदनुसार कार्रवाई की जाएगी।

ESI / Insurance policy is to be obtained from the date of actual commencement of work. The period between the date of actual commencement of work and effective date of valid insurance policy shall be treated as noncompliance of insurance policy and shall be governed accordingly.

- 3.3 समयबद्धता संविदा की आत्मा है तथा कार्य को कार्य की अनुसूची के अनुसार ही पूर्ण किया जाएगा।

The time shall be the essence of the contract & the work shall be completed as per the schedule of work.

4.0 सुरक्षा जमा Security Deposit:

- 4.1 सुरक्षा जमा राशि **₹ 44,58,933/- (रुपए चौवालीस लाख अठ्ठावन हजार नौ सौ तेतिस मात्र)** अर्थात संविदा मूल्य की राशि का 10% होगी तथा जीसीसी के खंड सं. 4.2 के अनुसार नियंत्रित होगी।

Security Deposit shall be @ 10% of the Contract value i.e. **₹ 44,58,933/- (Rupees Forty Four Lakh Fifty Eight Thousand Nine Hundred Thirty Three Only)** and shall be governed as per clause no. 4.2 of GCC.

- 4.2 सुरक्षा जमा की उपरोक्त की गई गणना को दो भागों में विभाजित किया जाएगा एवं तदनुसार प्रस्तुत किया जाएगा: Security Deposit as calculated above shall be split in following two parts and to be furnished accordingly:

- a) जीसीसी के खंड सं. 4.2.3 के अनुसार, कार्यनिष्पादन गारंटी (अर्थात सुरक्षा जमा का 50%) **₹ 22,29,467/- (रुपए बाईस लाख उनतीस हजार चार सौ सत्तासठ मात्र)** संविदा एवं सामाग्री प्रबंधन (वर्क्स ग्रुप) को निर्धारित प्रपत्र में जमा कराई जाएगी। एलओआई / कार्य आदेश जारी होने के 30 दिनों के भीतर कार्यनिष्पादन गारंटी प्रस्तुत नहीं किए जाने पर इस कार्य आदेश को निरस्त समझा जाएगा।

As per clause no. 4.2.3 of GCC, performance guarantee (i.e. 50% of Security Deposit) **₹ 22,29,467/- (Rupees Twenty Two Lakh Twenty Nine Thousand Four Hundred Sixty Seven Only)** in the acceptable form shall be submitted to Contract & Material Management (Works Group). In case, performance guarantee is not submitted within the 30 days of issue of LOI /work order then this work order shall be liable towards cancellation.

- b) प्रतिधारण राशि अर्थात सुरक्षा जमा (अर्थात सुरक्षा जमा का 50% जो **₹ 22,29,466/-** है) (रुपए बाईस लाख उनतीस हजार चार सौ छछट मात्र) की वसूली आपके चालू बिल (Running Bills) में से की जाएगी। Retention money (i.e. 50% of Security Deposit amounting **₹ 22,29,466/- (Rupees Twenty Two Lakh Twenty Nine Thousand Four Hundred Sixty Six Only)** shall be recovered from your Running Bills.

- 4.3 प्रतिधारण राशि की कटौती उपरोक्त गणना किए गए सुरक्षा जमा के 50% की वसूली होने तक किए गए कार्य के मूल्य से 6% की दर से चालू बिलों में से की जाएगी। सुरक्षा जमा की राशि पर कोई ब्याज नहीं लगेगा। Retention Money shall be deducted at the rate of 6% of the value of work done from Running Bills till the 50% of Security Deposit amount as calculated above, is recovered. Security deposit amount will not bear any interest.
- 4.4 सुरक्षा जमा का प्रतिदाय संविदा की समान्य शर्तों के खंड 4.3 के अनुसार नियंत्रित होगा। 03 (तीन) महीनों की “दोष देयता अवधि” (Defect Liability Period) (निविदा देस्तावेज के सेक्शन-I शिड्यूल-A के अनुसार) एनपीसीआईएल द्वारा पूर्णता प्रमाणपत्र जारी किए जाने की तारीख से प्रभावी होगा। Refund of security deposit shall be governed by clause no. 4.3 of General Conditions of Contract. “Defect Liability Period” (as per Schedule-A of Section-I of tender document) of **03 (Three) months** will be effective from the date of completion as certified by the NPCIL.

5.0 भुगतान की शर्तें **Payment Terms:**

- 5.1 SOQR की मदों के लिए प्रगामी भुगतान (progressive payment) मासिक आधार पर निष्पादित किए गए कार्य तथा प्रभारी अभियंता द्वारा प्रमाणित किए जाने के अधीन के मानव संसाधन द्वारा मजदूरी भुगतान प्रमाणपत्र तथा निविदा सूचना के सेक्शन-III के अनुलग्नक-I के अनुसार जीएसटी इन्वॉइस के साथ जीएसटी घोषणा प्रस्तुत करने पर चालू खाता बिलों (Running Account (RA) Bills) के माध्यम से अनुमोदित दरों के अनुसार किया जाएगा।

The progressive payment for the item of SOQR shall be made on monthly basis for the work executed & accepted as certified by EIC as per approved rates through Running Account (RA) Bills on submission of labour payment certificate issued by HR and GST invoice along with GST declaration as per Annexure-I of Section -III of Tender-Notice.

- 5.2 निविदा सूचना के सेक्शन-A के लागू खंड के अनुसार जल प्रभार की कटौती आपके बिलों में से की जाएगी। Water charges as per relevant clause of Schedule-A of Tender-Notice will be deducted from your bills. निविदा/संविदा की शर्तों के अनुसार प्रयोज्य प्रकार की अन्य वसूली जैसे दंड, किराया प्रभार, विद्युत प्रभार, यदि कोई हों, आदि भी संविदाकार के आर. ए. बिल में से की जाएगी।

Other recoveries if any, as per applicability such as penalty, hire charges, Electricity charges etc. shall also be made from Contractor's R.A. Bill as per Tender/Contract conditions.

5.3 **स्रोत पर कारों की कटौती Taxes Deduction at Source:**

आय कर: भारत सरकार/राज्य सरकार के विधिक निकायों द्वारा समय समय पर जारी अधिसूचनाओं के अनुसार प्रयोज्य।

Income Tax: As Applicable as per notification issued by the Statutory Body Govt. of India/State Govt. from time to time.

वस्तु एवं सेवा कर: भारत सरकार/राज्य सरकार के विधिक निकायों द्वारा समय समय पर जारी अधिसूचनाओं के अनुसार प्रयोज्य।

Goods & Service Tax: As Applicable as per notification issued by the Statutory Body Govt. of India/State Govt. from time to time.

कर: सीजीएसटी एवं एसजीएसटी अधिनियमों के “Anti-profiteering” प्रावधानों के तहत वस्तुओं एवं सेवाओं के आपूर्तिकर्ता होने के नाते आपको न्यून कराधान तथा साथ ही इनपुट टैक्स क्रेडिट पर मिलने वाले लाभ जैसे लाभों को अंतिम उपभोक्ता अर्थात् एनपीसीआईएल को हस्तांतरित करने हैं।

Tax: Under “Anti-profiteering” provision of CGST & SGST Acts, being suppliers of Goods & Services, you are mandatorily required to pass on such benefits of lower taxation as well as benefits on input tax credit to the ultimate consumer i.e. NPCIL.

प्रतिवर्ती प्रभार प्रक्रिया: यह वर्तमान में प्रयोज्य नहीं है तथा कर विभाग को प्रयोज्य जीएसटी जमा करने/रियायत देने की पूरी जिम्मेदारी/देयता मेसर्स खान कांटेक्टर की होगी।

Reverse Charge Mechanism: Presently not applicable and entire responsibility/liability of depositing/remitting the applicable GST to Tax Department will lie with **M/s KHAN CONTRACTOR**

उपरोक्त के अतिरिक्त, भारत सरकार/राज्य सरकार द्वारा समय-समय पर जारी अधिसूचना के आधार पर किसी अन्य कर की भी कटौती की जाएगी।

In addition to above, any other tax based on notification issued by Govt. of India/State Govt. from time to time shall also be deducted.

5.4 **संविदा के अलग-अलग स्तरों पर बोलीदाता द्वारा प्रस्तुत किए जाने वाले दस्तावेज निम्नानुसार हैं:**

Documents to be submitted by the bidder at different stages of contract are as follows:-

A) कार्य प्रारम्भ करने के पूर्व Before commencement of work:

संविदाकार कार्य प्रारम्भ करने के पहले निम्नलिखित दस्तावेज प्रभारी अभियंता के समक्ष प्रस्तुत करेगा।

The Contractor shall submit following documents to Engineer-in- Charge before commencements of work.

- a. कार्य आदेश/एलओआई/संविदा आदेश/संस्तुति आदेश स्वीकृति पत्र. Work order / LOI / Contract Order / Sanction Order acceptance letter.
- b. श्रमिक लाइसेन्स, यदि लागू हो, तो प्राप्त करने के लिए प्रधान नियोक्ता प्रमाणपत्र (फॉर्म-III) जारी किए जाने के लिए आवेदन।

Application for issue of Principal Employer's Certificate (Form-III) for getting a Labour license, if applicable.

- c. BOCW अधिनियम तथा BOCW उपकर अधिनियम अधीन संविदाओं के लिए, संविदाकारों को स्वयं को उक्त अधिनियम से तहत पंजीकृत करवाना होगा। इस पंजीकरण की प्रति प्रभारी अभियंता को प्रस्तुत करनी होगी।

For the Contracts covered under BOCW Act and BOCW Cess Act, the contractor must get themselves registered under the Act. The copy of registration along with the shall be submitted to Engineer-in- Charge.

- d. प्रीमियम की रसीदों के साथ बीमा योजनाओं की मूल प्रतियाँ

Original Insurance Policies along with premium receipts

- i. संपूर्ण संविदा मूल्य (जीएसटी सहित) के लिए संविदाकार की सर्व जोखिम बीमा पॉलिसी जिसमें प्रयोज्यता के अनुसार संविदा मूल्य की 10% राशि के लिए तृतीय पक्ष देनदारी (Third Party Liability) के लिए बीमा भी सम्मिलित है।

Contractor's All Risk Insurance policy for the whole contract value (Including GST) including insurance for Third Party Liability for 10% of the contract value as per the applicability.

- ii. ESI योजना के अधीन व्यक्तियों के नाम इंगित करता ESI दस्तावेज अथवा वर्क मैन मुआवजा नीति अथवा प्रयोज्यता के अनुसार दोनों।

ESI document indicating the names of persons covered under the ESI scheme OR Workmen Compensation Policy OR both as per the applicability.

- e. संविदा की समान्य शर्तों के खंड सं. 4.2.3 के अनुसार कार्यनिष्पादन गारंटी

Performance guarantee as per clause 4.2.3 of General Conditions of Contract.

B) RA बिल के भुगतान के लिए For payment of the RA Bill,

संविदाकार प्रभारी अभियंता को प्रथम आरए बिल के साथ निम्नलिखित दस्तावेज प्रस्तुत करेगा:

The contractor shall submit the following documents along with first RA bill to EIC.

- a. श्रमिक लाइसेंस, जहां कहीं भी प्रयोज्य हो (केवल प्रथम आरए बिल के साथ)
Labour license wherever applicable (along with first RA Bill only).
- b. जीएसटी अधिनियम के अनुसार जीएसटी पंजीकरण की प्रति (केवल प्रथम आरए बिल के साथ)
GST registration Copy as per GST Act (along with first RA Bill only).
- c. जीएसटी के लिए घोषणा पत्र (अनुलग्नक-I) Declaration form for GST (**Annexure-I**)
- d. पिछले माह के GST कटौती के प्रमाण |
Proof of previous month GST remittance.
- e. प्रतिष्ठान के ईपीएफ पंजीकरण की प्रति के साथ कर्मचारियों की यूनिवर्सल EPFO खाता संख्या, जो KYC विवरण जैसे आधार संख्या, मोबाइल नंबर तथा बैंक खाता संख्या से लिंक हो (केवल प्रथम चालू खाता बिल के साथ)|
Copy of registration of EPF for firm along with the Universal EPFO account number (UAN) of all the employees, which shall be linked to KYC details such as Aadhaar number, Mobile number and bank account number (along with first RA Bill only).
- f. साझा प्रतिष्ठान के मामले में साझेदारी के देस्तावेज तथा कंपनी के मामले में प्रतिनिधि का मुख्तारनामा (केवल प्रथम आरए बिल के साथ)
Partnership deed of firm in case of partnership firm or power of attorney of the representative in case of company (along with first RA Bill only).
- g. भुगतान के लिए संविदाकार का बैंक खाते के विवरण (केवल प्रथम आरए बिल के साथ)
Bank account details of the contractor for payment (along with first RA Bill only).
- h. PAN कार्ड की प्रति (केवल प्रथम आरए बिल के साथ)
Copy of PAN card (along with first RA Bill only).
- i. प्रत्येक श्रमिक एवं संविदाकार द्वारा विधिवत हस्ताक्षरित यूनिफॉर्म वितरण का रिकॉर्ड| प्रपत्र अनुलग्नक-D के रूप में संलग्न है।
Record of uniform distribution duly signed by the Contractor and each of his workers. Proforma is enclosed as Annexure-D
- j. बिल की अवधि के लिए एनपीसीआईएल के प्रतिनिधि की उपस्थिति प्रमाणित मजदूरी भुगतान पंजिका की प्रति तथा बैंक अंतरण का विवरण।
Copy of wage register witnessed by NPCIL representative for the bill period and bank transfer details.
- k. मानव संसाधन द्वारा जारी मासिक मजदूरी भुगतान प्रमाणपत्र
Monthly wage certificate issued by HR.
- l. पिछले माह के EPF जमा के दस्तावेजी प्रमाण जिसमें प्रत्येक UAN का स्टेटमेंट दर्शाया गया हो।
Documentary proof of previous month EPF deposition showing statement for each UAN.
- m. ESIC पंजीकरण के विवरण की प्रति
Copy of ESIC registration details.
- n. तीन प्रतियों में टैक्स इन्वॉइस/ई-इन्वॉइस अथवा ई-इन्वॉइस का वचनपत्र।
Tax invoice/e-invoice or undertaking of e-invoice in triplicate.
- o. पिछले माह की ESI जमा के दस्तावेजी प्रमाण के साथ श्रमिकवार कटौती का विवरण, यदि लागू हो।
Documentary proof of previous month ESI deposition including employee wise details of remittance, if applicable.
- p. पिछले माह के BOCW उपकर कटौती के लिए साक्ष्य, यदि लागू हों।
Proof of previous month BOCW Cess remittance if applicable.
- q. प्रधान मंत्री रोजगार प्रोत्साहन योजना (PMRPY) वचनबंध के लिए हस्ताक्षरित अनुलग्नक-एफ, यदि लागू हो (प्रथम आरए बिल के साथ)

C) अंतिम बिल के भुगतान के लिए for payment of the Final Bill:

आरए बिलों के लिए आवश्यक दस्तावेजों के साथ साथ निम्नलिखित दस्तावेजों को भी प्रस्तुत किया जाना है:

The following documents shall be submitted in addition to those required for RA bills:

- a. संविदाकार द्वारा दावा प्रस्तुत नहीं करने की घोषणा
No claim declaration by the Contractor.
- b. कर्मचारी भविष्य निधि एवं विविध प्रावधान अधिनियम, 1952 के संबंध में संविदाकार द्वारा क्षतिपूर्ति
Indemnification by the Contractor regarding compliance of EPF & MP Act, 1952.
- c. बेबाकी प्रमाण पत्र, यदि कोई हो
No dues certificates if any.
- d. PMRPY योजना की वचनबद्धता हेतु हस्ताक्षरित अनुलग्नक-जी
Signed Annexure- G for PMRPY Scheme undertaking.
- e. BOCW अधिनियम, 1996 की अनुपालना के संबंध में संविदाकार द्वारा क्षतिपूर्ति, यदि प्रयोज्य हो
Indemnification by the Contractor regarding compliance of BOCW Act, 1996, if applicable.
- f. वास्तविक समापन तिथि तक मानव संसाधन समूह से मजदूरी प्रमाण पत्र
Wages certificate from HR section up to actual date of completion.

D) बोलीदाताओं द्वारा विधिक अपेक्षाओं की अनुपालना

Compliances by the bidders on statutory requirement:

a. आरए बिल/अंतिम बिल RA Bill / Final Bill:

संविदाकार का निरंतर अनुवीक्षण किया जाएगा और संविदाकार द्वारा संविदा की सामान्य शर्तों अथवा किसी अन्य संविदा दस्तावेज में उल्लिखित विधिक प्रावधानों की अनुपालना करने में असफल होने पर चालू लेखा बिलों/ अंतिम बिल को रोक लिया जाएगा।

The Contractor will be continuously monitored and Running Account Bills/ Final Bill of the Contractor will be withheld if they fail to comply with statutory provisions as mentioned in the General Conditions of Contract or any other contract document.

b. निष्पादन बैंक गारंटी(पीबीजी)/सुरक्षा राशि(एसडी) जारी करना

Release of Performance Bank Guarantee (PBG) / Security Deposit (SD) :

संविदाकार को प्रभारी अभियंता द्वारा प्रमाणित समस्त विधिक अनुपालना समेत संविदा के संतोषजनक कार्यपूर्णता के उपरान्त पीबीजी एवं एसडी जारी की जाएगी।

Release of PBG & SD will be after the satisfactory completion of the Contract including all statutory compliances as certified by the Engineer-in-Charge.

6.0 संविदा मूल्य का समायोजन Contract Price Adjustment:

6.1 इस संविदा के लिए संविदा मूल्य के समायोजन की प्रयोज्यता जीसीसी के उपयुक्त नियम के अनुसार होगी।

Applicability of Contract Price Adjustment for this contract will be as per relevant clause of GCC.

7.0 मजदूरी एवं संविदा श्रमिक अधिनियम Wages & Contract Labour Act:

7.1 आपको संविदा की सामान्य शर्तों के खंड सं. 5.4 के संविदा श्रमिक अधिनियम (नियमन एवं उन्मूलन), 1970 विविध प्रावधानों तथा इसके पश्चात समय-समय पर बनाए गए नियमों की अनुपालना करनी होगी। यदि आपके संगठन पर संविदा श्रमिक अधिनियम, 1970 लागू नहीं होता है तो, इसके लिए आप कार्य प्रारंभ करने के पहले प्रभारी अभियंता को सूचित करेंगे।

You shall comply with various provisions of the Contract Labour (Regulations and Abolition) Act 1970 of GCC Clause No. 5.4 and rules framed thereafter from time to time. In case the Contract Labour Act 1970 does not apply to your organization, you shall intimate to the Engineer-In-Charge of this work before commencement of the work.

इसके अतिरिक्त आपको नीचे वर्णित अन्य सभी प्रावधानों की पालना करनी होगी:

Further, you shall also comply with the provisions of all other applicable laws such as:

- a) कर्मचारी राज्य बीमा (ईएसआई) अधिनियम-1948 अथवा वर्क मैन मुआवजा नीति (यदि सभी अथवा कुछ श्रमिक कर्मचारी राज्य बीमा अधिनियम-1948 के तहत पात्र नहीं होते हैं तो सभी/शेष वर्क मैन के लिए श्रमिक मुआवजा नीति की आवश्यकता होगी। अर्हता निर्धारित करने के लिए भारत सरकार द्वारा अधिनियम के तहत जारी अधिसूचना का संदर्भ लिया जाए)

Employees State Insurance (ESI) Act-1948 Or Workman Compensation Policy (if all or some of the workers are not covered under the Employees State Insurance Act. 1948, the Workman Compensation Policy will be required for all / remaining workmen/employees. Notification issued by Govt. of India under the Act may be referred for deciding the eligibility).

- b) मजदूरी भुगतान अधिनियम The Payment of Wages Act-1936.

- c) न्यूनतम मजदूरी अधिनियम The Minimum Wages Act-1948.

- d) कर्मचारी भविष्य निधि एवं विविध प्रावधान अधिनियम-1952

The Employee's Provident Fund and Miscellaneous Provision Act-1952.

- e) उपदान का भुगतान अधिनियम Payment of Gratuity Act-1972

- f) भवन तथा अन्य निर्माण श्रमिक (नियोजन का नियमन एवं सेवा शर्तें) अधिनियम-1996 (यदि प्रयोज्य हो)

The Building and Other Construction Workers (Regulation of Employment and Conditions of Services) Act-1996 (if applicable).

- g) अन्य प्रयोज्य श्रम कानून जो प्रधान नियोक्ता के रूप में किसी प्रकार के व्यय का उत्तरदायित्व प्रदान करते हैं। ऐसी किसी परिस्थिति के उत्पन्न होने पर, एनपीसीआईएल के पास आपसे/आपके बिलों से उनकी वसूली करने का अधिकार है।

Other applicable labour laws which attract any liability to incur any expenditure as Principal Employer. If such situation arises, NPCIL is entitled to recover the same from you/your bills.

- 7.2 यदि इस कार्य के लिए 19 से अधिक श्रमिक नियोजित किए जाने हैं तो आपको प्रधान नियोक्ता का प्रमाणपत्र प्रपट करने के लिए अनुरोध करना होगा। कृपया ध्यान दें कि इस कार्य आदेश के जारी होने के 15 दिनों के भीतर आपको इस कार्य में नियोजित किए जाने वाले अधिकतम श्रमिकों के लिए क्षेत्र के सहायक श्रम आयुक्त के पास श्रम अनुज्ञापत्र के लिए आवेदन करना होगा। आप संबंधित प्राधिकारियों से एक मान्य श्रम अनुज्ञापत्र प्राप्त किया जाना सुनिश्चित करेंगे तथा इस कार्य आदेश में 20 अथवा अधिक श्रमिक नियोजित करने से पूर्व प्रभारी अभियंता को श्रम अनुज्ञापत्र प्रस्तुत करेंगे।

You will have to give request of Principal Employer's Certificate for obtaining labour license, if more than 19 numbers of workman are proposed to be employed for this work. Please note that, you have to apply for a labour license in the office of Assistant Labour Commissioner of the area within 15 days from the date of issue of this work order for maximum number of workers you have indicated to engage on the work. You shall ensure to obtain a valid labour license from the concerned authorities and submit labour license to Engineer-In-Charge before engagement of 20 or more workers in work order.

- 7.3 संविदाकार को अपने सभी श्रमिकों को आगे आने वाले माह के 7वें दिन अथवा उसके पहले बैंक के माध्यम से मजदूरी का भुगतान करना होगा, अन्यथा एससीसी के भाग-I के श्रेणी I से श्रेणी IV के खंड सं. 19 के अनुसार दंड अधिरोपित किया जाएगा। संविदा श्रमिकों को राशि के अंतरण वाली बैंक द्वारा जारी बैंक स्टेटमेंट/ऑन लाइन द्वारा सृजित बैंक स्टेटमेंट निविदा दस्तावेज के भाग-III के लागू खंड के अनुसार कार्य प्रभारी अभियंता को प्रस्तुत की जानी चाहिए।

The contractor shall make the payment to all its labour on or before 7th day of succeeding month through bank, failing which penalty shall be imposed at the rate of as per Clause no. 19 category I to Category IV Part-I of SCC. Bank statement issued by bank/online system Generated Bank Statement having transferred the amount to the contract workers should be submitted to EIC of the work as per relevant clause of Section-III of Tender Documents.

- 7.4 संविदाकार को बोनस भुगतान अधिनियम, 1965 में उल्लिखित एवं निविदा दस्तावेज में एससीसी के संबंधित खंड के अनुसार बोनस का भुगतान करना होगा।

The contractor shall have to make payment of Bonus as prescribed under the Payment of Bonus Act-1965 & as per relevant clause of SCC in Tender Documents.

- 7.5 निविदा दस्तावेज के एससीसी के संबंधित खंड के अनुसार कार्य प्रभारी अभियंता के पास ईएसआई में अंशदान के दस्तावेजी प्रमाण प्रस्तुत करने होंगे।

Document evidence of ESI contribution is to be submitted to EIC of work. As per relevant clause of SCC in Tender Documents.

8.0 कार्य का निष्पादन Execution of work:

कार्य को निविदा में उल्लिखित निबंधनों, शर्तों एवं विनिर्देशनों की सख्ती से अनुपालना करते हुए सर्वश्रेष्ठ कार्य निष्पादन के रूप में निष्पादित किया जाना चाहिए। आपको निविदा दस्तावेज में उल्लिखित अनुभाग की विशेष आवश्यकता (यदि कोई हों) के अनुसार पात्र अभियंताओं/पर्यवेक्षकों की नियुक्ति करनी होगी तथा उन्हें बनाए रखना होगा। कार्य को संतोषजनक रूप से पूर्ण करने के लिए आप साइट एवं कार्य स्थल पर सभी आवश्यक मशीनरी तथा उपकरण एवं अन्य समग्रियाँ लाएंगे।

The work shall be carried out strictly in accordance with the terms, conditions and specifications stipulated in the tender and also in best workman like manner. You shall employ and maintain qualified engineers/supervisors as per Sectional Special Condition of Tender Documents (if any). You shall also bring to the site and place such machinery and equipments & other materials as are necessary for the satisfactory completion of work.

9.0 प्रभारी अभियंता Engineer-In-Charge:

श्री सुरेश कुमार गौतम, वैज्ञानिक अधिकारी/एफ (ईएमजी-सी) इस कार्य के प्रभारी अभियंता होंगे। आप प्रभारी अभियंता से परामर्श के उपरांत तत्काल कार्य आरम्भ हेतु आवश्यक व्यवस्थाएं करेंगे।

Shri S.K. Gautam, SO/F (EMG-C) will be the Engineer-in-charge of this work. You may make necessary arrangement for commencing the work immediately in consultation with Engineer-In-Charge.

- 10.0 आपसे आपके प्राधिकृत प्रतिनिधि के नाम सूचित करने का अनुरोध किया जाता है जो कि संविदा से जुड़े समस्त मामलों पर कार्य करेंगे एवं समुचित मूल्य के स्टाम्प पेपर पर विधिवत रूप से उनके नाम तैयार किया गया मुख्तारनामा प्रस्तुत करना होगा।

You are requested to inform the name of your authorized representative who will deal with all matters relating to the contract and the Power of Attorney in his favour duly executed on stamped paper of an appropriate value shall be furnished.

- 11.0** संविदा के निष्पादन के दौरान एवं पूर्णता प्रमाण पत्र जारी किए जाने तक आप सर्व संबंधित को तृतीय पक्ष देयता सहित कार्य, संरचना, संपत्ति आदि को आपके कारण होने वाले किसी नुकसान, टूट-फूट अथवा कार्य में तोड़-फोड़ की क्षतिपूर्ति करने के लिए पूरी तरह से उत्तरदायी होंगे, जिसका निर्धारण प्रभारी अभियंता द्वारा किया जाएगा तथा इस संबंध में उनका निर्णय अंतिम होगा।

During the execution of the contract and until completion certificate is issued, you will be fully liable to compensate all concerned for any loss, damage or destruction of work, structure, property etc. including third party risk arising due to causes attributable to you which will be decided by the Engineer-in-Charge, whose decision in this regard will be final.

12.0 संरक्षा एवं साफ-सफाई Safety & Housekeeping:

संविदाकार को संविदा की सामान्य शर्तों के खंड सं. 5.6 तथा 21-प.ऊ.नि.बो. संरक्षा मार्गदर्शन के अनुसार सभी संरक्षा नियमों एवं विनियमों की अनुपालना करनी होगी। संविदाकार निविदा दस्तावेज के संबंधित खंडों एवं प्रक्रियाविधियों के अनुसार सभी संरक्षा एहतियातों, संरक्षा प्रशिक्षणों, संरक्षा अनुमतियों (औद्योगिक एवं रेडियोलॉजिकल) अनुपालना एवं क्रियान्वयन तथा संबंधित कार्य क्षेत्र की उचित साफ-सफाई के लिए उत्तरदायी होगा।

Contractor has to comply all the safety rules & regulations as per GCC clause No. 5.6 and 21- AERB Safety guide. Contractor shall be responsible for the observance & implementation of all safety precautions, Safety Trainings, Safety permissions (Industrial / Radiological) and proper housekeeping of the respective working area as per procedures and as per relevant Clauses of Tender document.

13.0 करार Agreement:

अनुरोध है कि इस कार्यादेश के जारी होने के 30 दिनों के अन्दर करार तैयार करवाने के लिए रु 500/- का गैर न्यायिक स्टैम्प पेपर संविदा एवं सामाग्री प्रबंधन (वर्क्स समूह) में प्रस्तुत करने का कष्ट करें। इस कार्यादेश के जारी होने की तिथि अथवा प्रथम चालू बिल के जारी होने की तिथि, जो भी पहले हो, के 60 दिवसों के भीतर एनपीसीआईएल एवं **मेसर्स खान कांटेक्टर** के मध्य समस्त निबंधन एवं शर्तों को समाहित करते हुए एक औपचारिक करार निष्पादित किया जाएगा। औपचारिक समझौता निष्पादित किए जाने तक निविदा दस्तावेज में वर्णित निबंधन एवं शर्तों को कार्य आबंधित किए जाने तक हुए समस्त पत्राचार की विषयवस्तु के साथ पढ़ी जाए एवं इस कार्यादेश की विषयवस्तु एनपीसीआईएल एवं **मेसर्स खान कांटेक्टर** के मध्य बाध्यकारी संविदा बनेगी।

It is requested to submit a Non-Judicial Stamp paper of ₹ 500/- to Contract & Material Management (Works Group) office for preparation of agreement within 30 days of issue of this work order to prepare a formal agreement between NPCIL & **M/s KHAN CONTRACTOR** within 60 days from the date of issue of this work order or release of 1st RA bill, whichever is earlier. Till formal agreement is executed, the terms and conditions stipulated in the tender document read along with the contents of all correspondences exchanged till the award of work and the contents of this work order shall form a binding contract between NPCIL & **M/s KHAN CONTRACTOR**

14.0 सामान्य General :

- 14.1 संविदा अवधि के दौरान किसी विवाद/शंका, जो कुछ भी होने पर, संविदाकार एवं एनपीसीआईएल के मध्य निविदा की सामान्य शर्तें बाध्यकारी होंगी। यह कार्यादेश संविदा की सामान्य शर्तों(जीसीसी) के खंडों द्वारा अधिशासित होंगे। अन्य समस्त निबंधन एवं शर्तें निविदा दस्तावेज के अनुसार प्रयोज्य होंगी।

In case of any dispute/ confusion whatsoever it may be during the contract period, General Conditions of Contract of Tender shall be binding between the contractor and NPCIL. This work order will be governed by the clauses of the General condition of contract (GCC). All other terms and conditions will be applicable as per tender document.

14.2 शास्तियों का जहाँ भी उल्लेख है, उनमें GST अधिरोपित होगा। देय शास्ति राशि पर GST अलग से प्रभारित किया जाएगा।

Penalties wherever mentioned are excluding GST. GST will be charged extra over levied penalty amount.


15.0 आपसे इस कार्यादेश की पावती एवं स्वीकृति देने तथा प्रभारी अभियंता से परामर्श कर अनुसूची के अनुसार कार्य आरंभ करने का अनुरोध किया जाता है।

You are requested to acknowledge the receipt & acceptance of this work order and commence the work as per schedule in consultation with the Engineer-in-charge.

धन्यवाद Thanking you,

संलग्न: मात्राओं एवं दरों की अनूची (अनुलग्नक-1)

Encl: Schedule of Quantities & Rates (Annexure-I)



(नौनिहाल सिंह मीणा Naunihal Singh Meena)

उप महाप्रबंधक सीएवंएमएम (कार्य समूह), आर.आर.साईट

न्यूक्लियर पावर कॉर्पोरेशन ऑफ इंडिया लिमिटेड के लिए एवं की ओर से

For & on behalf of the Nuclear Power Corporation of India Limited

NUCLEAR POWER CORPORATION OF INDIA LIMITED

(A Government of India Enterprise)

Rawatbhata Rajasthan Site

Schedule Of Quantities And Rates



Print Date: 18-Jul-2026



Name of Work: Biennial Contract for Repair-Maintenance of Building and External Civil Infrastructure work in AnuKiran and AnuChhaya colonies at R.R. Site.
WO / SOQR Number : 64820
Agency Name : M/s KHAN CONTRACTOR

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Amount in ₹
Rate in Words						
Schedule : NA:NA						
1	Surface Dressing of Ground including removing vegetations and / or inequalities not exceeding 15 cms. Deep and disposal of rubbish upto lead of 500 m and lift upto 1.5 m for all kind of soil. as per specifications and direction of EIC.	SqM	28.609			0
				Rupees Twenty Eight and Sixty Paise Only		
2	Excavation of Earth work in all types of ground substrata consisting of hard rock / fragmented rock / soft rock / ordinary soils / filled up ground / murrum requiring use of rock breaker, drilling, chiseling with mechanical / manual means etc. up to a depth of 1.5 m from the original ground level and dewatering if required for foundation of walls, columns, platforms etc. including backfilling with selected excavated materials in plinth and foundation trenches in layers not exceeding 200 mm thick, watering ramming etc. complete and disposing off the surplus materials to a maximum radially measured lead of 1.0 KM. as per drawings, design , safety and specifications and directions of the Engineer.	CuM	655.5548			0
				Rupees Six Hundreds Fifty Five and Fifty Five Paise Only		
3	Surface Excavation of Earth work not exceeding 30cm in depth but exceeding 1.5 m in width as well as 10 Sqm on plan including disposal of excavated earth up to 1.0 KM and lift up to 1.5 m, disposed soil to be leveled and neatly dressed etc. completed and disposing off the surplus materials to a maximum lead of 1.0 KM. radius as per drawings, specifications and as directed by the Engineer.	SqM	116.0708			0
				Rupees One Hundreds Sixteen and Seven Paise Only		
4	Supplying of Good Earth at site excavated and brought from outside (borrow pits / stock piles) free from weeds, roots, rubbles and other foreign material including royalty and carriage and filling in trenches, plinth and sides of foundation and other area etc. in layers not exceeding 20cm in depth consolidating each deposited layers by ramming and watering and lift upto 1.5m etc. complete (only consolidated fill shall be paid).	CuM	658.007			0
				Rupees Six Hundreds Fifty Eight and Paise Only		
5	Providing and Operation of Hydraulic Excavator/ J.C.B. of 1 cum bucket for clearing of rubbish, garbage, debris, Excavation work etc including cost of services of operating staff, Cost of lubricating oil, Diesel / petrol/kerosene oil, other consumables for running the machine all complete as directed by the Engineer-in-charge.	Per Hour	1120.6554			0
				Rupees One Thousand One Hundreds Twenty and Sixty Five Paise Only		
6	Supply and operation of 8 to 10 Tonne road roller with driver and two nos unskilled worker for ground levelling and true grade line (Uniform Surface etc) including all consumables i.e. diesel oil for lubricants etc all complete and as per Direction of the Engineer-in-charge (Working times 8 Hrs per day).	Per Day	5090.7672			0
				Rupees Five Thousand Ninety and Seventy Six Paise Only		
7	Providing and laying 150 mm thick Stone Soling under floors properly hand packed, filling interstices with spalls, gravels and inert fine material and consolidating to required gradient and camber, spreading, watering etc. complete as per drawings, specifications and direction of Engineer.	SqM	230.5068			0
				Rupees Two Hundreds Thirty and Fifty Paise Only		
8	Providing and laying 200 mm thick Stone Soling using quarry stone properly hand packed, filling interstices with spells, gravels and inert fine material and consolidating with power road roller to required gradient and camber including spreading, watering and rolling binding material etc. complete as per drawings, specifications and direction of Engineer.	SqM	287.7248			0
				Rupees Two Hundreds Eighty Seven and Seventy Two Paise Only		
9	Providing and laying in position Plain Cement Concrete (PCC) of 1:3:6 (1 Cement: 3 coarse Sand : 6 Graded Stone aggregate 20 mm nominal size) -at all level , transporting of concrete to site, laying, consolidation, finishing, curing etc. all complete excluding cost of centering & shuttering, as per direction of Engineer-in-charge.	CuM	5171.6898			0
				Rupees Five Thousand One Hundreds Seventy One and Sixty Eight Paise Only		
10	Providing and laying in position cement concrete of 1:2:4 (1 Cement: 2 coarse Sand : 4 Graded Stone aggregate 20 mm nominal size) - at all level, transporting of concrete to site, laying, consolidation, finishing, curing etc. all complete excluding cost of centering & shuttering, as per direction of Engineer-in-charge.	CuM	5661.3124			0
				Rupees Five Thousand Six Hundreds Sixty One and Thirty One Paise Only		
11	Providing and laying in position Cement Concrete of 1:1.5:3 (1 Cement: 1.5 coarse Sand : 3 Graded Stone aggregate 20 mm nominal size) - at all level, transporting of concrete to site, laying, consolidation, finishing, curing etc. all complete excluding cost of centering & shuttering, as per direction of Engineer-in-charge.	Cum	6052.847			0
				Rupees Six Thousand Fifty Two and Eighty Four Paise Only		
12	Providing and laying cement concrete of 1:2:4 (1 Cement : 2 Coarse sand : 4 graded stone aggregate 20 mm nominal size) machine mixed in approach pavement to garages etc. in suitable size of pannels including consolidation with needle and vibro compactor equipment and finishing with power floater and trowelled to desired finish & finally giving required broom finish with suitable means, sawing the contraction joint with machanical saw at specified spacing, the width of sawed groove shall be 6mm thick and depth shall be 1/4th of thickness of pavement and sawing operation should be carried out as soon as the concrete is ready to accept the saw cut without trowelling. The joint should be field with approved bitumastic sealant including transporting of concrete to site of laying including cost of centering and shuttering, finishing, curing etc. all Complete with all material and labour as per specifications and direction of Engineer-in-charge. (Qty of water used per bag of cement shall not be more than 22.5 ltr. cement admixture shall be added if required for desired workability)	CuM	7126.9106			0
				Rupees Seven Thousand One Hundreds Twenty Six and Ninety One Paise Only		
13	Providing and Application of IRONITE NO.3 powder (Metallic Dry shake natural cement colour) @ 6 Kgs/m2 sprinkled over green concrete with 1/3rd of the dry shake to be sprinkled in First pass and floated with Power float, remaining 2/3rd of dry shake to be sprinkled in next pass and the floor laid floated & trowelled to acquire desired finish.	SqM	133.2362			0
				Rupees One Hundreds Thirty Three and Twenty Three Paise Only		
14	Providing and laying in position machine batched, machine mixed and machine vibrated Design Mix Cement Concrete of all grades for Reinforced cement concrete or other works using 20mm size stone aggregates including transporting of concrete to site for laying but excluding the cost of centering, shuttering and reinforcement, including cost of finishing, compaction, curing, approved chemical admixtures conforming to IS 9103 in recommended proportions for achieving slump not less than 120mm and water/cement ratio not more than 0.42 at all level & for all sections as per drawings, specifications & direction of Engineer-in-charge. Use of concrete retarding agent / accelerator conforming to IS 9103 shall also be done if situation demands so. Rates should be based on using 350 kg of OPC 43 grade cement per Cum of concrete.	CuM	6866.16			0
				Rupees Six Thousand Eight Hundreds Sixty Six and Sixteen Paise Only		
15	Supplying Water Proofing Material Dr. Fixit Pidi proof LW plus / Complast X-421 1C of fosroc / STP no 1 of STP Ltd. as approved in NPCIL store & issuing the same from NPCIL store as per site requirement for mixing in cement plaster work / concrete work in proportion as recommended by the manufacturers etc. complete as per direction of Engineer-in-charge.	Litre	88.2792			0
				Rupees Eighty Eight and Twenty Seven Paise Only		



Name of Work: Biennial Contract for Repair-Maintenance of Building and External Civil Infrastructure work in AnuKiran and AnuChhaya colonies at R.R. Site.
WO / SOQR Number : 64820
Agency Name : M/s KHAN CONTRACTOR

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Amount in ₹
		Rate in Words				
16	Providing and laying Thermo-Mechanically Treated Reinforcement Bars of grade as specified in drawings/specifications and as directed by engineer conforming to IS : 1786 latest revision or the latest relevant code for RCC work including straightening, cutting, bending, placing in position and binding with 20 gauge annealed binding wire and cement mortar cover block of all size in C.M. 1:2 MIX etc. all complete- as per drawings, specifications & direction of engineer in charge.	Kg	76.8356			0
				Rupees Seventy Six and Eighty Three Paise Only		
17	Transporting of Re-steel from NPCIL Phase-1 store to site and laying Reinforcement bars for R.C.C. work including, cleaning straightening, cutting, bending, placing in position and binding with 20 gauge annealed binding wire and cement mortar cover block of 1:2 MIX etc. all complete- as per drawings, specifications & direction of engineer in charge.	Kg	40.0526			0
				Rupees Forty and Five Paise Only		
18	Providing Form Work of battened frame with sheathing having plywood lining / MS angle frame with sheathing of MS plate lining so as to give fair finish including centering shuttering strutting and propping etc. height of propping and centering below supporting floor not exceeding 3.5 meters to ceilings and removal of same for foundation, footings, columns, wall, Suspended floors, stairs, landings, balconies, lintels, beams, plinth beams, girders, cantilevers and access platform etc. complete at all level of floors / roof as per specifications and direction of Engineer in charge.	SqM	632.6676			0
				Rupees Six Hundreds Thirty Two and Sixty Six Paise Only		
19	Providing & laying Random Rubble Masonry with hard stone in foundation and plinth level of building & upto 3.00 Mtr. height from NGL for boundary/compound wall with Cement mortar 1:6 (1 Cement :6 Coarse sand) including cost of labour, materials, curing , raking out the joints , finishing, scaffoldings etc. all complete as per specifications and direction of Engineer in charge.	CuM	4865.9822			0
				Rupees Four Thousand Eight Hundreds Sixty Five and Ninety Eight Paise Only		
20	Providing and laying Fly-ash Brick Masonry class designation- 75 (IS-12894 -latest revision) in cement mortar 1:6 (1 cement : 6 coarse sand) upto plinth level including cost of labour, materials, curing, finishing, scaffoldings etc. all complete as per drawings, specifications and direction of Engineer in charge.	CuM	5523.1718			0
				Rupees Five Thousand Five Hundreds Twenty Three and Seventeen Paise Only		
21	Providing and laying Fly-ash Brick Masonry using Fly-ash building bricks of class designation- 75 (IS-12894 -latest revision) in cement mortar 1:6 (1 cement : 6 coarse sand) in superstructure above plinth level up to floor five level as per specifications and direction of Engineer including cost of labour, materials, curing, finishing, scaffoldings etc. all complete as per drawings, specifications and direction of Engineer in charge.	CuM	6186.9006			0
				Rupees Six Thousand One Hundreds Eighty Six and Ninety Paise Only		
22	Providing and laying Half Brick Masonry using fly ash bricks of class designation-75 (IS-12894 -latest revision) in cement mortar 1:4 (1 cement : 4 coarse sand) with RCC 1:2:4 (1 Cement : 2 Coarse sand : 4 graded stone aggregate 20 mm nominal size) stiffeners 75 mm thick horizontally @ 1000mm c/c excluding cost of laying reinforcement but including cost of RCC stiffeners in superstructure above plinth level upto floor five level including cost of labour, materials, curing, finishing, scaffoldings, shuttering etc. all complete as per specifications and direction of Engineer in charge. Note - Reinforcement bars to be paid in relevant item.	SqM	927.749			0
				Rupees Nine Hundreds Twenty Seven and Seventy Four Paise Only		
23	Providing and laying 6mm thick Cement Plaster (1 cement : 3 sand) in single coat on RCC ceiling face & parapet coping etc. for interior plastering at all levels including necessary grooves at the junction of RCC and brickwork arises, internal rounded angle, chamfers and / or rounded angles not exceeding 80 mm in girth including scaffolding, finishing, curing etc all complete as per specifications and direction of engineer.	SqM	264.0202			0
				Rupees Two Hundreds Sixty Four and Two Paise Only		
24	Providing and laying 15mm thick Cement Plaster 1:4 (1 cement : 4 fine sand) in single coat on either side of single or half brick wall for interior plastering at all levels using galvanized M.S. wire of I.S. gauge designation 26 s.w.g. chicken mesh over junctions of brick work, beams and column as required including necessary grooves at the junction of RCC and brick work, arises, internal rounded angles, chamfers and / or rounded angles not exceeding 80mm in girth including scaffolding, finishing, curing etc all complete as per specifications and direction of engineer.	SqM	359.656			0
				Rupees Three Hundreds Fifty Nine and Sixty Five Paise Only		
25	Providing and laying 18 mm thick Cement Plaster in two coats under layer 12 mm thick cement plaster 1:4(1 cement : 4 fine sand) finished with a top layer 6mm thick cement plaster 1:4 (1 cement : 4 fine sand) on either side of single or half brick masonry walls for exterior plastering at all height and using galvanized M.S. wire of I.S. gauge designation 26 S.W.G. chicken mesh over junctions of brick work, beams and column as required including necessary grooves at the junction of RCC and brick work, arises, internal rounded angles, chamfers and / or rounded angles not exceeding 80mm in girth including scaffolding, finishing, curing etc all complete as per specifications and direction of engineer.	SqM	471.6398			0
				Rupees Four Hundreds Seventy One and Sixty Three Paise Only		
26	Providing and laying 20 mm thick Cement Plaster of mix :- 1:4 (1 cement : 4 fine sand) including finishing, curing, scaffoldings etc. complete at all height as per direction of Engineer-in-charge.	SqM	421.7784			0
				Rupees Four Hundreds Twenty One and Seventy Seven Paise Only		
27	Neat Cement Punning including finishing, curing, etc. including cost of material and labour complete as per direction of Engineer-in-charge.	SqM	68.6616			0
				Rupees Sixty Eight and Sixty Six Paise Only		
28	Providing and laying 50 mm thick CC 1:2:4 for COPING using 12mm down aggregates, finishing the exposed surfaces with cement mortar 1 : 4 including fixing of broken glass pieces on top of coping wherever required, finishing, formwork, curing, scaffoldings etc. complete as per direction of Engineer-in-charge.	SqM	169.2018			0
				Rupees One Hundreds Sixty Nine and Twenty Paise Only		
29	Pointing on Stone Work with cement mortar 1:3 (1 cement :3 fine sand): Raised and cut pointing including finishing, curing, scaffoldings etc. complete at all height as per direction of Engineer-in-charge.	SqM	259.1158			0
				Rupees Two Hundreds Fifty Nine and Eleven Paise Only		
30	Providing & laying garage and Stilt Flooring Cement Concrete 1:2:4 (1 cement : 2 coarse sand :4 graded stone aggregate of approved size) in 50mm average thickness laid in suitable panels including Supply & Fixing of 40 mm x 4 mm glass strip in specified grid pattern in line and level including cost of shuttering, compaction, finishing and curing etc. all complete as per drawings, specifications and direction of engineer in charge.	SqM	559.1016			0
				Rupees Five Hundreds Fifty Nine and Ten Paise Only		
31	Providing and laying Kerb Stone of M-25 grade at or near ground level required size factory made cement concrete in position to the required line, level and curvature, jointed with cement mortar 1:3 (1 cement: 3 coarse sand), including making joints with or without grooves (thickness of joints except at sharp curve shall not to more than 5mm), including making drainage opening wherever required complete etc. as per specification & direction of Engineer-in-charge. (Precast C.C. kerb stone shall be approved by Engineer-in-charge).	CuM	7524.9844			0
				Rupees Seven Thousand Five Hundreds Twenty Four and Ninety Eight Paise Only		
32	Providing and laying Precast Cement Concrete Interlocking Pavers Block M-35 grade and 60mm thick factory made conforming to IS 15658 : 2006 made by block making machine with strong vibratory compaction and of approved shape pattern laid in required slope over and including 50mm thick compacted bed of fine sand, filling the joints with fine sand etc. all complete as per the specification & direction of Engineer ? in ? charge.	sqm	814.1304			0
				Rupees Eight Hundreds Fourteen and Thirteen Paise Only		
33	Providing and laying Coloured Precast Cement Concrete Interlocking Pavers Block M-35 grade and 80mm thick factory made conforming to IS 15658 : 2006 made by block making machine with strong vibratory compaction and of approved colour, size and shape pattern laid in required slope over and including 50mm thick compacted bed of fine sand, filling the joints with fine sand etc. all complete as per the specification & direction of Engineer ? in ? charge.	Sqm	905.6792			0
				Rupees Nine Hundreds Five and Sixty Seven Paise Only		



Name of Work: Biennial Contract for Repair-Maintenance of Building and External Civil Infrastructure work in AnuKiran and AnuChhaya colonies at R.R. Site.
WO / SOQR Number : 64820
Agency Name : M/s KHAN CONTRACTOR

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Amount in ₹
		Rate in Words				
34	Providing and fixing 10mm thick ENDURA TILES of approved brand, size and shade laid over a base of 20 mm av. thick cement mortar 1:4 (1 cement : 4 coarse sand) including ordinary Portland and polymer based cement slurry including grouting the joints with BAL ENDURA grouts (the joints between the tiles shall be 3mm to 5mm wide and 6mm to 8mm deep as per regular tiling procedure) and curing etc. all complete as per specifications and direction of engineer in charge.	SqM		1204.0302		0
		Rupees One Thousand Two Hundreds Four and Three Paise Only				
35	Chequerred Precast Cement Concrete Tiles 22 mm thick in footpath & courtyard, jointed with neat cement slurry mixed with pigment to match the shade of tiles, including rubbing and cleaning etc. complete, on 20 mm thick bed of cement mortar 1:4 (1 cement: 4 coarse sand). Dark shade pigment using ordinary cement including finishing & curing work at all level etc. complete as per direction of engineer in charge.	SqM		943.2796		0
		Rupees Nine Hundreds Forty Three and Twenty Seven Paise Only				
36	Providing and fixing up to floor five level RCC Precast Structural Elements / Members of size and thickness as required and as specify by EIC in lintel beam, slab, trench / drain covers etc. in cement concrete 1:1.5:3 mix (1 cement :1.5 coarse sand: 3 graded stone aggregate 20 mm nominal size) with maximum water content of 22.5 ltr. per bag of cement and additional slump generated by adding suitable quality cement admixture including fixing M.S. angle frame of required size all around the precast member to protect the edges wherever required, including hoisting and setting in position with cement mortar 1:3 (1 Cement: 3 coarse sand), Cost of required centering, shuttering including finishing smooth exposed surfaces, curing etc. all complete. at all level as per specification and direction of Engineer-in-charge. Note : Providing fabrication and fixing reinforcement and M.S. angle frame shall be paid in relevant item	CuM		7480.8448		0
		Rupees Seven Thousand Four Hundreds Eighty and Eighty Four Paise Only				
37	Providing & fixing Precast Cement Concrete Jali 1:2:4 (1 Cement :2 Coarse sand:4 graded stone aggregate 6mm nominal size) reinforced with 1.6 mm dia mild steel wire including centering and shuttering, compaction, roughening cleaning and finishing in cement mortar 1:3 (1 Cement :3 fine sand) etc. complete excluding plastering of the jambs, sills and soffits. 50 mm thick including transporting to site as per specification & direction of Engineer-in-charge	SqM		1619.2694		0
		Rupees One Thousand Six Hundreds Nineteen and Twenty Six Paise Only				
38	Providing & fixing 18mm to 22mm thick both face polished Kota Stone Shelves fixed in walls in cement mortar 1:3 (1 cement : 3 coarse sand) including cutting chases in masonry/plaster, finishing, making good the same, full moulding of exposed edges at all level complete as per specification and as directed by engineer in charge.	SqM		620.4066		0
		Rupees Six Hundreds Twenty and Forty Paise Only				
39	Providing and fixing polished Kota Stone Slab Flooring 18 to 22 mm thick in flooring, tread of steps, landing, laid over 20 mm (average) thick base of cement mortar 1:4 (1 Cement: 4 sand) and jointed with white cement slurry mixed with pigment to match the shade of the slab, including edge molding and cutting three nos. grooves neatly in longitudinal direction of steps for antiskid purpose, rubbing and polishing complete, including cutting of slot (without edge splitting) using mechanical means for receiving the handrail supports including finishing & curing work at all level etc. complete (size of kota stone shall cover full length & width of stair case treads as shown in drawings) as per specification & direction of Engineer-in-charge.	SqM		933.4708		0
		Rupees Nine Hundreds Thirty Three and Forty Seven Paise Only				
40	Providing and fixing polished Kota Stone Slab Flooring 18 to 22 mm thick in risers of steps, skirting, dado and pillars laid on 12 mm (average) thick cement mortar 1:3 (1 Cement 3: sand) and jointed with white cement slurry mixed with pigment to match the shade of the slab, rubbing and polishing complete, including finishing & curing work at all level etc. complete as per specification & direction of Engineer-in-charge. (size of kota stone shall cover full length & width of stair case risers as shown in drawings)	SqM		1231.8218		0
		Rupees One Thousand Two Hundreds Thirty One and Eighty Two Paise Only				
41	Providing and fixing Premium Quality Mat Finished Ceramic Floor Tiles of size 300x300mm and 6mm thickness conforming to IS: 15622 (latest revision) of H&R JOHNSON (pure mat finish Rustic /Lenox series) / KAJARIA (Digital floor -stain mat plain & printed mat finish) / NITCO (Crust digital floor tiles premium) as approved in required shade, laid on 20 mm thick bed of cement mortar 1:4 (1 cement: 4 sand) including grouting the joints using special tiles grout FEVIMAT - TG of Pidilite or similar approved make complete including covering of floor tiles with 3mm th. PVC tile protection sheet over it to protect the tile from painting stains and scratches during various finishing activities including finishing and curing work at all level etc. all complete as per specification & direction of Engineer in charge.	SqM		1080.6028		0
		Rupees One Thousand Eighty and Sixty Paise Only				
42	Providing and fixing Premium Quality Special Printed Ceramic Glazed Wall Tiles of size 450mmx300mm and 6mm thickness of approved shade in base and highlighter conforming to IS: 15622 (latest revision) of H&R JOHNSON wall tiles (DIGITAL PRINTED SERIES) / KAJARIA (Digital & power line) / NITCO (Cosmos digital wall tiles) as approved in skirting and dado over 12mm thick bed of cement mortar 1:3(1 cement :3 sand) including grouting the joints using special tiles grout FEVIMAT - TG of Pidilite or similar approved make complete including protecting the tiles from painting stains and scratches during various finishing activities including finishing and curing work at all level etc. all complete as per specification & direction of Engineer in charge.	SqM		1186.8648		0
		Rupees One Thousand One Hundreds Eighty Six and Eighty Six Paise Only				
43	Polishing on masonry or concrete floor with wax polish of approved brand and manufacture after cleaning / scrubbing of surfaces with wire brushes, soft brushes & sand papers including the cost of materials, labour, cleaning of area after polishing etc., complete as per direction of Engineer-In-charge.	SqM		80.1052		0
		Rupees Eighty and Ten Paise Only				
44	Providing and laying Premium Quality Polished Vitrified Tiles of required size (600mm x 600mm / 600mm x 1200mm as required) of approved shade and conforming to IS: 15622 (latest revision) of H&R JOHNSON (pure mat /polish finish GVT series) / KAJARIA (Desert series - mat/polish finish)/ NITCO (Architect series - mat/polish finish) as approved, laid on 20 mm thick cement mortar 1:4 (1 Cement: 4 sand) in floors and skirting including grouting the joints using special tile grout FEVIMATE-TG of Pidilite or similar approved make complete: including covering of tiles with 3mm th. PVC tile protection sheet over it for protection of tiles from paint stains, scratch during various finishing activities including finishing and curing at all levels etc. all complete as per specification and direction of Engineer-in-charge.	SqM		1343.8056		0
		Rupees One Thousand Three Hundreds Forty Three and Eighty Paise Only				
45	Providing and laying Terrazzo Tiles 22mm thick with graded marble chips of size up to 6mm in floors jointed with neat cement slurry mixed with pigment to match the shade of the tiles including rubbing and polishing complete on 20 mm thick bed of cement mortar 1:4 (1Cemnt:4 Coarse sand): Light shade using white cement including finishing & curing work at all level etc. complete as per direction of Engineer-in-charge.	SqM		1135.3686		0
		Rupees One Thousand One Hundreds Thirty Five and Thirty Six Paise Only				
46	Providing and fixing Polyvinyl Chloride Sheet 3 MM thickness / P.V.C. Tile (of other woven fabric flooring / using rubber base adhesives including rolling with light wooden roller complete (3.0 mm thick sheet) as per specification & direction of EIC.	SqM		1152.534		0
		Rupees One Thousand One Hundreds Fifty Two and Fifty Three Paise Only				
47	Providing and fixing 14 to 16 mm thick Marble Stone gang saw cut, mirror polished, premoulded and prepolished, machine cut on wall tops, sides, facias and similar locations of required size (all size), approved shade, colour and texture over 12 mm thick (average) base cement mortar 1:3 (1 cement : 3 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges wherever required to give high gloss finish etc. complete at all levels. (Base rate of marble stone shall not be less than 600/- per Sqm)	SqM		3375.0446		0
		Rupees Three Thousand Three Hundreds Seventy Five and Four Paise Only				



Name of Work: Biennial Contract for Repair-Maintenance of Building and External Civil Infrastructure work in AnuKiran and AnuChhaya colonies at R.R. Site.
WO / SOQR Number : 64820
Agency Name : M/s KHAN CONTRACTOR

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Amount in ₹
		Rate in Words				
48	Providing and fixing in full width & length 15mm to 18mm thick Granite Black or any other approved shade / colour / texture gang saw cut mirror polished, premoulded, machine cut for kitchen platforms, fascias and similar locations laid over 20 mm thick base cement mortar 1:4 (1 Cement :4 sand) with joints treated with white cement mixed with matching pigment, epoxy touch ups, including rubbing, curing, edge moulding and polishing to edge to give high gloss finish etc. complete at all levels: Area of slab over 0.50 Sqm. including finishing & curing work at all level etc. complete as per drawing, specifications and direction of Engineer-in-charge. (Base rate of granite shall not be less than Rs. 1800 / Sqm) Note:- Sample of granite shall be approved by EIC before bulk purchase.	SqM		3890.0066		0
		Rupees Three Thousand Eight Hundreds Ninety and Paise Only				
49	Providing and fixing 15 to 18mm thick Granite Black or any other approved shade / colour / texture gang saw cut mirror polished, premoulded, machine cut for wash basin counter including cutting opening for wash basin making half round edge moulding in granite stone for counter etc. all complete of required size laid over 20 mm thick base cement mortar 1:4 (1 Cement :4 sand) with joints treated with white cement mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edge to give high gloss finish etc. complete at all levels: as per drawing, specifications and direction of Engineer-in-charge. (Base rate of granite shall not be less than Rs. 1800 / Sqm) Note:- Sample of granite shall be approved by EIC before bulk purchase.	SqM		4263.5584		0
		Rupees Four Thousand Two Hundreds Sixty Three and Fifty Five Paise Only				
50	Providing and fixing factory made 30 mm thick Flush door shutter single / double leaf conforming to IS ; 2202(part-1) of make KITPLY / GREENLAM / CENTURY as approved by EIC, with Block board core & frame of well seasoned hard wood, cross band made from BWP grade veneers and commercial BWP grade face veneers on both sides of shutter including providing and fixing 2nd class teak wood leaping of suitable size and shape all around the edges including approved brand stainless steel fixtures like Tower bolt (size-250mmx12mm), Tadi latch (300mmx14mm), Aldrop (300mmX16mm), Handles plate type - 100mm size (size shall be confirming to IS:208) - 02 nos, Magnetic Cather etc. painting two coats of synthetic enamel paint over a coat of primer of approved brand etc. complete as per drawings, specifications and direction of Engineer. Note - actual area of shutter will be paid.	SqM		2770.1686		0
		Rupees Two Thousand Seven Hundreds Seventy and Sixteen Paise Only				
51	Providing and fixing factory made 35 mm thick both side laminated flush door shutters single leaf conforming to IS ; 2202(part-1) of make KITPLY/ GREENLAM / CENTURY as approved by EIC with Block board core & frame of well seasoned hard wood, cross band made from BWP grade veneers and commercial BWP grade face veneers on both sides of shutter including providing and fixing 2nd class teak wood leaping of suitable size and shape all around the edges including supply and fixing of approved brand stainless steel fixtures like Tower bolt (size-250mm long rod size 12mm), Tadi latch (300mm long rod size 14mm), Aldrop (300X16mm), Handles plate type - 100mm size (size shall be confirming to IS:208) - 02 nos, Magnetic Cather etc. with approved quality judas eye, safety chain etc. complete as per drawings, specifications and direction of Engineer. (Door skin shall be 1.0 mm thick on front face and 0.8mm thick on back face with the provision of edge bending of decorative high pressure laminated sheet of plain/wood grain in gloss/ matt/ suede finish with high density protective surface layer of make KITPLY / GREENLAM / CENTURY as approved by EIC). Note - actual area of shutter will be paid.	SqM		3402.0188		0
		Rupees Three Thousand Four Hundreds Two and One Paise Only				
52	Providing and fixing 30mm thick factory made pre-laminated PVC Door Shutter of approved make and design consisting of frame made out of M.S. tubes of 19 gauge thickness and size of 19 mm x 19 mm for styles and 15x15 mm for top & bottom rails. M.S. frame shall have a coat of steel primers of approved make. M.S. frame covered with 5 mm thick heat molded PVC 'C' channel of size 30 mm thickness, 95 mm width out of which 75 mm shall be flat and 20 mm shall be tapered in 45 degree angle on both side forming styles and 5 mm thick, 115 mm wide PVC sheet out of which 95 mm shall be flat and 20 mm shall be tapered in 45 degree on the inner side to form top and bottom rail and 140 mm wide PVC sheet out of which 100 mm shall be flat and 20 mm shall be tapered on both sides to form lock rail. Top, bottom and lock rails shall be provided both side of the panel. 10 mm (5 mm x 2) thick, 20 mm wide cross PVC sheet be provided as gap insert for top rail & bottom rail, paneling of 5 mm thick both side PVC sheet to be fitted in the M.S. frame welded/ sealed to the styles & rails with 7 mm (5 mm+2 mm) thick x 15 mm wide PVC sheet beading on inner side, and joined together with solvent cement adhesive. An additional 5 mm thick PVC strip of 20 mm width is to be stuck on the interior side of the 'C' Channel using PVC solvent adhesive etc. including all SS fitting and fixtures such as 1 nos Tadi latch 200mm longx12mm rod size, 2 nos. tower bolt 250mm x 12mm, 2 nos. plat type handles - 100mm size (size shall be confirming to IS:208) of approved brand complete as per drawing, specification & direction of Engineer-in-charge.	SqM		2385.1732		0
		Rupees Two Thousand Three Hundreds Eighty Five and Seventeen Paise Only				
53	Supplying and fixing Rolling Shutters of approved make, made of required size M.S. laths interlocked together through their entire length and jointed together at the end by end locks mounted on specially designed pipe shaft with brackets, side guides and arrangements for inside and outside locking with push and pull operation complete including the cost of providing and fixing necessary 27.5cm long wire spring grade No. 2 and M.S. top cover of required thickness for rolling shutters. 80mmx0.90mm M.S. laths with 0.90mm thick top cover all complete as per drawings , specifications & direction of engineer in charge.	SqM		2391.7124		0
		Rupees Two Thousand Three Hundreds Ninety One and Seventy One Paise Only				
54	Providing and fixing in position Collapsible Steel Shutter with Vertical M.S. channels 20X10X2 mm and bracket with flat iron diagonals 20X5 mm size with top and bottom rails of T-iron 40X40X6 mm with 40mm dia steel pulleys / ball bearing with bolt,nuts , locking arrangements inside and outside stoppers, handles etc. and applying a priming coat of approved steel primer all as per standard design ,all complete as per drawings, specifications & direction of engineer in charge.	Kg		79.2878		0
		Rupees Seventy Nine and Twenty Eight Paise Only				
55	Providing and fixing double leaf cupboard shutters with frame fabricated from 18-19mm thick BWP grade block board conforming to IS:1659, Kit board gold / Greenlam / Century make with laminate of approved make (Kit ply / Greenlam / Century) and shade on both faces (1 mm thk. laminate on front face and 0.8 mm thk. on back face with the provision of edge bending) including IInd class teak wood lipping of 19mm wide x 6 mm thick with necessary S.S screws and bright finished heavy duty stainless steel fixtures of approved brand (two nos handles plate type - 100mm size (size shall be confirming to IS:208), two nos. magnets, two nos. tower bolt of 100mmx10mm rod size, one nos. hasps and staples etc.), Stainless Steel Butt hinges / S.S. piano hinges etc. as approved all complete as per drawings, specifications and directions of Engineer-in-charge with Note - actual area of shutter with frame will be paid.	SqM		2587.8884		0
		Rupees Two Thousand Five Hundreds Eighty Seven and Eighty Eight Paise Only				
56	Providing and fixing 30mm thick IInd class M.P. teakwood G.I. wiremesh shutters using wire mesh of average aperture 1.4mm with wire of dia 24 gauge for door / window / ventilators including two coats of approved synthetic enamel paint over a coat of approved wood primer and also including ISI marked bright finished heavy duty M.S butt hinges with necessary screws and fixtures like havey duty Aluminium Tower bolts (size-200mm long), Handles (125mm long) etc: All as per specifications and direction of Engineer-in-charge. Fabrication details of styles, rails, teakwood, beading shall be as per standard I.S. specifications. Note - actual area of shutter will be paid.	SqM		3814.8058		0
		Rupees Three Thousand Eight Hundreds Fourteen and Eighty Paise Only				
57	Providing and fixing 30mm thick second class M.P. teak wood glazed shutters for windows / ventilators using 4 mm thick FLOAT glass panes including two coats of approved synthetic enamel paint over a coat of approved wood primer and also including bright finished ISI marked heavy duty M.S butt hinges with necessary screws and fixtures like heavy duty Aluminium Tower bolt (size-200mm long), Handles (125mm long) etc: as per specification and directions of Engnieer-in-charge fabricating details of styles, rails, teakwood, beading shall be as per standard I.S. specification Note - actual area of shutter will be paid.	SqM		3546.6986		0
		Rupees Three Thousand Five Hundreds Forty Six and Sixty Nine Paise Only				
58	Providing and fixing wooden moulded corner beading of triangular shape to the junction of panelling etc. with iron screws, plugs etc. complete 2nd class teak wood: 50x50mm(base and height) as per drawings, specifications and directions of Engineer-in-charge.	Metre		335.9514		0
		Rupees Three Hundreds Thirty Five and Ninety Five Paise Only				



Name of Work: Biennial Contract for Repair-Maintenance of Building and External Civil Infrastructure work in AnuKiran and AnuChhaya colonies at R.R. Site.
WO / SOQR Number : 64820
Agency Name : M/s KHAN CONTRACTOR

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Amount in ₹
		Rate in Words				
59	Providing & Fixing of 2nd class teak wood lipping/moulded beading or taj beading of size 18x5 mm fixed with wooden adhesive of approved quality and screws/ nails on the edges of the pre-laminated particle board etc. complete as per drawings, specifications and directions of Engineer-in-charge.	Metre		84.1922		0
				Rupees Eighty Four and Nineteen Paise Only		
60	Providing and fixing colour anodized aluminium work for doors, windows, ventilators and partitions as per the material, fabrication and dimensional specifications/ requirement of IS: 1948 from aluminum alloy extruded sections, tubular / appropriate Z and or other sections of approved make conforming to grade HE9-WP of IS : 733 and HV9-WP of IS: 1285, fixed with raw plugs and screws or with fixing clips, or with expansion hold fasteners including necessary filling up of gaps at junctions, at top, bottom and sides with required neoprene felt and silicon whether sealant etc. Aluminium sections shall be smooth, rust free, straight, mitered and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling. C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. : For shutters of doors, windows & ventilators including providing and fixing approved ss hinges/ pivots/ rollers suitable for sliding / openable window and providing and fixing approved fittings i.e. two handle with locking arrangement for each sliding window shutter and one handle as well as two tower bolt for each glass / jali shutter with provisions of one gate hook for each glass shutter for openable window wherever required as approved including the cost of neoprene gasket all complete: colored anodized coated aluminium (thickness of anodized coating 15 micron). The finished arrangement shall be fully water tight. Note : 1. Payment of Glazing / SS wire mesh to be paid in relevant item in line with their specifications. 2. Cost of SS hinges / pivot / rollers are to be included in the quoted rate and no payment shall be made for providing and fixing the same.	Kg		372.7344		0
				Rupees Three Hundreds Seventy Two and Seventy Three Paise Only		
61	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with neoprene gasket and silicon sealant etc. complete as per the architectural drawings and the directions of engineer-in-charge. With float glass panes of 4.0 mm thickness (Cost of aluminium snap beading shall be included in basic item)	SqM		1000.4976		0
				Rupees One Thousand and Forty Nine Paise Only		
62	Providing and fixing pre-fabricated deco grill or equivalent expanded Aluminum grills made of anodized aluminum as per design and drawing having members section of size 7.5 mm X 6.0 mm and opening of size 102 mm X 99 mm fixed to staircase opening with aluminum frame with required screws. Y & H aluminum section as per drawing at the ends and middle joints at all heights etc. complete as per specification & directed by the engineer.	Kg		538.6666		0
				Rupees Five Hundreds Thirty Eight and Sixty Six Paise Only		
63	Providing and fixing M.S. grills of required pattern in frames of windows, ventilators, balconies etc. with M.S.flats, square or round bars ets. all complete including applying two coat of approved quality synthetic enamel paint over a priming coat of approved steel primer. Fixed to steel/ aluminium window by welding/riveted or bolted all complete as per standard design, drawing, specification and direction of engineer in charge. MS grill design & drawing shall be prepared & submitted by the contracting agency for the approval of EIC.	Kg		123.4274		0
				Rupees One Hundreds Twenty Three and Forty Two Paise Only		
64	Structural steel work riveted, bolted or welded in built up sections, trusses and frame work M.S. door & fix ventilators, anchors etc made out M.S. angle, channels, flats, rods, bars, weld mesh, M.S. pipe etc including supplying, cutting, hoisting, fixing in position and applying two coat of approved quality synthetic enamel paint over a priming coat of approved steel primer all complete as per standard design, including the cost of all material and labour complete- as per drawings , specifications & direction of engineer in charge.	Kg		98.9054		0
				Rupees Ninety Eight and Ninety Paise Only		
65	Providing and fixing stainless steel (Grade 304) railing made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel dash fasteners , stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-in-charge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.).	Kg		524.7708		0
				Rupees Five Hundreds Twenty Four and Seventy Seven Paise Only		
66	Providing and fixing of pelmets solid PVC sheet made out of 18 mm thick (one side laminated other side balancing white with 600 kg /Cum density) and 120 mm wide approved brand & shade including nickle plated M.S. Pipe 20 mm dia. (heavy type) curtain rod with nickel plated brackets, including fixing with 25x3 mm M.S. Flat 10 cm long fixed to pelmet on both inner side of pelmet and rawl plugs 75 mm long etc. all complete in all respect as per specification & direction of engineer-in-charge Note- only length of pelmet (No over change shall be paid)	Rm		637.572		0
				Rupees Six Hundreds Thirty Seven and Fifty Seven Paise Only		
67	Providing and fixing curtains velvet cloth or other approved curtains including 25mm dia SS rods with decorative end sockets. Items to be completed in all respect for use along with all fittings. All the material to be approved by "EIC" before fixing etc.	Sqm		1621.7216		0
				Rupees One Thousand Six Hundreds Twenty One and Seventy Two Paise Only		
68	Providing and fixing venetian blinds of make ALASKA / VISTA / NEWTECH of approved shade with all standard fixing arrangements including cost of drilling holes, fixing screws, handling etc. all complete as directed by engineer.	Sqm		1315.1966		0
				Rupees One Thousand Three Hundreds Fifteen and Nineteen Paise Only		
69	Providing & Applying Acrylic Polymer chemical for cracks for interiors as Directed by the Engineer-in-Charge.	Kg		139.7754		0
				Rupees One Hundreds Thirty Nine and Seventy Seven Paise Only		
70	Providing and applying Two coats of SBR Latex mixed with cement in specified proportion (cement mixed with waterproofing material such as PIDICRETE URP of Dr. FIXIT / Hydro proof extra of fosroc / Shalcrete-R of STP Ltd. / Tapcrete P-151 of Cico technologies conforming to relevant IS as approved by engineer in charge in the proportion as recommended by manufacturers forming 300 - 400 microns thick layer in 2 coats of application on treated surface, RCC sunken slab or where ever required including hacking/cleaning and washing the surface etc. all complete as per specification and direction of engineer in charge. Note:- The whole treated area shall be flooded with water for a minimum period of 4 days for water tightness test.	Sqm		506.788		0
				Rupees Five Hundreds Six and Seventy Eight Paise Only		



Name of Work: Biennial Contract for Repair-Maintenance of Building and External Civil Infrastructure work in AnuKiran and AnuChhaya colonies at R.R. Site.
WO / SOQR Number : 64820
Agency Name : M/s KHAN CONTRACTOR

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Amount in ₹
		Rate in Words				
71	Providing and laying integral cement based water proofing treatment including preparation of surface by hacking, cleaning and washing the roof top as required for treatment of roofs, balconies, terraces etc consisting of following operations: a) Applying two coat of waterproof cement slurry (cement mixed with waterproofing material such as PIDICRETE URP of Dr. FIXIT / Hydro proof extra of fosroc / Shalicrote-R of STP Ltd. / Tapcrete P-151 of Cico technologies confirming to relevant IS as approved by engineer in charge in the proportion as recommended by manufacturer) on the prepare surface over the RCC slab including adjoining walls up to 300mm height. b) Laying machine mixed brick bats with mortar in proper slope (1 in 40 to 1 in 60) using broken bricks/brick bats 25 mm to 100mm size with 50% of cement mortar 1: 4 (1 cement : 4 coarse sand) admixed with approved water proofing compound in the proportion as recommended by manufacturer (Cico No.1 of Cico technologies or similar approved product of Pidilite / Fosroc / STP Ltd. as approved by engineer in charge) conforming to relevant IS over 20 mm thick layer of cement mortar of mix 1: 4 (1 cement : 4 coarse sand) admixed with approved waterproofing compound in the proportion as recommended by manufacturer (Cico No.1 of Cico technologies or other similar approved product of Pidilite / Fosroc / STP Ltd. as approved by engineer in charge) conforming to relevant IS to required slope and treating similarly the adjoining walls up to 300mm height including rounding of junction of walls and slabs. c) After two Days of proper curing applying a coat of cement slurry using 2.75 kg/sqm of cement admixed with approved water proofing compound in the proportion as recommended by manufacturer (Cico No.1 of Cico technologies or similar approved product of Pidilite / Fosroc / STP Ltd. as approved by engineer in charge) conforming to relevant IS. d) Finishing the entire surface (horizontal as well as vertical) with 25mm thick jointless cement concrete of mix 1:1.5:3 (1 cement : 1.5 course sand : 3. 10mm down aggregate) admixed with approved water proofing compound in the proportion as recommended by manufacturer (Cico No.1 of Cico technologies or similar approved product of Pidilite / Fosroc / STP Ltd. as approved by engineer in charge) conforming to relevant IS including finally finishing the surface with trowel with neat cement slurry and making pettern of size 100x100mm Sqare 3mm deep. e) The whole terrace so finished shall be flooded with water for minimum period of two week for curing and for final test. All above operations to be done in order and as directed and specified by the Engineer ? In charge. : The average thickness of brick bat coba shall be 120mm and minimum thickness at khurra as 65mm. before laying 25mm thk. CC (1:1.5:3) (Payment shall be made for plan area of roof treated)	SqM	1244.9002			0
		Rupees One Thousand Two Hundreds Forty Four and Ninety Paise Only				
72	Providing and laying in situ seven course water proofing treatment with APP (Atactic Polypropylene) modified Polymeric membrane over roof consisting of first coat of bitumen primer@ 1.20Kg per Sqm, 2nd, 4th & 6th courses of bonding material @ 1.20 Kg/Sqm, which shall consist of blown type bitumen of grade 85/25 conforming to IS: 702, 3rd and 5th layers of roofing membrane APP modified Polymeric membrane 2.0mm thick of 3.0Kg/sqm weight consisting of five layers prefabricated with centre core as 100micron HMHDPE film. 7th, the top most layer shall be finished with brick tiles of class designation 100 grouted with cement mortar 1:3 (1cement : 3 fine sand) mixed with 2% integral water proofing compound by weight of cement over a 12mm layer of cement mortar 1:3 (1cement : 3 fine sand) and finished near which shall be paid for separately	SqM	613.05			0
		Rupees Six Hundreds Thirteen and Five Paise Only				
73	Supplying and fixing in required slope 20 mm thick cement tiles (conforming to relevant I.S) in 20 mm average thick cement sand mortar layer 1:4, admixed with water proofing compound as per manufacturer's specifications (Cico No.1 or equivalent conforming to relevant IS and as approved by engineer) laid over the existing roof surface after its thorough preparation through removal of loose layer, hacking and water washing followed by liberal spreading of neat cement slurry before laying cement mortar layer including grouting the tile joints with cement slurry all complete as per specifications and directions of the engineer. The whole terrace so finished shall be flooded with water for minimum period of two week for curing and for final test.	SqM	1118.2032			0
		Rupees One Thousand One Hundreds Eighteen and Twenty Paise Only				
74	Removing old paint coatings from the concrete / plastered surfaces including ceiling and making them even and free from all kinds of defects such as burrs, undulations, imperfections by all suitable means such as scrapping, grinding, scrubbing, sand papering including repair of dents as per standard procedures etc. to make the surface ready to receive fresh coat of paints all as per direction of engineer including cost of consumables, labour, tools tackles, scaffolding, protective gears, house keeping etc.	SqM	31.8786			0
		Rupees Thirty One and Eighty Seven Paise Only				
75	Applying Birla/JK/Asian white cement based wall putty (two coats) including base coat of alkaline resistance cement primer over cement plaster/ concrete surfaces after cleaning / scrubbing of the surfaces with wire brushes, soft brushes, sand papers, steel sheet scrappers and mechanical grinder etc. for removing all kind of burrs, imperfections, undulations and other such defects existing in the surface to achieve plain & even surface. including the cost of materials, labour etc. all complete as per direction of Engineer-in-Charge.	SqM	124.2448			0
		Rupees One Hundreds Twenty Four and Twenty Four Paise Only				
76	Supply and application of Distemper of make Asian Tractor aqalock distemper (code 0013) of asian brand / Nerolac Beauty acrylic distemper / Bison acrylic distemper of Berger as approved to give an even shade: two coats over and including priming coat of approved primer of make Asian Trucare wall primer (0360) / Nerolac premium primer water thinnable / BP cement primer water thinnable of Berger as approved over well and evenly prepared concrete / plastered new / old surfaces including the cost of materials, consumables, labour, scaffolding, protective gears, house keeping etc. complete as per the direction of engineer. The item rate includes spreading of suitable clean protection covering on all exposed surfaces to protect them from staining. All surfaces surrounding to painted area such as door & window frames, glass pans, electrical fittings, switch board, floors, skirting, platform etc. shall be cleaned to sparkling clean condition using suitable thinners, detergents, chemical cleaners etc. under the scope of the item. including the cost of materials, labour etc. all complete as per specification & direction of Engineer-in-Charge. Note:- Painting to be takenup after attending all seepage / leakage problem. No peel off of paint & seepage spots shall be allowed.	SqM	163.48			0
		Rupees One Hundreds Sixty Three and Forty Eight Paise Only				
77	Supply and applying premium emulsion paint of make Asian paint premium emulsion (product code 011) / Nerolac Beauty gold / Rangoli total care of Berger as approved to give an even shade: - Two coats on new work including priming coat with approved cement primer of make Asian Trucare wall primer (0360) / Nerolac premium primer water thinnable / BP cement primer water thinnable of Berger as approved after cleaning / scrubbing of the surfaces with wire brushes, soft brushes, sand papers, steel sheet scrappers and mechanical grinder etc. for removing all kind of burrs, imperfections, undulations and other such defects existing in the surface to achieve plain & even surface. The item rate include spreading of suitable clean protection covering on all exposed surfaces to protect them from staining. All surfaces surrounding to painted area such as door & window frames, glass pans, electrical fittings, switch board, floors, skirting, platform etc. shall be cleaned to sparkling clean condition using suitable thinners, detergents, chemical cleaners etc. under the scope of the item. including the cost of materials, labour etc. all complete as per specification & direction of Engineer-in-Charge. Note:- Painting to be takenup after attending all seepage / leakage problem. No peel off of paint & seepage spots shall be allowed.	SqM	170.0192			0
		Rupees One Hundreds Seventy and One Paise Only				



Name of Work: Biennial Contract for Repair-Maintenance of Building and External Civil Infrastructure work in AnuKiran and AnuChhaya colonies at R.R. Site.
WO / SOQR Number : 64820
Agency Name : M/s KHAN CONTRACTOR

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Amount in ₹
		Rate in Words				
78	Supplying and applying wheather proof exterior emulsion paint of make Asian dust proof (code 0012) / Nerolac excel / Weather coat smooth of Berger as approved of required shade on New work Two coats including base coat of exterior wall primer of make Asian exterior Trucare wall primer (0065) / Nerolac exterior primer / Weather coat exterior primer of Berger as approved after cleaning / scrubbing of the surfaces with wire brushes, soft brushes, sand papers, steel sheet scrappers and mechanical grinder etc. for removing all kind of burrs, imperfections, undulations and other such defects existing in the surface including filling surface imperfections such as holes, dents, cracks by using mixture of white cement & fine sand (in the ratio of 1:3) to achieve plain & even surface. The item rate include spreading of suitable clean protection covering on all exposed surfaces to protect them from staining. All surfaces surrounding to painted area such as window / ventilator frames, glass pans etc. shall be cleaned to sparkling clean condition using suitable thinners, detergents, chemical cleaners etc. under the scope of the item. including the cost of materials, labour etc. all complete as per specification & direction of Engineer-in-Charge. Note:- Painting to be takenup after attending all seepage / leakage problem. No peel off of paint & seepage spots shall be allowed.	SqM		165.1148		0
				Rupees One Hundreds Sixty Five and Eleven Paise Only		
79	Supplying and application of 2 coats of Synthetic Enamel Paint Asian Apcolite Premium Enamel (0064) / Nerolac Synthetic Enamel / Laxol stain enamel of Berger on New / Old Concrete / Plastered / Steel / Wooden surfaces after application of primer coat (Asian Paint Metal Primer or similar quality in Berger / Nerolac) on the surfaces well prepared through scrapping, scrubbing, grinding and cleaning using wire brushes, soft brushes & sand papers etc. including cost of materials, labour, consumables cleaning of area after painting etc. complete as per direction of Engineer-in-Charge. The item rate includes the cost of spreading suitable clean protection covering on all exposed surfaces to protect them from staining, cleaning of old stained / freshly stained surfaces surrounding to painted area such as door - window frames & glass panes, electrical fittings, switch boards, floors, skirting, platform etc. to sparkling clean condition with the use of suitable thinners, detergents, chemical cleaners etc.	Sqm		169.2018		0
				Rupees One Hundreds Sixty Nine and Twenty Paise Only		
80	Painting background in 2 coats and Writing letters / Figures / Numerals on any new/old surface such as plastered, concrete, metal etc using (Apcolite Synthetic Enamel Paint of Asian Paint Product Code No 0001) of spcified shade including cost of paint material and metallic stencils for Alphabets / Numerals all complete as per the directions & Specifications of Engineer-in-charge.	SqM		796.1476		0
				Rupees Seven Hundreds Ninety Six and Fourteen Paise Only		
81	Providing and fixing best quality stainless steel kitchen sink of SS grade 304 glossy finish (Jayna / Nirali / Carysil / Franke Brand) as approved without drain board of overall size 610 x 457 x 200 mm (24"x18"x8") including all accessories such as choke stop stainer, outlet pipe upto floor trap etc. as required all complete as per drawing, specifications and direction of engineer in charge	Each		4360.0116		0
				Rupees Four Thousand Three Hundreds Sixty and One Paise Only		
82	Providing and fixing in position white glazed vitreous china ware wash basin 'H&R JOHNSON' / 'PARRY' / 'CERA' as approved of following accessories jointed watertight as given below : (a). One no. wash basin of make 'H&R JOHNSON' (P1015PW size 500 x 400 mm) / 'PARRY' (Indus C0471 size 500x400 mm) / 'CERA' (Counsel S2040101 size 510x400mm) as approved. (b). One pair of wall bracket of 35mm x 35mm x 5mm M.S. angle painted with two coats of synthetic enamel paint over a coat of primer of approved quality and make. (c). One no. 32mm dia C.P. brass waste coupling with C.P. grating of Cat. No. ALD709 of Jaquar or similar approved quality of KOHLER / GROHE as approved. (d). One no. 32mm dia C.P. brass bottle trap with wall flange and connected C.P. pipe of cat. No ALD 769 of Jaquar or similar approved quality of KOHLER/GROHE as approved. (e). Two nos. 15mm dia C.P. brass angle valve with C.P. flange of superior quality (Jaquar CLARION cat. No. 23059 or similar approved quality of KOHLER / GROHE as approved). (f). One no. central hole C.P. brass basin mixer without popup waste system with 450mm long braided hoses of superior quality (Jaquar clarion cat. no. CQT 23167B or similar approved quality of KOHLER/GROHE as approved). (g). 32mm dia B class G.I. waste pipe (concealed) of required length (from bottle trap to nahani trap) including painting with anti corrosive bituminous paint.	Nos.		7792.2742		0
				Rupees Seven Thousand Seven Hundreds Ninety Two and Twenty Seven Paise Only		
83	Providing and fixing in position white glazed vitreous under counter oval shape china ware wash basin of make H&R JOHNSON / 'PARRY' / 'CERA' as approved comprising of following accessories jointed watertight as given below: (a). One no. oval shape white wash basin H&R JOHNSON CRESS (UC WB P0813PW size 550x450mm) / 'PARRY' (Cascade NXT C0407 size550x445mm) / 'CERA' (Oval under counter S2030104 size560x470mm) as approved.	Each		2874.7958		0
				Rupees Two Thousand Eight Hundreds Seventy Four and Seventy Nine Paise Only		
84	Providing & Fixing of white glazed vitreous china ware WASH BASIN 510mm X 400mm of make "H&R Johnson " or "PARRY", CERA, as approved by EIC With one,two tap hole and one over flow hole antisplash as Directed by the Engineer-in-Charge.	Each		1223.6478		0
				Rupees One Thousand Two Hundreds Twenty Three and Sixty Four Paise Only		
85	Providing & Fixing of white glazed vitreous china ware WASH BASIN 460mm X 310mm of make "HINDWARE" or "PARRY", CERA, H&R JOHNSON as approved by EIC With one,two tap hole and one over flow hole antisplash as Directed by the Engineer-in-Charge.	Each		874.618		0
				Rupees Eight Hundreds Seventy Four and Sixty One Paise Only		
86	Providing and fixing floor mounted, white vitreous china single piece, double traps syphonic water closet of approved brand/make, shape, size and pattern including integrated white vitreous china cistern of capacity 10 litres with dual flushing system, including all fittings and fixtures with seat cover, cistern fittings, nuts, bolts and gasket etc including making connection with the existing P/S trap, complete in all respect as per directions of Engineer-in-Charge.	Each		14513.7544		0
				Rupees Fourteen Thousand Five Hundreds Thirteen and Seventy Five Paise Only		
87	Providing and fixing European type water closet white glazed vitreous china ware concealed S trap of 'H&R JOHNSON' (Ruby concealed trap EWC P0448PW / 'PARRYWARE' (NIAGARA C0252(S) / 'CERA' (CIGNIA Concealed S1051108 S trap) as approved with Germfree EWC solid seat cover with C.P. brass hinges and rubber buffers of approved brand, with low level placed PVC flushing cistern (Dual Flush Tank white) connected with 32 mm dia PVC flush pipe with fittings and brackets, 15mm dia PVC inlet connection of required length and approved brand, 15mm dia C.P. brass angle valve with C.P. flange of superior quality all complete as per specification and direction of engineer in charge comprising following accessories: (a). White vitreous china wash down European type W.C. pan with white vitreous china 'S' trap of approved brand. (b). Germfree EWC solid seat cover (white) of H&R Johnson (P0424PW) / Parry (E8094) / Cera (Carina plus B1510106) with C.P. brass hinges and rubber buffers of approved brand (c). Low level placed PVC flushing cistern Dual Flush Tank (white) of H & R Johnson (P2829PW) / Parry (Slim-line Hexa E8319) / Cera (Corona B1020102) as approved with all accessories complete.. (d). 15mm dia heavy duty PVC inlet connection of required length and approved brand with brass unions complete. (e). 15mm dia C.P. brass angle valve with C.P. flange of superior quality (Jaquar clarion cat. No. CQT 23059 or similar approved quality of KOHLER/GROHE as approved). (f). Jet spray provision of ESSCO make ALE-ESS 547 with 1Meter PVC tube (stainless steel) with 01 nos 15mm dia CP brass angle valve with Cp flange of Jaquar clarion (Code CQT 23059) or similer approved quality of KOHLER/GROHE as approved.	Nos.		7677.8382		0
				Rupees Seven Thousand Six Hundreds Seventy Seven and Eighty Three Paise Only		
88	Providing & Fixing of approved quality European type white glazed vitreous china ware water closet concealed S trap of 'H&R JOHNSON' (Ruby concealed trap EWC P0448PW / 'PARRYWARE' (NIAGARA C0252(S) / 'CERA' (CIGNIA Concealed S1051108 S trap).	Each		2309.155		0
				Rupees Two Thousand Three Hundreds Nine and Fifteen Paise Only		



Name of Work: Biennial Contract for Repair-Maintenance of Building and External Civil Infrastructure work in AnuKiran and AnuChhaya colonies at R.R. Site.
WO / SOQR Number : 64820
Agency Name : M/s KHAN CONTRACTOR

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Amount in ₹
		Rate in Words				
89	Providing and fixing Orissa pattern Water Closet (OP 23 (Open rim) of H & R Johnson / Orissa C0117 of Parryware/ Orissa COVYS 3010104 of CERA as approved with low level placed PVC flushing cistern (Dual Flush Tank (white) of H & R Jhonson / CERA/ Parry) connected with 32 mm dia PVC flush pipe with all fittings and brackets with C.P. brass angle cock with CP flange (Clarion cat No. CQT 23059 make of JAQUAR or similar approved quality in KOHLER / GROHE and 15 mm dia high quality PVC inlet connection of required length with all accessories, fittings & fixtures of best quality and brand. Item includes essentially following. (a). Orissa pattern white glazed vitreous china W.C. pan of size 580mm x 440mm of approved brand and 100mm dia sand cast iron 'P' trap. (b). Low level placed PVC flushing cistern Dual Flush Tank (white) of H & R Johnson (P2829PW) / Parry (Slim-line E8110 Deluxe) / Cera (Corona B1020102) as approved with all accessories complete. (c). 15mm dia PVC inlet connection of required length of approved brand with heavy duty C.P. brass unions and rubber washer etc. (d). 15mm dia C.P. brass angle valve with C.P. flange of superior quality (Jaquar Clarion cat. No. CQT 23059 or similar approved quality of KOHLER / GROHE as approved).	Each		6665.897		0
		Rupees Six Thousand Six Hundreds Sixty Five and Eighty Nine Paise Only				
90	Providing & Fixing white vitreous china Orissa pattern water closet (OP 23) (open ring) of H&R Johnson / Orissa C0117 of Paryware / Orissa COLVIN S 3010108SN of Cera as approved quality .	Each		2471.0002		0
		Rupees Two Thousand Four Hundreds Seventy One and Four Paise Only				
91	Providing & Fixing of approved quality Anglo Indian W.C. PAN (PERRYWARE, HINDWARE OR CERA/JOHNSON make only).	Each		4189.175		0
		Rupees Four Thousand One Hundreds Eighty Nine and Seventeen Paise Only				
92	Providing & Fixing Low level placed PVC flushing cistern Dual Flush Tank (white) of H & R Johnson (P2829PW) / Parry (Slim-line Hexa E8319) / Cera (Compass dual flush cistern B 1020106SN) as approved with all accessories complete. as Directed by the Engineer-in-Charge.	Each		1221.1956		0
		Rupees One Thousand Two Hundreds Twenty One and Nineteen Paise Only				
93	Providing & Fixing of approved quality URINAL (JHONSON PREMIUM COLLECTION/ PARRY WERE / HINDWARE) Dimensions:610 x 390 x390 mm TOPAZ HALF STALL URINAL IN WHITE COLOUR as Directed by the Engineer-in-Charge.	Each		3751.0486		0
		Rupees Three Thousand Seven Hundreds Fifty One and Four Paise Only				
94	Providing & Fixing of approved quality URINAL (JHONSON PREMIUM COLLECTION/ PARRY WERE / HINDWARE) Dimensions: 450 X 325 x 280 mm RUBY FLAT BLACK URINAL IN WHITE COLOUR as Directed by the Engineer-in-Charge.	Each		1613.5476		0
		Rupees One Thousand Six Hundreds Thirteen and Fifty Four Paise Only				
95	Providing & Fixing of Chromium plated (C.P.) urinal brass spreader fittings of approved make as Directed by the Engineer-in-Charge.	Each		174.9236		0
		Rupees One Hundreds Seventy Four and Ninety Two Paise Only				
96	Providing and laying or fixing ventilation pipes and fittings 50 mm dia in position, under floor or against walls, ISI market sand cast iron, socket and spigot soil, waste including cost of all fittings like bends, offset tees, tapers, collars, connection plugs, shoes, cowls and clamps conforming to IS : 1729 and jointing with tarred spun yarn and molten pig lead, caulking the joints, testing and painting with two coats of approved paint of required shade including cutting chase or holes in walls and floors and making good where required etc. complete.	Metre		768.356		0
		Rupees Seven Hundreds Sixty Eight and Thirty Five Paise Only				
97	Providing and laying or fixing ventilation pipes and fittings 75 mm dia in position, under floor or against walls, ISI market sand cast iron, socket and spigot soil, waste including cost of all fittings like bends, offset tees, tapers, collars, connection plugs, shoes, cowls and clamps conforming to IS : 1729 and jointing with tarred spun yarn and molten pig lead, caulking the joints, testing and painting with two coats of approved paint of required shade including cutting chase or holes in walls and floors and making good where required etc. complete.	Metre		935.1056		0
		Rupees Nine Hundreds Thirty Five and Ten Paise Only				
98	Providing and laying or fixing ventilation pipes and fittings 100 mm dia in position, under floor or against walls, ISI market sand cast iron, socket and spigot soil, waste including cost of all fittings like bends, offset tees, tapers, collars, connection plugs, shoes, cowls and clamps conforming to IS : 1729 and jointing with tarred spun yarn and molten pig lead, caulking the joints, testing and painting with two coats of approved paint of required shade including cutting chase or holes in walls and floors and making good where required etc. complete.	Metre		1005.402		0
		Rupees One Thousand Five and Forty Paise Only				
99	Providing and laying 150mm dia. R.C.C. hume pipes non-pressure NP2 class (light duty) jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete:	Metre		432.4046		0
		Rupees Four Hundreds Thirty Two and Forty Paise Only				
100	Providing and laying 200mm dia R.C.C. hume pipes non-pressure NP2 class (light duty) jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete as per drawings, specifications and as directed of the EIC.	Metre		573.8148		0
		Rupees Five Hundreds Seventy Three and Eighty One Paise Only				
101	Providing and laying 300mm dia. R.C.C. hume pipes non-pressure NP2 class (light duty) jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete:	Metre		791.2432		0
		Rupees Seven Hundreds Ninety One and Twenty Four Paise Only				
102	Providing and laying 450mm dia. R.C.C. hume pipes non-pressure NP2 class (light duty) jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete:	Metre		1262.0656		0
		Rupees One Thousand Two Hundreds Sixty Two and Six Paise Only				
103	Providing & Fixing of 100 MM DIA. S.W.P Pipes approved quality as Directed by the Engineer-in-Charge:	Each		166.7496		0
		Rupees One Hundreds Sixty Six and Seventy Four Paise Only				
104	Providing & Fixing of 150 MM DIA. S.W.P Pipes approved quality as Directed by the Engineer-in-Charge:	Each		218.2458		0
		Rupees Two Hundreds Eighteen and Twenty Four Paise Only				
105	Providing and fixing PVC Rain water pipes on wall face / embedded in ground un plasticized Rigid of Jain Irrigation / Finolex / Supreme as approved conforming to IS:13592 type A (4 Kg/Cm2) including shoes, bends, clamps etc. all complete jointing with seal ring leaving 10 mm for thermal expansion (I) single socketed pipes:110 mm dia.	Metre		318.786		0
		Rupees Three Hundreds Eighteen and Seventy Eight Paise Only				



Name of Work: Biennial Contract for Repair-Maintenance of Building and External Civil Infrastructure work in AnuKiran and AnuChhaya colonies at R.R. Site.
WO / SOQR Number : 64820
Agency Name : M/s KHAN CONTRACTOR

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Amount in ₹
		Rate in Words				
106	Providing & Fixing of UPVC Pipes (IS : 15328) for Drainage / Sewerage System of Supreme/ Finlox / Jain Irrigation as approved make including jointing pipe with solvent cement rubber sing and Lubricant. (i) 160 mm SN - 4	Metre		470.005		0
				Rupees Four Hundreds Seventy and Paise Only		
107	Providing & Fixing of UPVC Pipes (IS : 15328) for Drainage / Sewerage System of Supreme/ Finlox / Jain Irrigation as approved make including jointing pipe with solvent cement rubber sing and Lubricant. (i) 110 mm SN - 8	Metre		306.525		0
				Rupees Three Hundreds Six and Fifty Two Paise Only		
108	Providing and fixing class 'B' G.I. pipe of approved brand confirming to IS 1239 of following nominal bore with all fittings and specials of heavy duty as required including cutting the walls, floors trenching & refilling as required, making them good, clamping on wall of approved quality claimps as per specifications, testing the line etc. complete as per drawings, specifications and direction of engineer. 15mm dia nominal bore. Exposed on wall	Metre		304.8902		0
				Rupees Three Hundreds Four and Eighty Nine Paise Only		
109	Providing and fixing class 'B' G.I. pipe of approved brand confirming to IS 1239 of following nominal bore with all fittings and specials of heavy duty as required including cutting the walls, floors trenching & refilling as required, making them good, clamping on wall of approved quality claimps as per specifications, testing the line etc. complete as per drawings, specifications and direction of engineer. 20mm dia nominal bore exposed on wall.	Metre		343.308		0
				Rupees Three Hundreds Forty Three and Thirty Paise Only		
110	Providing and fixing class 'B' G.I. pipe of approved brand confirming to IS 1239 of following nominal bore with all fittings and specials of heavy duty as required including cutting the walls, floors trenching & refilling as required, making them good, clamping on wall of approved quality claimps as per specifications, testing the line etc. complete as per drawings, specifications and direction of engineer. 25mm dia. nominal bore exposed on wall	Metre		449.57		0
				Rupees Four Hundreds Forty Nine and Fifty Seven Paise Only		
111	Providing and fixing class 'B' G.I. pipe of approved brand confirming to IS 1239 of following nominal bore with all fittings and specials of heavy duty as required including cutting the walls, floors trenching & refilling as required, making them good, clamping on wall of approved quality claimps as per specifications, testing the line etc. complete as per drawings, specifications and direction of engineer. 32mm dia. nominal bore exposed on wall	Metre		535.397		0
				Rupees Five Hundreds Thirty Five and Thirty Nine Paise Only		
112	Providing and fixing class 'B' G.I. pipe of approved brand confirming to IS 1239 of following nominal bore with all fittings and specials of heavy duty as required including cutting the walls, floors trenching & refilling as required, making them good, clamping on wall of approved quality claimps as per specifications, testing the line etc. complete as per drawings, specifications and direction of engineer. 40mm dia. nominal bore exposed on wall	Metre		720.1294		0
				Rupees Seven Hundreds Twenty and Twelve Paise Only		
113	Providing and fixing class 'B' G.I. pipe of approved brand confirming to IS 1239 of following nominal bore with all fittings and specials of heavy duty as required including cutting the walls, floors trenching & refilling as required, making them good, clamping on wall of approved quality claimps as per specifications, testing the line etc. complete as per drawings, specifications and direction of engineer. 50mm dia. nominal bore exposed on wall	Metre		798.5998		0
				Rupees Seven Hundreds Ninety Eight and Fifty Nine Paise Only		
114	Providing & Fixing WATER TANK 500 Litre Capacity of SINTEX PURE ROTO MOULD WHITE, Three Layer silver coated insulated antibacterial as Directed by the Engineer-in-Charge.	Each		4956.7136		0
				Rupees Four Thousand Nine Hundreds Fifty Six and Seventy One Paise Only		
115	Providing & Fixing WATER TANK 1000 Litre Capacity of SINTEX PURE ROTO MOULD WHITE, Three Layer silver coated insulated antibacterial as Directed by the Engineer-in-Charge.	Each		9391.1086		0
				Rupees Nine Thousand Three Hundreds Ninety One and Ten Paise Only		
116	Providing & Fixing WATER TANK 2000 Litre Capacity of SINTEX PURE ROTO MOULD WHITE, Three Layer silver coated insulated antibacterial as Directed by the Engineer-in-Charge.	Each		18260.716		0
				Rupees Eighteen Thousand Two Hundreds Sixty and Seventy One Paise Only		
117	Providing and fixing 150mm X 150mm size square mouth gully trap in position best quality salt glazed stone ware with C.I. grating and 100mm P type outlet with 40mm thick precast cement conc. Cover fixed in M.S. angle frame (made out of required size angle) at top and constructing brick masonry chamber 300mm X 300mm internal size in 115mm thick brick masonry in cement mortar 1:4 (1 cement : 4 fine sand) with necessary excavation in all types of soils, bed of 100mm thick cement concrete 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate of 40mm nominal size) for foundation and around the trap and plastering with cement mortar 1:4 (1 cement : 4 fine sand) 15mm thick on internal and external surfaces, on top and upto 150mm below ground level, finished smooth, curing and fixing M.S. angle frame and precast conc. cover in 40 mm thick cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate of 20mm nominal size) and painting the grating & frame with two coats of approved anticorrosive paint etc. complete as per drawings and specifications. Note :- Reinforcement and MS angle frame shall be paid in relevant item.	Each		1561.234		0
				Rupees One Thousand Five Hundreds Sixty One and Twenty Three Paise Only		
118	Providing & fixing 100mm dia PVC waste coupling for kitchen sink with all fittings (900mm long suitable dia out let PVC pipe etc.) of approved quality to fit as per spot work requirement or as per directed by EIC.	Each		299.9858		0
				Rupees Two Hundreds Ninety Nine and Ninety Eight Paise Only		
119	Providing & fixing 100mm dia SS waste coupling for kitchen sink with all fittings (900mm long suitable dia out let PVC pipe etc.) of approved quality to fit as per spot work requirement or as per directed by EIC.	Each		356.3864		0
				Rupees Three Hundreds Fifty Six and Thirty Eight Paise Only		
120	Providing & fixing F-type SS bracket pair of size 6 inch long for glass self to fit for holding the glass as per spot work requirement & as directed by EIC.	Each		344.9428		0
				Rupees Three Hundreds Forty Four and Ninety Four Paise Only		
121	Providing & Fixing of Good quality C.P. brass bib cock 15 mm dia of weighing not less than 400 gm. as per direction of EIC.	Each		356.3864		0
				Rupees Three Hundreds Fifty Six and Thirty Eight Paise Only		
122	Providing and fixing C.P. brass bib cock with C.P. flange 15 mm nominal bore of superior quality (Jaquar Clarion cat no. 23047 or similar approved quality of GROHE/KOHLER as approved) :	Each		754.4602		0
				Rupees Seven Hundreds Fifty Four and Forty Six Paise Only		
123	Providing & Fixing of brass BIB cock 15 mm dia good quality of weighing not less than 400 gm.	Each		257.481		0
				Rupees Two Hundreds Fifty Seven and Forty Eight Paise Only		



Name of Work: Biennial Contract for Repair-Maintenance of Building and External Civil Infrastructure work in AnuKiran and AnuChhaya colonies at R.R. Site.
WO / SOQR Number : 64820
Agency Name : M/s KHAN CONTRACTOR

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Amount in ₹
		Rate in Words				
124	Providing & Fixing of PVC bib cock 15mm dia good quality (PRAYAG BRAND) or equivalent.	Each		272.1942		0
				Rupees Two Hundreds Seventy Two and Nineteen Paise Only		
125	Providing & Fixing of C.P. brass stop cock 15 mm dia good quality of weighting not less than 400 gm. As per direction of EIC.	Each		514.962		0
				Rupees Five Hundreds Fourteen and Ninety Six Paise Only		
126	Providing & Fixing of brass stop cock 15 mm dia approved quality of weighing not less than 400 gm.	Each		257.481		0
				Rupees Two Hundreds Fifty Seven and Forty Eight Paise Only		
127	Providing & Fixing of P.V.C. Stop Cock approved quality (PRAYAG MAKE) as Directed by the Engineer-in-Charge.	Each		272.1942		0
				Rupees Two Hundreds Seventy Two and Nineteen Paise Only		
128	Providing and fixing C.P. brass Angular stop cock with C.P. flange 15 mm nominal bore of superior quality (Jaquar Clarion cat no. 23059 or similar approved quality of GROHE/KOHLER as approved) :	Each		668.6332		0
				Rupees Six Hundreds Sixty Eight and Sixty Three Paise Only		
129	Providing & Fixing of Jet Spray for European W.C. as Directed by the Engineer-in-Charge.	Each		219.8806		0
				Rupees Two Hundreds Nineteen and Eighty Eight Paise Only		
130	Providing & Fixing of Heavy Duty C.P. Luxury Health Forcet with all Fittings as Directed by the Engineer-in-Charge.	Each		567.2756		0
				Rupees Five Hundreds Sixty Seven and Twenty Seven Paise Only		
131	Providing & Fixing of approved C.P.brass pillar cock 15 mm dia. of weighting not less than 600 gm. (IS-1795 - 1982).	Each		470.8224		0
				Rupees Four Hundreds Seventy and Eighty Two Paise Only		
132	Providing and fixing C.P. brass pillar cock of superior quality 15 mm nominal bore (Jaquar continantal cat no. CON-021 or similar approved quality of GROHE/KOHLER as approved) :	Each		1224.4652		0
				Rupees One Thousand Two Hundreds Twenty Four and Forty Six Paise Only		
133	Providing and fixing C.P. brass wall mixer with 3 in 1 system with provision for both hand shower and over head shower complete with 115mm long bend pipe on upper side, connecting legs and flanges (without hand & over head shower) CQT - 23281UPR of Jaquar Clarion series or similar approved quality of GROHE/KOHLER as approved.	Each		3632.5256		0
				Rupees Three Thousand Six Hundreds Thirty Two and Fifty Two Paise Only		
134	Providing & Fixing of C.P. Wash Basin Mixer of approved brand as Directed by the Engineer-in-Charge.	Each		1870.2112		0
				Rupees One Thousand Eight Hundreds Seventy and Twenty One Paise Only		
135	Providing & Fixing of C.P. brass shower rose with 15 or 20 mm inlet : 100 mm dia as directed by the Engineer-in-Charge.	Each		129.1492		0
				Rupees One Hundreds Twenty Nine and Fourteen Paise Only		
136	Providing and fixing C.P. brass shower rose with Shower arm 160mm long and wall flange of superior quality (Jaquar cat no. OHS 1989 & SHA 477 or similar approved quality of GROHE/KOHLER as approved).	Each		1453.3372		0
				Rupees One Thousand Four Hundreds Fifty Three and Thirty Three Paise Only		
137	Providing & fixing sink cock (wall mounting) with C.P. flange and swinging casted spout superior quality (Jaquar Clarion cat no. 23347 or similar approved quality of GROHE/KOHLER as approved).	Each		1147.6296		0
				Rupees One Thousand One Hundreds Forty Seven and Sixty Two Paise Only		
138	Providing & Fixing of approved quality C.P. Bottel Trap Heavy Duty (Weight not less than 500 Grams) as Directed by the Engineer-in-Charge.	Each		750.3732		0
				Rupees Seven Hundreds Fifty and Thirty Seven Paise Only		
139	Providing & Fixing of approved quality C.P. Waste Coupling 32mm Dia. as Directed by the Engineer-in-Charge.	Each		219.8806		0
				Rupees Two Hundreds Nineteen and Eighty Eight Paise Only		
140	Providing & Fixing of approved quality C.P. Waste Coupling 40mm Dia. as Directed by the Engineer-in-Charge.	Each		249.307		0
				Rupees Two Hundreds Forty Nine and Thirty Paise Only		
141	Providing & Fixing of approved quality C.P. Waste Coupling 50mm Dia. as Directed by the Engineer-in-Charge.	Each		277.916		0
				Rupees Two Hundreds Seventy Seven and Ninety One Paise Only		
142	Providing & Fixing of approved quality Brass Spindle Small size as Directed by the Engineer-in-Charge.	Each		143.045		0
				Rupees One Hundreds Forty Three and Four Paise Only		
143	Providing & Fixing of approved quality Brass Spindle Medium size as Directed by the Engineer-in-Charge.	Each		152.8538		0
				Rupees One Hundreds Fifty Two and Eighty Five Paise Only		



Name of Work: Biennial Contract for Repair-Maintenance of Building and External Civil Infrastructure work in AnuKiran and AnuChhaya colonies at R.R. Site.
WO / SOQR Number : 64820
Agency Name : M/s KHAN CONTRACTOR

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Amount in ₹
		Rate in Words				
144	Providing & Fixing of approved quality Brass Spindle Big HEAVY size as Directed by the Engineer-in-Charge.	Each		161.8452		0
				Rupees One Hundreds Sixty One and Eighty Four Paise Only		
145	Providing & Fixing of approved quality Brass Spindle for Concealed Stop Cock as Directed by the Engineer-in-Charge.	Each		194.5412		0
				Rupees One Hundreds Ninety Four and Fifty Four Paise Only		
146	Providing & Fixing of brass spindle - regular - SOLO / CLARION - COLD - UNIT-2 (Cat. No. ZCQ-CHR-023B) of Jaquar make fit for all type & size C.P. Jaquar fittings as per spot work requirement & as directed by EIC.	Each		430.7698		0
				Rupees Four Hundreds Thirty and Seventy Six Paise Only		
147	Providing & Fixing of approved quality Brass JUMPER as Directed by the Engineer-in-Charge.	Each		30.2438		0
				Rupees Thirty and Twenty Four Paise Only		
148	Providing & Fixing of approved quality P.V.C. Washer for Bibcock as Directed by the Engineer-in-Charge.	Kg		98.088		0
				Rupees Ninety Eight and Eight Paise Only		
149	Providing & Fixing of approved quality Gun Metal MANIK / L & K Make Wheel Valve Screw down Type, Heavy Duty Conforming to IS - 778: 15 mm dia. as Directed by the Engineer-in-Charge.	Each		284.4552		0
				Rupees Two Hundreds Eighty Four and Forty Five Paise Only		
150	Providing & Fixing of approved quality Gun Metal MANIK / L & K Make Wheel Valve Screw down Type, Heavy Duty Conforming to IS - 778: 20 mm dia. as Directed by the Engineer-in-Charge.	Each		393.9868		0
				Rupees Three Hundreds Ninety Three and Ninety Eight Paise Only		
151	Providing and fixing in position heavy duty gun metal wheel valve screw down type confirming to IS: 778 latest revision of approved make including the cost of all jointing materials, fittings and testing etc. complete as per specifications of the following nominal bore. - 25mm dia	Each		422.5958		0
				Rupees Four Hundreds Twenty Two and Fifty Nine Paise Only		
152	Providing and fixing in position heavy duty gun metal wheel valve screw down type confirming to IS: 778 latest revision of approved make including the cost of all jointing materials, fittings and testing etc. complete as per specifications of the following nominal bore. - 32mm dia	Each		605.6934		0
				Rupees Six Hundreds Five and Sixty Nine Paise Only		
153	Providing and fixing in position heavy duty gun metal wheel valve screw down type confirming to IS: 778 latest revision of approved make including the cost of all jointing materials, fittings and testing etc. complete as per specifications of the following nominal bore. - 40mm dia	Each		820.6696		0
				Rupees Eight Hundreds Twenty and Sixty Six Paise Only		
154	Providing & Fixing of approved quality Gun Metal FERRULE Heavy Duty as Directed by the Engineer-in-Charge. : 20 mm dia.	Each		280.3682		0
				Rupees Two Hundreds Eighty and Thirty Six Paise Only		
155	Supplying of approved quality Gun Metal FERRULE Heavy Duty as Directed by the Engineer-in-Charge: 30 mm dia.	Each		411.1522		0
				Rupees Four Hundreds Eleven and Fifteen Paise Only		
156	Providing & Fixing of PVC connection pipe (PRAYAG MAKE) with PVC unions : 30 cm length : 15 mm nominal bore as Directed by the Engineer-in-Charge.	Each		164.2974		0
				Rupees One Hundreds Sixty Four and Twenty Nine Paise Only		
157	Providing & Fixing PVC connection pipe (PRAYAG MAKE) with PVC unions : 45 cm length : 15 mm nominal bore as Directed by the Engineer-in-Charge.	Each		177.3758		0
				Rupees One Hundreds Seventy Seven and Thirty Seven Paise Only		
158	Providing & Fixing of uplasticised PVC connection pipe (PRAYAG MAKE) with PVC unions : 60 cm length : 15 mm nominal bore as Directed by the Engineer-in-Charge.	Each		191.2716		0
				Rupees One Hundreds Ninety One and Twenty Seven Paise Only		
159	Providing & Fixing of CP connection pipe : 45 cm length : 15 mm nominal bore as Directed by the Engineer-in-Charge.	Each		183.915		0
				Rupees One Hundreds Eighty Three and Ninety One Paise Only		
160	Providing & Fixing of approved quality Brass Float Valve 15 mm Dia as Directed by the Engineer-in-Charge.	Each		193.7238		0
				Rupees One Hundreds Ninety Three and Seventy Two Paise Only		
161	Providing & Fixing of approved quality Brass Float Valve 25 mm Dia as Directed by the Engineer-in-Charge.	Each		458.5614		0
				Rupees Four Hundreds Fifty Eight and Fifty Six Paise Only		
162	Providing & Fixing of approved quality Brass Float Valve 32 mm Dia. as Directed by the Engineer-in-Charge.	Each		555.0146		0
				Rupees Five Hundreds Fifty Five and One Paise Only		
163	Providing & Fixing of approved quality Brass Chiria for Float Valve 32mm as Directed by the Engineer-in-Charge.	Each		44.957		0
				Rupees Forty Four and Ninety Five Paise Only		
164	Providing & Fixing of approved quality Float Valve Aluminium RODS as per requirement Heavy Duty as Directed by the Engineer-in-Charge	Each		40.0526		0
				Rupees Forty and Five Paise Only		
165	Providing & Fixing of approved quality Float Valve P.V.C. BALLS Heavy Duty as Directed by the Engineer-in-Charge: 100 MM DIA	Each		44.957		0
				Rupees Forty Four and Ninety Five Paise Only		



Name of Work: Biennial Contract for Repair-Maintenance of Building and External Civil Infrastructure work in AnuKiran and AnuChhaya colonies at R.R. Site.
WO / SOQR Number : 64820
Agency Name : M/s KHAN CONTRACTOR

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Amount in ₹
		Rate in Words				
166	Providing & Fixing of approved quality Float Valve P.V.C. BALLS Heavy Duty as Directed by the Engineer-in-Charge: 150 MM DIA	Each		78.4704		0
				Rupees Seventy Eight and Forty Seven Paise Only		
167	Providing & Fixing of approved quality Float Valve P.V.C. BALLS Heavy Duty as Directed by the Engineer-in-Charge: 250 MM DIA	Each		406.2478		0
				Rupees Four Hundreds Six and Twenty Four Paise Only		
168	Providing & Fixing of P.V.C. Syphon Set as Directed by the Engineer-in-Charge.	Each		296.7162		0
				Rupees Two Hundreds Ninety Six and Seventy One Paise Only		
169	Providing & Fixing of 32mm dia PVC flushing bend for low level cistern as Directed by the Engineer-in-Charge.	Each		68.6616		0
				Rupees Sixty Eight and Sixty Six Paise Only		
170	Providing & Fixing of Handle for Low Level Cistern as Directed by the Engineer-in-Charge.	Each		176.5584		0
				Rupees One Hundreds Seventy Six and Fifty Five Paise Only		
171	Providing & Fixing of PVC waste pipe 1 inch dia 900mm long with 32mm PVC waste coupling for Kitchen Sink & Wash Basin with all fittings as Directed by the Engineer-in-Charge.	Each		49.044		0
				Rupees Forty Nine and Four Paise Only		
172	Providing & Fixing of approved quality 15 mm Ball Valves (FEMALE THREAD PRAYAG BRAND Catalogue No 251) as Directed by the Engineer-in-Charge.	Each		249.307		0
				Rupees Two Hundreds Forty Nine and Thirty Paise Only		
173	Providing & Fixing of approved quality 20 mm Ball Valves (FEMALE THREAD PRAYAG BRAND Catalogue No 252) as Directed by the Engineer-in-Charge.	Each		316.3338		0
				Rupees Three Hundreds Sixteen and Thirty Three Paise Only		
174	Providing & Fixing of approved quality 25 mm Ball Valves (FEMALE THREAD PRAYAG BRAND Catalogue No 253) as Directed by the Engineer-in-Charge.	Each		374.3692		0
				Rupees Three Hundreds Seventy Four and Thirty Six Paise Only		
175	Providing & Fixing of approved quality PTMT Ball Cock 15mm complete with Epoxy Coated Aluminium Rod & H.D. Ball as Directed by the Engineer-in-Charge.	Each		134.871		0
				Rupees One Hundreds Thirty Four and Eighty Seven Paise Only		
176	Providing & Fixing of C.P. Cap for Angle Valve & Concealed Valve as Directed by the Engineer-in-Charge.	Each		113.6186		0
				Rupees One Hundreds Thirteen and Sixty One Paise Only		
177	Providing & Fixing P.V.C. Toilet Seat Cover Heavy Duty HINDWARE / CERA / PARRYWARE/H&R JHONSAN make for European W.C. as Directed by the Engineer-in-Charge.	Each		707.051		0
				Rupees Seven Hundreds Seven and Five Paise Only		
178	Providing & Fixing of P.V.C. Toilet Seat Cover Heavy Duty HINDWARE / CERA / PARRYWARE/JHONSAN make for ANGLO INDIAN W.C. as Directed by the Engineer-in-Charge.	Each		841.922		0
				Rupees Eight Hundreds Forty One and Ninety Two Paise Only		
179	Providing & Fixing of Pig Lead as Directed by the Engineer-in-Charge.	Kg		252.5766		0
				Rupees Two Hundreds Fifty Two and Fifty Seven Paise Only		
180	Providing & Fixing of Hamp Spun Yard (JUTE) as Directed by the Engineer-in-Charge.	Kg		161.0278		0
				Rupees One Hundreds Sixty One and Two Paise Only		
181	Providing & Fixing of P.V.C Bend 110 mm Dia for Rain Water Pipes as Directed by the Engineer-in-Charge.	Each		171.654		0
				Rupees One Hundreds Seventy One and Sixty Five Paise Only		
182	Providing & Fixing of approved quality SHOE for Rain Water Pipes as Directed by the Engineer-in-Charge 110 MM DIA.	Each		93.1836		0
				Rupees Ninety Three and Eighteen Paise Only		
183	Providing & Fixing of approved quality COLLER for Rain Water Pipes as Directed by the Engineer-in-Charge: 110 MM DIA.	Each		78.4704		0
				Rupees Seventy Eight and Forty Seven Paise Only		
184	Providing and fixing G.I. Union in G.I. pipe including cutting and threading the pipe and making long screws etc. complete : 15 mm nominal bore.	Each		264.0202		0
				Rupees Two Hundreds Sixty Four and Two Paise Only		
185	Providing and fixing G.I. Union in G.I. pipe including cutting and threading the pipe and making long screws etc. complete : 20 mm nominal bore.	Each		285.2726		0
				Rupees Two Hundreds Eighty Five and Twenty Seven Paise Only		
186	Providing and fixing G.I. Union in G.I. pipe including cutting and threading the pipe and making long screws etc. complete : 25 mm nominal bore.	Each		352.2994		0
				Rupees Three Hundreds Fifty Two and Twenty Nine Paise Only		
187	Providing and fixing G.I. Union in G.I. pipe including cutting and threading the pipe and making long screws etc. complete : 32 mm nominal bore.	Each		389.8998		0
				Rupees Three Hundreds Eighty Nine and Eighty Nine Paise Only		



Name of Work: Biennial Contract for Repair-Maintenance of Building and External Civil Infrastructure work in AnuKiran and AnuChhaya colonies at R.R. Site.
WO / SOQR Number : 64820
Agency Name : M/s KHAN CONTRACTOR

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Amount in ₹
		Rate in Words				
188	Providing & Fixing of approved quality GI fittings of Heavy duty ISI marked 20 mm to 15 mm dia reducer Elbow as Directed by the Engineer-in-Charge.	Each		256.6636		0
				Rupees Two Hundreds Fifty Six and Sixty Six Paise Only		
189	Providing & Fixing of approved quality GI fittings of Heavy duty ISI marked 25 mm to 15 mm dia Reducer Elbow as Directed by the Engineer-in-Charge.	Each		271.3768		0
				Rupees Two Hundreds Seventy One and Thirty Seven Paise Only		
190	Providing & Fixing of approved quality GI fittings of Heavy duty ISI marked 25 mm to 20 mm dia reducer Elbow as Directed by the Engineer-in-Charge.	Each		271.3768		0
				Rupees Two Hundreds Seventy One and Thirty Seven Paise Only		
191	Providing & Fixing of approved quality GI fittings of Heavy duty ISI mark 32 mm to 15 mm dia Reducer ELBOW as Directed by the Engineer-in-Charge.	Each		295.8988		0
				Rupees Two Hundreds Ninety Five and Eighty Nine Paise Only		
192	Providing & Fixing of approved quality GI fittings of Heavy duty ISI mark 32 mm to 20 mm dia Reducer ELBOW as Directed by the Engineer-in-Charge.	Each		295.8988		0
				Rupees Two Hundreds Ninety Five and Eighty Nine Paise Only		
193	Providing & Fixing of approved quality GI fittings of Heavy duty ISI mark 32 mm to 25 mm dia Reducer ELBOW as Directed by the Engineer-in-Charge.	Each		295.8988		0
				Rupees Two Hundreds Ninety Five and Eighty Nine Paise Only		
194	Providing & Fixing of approved quality G.I. elbow 15 mm. dia. Heavy duty as Directed by the Engineer-in-Charge.	Each		244.4026		0
				Rupees Two Hundreds Forty Four and Forty Paise Only		
195	Providing & Fixing of approved quality G.I. elbow 20 MM dia. Heavy duty as Directed by the Engineer-in-Charge.	Each		254.2114		0
				Rupees Two Hundreds Fifty Four and Twenty One Paise Only		
196	Providing & Fixing of approved quality G.I. elbow 25 MM dia. Heavy duty as Directed by the Engineer-in-Charge.	Each		267.2898		0
				Rupees Two Hundreds Sixty Seven and Twenty Eight Paise Only		
197	Providing & Fixing of approved quality G.I. elbow 32 mm. dia. Heavy duty as Directed by the Engineer-in-Charge.	Each		289.3596		0
				Rupees Two Hundreds Eighty Nine and Thirty Five Paise Only		
198	Providing & Fixing of approved quality G.I. nipple 15 mm dia of 50 mm long as Directed by the Engineer-in-Charge.	Each		26.9742		0
				Rupees Twenty Six and Ninety Seven Paise Only		
199	Providing & Fixing approved quality G.I. nipple 15 mm dia of 100 mm long as Directed by the Engineer-in-Charge.	Each		30.2438		0
				Rupees Thirty and Twenty Four Paise Only		
200	Providing & Fixing of approved quality G.I. nipple 15 mm dia of 150 mm long as Directed by the Engineer-in-Charge.	Each		35.1482		0
				Rupees Thirty Five and Fourteen Paise Only		
201	Providing & Fixing of approved quality G.I. nipple 20 mm dia of 50 mm long as Directed by the Engineer-in-Charge.	Each		30.2438		0
				Rupees Thirty and Twenty Four Paise Only		
202	Providing & Fixing of approved quality G.I. nipple 20 mm dia of 100 mm long as Directed by the Engineer-in-Charge.	Each		33.5134		0
				Rupees Thirty Three and Fifty One Paise Only		
203	Providing & Fixing of approved quality G.I. nipple 20 mm dia of 150 mm long as Directed by the Engineer-in-Charge.	Each		40.0526		0
				Rupees Forty and Five Paise Only		
204	Providing & Fixing of approved quality G.I. nipple 25 mm dia of 50 mm long as Directed by the Engineer-in-Charge.	Each		33.5134		0
				Rupees Thirty Three and Fifty One Paise Only		
205	Providing & Fixing of approved quality G.I. nipple 25 mm dia of 100 mm long as Directed by the Engineer-in-Charge.	Each		40.0526		0
				Rupees Forty and Five Paise Only		
206	Providing & Fixing of approved quality G.I. nipple 25 mm dia of 150 mm long as Directed by the Engineer-in-Charge.	Each		49.8614		0
				Rupees Forty Nine and Eighty Six Paise Only		
207	Providing & Fixing of approved quality G.I. nipple 32 mm dia of 50 mm long as Directed by the Engineer-in-Charge.	Each		35.9656		0
				Rupees Thirty Five and Ninety Six Paise Only		
208	Providing & Fixing of approved quality G.I. nipple 32 mm dia. 100 mm long as Directed by the Engineer-in-Charge.	Each		45.7744		0
				Rupees Forty Five and Seventy Seven Paise Only		
209	Providing & Fixing of approved quality G.I. nipple 32 mm dia of 150 mm long as Directed by the Engineer-in-Charge.	Each		59.6702		0
				Rupees Fifty Nine and Sixty Seven Paise Only		
210	Providing & Fixing of approved quality G.I. plug 15 mm. dia. Heavy duty as Directed by the Engineer-in-Charge.	Each		25.3394		0
				Rupees Twenty Five and Thirty Three Paise Only		



Name of Work: Biennial Contract for Repair-Maintenance of Building and External Civil Infrastructure work in AnuKiran and AnuChhaya colonies at R.R. Site.
WO / SOQR Number : 64820
Agency Name : M/s KHAN CONTRACTOR

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Amount in ₹
		Rate in Words				
211	Providing & Fixing of approved quality G.I. plug 20 mm. dia. Heavy duty as Directed by the Engineer-in-Charge.	Each		27.7916		0
				Rupees Twenty Seven and Seventy Nine Paise Only		
212	Providing & Fixing of approved quality G.I. plug 25 mm. dia. B- class as Directed by the Engineer-in-Charge.	Each		30.2438		0
				Rupees Thirty and Twenty Four Paise Only		
213	Providing & Fixing of approved quality G.I. plug 32 mm. dia. B- class as Directed by the Engineer-in-Charge.	Each		35.1482		0
				Rupees Thirty Five and Fourteen Paise Only		
214	Providing & Fixing of approved quality G.I. holder clamp 15 mm. dia. Heavy duty as Directed by the Engineer-in-Charge.	Each		23.7046		0
				Rupees Twenty Three and Seventy Paise Only		
215	Providing & Fixing of approved quality G.I. holder clamp 20 MM. dia. Heavy duty as Directed by the Engineer-in-Charge.	Each		25.3394		0
				Rupees Twenty Five and Thirty Three Paise Only		
216	Providing & Fixing of approved quality G.I. holder clamp 25 MM. dia. Heavy duty as Directed by the Engineer-in-Charge.	Each		27.7916		0
				Rupees Twenty Seven and Seventy Nine Paise Only		
217	Providing & Fixing of approved quality G.I. holder clamp 32 MM. dia. Heavy duty as Directed by the Engineer-in-Charge.	Each		32.696		0
				Rupees Thirty Two and Sixty Nine Paise Only		
218	Providing & Fixing of approved quality G.I. holder clamp 40 MM. dia. Heavy duty as Directed by the Engineer-in-Charge.	Each		35.1482		0
				Rupees Thirty Five and Fourteen Paise Only		
219	Providing & Fixing of approved quality G.I. holder clamp 50 MM. dia. Heavy duty as Directed by the Engineer-in-Charge.	Each		40.0526		0
				Rupees Forty and Five Paise Only		
220	Providing & Fixing of approved quality GI fittings of Heavy duty class ISI marked 15mm dia Socket (Ordinary/reducing type) as Directed by the Engineer-in-Charge.	Each		35.1482		0
				Rupees Thirty Five and Fourteen Paise Only		
221	Providing & Fixing of approved quality GI fittings of Heavy duty class ISI marked 20mm dia Socket (Ordinary/reducing type) as Directed by the Engineer-in-Charge.	Each		43.3222		0
				Rupees Forty Three and Thirty Two Paise Only		
222	Providing & Fixing of approved quality GI fittings of Heavy duty class ISI marked 25mm dia Socket (Ordinary/reducing type) as Directed by the Engineer-in-Charge.	Each		48.2266		0
				Rupees Forty Eight and Twenty Two Paise Only		
223	Providing & Fixing of approved quality GI fittings of Heavy duty class ISI marked 32mm dia Socket (Ordinary/reducing type) as Directed by the Engineer-in-Charge.	Each		62.9398		0
				Rupees Sixty Two and Ninety Three Paise Only		
224	Providing & Fixing of approved quality GI fittings of Heavy duty class ISI marked 15 mm dia Bend(Ordinary / reducing type) as Directed by the Engineer-in-Charge.	Each		33.5134		0
				Rupees Thirty Three and Fifty One Paise Only		
225	Providing & Fixing of approved quality GI fittings of Heavy duty class ISI marked 20 mm dia Bend(Ordinary / reducing type) as Directed by the Engineer-in-Charge.	Each		39.2352		0
				Rupees Thirty Nine and Twenty Three Paise Only		
226	Providing & Fixing of approved quality GI fittings of Heavy duty class ISI marked 25 mm dia Bend(Ordinary / reducing type) as Directed by the Engineer-in-Charge.	Each		46.5918		0
				Rupees Forty Six and Fifty Nine Paise Only		
227	Providing & Fixing of approved quality GI fittings of Heavy duty class ISI marked 32 mm dia Bend(Ordinary / reducing type) as Directed by the Engineer-in-Charge.	Each		49.8614		0
				Rupees Forty Nine and Eighty Six Paise Only		
228	Providing & Fixing of approved quality GI fittings of Heavy duty ISI marked 20 mm to 15 mm dia Reducer TEE as Directed by the Engineer-in-Charge.	Each		62.9398		0
				Rupees Sixty Two and Ninety Three Paise Only		
229	Providing & Fixing of approved quality GI fittings of Heavy duty ISI marked 25 mm to 15 mm dia Reducer TEE as Directed by the Engineer-in-Charge.	Each		76.0182		0
				Rupees Seventy Six and One Paise Only		
230	Providing & Fixing of approved quality GI fittings of Heavy duty ISI marked 25 mm to 20 mm dia Reducer TEE as Directed by the Engineer-in-Charge.	Each		50.6788		0
				Rupees Fifty and Sixty Seven Paise Only		
231	Providing & Fixing of approved quality GI fittings of Heavy duty ISI marked 32 mm to 15 mm dia Reducer TEE as Directed by the Engineer-in-Charge.	Each		67.0268		0
				Rupees Sixty Seven and Two Paise Only		
232	Providing & Fixing of approved quality GI fittings of Heavy duty ISI marked 32 mm to 20 mm dia Reducer TEE as Directed by the Engineer-in-Charge.	Each		67.0268		0
				Rupees Sixty Seven and Two Paise Only		
233	Providing & Fixing of approved quality GI fittings of Heavy duty ISI marked 32 mm to 25 mm dia Reducer TEE as Directed by the Engineer-in-Charge.	Each		67.0268		0
				Rupees Sixty Seven and Two Paise Only		
234	Providing & Fixing of approved quality G.I. Tee 15 mm. dia Heavy duty as Directed by the Engineer-in-Charge.	Each		44.957		0
				Rupees Forty Four and Ninety Five Paise Only		
235	Providing & Fixing of approved quality G.I. Tee 20 mm.dia. Heavy duty as Directed by the Engineer-in-Charge.	Each		58.8528		0
				Rupees Fifty Eight and Eighty Five Paise Only		
236	Providing & Fixing of approved quality G.I. Tee 25 mm.dia. Heavy duty as Directed by the Engineer-in-Charge.	Each		77.653		0
				Rupees Seventy Seven and Sixty Five Paise Only		



Name of Work: Biennial Contract for Repair-Maintenance of Building and External Civil Infrastructure work in AnuKiran and AnuChhaya colonies at R.R. Site.
WO / SOQR Number : 64820
Agency Name : M/s KHAN CONTRACTOR

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Amount in ₹
		Rate in Words				
237	Providing & Fixing of approved quality G.I. Tee 32 mm. dia Heavy duty as Directed by the Engineer-in-Charge.	Each		96.4532		0
				Rupees Ninety Six and Forty Five Paise Only		
238	Providing & Fixing of approved quality Teflon Tape (1/2") as Directed by the Engineer-in-Charge.	Each		40.0526		0
				Rupees Forty and Five Paise Only		
239	Providing & Applying of M Seal Pidilite in one kg pack as Directed by the Engineer-in-Charge.	Kg		470.005		0
				Rupees Four Hundreds Seventy and Paise Only		
240	Removing M.S. Flat from the Window / Balcony Grills for opening of Night Latch at all heights with necessary arrangements etc., complete as directed by the Engineer-in-Charge.	Each		208.437		0
				Rupees Two Hundreds Eight and Forty Three Paise Only		
241	Providing and fixing cut edge mirror 6mm thick of overall size 600X450mm especially fabricated with superior glass (of approved quality) with designer acrylic PVC frame of approved colour and make mounted around with 6mm thick non-water absorbent Acrylic/PVC material backing fixed with cleats, all complete as per the specifications and directions of Engineer.	Each		1521.9988		0
				Rupees One Thousand Five Hundreds Twenty One and Ninety Nine Paise Only		
242	Providing and fixing glass shelf 6mm thick Jaquar continental Cat no. 1171, or similar approved quality of GROHE/KOHLER brand including all fixtures and fittings complete as per specifications.	Each		1532.625		0
				Rupees One Thousand Five Hundreds Thirty Two and Sixty Two Paise Only		
243	Providing & Fixing of 6mm thick 600mm x 125mm wide glass self with rounded edge (alround) as Directed by the Engineer-in-Charge.	Each		58.0354		0
				Rupees Fifty Eight and Three Paise Only		
244	Providing and fixing C.P. brass towel rail of Jaquar Continental cat no. 1111, 600mm long or similar approved quality of GROHE/KOHLER brand including all fixtures and fittings complete as per specifications.	Each		1369.9624		0
				Rupees One Thousand Three Hundreds Sixty Nine and Ninety Six Paise Only		
245	Providing and fixing C.P. brass towel ring of Jaquar Continental cat no. 1121 or similar approved quality of GROHE/KOHLER brand including all fixtures and fittings complete as per specifications.	Each		1028.2892		0
				Rupees One Thousand Twenty Eight and Twenty Eight Paise Only		
246	Providing and fixing best quality painted metallic cloth hanger having 460 mm length as approved by engineer in charge and as per specifications.	Nos.		423.4132		0
				Rupees Four Hundreds Twenty Three and Forty One Paise Only		
247	Providing & Fixing of Water proof plywood 4 mm thick ISI marked.	SqM		49.8614		0
				Rupees Forty Nine and Eighty Six Paise Only		
248	Providing & Fixing of Water proof plywood 6 mm thick ISI marked.	SqM		59.6702		0
				Rupees Fifty Nine and Sixty Seven Paise Only		
249	Providing & Fixing of Water proof plywood 8 mm thick ISI marked.	SqM		68.6616		0
				Rupees Sixty Eight and Sixty Six Paise Only		
250	Providing & Fixing of Water proof plywood 12 mm thick ISI marked.	SqM		83.3748		0
				Rupees Eighty Three and Thirty Seven Paise Only		
251	Providing & Fixing of Commercial plywood 4 mm thick ISI marked .	SqM		40.0526		0
				Rupees Forty and Five Paise Only		
252	Providing & Fixing of COMMERCIAL PLYWOOD 6 mm thick ISI marked .	SqM		44.1396		0
				Rupees Forty Four and Thirteen Paise Only		
253	Providing & Fixing of COMMERCIAL PLYWOOD 12 mm thick ISI marked.	SqM		57.218		0
				Rupees Fifty Seven and Twenty One Paise Only		
254	Providing & Fixing of Commercial plywood 19 mm thick ISI marked.	SqM		68.6616		0
				Rupees Sixty Eight and Sixty Six Paise Only		
255	Providing & Fixing of 12mm thick Teakwood rib 25mm wide as Directed by the Engineer-in-Charge.	Metre		35.1482		0
				Rupees Thirty Five and Fourteen Paise Only		
256	Providing & Fixing of 12mm thick Teakwood rib 40mm wide as Directed by the Engineer-in-Charge.	Metre		41.6874		0
				Rupees Forty One and Sixty Eight Paise Only		
257	Providing & Fixing of 1.0 mm thick decorative laminated sheet as Directed by the Engineer-in-Charge.	SqM		339.221		0
				Rupees Three Hundreds Thirty Nine and Twenty Two Paise Only		
258	Providing and fixing 12mm thick prelaminated particle board flat pressed three layer or graded wood particle board conforming to IS: 12823 Grade I Type II, in paneling fixed in aluminium doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of engineer-in-charge :Pre-laminated particle board with decorative lamination on one side and balancing lamination on other side.	SqM		905.6792		0
				Rupees Nine Hundreds Five and Sixty Seven Paise Only		
259	Providing & Fixing MS Wire Nails as Directed by the Engineer-in-Charge.	Kg		587.7106		0
				Rupees Five Hundreds Eighty Seven and Seventy One Paise Only		



Name of Work: Biennial Contract for Repair-Maintenance of Building and External Civil Infrastructure work in AnuKiran and AnuChhaya colonies at R.R. Site.
WO / SOQR Number : 64820
Agency Name : M/s KHAN CONTRACTOR

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Amount in ₹
		Rate in Words				
260	Providing & Fixing approved quality of M.S. Black (Shoes Nails) as directed by the Engineer and deposited in civil maintenance store.	Kg	1217.1086			0
				Rupees One Thousand Two Hundreds Seventeen and Ten Paise Only		
261	Providing & Fixing of the following approved quality fittings Stainless Steel Aldrop of 16mm dia 300 mm long with necessary nuts & screws etc.: S.S. Aldrop as Directed by the Engineer-in-Charge.	Each	437.309			0
				Rupees Four Hundreds Thirty Seven and Thirty Paise Only		
262	Providing & Fixing of the following approved quality fittings Sliding door bolts of 16mm dia 300 mm long with necessary nuts & screws etc.: Anodized Aluminium as Directed by the Engineer-in-Charge.	Each	188.002			0
				Rupees One Hundreds Eighty Eight and Paise Only		
263	Providing & Fixing of Sliding Door Bolts of 16mm Dia 300 mm Long with necessary nuts & screws etc.: M.S. NICKLE CHROMIUM as Directed by the Engineer-in-Charge.	Each	146.3146			0
				Rupees One Hundreds Forty Six and Thirty One Paise Only		
264	Providing & Fixing of Anodised Aluminium handles 125 mm with plate 175x32 mm Door handle as Directed by the Engineer-in-Charge.	Each	58.0354			0
				Rupees Fifty Eight and Three Paise Only		
265	Providing & Fixing of M.S. Nickel Chromium "D" Heavy quality Door Handle of 125 mm Long as Directed by the Engineer-in-Charge.	Each	31.8786			0
				Rupees Thirty One and Eighty Seven Paise Only		
266	Providing & Fixing of Anodized Aluminium Tower Bolts 100 mm long as Directed by the Engineer-in-Charge.	Each	46.5918			0
				Rupees Forty Six and Fifty Nine Paise Only		
267	Providing & Fixing of Anodized Aluminium Tower Bolts 150 mm long as Directed by the Engineer-in-Charge.	Each	55.5832			0
				Rupees Fifty Five and Fifty Eight Paise Only		
268	Providing & Fixing of Anodized Aluminium Tower Bolts 200 mm long as Directed by the Engineer-in-Charge.	Each	64.5746			0
				Rupees Sixty Four and Fifty Seven Paise Only		
269	Providing & Fixing of ISI marked M.S. NICKLE CHROMIUM TOWER BOLT: 250 x 10 mm as Directed by the Engineer-in-Charge.	Each	59.6702			0
				Rupees Fifty Nine and Sixty Seven Paise Only		
270	Providing & Fixing of ISI marked M.S. NICKLE CHROMIUM TOWER BOLT: 200 x 10 mm as Directed by the Engineer-in-Charge.	Each	54.7658			0
				Rupees Fifty Four and Seventy Six Paise Only		
271	Providing & Fixing of ISI marked M.S. NICKLE CHROMIUM TOWER BOLT BLACK FINISH (BARREL TYPE): 150 x 10 mm as Directed by the Engineer-in-Charge.	Each	54.7658			0
				Rupees Fifty Four and Seventy Six Paise Only		
272	Providing & Fixing of ISI marked M.S. NICKLE CHROMIUM TOWER BOLT BLACK FINISH (BARREL TYPE): 100 x 10 mm as Directed by the Engineer-in-Charge.	Each	39.2352			0
				Rupees Thirty Nine and Twenty Three Paise Only		
273	Providing & Fixing of Anodized Aluminium Hasps & staples of 100mm size with necessary screws etc. as Directed by the Engineer-in-Charge.	Each	39.2352			0
				Rupees Thirty Nine and Twenty Three Paise Only		
274	Providing & Fixing of M.S. Oxidized Butt Hinges of 75 mm (14 Gauge) size with necessary screws etc., as Directed by the Engineer-in-Charge.	Each	27.7916			0
				Rupees Twenty Seven and Seventy Nine Paise Only		
275	Providing & Fixing of M.S. Oxidized butt Hinges of 100mm (14 gauge) sizes as Directed by the Engineer-in-Charge.	Each	30.2438			0
				Rupees Thirty and Twenty Four Paise Only		
276	Providing & Fixing of M.S. Oxidized butt Hinges of 125mm (12 gauge) sizes as Directed by the Engineer-in-Charge.	Each	35.9656			0
				Rupees Thirty Five and Ninety Six Paise Only		
277	Providing & Fixing of approved quality Stainless steel butt hinges 100mm size as Directed by the Engineer-in-Charge.	Each	130.784			0
				Rupees One Hundreds Thirty and Seventy Eight Paise Only		
278	Providing & Fixing of approved quality C.P. Hooks and eyes of 15 mm dia 150 mm long for shutters as Directed by the Engineer-in-Charge.	Each	34.3308			0
				Rupees Thirty Four and Thirty Three Paise Only		
279	Providing & Fixing of Galvanized M.S. wire mesh of 0.56 - 0.63 mm dia with 12 mesh per 2.5 cm in either as Directed by the Engineer-in-Charge.	SqM	304.8902			0
				Rupees Three Hundreds Four and Eighty Nine Paise Only		
280	Providing & Fixing of S.S. wire mesh 0.56 - 0.63 mm dia with 12 mesh per 2.5 cm in either as Directed by the Engineer-in-Charge.	SqM	532.9448			0
				Rupees Five Hundreds Thirty Two and Ninety Four Paise Only		
281	Providing & Fixing of GI chicken mesh 20mm x 20mm x 26 SWG as Directed by the Engineer-in-Charge.	SqM	116.0708			0
				Rupees One Hundreds Sixteen and Seven Paise Only		
282	Providing & Fixing of M.S. Door Tee spring (YEN BRAND FOR DESIGNER DOOR SPRING HELIX) as Directed by the Engineer-in-Charge.	Each	191.2716			0
				Rupees One Hundreds Ninety One and Twenty Seven Paise Only		
283	Providing & Fixing of 18-20mm dia plain Heavy duty Aluminium pipe for pelmets as Directed by the Engineer-in-Charge.	Metre	48.2266			0
				Rupees Forty Eight and Twenty Two Paise Only		



Name of Work: Biennial Contract for Repair-Maintenance of Building and External Civil Infrastructure work in AnuKiran and AnuChhaya colonies at R.R. Site.
WO / SOQR Number : 64820
Agency Name : M/s KHAN CONTRACTOR

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Amount in ₹
		Rate in Words				
284	Providing & Fixing of approved quality Pelmate Socket as Directed by the Engineer-in-Charge.	Each		116.0708		0
				Rupees One Hundreds Sixteen and Seven Paise Only		
285	Providing & Fixing of 25mm dia ribbed Heavy Duty Aluminium rod for Towel rod as Directed by the Engineer-in-Charge.	Metre		63.7572		0
				Rupees Sixty Three and Seventy Five Paise Only		
286	Providing & Fixing of approved quality Heavy Duty C.P. brass brackets for Towel rod as Directed by the Engineer-in-Charge.	Each		28.609		0
				Rupees Twenty Eight and Sixty Paise Only		
287	Providing & Fixing of Heavy Duty Aluminium anodized bracket for 125 mm wide glass shelf as Directed by the Engineer-in-Charge.	1pair		44.957		0
				Rupees Forty Four and Ninety Five Paise Only		
288	Providing & Fixing of approved quality of 4mm thick plain glass in required size as Directed by the Engineer-in-Charge.	SqM		935.923		0
				Rupees Nine Hundreds Thirty Five and Ninety Two Paise Only		
289	Providing & Fixing of approved quality of 5mm thick plain glass in required size as Directed by the Engineer-in-Charge.	SqM		993.9584		0
				Rupees Nine Hundreds Ninety Three and Ninety Five Paise Only		
290	Providing & Fixing of approved quality of 6 mm thick plain glass in required size as Directed by the Engineer-in-Charge.	SqM		1110.0292		0
				Rupees One Thousand One Hundreds Ten and Two Paise Only		
291	Providing & Fixing of approved quality of 8 mm thick plain glass in required size as Directed by the Engineer-in-Charge.	SqM		1485.2158		0
				Rupees One Thousand Four Hundreds Eighty Five and Twenty One Paise Only		
292	Providing & Fixing of approved quality of 12 mm thick plain glass in required size as Directed by the Engineer-in-Charge.	SqM		1967.4818		0
				Rupees One Thousand Nine Hundreds Sixty Seven and Forty Eight Paise Only		
293	Providing & Fixing approved quality of 4mm thick frosted glass in required size as Directed by the Engineer-in-Charge.	SqM		1044.6372		0
				Rupees One Thousand Forty Four and Sixty Three Paise Only		
294	Providing and fixing Sun control film 25 micron thick of approved colour and shade, complete in all respect at all level, as directed by Engineer -in- charge	SqM		353.1168		0
				Rupees Three Hundreds Fifty Three and Eleven Paise Only		
295	Providing & Fixing Aluminium sliding window lock approved and as Directed by the Engineer-in-Charge.	Each		161.8452		0
				Rupees One Hundreds Sixty One and Eighty Four Paise Only		
296	Providing & Fixing of Aluminium U Channel of size 6 mm x 6 mm as Directed by the Engineer-in-Charge.	Rm		157.7582		0
				Rupees One Hundreds Fifty Seven and Seventy Five Paise Only		
297	Providing & Fixing of Chromium plated (C.P.) liquid Soap containers of brass of approved make as Directed by the Engineer-in-Charge.	Each		232.959		0
				Rupees Two Hundreds Thirty Two and Ninety Five Paise Only		
298	Providing & Fixing of Steel Window Handle Heavy Type suitable for steel window with necessary type bolts washers as Directed by the Engineer-in-Charge.	Each		52.3136		0
				Rupees Fifty Two and Thirty One Paise Only		
299	Providing & Fixing of M.S. Oxidized Heavy Duty Channel Clipped Peg Stays for Steel Windows with necessary secrews as Directed by the Engineer-in-Charge.	Each		49.044		0
				Rupees Forty Nine and Four Paise Only		
300	Providing & Fixing of M.S. Nut Bolts etc. as Directed by the Engineer-in-Charge.	Kg		212.524		0
				Rupees Two Hundreds Twelve and Fifty Two Paise Only		
301	Providing & Fixing of SAFETY CHAIN for Main Door as Directed by the Engineer-in-Charge.	Each		85.827		0
				Rupees Eighty Five and Eighty Two Paise Only		
302	Providing & Fixing of Rubber Bush Buffer 50 mm Long as Directed by the Engineer-in-Charge.	Each		49.044		0
				Rupees Forty Nine and Four Paise Only		
303	Providing and fixing aluminum hanging floor door stopper ISI marked anodized (anodic coating not less than grade AC 10 as per IS: 1868) transparent or dyed to required colour and shade with necessary screws etc. complete: Single rubber stoper as per drawings, specifications and directions of Engineer-in-charge.	Each		30.2438		0
				Rupees Thirty and Twenty Four Paise Only		
304	Providing & Fixing of PVC Roller suitable for Sliding Window Shutter as Directed by the Engineer-in-Charge.	Each		40.0526		0
				Rupees Forty and Five Paise Only		
305	Providing & Applying of Fevicol Pidilite (R) SH Brand (synthetic resin adhesive) in one kg pack as Directed by the Engineer-in-Charge.	Kg		458.5614		0
				Rupees Four Hundreds Fifty Eight and Fifty Six Paise Only		



Name of Work: Biennial Contract for Repair-Maintenance of Building and External Civil Infrastructure work in AnuKiran and AnuChhaya colonies at R.R. Site.
WO / SOQR Number : 64820
Agency Name : M/s KHAN CONTRACTOR

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Amount in ₹
		Rate in Words				
306	Providing & Applying of PUTTY (Wood Work) as Directed by the Engineer-in-Charge.	Kg	138.1406			0
				Rupees One Hundreds Thirty Eight and Fourteen Paisa Only		
307	Providing & Applying of Glass putty as Directed by the Engineer-in-Charge.	Kg	49.044			0
				Rupees Forty Nine and Four Paisa Only		
308	Providing & Fixing of neoprin rubber gasket for glazed pannels etc. as Directed by the Engineer-in-Charge.	Metre	138.1406			0
				Rupees One Hundreds Thirty Eight and Fourteen Paisa Only		
309	Providing & Fixing of Silicon as Directed by the Engineer-in-Charge.	Litre	827.2088			0
				Rupees Eight Hundreds Twenty Seven and Twenty Paisa Only		
310	Providing and fixing 'GODREJ' or other approved similar make night latch with 3 keys including all fittings and fixtures as per manufacture's specifications complete as per specifications and direction of EIC.	Each	1004.5846			0
				Rupees One Thousand Four and Fifty Eight Paisa Only		
311	Providing & Fixing of Bright Finished Brass 100 mm mortice latch and lock with 6 levers and pair of lever handles with necessary screws etc., complete (Best make of approved quality) as Directed by the Engineer-in-Charge.	Each	559.1016			0
				Rupees Five Hundreds Fifty Nine and Ten Paisa Only		
312	Providing & Fixing of Godrej mark Cylindrical Locks ? Keyed (Entrance) Polished Brass (Product No.5328) as directed by the engineer.	Each	959.6276			0
				Rupees Nine Hundreds Fifty Nine and Sixty Two Paisa Only		
313	Providing & Fixing of aluminium handle of American / Round shaped suitable for aluminium doors of heavy quality as Directed by the Engineer-in-Charge.	Each	123.4274			0
				Rupees One Hundreds Twenty Three and Forty Two Paisa Only		
314	Repairing of self coiling type existing roling shutter for proper functioing including greasing of coils, ball bearing and vertical channels etc. all complete	Each	250.1244			0
				Rupees Two Hundreds Fifty and Twelve Paisa Only		
315	Providing and fixing Corner cabinet "icon" or similar approved brand having double door as per specification & direction of engineer in charge.	Each	1575.1298			0
				Rupees One Thousand Five Hundreds Seventy Five and Twelve Paisa Only		
316	Providing & Fixing of Hole Tide Liquid Solvent as Directed by the Engineer-in-Charge.	kg	489.6226			0
				Rupees Four Hundreds Eighty Nine and Sixty Two Paisa Only		
317	Providing & Applying of EMERY PAPER / SAND PAPER of following sizes 60 no as Directed by the Engineer-in-Charge.	Each	26.1568			0
				Rupees Twenty Six and Fifteen Paisa Only		
318	Providing & Applying of EMERY PAPER / SAND PAPER of following sizes 80 no as Directed by the Engineer-in-Charge.	Each	26.1568			0
				Rupees Twenty Six and Fifteen Paisa Only		
319	Providing & Applying of EMERY PAPER / SAND PAPER of following sizes 100 no as Directed by the Engineer-in-Charge.	Each	26.1568			0
				Rupees Twenty Six and Fifteen Paisa Only		
320	Providing & Fixing of DRILL BITS FOR BOASCH Power Drill Machine - GBM 13 - 2 Part No. - 0601169055 Wt - 1.95 as Directed by the Engineer-in-Charge.	Each	1065.0722			0
				Rupees One Thousand Sixty Five and Seven Paisa Only		
321	Providing & Fixing of DRILL BITS FOR BOASCH Power Drill Machine - GBH 4 DFE Part No. 0611236703 Wt. 3.9 Kg as Directed by the Engineer-in-Charge.	Each	1498.2942			0
				Rupees One Thousand Four Hundreds Ninety Eight and Twenty Nine Paisa Only		
322	Providing & Fixing of DRILL BITS FOR BOASCH Power Drill Machine - GSH 11 E Part No. 0611316703 Wt 10.1 Kg as Directed by the Engineer-in-Charge.	Each	1678.9396			0
				Rupees One Thousand Six Hundreds Seventy Eight and Ninety Three Paisa Only		
323	Providing & Applying of Concrete drill bit upto 6mm dia for drilling machine of approved brand or BUSH OR HILTI MAKE as Directed by the Engineer-in-Charge.	Each	794.5128			0
				Rupees Seven Hundreds Ninety Four and Fifty One Paisa Only		
324	Providing & Applying of Full size Concrete drill bit upto 12mm dia for drilling machine of approved brand or BUSH OR HILTI MAKE as Directed by the Engineer-in-Charge.	Each	931.0186			0
				Rupees Nine Hundreds Thirty One and One Paisa Only		
325	Providing & Applying of Full size Concrete drill bit upto 16mm dia for drilling machine of approved brand or BUSH OR HILTI MAKE as Directed by the Engineer-in-Charge.	Each	941.6448			0
				Rupees Nine Hundreds Forty One and Sixty Four Paisa Only		
326	Providing & Applying of Full size Concrete drill bit upto 20mm dia for drilling machine of approved brand or BUSH OR HILTI MAKE as Directed by the Engineer-in-Charge.	Each	988.2366			0
				Rupees Nine Hundreds Eighty Eight and Twenty Three Paisa Only		



Name of Work: Biennial Contract for Repair-Maintenance of Building and External Civil Infrastructure work in AnuKiran and AnuChhaya colonies at R.R. Site.
WO / SOQR Number : 64820
Agency Name : M/s KHAN CONTRACTOR

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Amount in ₹
		Rate in Words				
327	Providing & Applying of Hammer drilling machine with drilling upto 30mm dia on Hire charges basis per day.	Each		703.7814		0
				Rupees Seven Hundreds Three and Seventy Eight Paise Only		
328	Providing and fixing double action hydraulic floor spring of approved brand and manufacture IS: 6315 marked, for doors, including cost of cutting floors as required, embedding in floors and cover plates with brass pivot and single place M.S. sheet outer box with slide plate etc. complete as per the direction of Engineer-in-charge : With stainless steel cover plate.	Each		2084.37		0
				Rupees Two Thousand Eighty Four and Thirty Seven Paise Only		
329	Providing & Fixing of Godrej mark Hydraulic Door Closers, Door Closer Single / Two Speed (T) {Product No 9185 / 3975} as directed by the Engineer.	Each		957.1754		0
				Rupees Nine Hundreds Fifty Seven and Seventeen Paise Only		
330	Providing & Fixing of medium duty hydrolically regulated door closer of type-2, suitable for left or right or universal with necessary screws/ nuts, bolts etc. complete as Directed by the Engineer-in-Charge.	Each		764.269		0
				Rupees Seven Hundreds Sixty Four and Twenty Six Paise Only		
331	Providing & Fixing Godrej mark Euro Profile Handle Set - 240 mm Universal / Supreme (Gold) (Product No. 9933 / 9932) as Directed by the Engineer-in-Charge.	Each		992.3236		0
				Rupees Nine Hundreds Ninety Two and Thirty Two Paise Only		
332	Providing & Fixing of Nickel plated M.S. wood screw 15mm long as Directed by the Engineer-in-Charge.	Each		2.4522		0
				Rupees Two and Forty Five Paise Only		
333	Providing & Fixing of Nickel plated M.S. wood screw 20mm long as Directed by the Engineer-in-Charge.	Each		2.4522		0
				Rupees Two and Forty Five Paise Only		
334	Providing & Fixing of Nickel plated M.S. wood screw 25mm long as Directed by the Engineer-in-Charge.	Each		3.2696		0
				Rupees Three and Twenty Six Paise Only		
335	Providing & Fixing of Nickel plated M.S. wood screw 32mm long as Directed by the Engineer-in-Charge.	Each		3.2696		0
				Rupees Three and Twenty Six Paise Only		
336	Providing & Fixing of Nickel plated M.S. wood screw 40mm long as Directed by the Engineer-in-Charge.	Each		4.087		0
				Rupees Four and Eight Paise Only		
337	Providing & Fixing of Nickel plated M.S. wood screw 50mm long as Directed by the Engineer-in-Charge.	Each		4.087		0
				Rupees Four and Eight Paise Only		
338	Providing & Fixing of Nickel plated M.S. wood screw 75mm long as Directed by the Engineer-in-Charge.	Each		5.7218		0
				Rupees Five and Seventy Two Paise Only		
339	Providing & Fixing of Non Breakable P.V.C. Nylon Sleeves: 25 mm Long as Directed by the Engineer-in-Charge.	Nos.		2.4522		0
				Rupees Two and Forty Five Paise Only		
340	Providing & Fixing of Non Breakable P.V.C. Nylon Sleeves: 35 mm Long as Directed by the Engineer-in-Charge.	Nos.		2.4522		0
				Rupees Two and Forty Five Paise Only		
341	Providing & Fixing of Non Breakable P.V.C. Nylon Sleeves: 50 mm Long as Directed by the Engineer-in-Charge.	Nos.		3.2696		0
				Rupees Three and Twenty Six Paise Only		
342	Providing & Applying of GREASE of Best Quality as Directed by the Engineer-in-Charge.	Kg		134.871		0
				Rupees One Hundreds Thirty Four and Eighty Seven Paise Only		
343	Providing and fixing factory made ISI marked steel glazed doors, windows and ventilators, side /top /centre hung, with beading and all members such as F7D,F4B, K11 B and K12 B etc. complete of standard rolled steel sections, joints mitred and flash butt welded and sash bars tenoned and riveted, including providing and fixing of hinges, pivots, including priming coat of approved steel primer, complete all as per approved design, including Fixing with 15x3 mm lugs 10 cm long embedded in cement concrete block 15x10x10 cm of C.C. 1:3:6 (1 Cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size) Note :- Sectional weight of only steel members shall be measured for payment.	Kg		168.3844		0
				Rupees One Hundreds Sixty Eight and Thirty Eight Paise Only		
344	Providing & Fixing of Aluminium sheet 1mm thick as Directed by the Engineer-in-Charge.	Kg		292.6292		0
				Rupees Two Hundreds Ninety Two and Sixty Two Paise Only		
345	WOOD WORK REPAIR:- Repairing of sofa etc including replacement of high density cushion (40 kg / CuM) and cloth of standard and approved make & colour etc. with Paint/ polishing on wooden portion. Repairing to be taken up including replacing spring, wood etc. as per functional requirement to look like new one. Note:- Rate of cloth shall be not less than @ Rs. 300 per SqM.					
345.1	Sofa five seater set.	Nos		9727.06		0
				Rupees Nine Thousand Seven Hundreds Twenty Seven and Six Paise Only		
345.2	Sofa three seater.	Nos		6048.76		0
				Rupees Six Thousand Forty Eight and Seventy Six Paise Only		



Name of Work: Biennial Contract for Repair-Maintenance of Building and External Civil Infrastructure work in AnuKiran and AnuChhaya colonies at R.R. Site.
WO / SOQR Number : 64820
Agency Name : M/s KHAN CONTRACTOR

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Amount in ₹
		Rate in Words				
345.3	Sofa single seater.	Nos		2254.3892		0
				Rupees Two Thousand Two Hundreds Fifty Four and Thirty Eight Paisa Only		
346	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with Second class teak wood complete as per drawings, specifications and direction of Engineer.	CuM		107269.8542		0
				Rupees One Lakh Seven Thousand Two Hundreds Sixty Nine and Eighty Five Paisa Only		
347	Providing & Fixing of modular kitchen parts having manually fabricated shutters in 19mm thick marine ply having area about 2.5 sqm (deviation upto (+/-) 10.00% shall be included in the quoted rate) confirming to IS 710, KITPLY GOLD / GREENLAM / CENTURY make as approved with laminate of approved make (Kitplay / Greenlam / Century) & shade on both faces (1mm th. laminate of front face & 0.8mm on back face with the provision of edge bending) including 2nd class teak wood leaping of suitable size along with all necessary SS 202 grade branded (AVRO / LIFE TIME) accessories, hardware fittings and fixtures for commissioning of the modular kitchen as per site requirement:-					
347.01	SS C/S Bsk. 21"	Each		913.8532		0
				Rupees Nine Hundreds Thirteen and Eighty Five Paisa Only		
347.02	SS M.P. Bsk. 21"x 4"	Each		821.487		0
				Rupees Eight Hundreds Twenty One and Forty Eight Paisa Only		
347.03	SS Thali Bsk. 21"	Each		1047.0894		0
				Rupees One Thousand Forty Seven and Eight Paisa Only		
347.04	SS Pull Out 6" x 3" (Two Shelf bottle pullout)	Each		1952.7686		0
				Rupees One Thousand Nine Hundreds Fifty Two and Seventy Six Paisa Only		
347.05	SS P. Cut Bsk. 21"	Each		1336.449		0
				Rupees One Thousand Three Hundreds Thirty Six and Forty Four Paisa Only		
347.06	SS MP Bsk. 21" x 4"	Each		821.487		0
				Rupees Eight Hundreds Twenty One and Forty Eight Paisa Only		
347.07	SS M.P. BSK. 21" x 6"	Each		936.7404		0
				Rupees Nine Hundreds Thirty Six and Seventy Four Paisa Only		
347.08	Frame wood 2.5"	Each		322.873		0
				Rupees Three Hundreds Twenty Two and Eighty Seven Paisa Only		
347.09	Tele. Channels. 20"	Each		449.57		0
				Rupees Four Hundreds Forty Nine and Fifty Seven Paisa Only		
347.10	Soft closing Hinges 0^ & 8^	Each		349.0298		0
				Rupees Three Hundreds Forty Nine and Two Paisa Only		
347.11	Handles Assorted sizes (SS 8mm)	Each		260.7506		0
				Rupees Two Hundreds Sixty and Seventy Five Paisa Only		
347.12	Fascia / Shutters (Bottom) including laminates.	SqM		1963.3948		0
				Rupees One Thousand Nine Hundreds Sixty Three and Thirty Nine Paisa Only		
348	Providing & fixing Aluminium Aldrops, handle (all types), hinges, tower bolt, pagstray, I-hooks etc. to fit & Shape as per spot work requirement & as directed by EIC.					
348.1	For Anodised Aluminium	Kg		595.0672		0
				Rupees Five Hundreds Ninety Five and Six Paisa Only		
348.2	For Coloured Aluminium	Kg		675.1724		0
				Rupees Six Hundreds Seventy Five and Seventeen Paisa Only		
349	Supply & Fixing of Gal Valume sheeting over truss, Color complying to ASTM A792, base metal thickness 0.80mm, alloy coating AZ 150 (Aluminium 55%, Zin 43.50% and Silicon 1.5%).Yield Strength: 350 MPA, Paint coating regular modified polyster top coat 25 microns & bottom coat 12 microns epoxy, top color: Combination of Blue and Off White and bottom color grey. The Steel Sheet shall be 3'-0" (914mm) width which shall be curved and moulded at site using mechanical press and dies to the desired shape to form 2'-0" (605mm) wide interlocking panels. These panels shall be erected in position and the joints are seamed with gasket etc. whenever is required. The installation should be done by mechanized system. (Mesurment to be paid actual area of sheet as per site. Over lap of sheet area not to be paid.)	SqM		1597.1996		0
				Rupees One Thousand Five Hundreds Ninety Seven and Nineteen Paisa Only		



Name of Work: Biennial Contract for Repair-Maintenance of Building and External Civil Infrastructure work in AnuKiran and AnuChhaya colonies at R.R. Site.
WO / SOQR Number : 64820
Agency Name : M/s KHAN CONTRACTOR

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Amount in ₹
		Rate in Words				
350	Providing corrugated 6mm thick Coloured Fiber sheet roofing including vertical/ curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diaMetre with bitumen and G.I. limpet washer filled with white lead excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. (Weight of 6 mm fiber sheet not less than 10.76 Kg/M2)	SqM		1744.3316		0
				Rupees One Thousand Seven Hundreds Forty Four and Thirty Three Paisa Only		
351	Providing corrugated G.S. (Galvanised steel) sheet roofing including vertical/ curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diaMetre with bitumen and G.I. limpet washer filled with white lead and including a coat of approved steel primer and two coat of approved paint on a overlapping of sheets complete (up to any pitch in horizontal/ vertical or curved surfaces) excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required: 0.63 mm thick with zinc coating not less than 275 gm/m2.	SqM		860.7222		0
				Rupees Eight Hundreds Sixty and Seventy Two Paisa Only		
352	Providing ridges or hips of width 60 cm over all width plain G.S. sheet fixed with polymer coated J or L hooks, bolts and nuts 8 mm dia. G.I. limpet and bitumen washers complete. 0.80 mm thick with Zinc coating not less than 275gm/m2.	Metre		756.9124		0
				Rupees Seven Hundreds Fifty Six and Ninety One Paisa Only		
353	Providing non-asbestos high impact polypropylene reinforced cement 6mm thick corrugated sheet (as per IS CODE) roofing up to any pitch and fixing with polymer coated J, or L hooks, bolts and nuts 8 mm dia G.I plain and bitumen washers or with self drilling faster and EPDM washers etc. complete excluding the cost of purlins, rafters and trusses: corrugated sheet and including cutting to size and shape wherever required.	SqM		405.4304		0
				Rupees Four Hundreds Five and Forty Three Paisa Only		
354	Supplying factory made fiberglass reinforced plastics (F.R.P) chajja 4mm thick of required colour,size and design made by resin transfer moulding (RTM) machine technology, resulting in void free compact laminate in single piece, having smooth gradual slope curvature for easy drainage of water and duly reinforced by 2nos. vertically and 1 nos. horizontally 50x2mm thick M.S flat with with 12mm in built hole for grouting on the existing wall along with the 50mm flanges duly inserted and sealed in the wall complete in one single piece casted monolithically,including all necessary fitting. The ERP Chajja should be manufactured using unsaturated polyester resin as per IS: 6746 duly reinforced with fiber glass chopped strand mat(CSM) as per IS: 11551 complete with protective Gel coat U/V coating on top for complete resistance from the extreme of temperature, weather & sunlight. etc. complete as per drawings, specifications and directions of Engineer-in-charge.	SqM		4122.9656		0
				Rupees Four Thousand One Hundreds Twenty Two and Ninety Six Paisa Only		
355	Providing and maintaining in operating condition brand new Single phase welding set with lead on Hire charges basis complete as required for completing the jobs daily.	Each		31.0612		0
				Rupees Thirty One and Six Paisa Only		
356	Providing & Applying super bond of Ador or Norma of D&H secheren welding rod 2.5mm (Metal No.-6013) as Directed by the Engineer-in-Charge.	Kg		755.2776		0
				Rupees Seven Hundreds Fifty Five and Twenty Seven Paisa Only		
357	Providing & Applying of (LUNKER MAKE) High speed Hack blade (ISI marked) as Directed by the Engineer-in-Charge.	Each		34.3308		0
				Rupees Thirty Four and Thirty Three Paisa Only		
358	Providing & Fixing of M.S. Welded Mesh 6 mm x 6 mm size as Directed by the Engineer-in-Charge.	Kg		183.0976		0
				Rupees One Hundreds Eighty Three and Nine Paisa Only		
359	Providing and fixing concertina coil fencing with required dia 610mm (having 15 nos. round per 6 Metre length) up to 3m height of wall with existing angle iron ??Y? shaped placed 2.4m or 3.00 m apart and with 9 horizontal R.B.T. stud tied with G.I. staples and G.I. clips to retain horizontal including necessary belts or G.I. barbed wire tied to angle iron all complete as per direction of Engineer-in-charge with reinforced barbed tape (R.B.T.) / Spring core (2.5mm thick) wire of high tensile strength of 165 kg/sq. mm with tape (0.52mm thick) and weight 43.47 gm/Metre (cost of M.S. angle, C.C. blocks shall be paid separately).	Rm		242.7678		0
				Rupees Two Hundreds Forty Two and Seventy Six Paisa Only		
360	Providing and fixing G.I. chain link fabric fencing of required width in mesh size 50 x 50mm made of G.I. wire of dia 4mm including strengthening with 2 mm dia wire or nuts, bolts and washers as required complete as per the direction of Engineer ? In charge.	SqM		694.79		0
				Rupees Six Hundreds Ninety Four and Seventy Nine Paisa Only		
361	Fencing with angle iron post placed at required distance, embedded in cement concrete blocks, every 15th post, last but one end post and corner post shall be strutted on both sides and end post one side only and provided with horizontal lines and two diagonals interwoven with horizontal wires, of barbed wire 9.38 kg per 100 m (minimum) between the two posts filled and fixed with G.I. staples, turn buckles etc. complete.(cost of posts, struts, earth work and concrete to be paid for separately):- Payment to be made per meter cost of total length of barbed wire used. : With G.I. barbed wire.	Metre		17.9828		0
				Rupees Seventeen and Ninety Eight Paisa Only		
362	French sprit polishing two coat on old work after cleaning / scrubbing of surfaces with soft brushes & sand papers including the cost of materials, labour, cleaning of area after painting etc. complete as per direction of Engineer-in-Charge.	SqM		201.0804		0
				Rupees Two Hundreds One and Eight Paisa Only		
363	Providing & Applying Touchwood interior wood finish as Directed by the Engineer-in-Charge.	Litre		2299.3462		0
				Rupees Two Thousand Two Hundreds Ninety Nine and Thirty Four Paisa Only		
364	Providing & Applying of ASIAN Paint WOOD PRIMER PINK (0007 / GR-2) as Directed by the Engineer-in-Charge.	Litre		223.9676		0
				Rupees Two Hundreds Twenty Three and Ninety Six Paisa Only		
365	Supplying of Thinner for General purpose Berger paint 800 as directed by Engineer-in-charge.	Litre		143.8624		0
				Rupees One Hundreds Forty Three and Eighty Six Paisa Only		
366	Providing & Applying of ASIAN / Nerolac Paint METAL PRIMER RED OXIDE (0005 / GR-0) as Directed by the Engineer-in-Charge.	Litre		146.3146		0
				Rupees One Hundreds Forty Six and Thirty One Paisa Only		
367	Providing & Applying of Plaster of Paris as Directed by the Engineer-in-Charge.	Kg		110.349		0
				Rupees One Hundreds Ten and Thirty Four Paisa Only		



Name of Work: Biennial Contract for Repair-Maintenance of Building and External Civil Infrastructure work in AnuKiran and AnuChhaya colonies at R.R. Site.
WO / SOQR Number : 64820
Agency Name : M/s KHAN CONTRACTOR

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Amount in ₹
						Rate in Words
368	Providing & Applying of LIME (WHITING) as Directed by the Engineer-in-Charge.	Kg	111.1664			0
						Rupees One Hundreds Eleven and Sixteen Paise Only
369	Providiing & Mixing of Green or Blue Medium Shade Pigment and deposite in Civil Maintenance Store.	Kg	72.7486			0
						Rupees Seventy Two and Seventy Four Paise Only
370	Providing & Applying of Anticorrosive Bituminous Paint (Black) as Directed by the Engineer-in-Charge.	Litre	134.871			0
						Rupees One Hundreds Thirty Four and Eighty Seven Paise Only
371	Providing & Applying of Araldite as Directed by the Engineer-in-Charge.	kg	803.5042			0
						Rupees Eight Hundreds Three and Fifty Paise Only
372	Replacing the existing WC and providing & fixing New Anglo Indian WC of make "HINDWARE" or "parry" , CERRA OR JHONSAN as approved by EIC and depositing the old WC is store as per direction of Engineer In Charge .	Each	3916.9808			0
						Rupees Three Thousand Nine Hundreds Sixteen and Ninety Eight Paise Only
373	Providing & Fixing of approved brand 100mm dia. C.P. Grating as Directed by the Engineer-in-Charge.	Each	49.8614			0
						Rupees Forty Nine and Eighty Six Paise Only
374	Providing & Fixing of C.I. grating for gully trap as Directed by the Engineer-in-Charge.	Each	49.044			0
						Rupees Forty Nine and Four Paise Only
375	Providing & Applying Acrylic Polymer chemical for cracks for interiors as Directed by the Engineer-in-Charge.	kg	139.7754			0
						Rupees One Hundreds Thirty Nine and Seventy Seven Paise Only
376	Providing and fixing glass / pvc strips in joints of terrazzo/ cement concrete floors: 40 mm wide and 4 mm thick including finishing & curing work at all level etc. complete as per direction of Engineer-in-charge	Rm	72.7486			0
						Rupees Seventy Two and Seventy Four Paise Only
377	Providing & Stacking of ordinary portland cement of 43 grade (OPC -43) confirming to relevent IS code and deposited in civil maintenance store along with voucher. (Note - Test certificate of cement obtained from the manufacturer shall be submitted for a qty. more than 1.0 MT brought).	MT	5826.4272			0
						Rupees Five Thousand Eight Hundreds Twenty Six and Forty Two Paise Only
378	Providing & Stacking of white cement conforming to relevent IS code as Directed by the Engineer-in-Charge.	MT	12945.1638			0
						Rupees Twelve Thousand Nine Hundreds Forty Five and Sixteen Paise Only
379	Providing & Spreding of good quality crusher aggregate 20mm down gauge as Directed by the Engineer-in-Charge.	CuM	1172.1516			0
						Rupees One Thousand One Hundreds Seventy Two and Fifteen Paise Only
380	Providing & depositing of screened river sand / manufactured sand suitable for concrete/ masonry/ plaster works as approved as Directed by the Engineer-in-Charge.	CuM	1639.7044			0
						Rupees One Thousand Six Hundreds Thirty Nine and Seventy Paise Only
381	Providing & Stacking of good quality bricks 230 x 115 x 75 mm size as approved as Directed by the Engineer-in-Charge.	Each	6.5392			0
						Rupees Six and Fifty Three Paise Only
382	Providing and fixing of approved quality 18mm thick black granite stone of size about - 1200 mm x 750 mm with nomenclature as per standered prectice, specification and as per direction of EIC.	Nos.	6901.3082			0
						Rupees Six Thousand Nine Hundreds One and Thirty Paise Only
383	Providing and fixing of Cinch Anhor/ Anchor fastner, Screw headed / sunken / Capstan headed bolts alongwith washer of following sizes as approved by the Engineer.					
383.1	M-8	Each	76.0182			0
						Rupees Seventy Six and One Paise Only
383.2	M-10	Each	85.0096			0
						Rupees Eighty Five and Paise Only
383.3	M-12	Each	100.5402			0
						Rupees One Hundreds and Fifty Four Paise Only
383.4	M-16	Each	120.9752			0
						Rupees One Hundreds Twenty and Ninety Seven Paise Only
384	Dismantling Stone Slab Flooring laid in Cement mortar including stacking of serviceable material and disposal of unserviceable material within 500 Metres lead as per direction of engineer in charge.	SqM	221.5154			0
						Rupees Two Hundreds Twenty One and Fifty One Paise Only
385	Demolishing stone rubble masonry manually / by mechanical means including stacking of serviceable material and disposal of unserviceable material within 500 meters lead as per direction of Engineer-in-charge In cement mortar.	CuM	2054.1262			0
						Rupees Two Thousand Fifty Four and Twelve Paise Only
386	Demolishing cement concrete manually by mechanical means including disposal of materials within 500 metres lead as per direction of engineer in charge, 1:3:6 or richer mix.	CuM	2027.9694			0
						Rupees Two Thousand Twenty Seven and Ninety Six Paise Only



Name of Work: Biennial Contract for Repair-Maintenance of Building and External Civil Infrastructure work in AnuKiran and AnuChhaya colonies at R.R. Site.
WO / SOQR Number : 64820
Agency Name : M/s KHAN CONTRACTOR

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Amount in ₹
		Rate in Words				
387	Dismantling of any type plaster Inside & Outside in Cement Plaster including disposal of Unserviceable material Withing 1.0 KM Lead.	SqM		17.1654		0
				Rupees Seventeen and Sixteen Paise Only		
388	Dismantling roofing including ridges, hips valleys and gutters etc, and stacking the material within 500 meters lead of: G.S. Sheet.	SqM		138.958		0
				Rupees One Hundreds Thirty Eight and Ninety Five Paise Only		
389	Providing & Fixing of approved quality Agro shading net of NETLON make of 50% perforation for covering of green house for ornamental plants in nursery as Directed by the Engineer-in-Charge.	sqm		75.2008		0
				Rupees Seventy Five and Twenty Paise Only		
390	Supplying of Fresh Liquied Handwash (Santoor Gentle Handwash/Dettol/Perl/Lifeboye etc.) as Directed by the Engineer-in-Charge.	Kg		87.4618		0
				Rupees Eighty Seven and Forty Six Paise Only		
391	Supplying and applying Mirror polishing on marble work/Granite work/stone work where ever required to give high gloss finish complete.	SqM		407.0652		0
				Rupees Four Hundreds Seven and Six Paise Only		
392	Providing and fixing retro-reflective Cautionary, Mandatory & Informatory sign boards of required size and shape made out of 2 mm thick aluminum sheet face to be fully covered with high intensity encapsulated lens type retro-reflective sheeting, Letters symbols, borders etc. will be as per IRC : 67 with required colors scheme on the boards and with the high intensity grade A as per specification and as approved by Engineer In charge. Note: Structural steel support of specified configuration as required for installing sign - boards shall be paid separately under relevant items.	SqM		4539.0222		0
				Rupees Four Thousand Five Hundreds Thirty Nine and Two Paise Only		
393	Providing and applying 2.5 mm thick road marking strips (retro- reflective) of specified shade/ colour using hot thermoplastic material by fully/ semi automatic thermoplastic paint applicator machine fitted with profile shoe, glass beads dispenser, propane tank heater and profile shoe heater, driven by experienced operator on road surface including cost of material, labour, T&P, cleaning the road surface of all dirt, seals, oil, grease and foreign material etc. complete as per direction of Engineer-in-charge and accordance with applicable specifications.	sqm		530.4926		0
				Rupees Five Hundreds Thirty and Forty Nine Paise Only		
394	Accomplishing the task of movement of materials, documents etc., on all working days on daily basis by engaging minimum number of courier cum rigger (Un Skilled) as specified in the conditions of contract.	1 Task per		864.8092		0
				Rupees Eight Hundreds Sixty Four and Eighty Paise Only		
395	Accomplishing the task of Fitter cum Welding related works (Skilled) like cutting, bending, fixing and welding of metals as per desired pattern / drawing or repairing of existing buildings and structures, doors & windows and furniture and all other types of complaints received from residents and offices at R.R. Site colonies with all required tools & plants but excluding welding machine and consumables which will be supplied by NPCIL, by engaging the minimum required fitter cum welders as specified in conditions of contract, complete on all working days on daily basis. (With all tools & tackles as required)	1 Task per		1209.752		0
				Rupees One Thousand Two Hundreds Nine and Seventy Five Paise Only		
396	Accomplishing the task of Painting related works (Semi -skilled) like applying paints or polishing on new or repairing or repainting of existing buildings and structures, doors & windows and furniture and all other types of complaints received from residents and offices at R.R. Site colonies with all required tools & tackles like Brush, putty plate, spray roller etc.by engaging the minimum required painter as specified in conditions of contract, complete on all working days on daily basis.	1 Task per		1020.9326		0
				Rupees One Thousand Twenty and Ninety Three Paise Only		
397	Accomplishing the task of Carpentry works (Skilled) like making new or repairing of existing doors & windows and furniture and all other types of complaints received from residents and offices at R.R. Site colonies with all required tools & tackles as required by engaging the minimum required carpenters as specified in conditions of contract, complete on all working days on daily basis.	1 Task per		1209.752		0
				Rupees One Thousand Two Hundreds Nine and Seventy Five Paise Only		
398	Accomplishing the task of Engineering assistance (Skilled) works in various Civil Engg., construction / maintenance works like supervision, taking measurement etc. as specified in conditions of contract & as directed by engineer-in-charge complete on all working days on daily basis. (atleast 2 year construction/Maintenance work exprience)	1 Task per		1191.7692		0
				Rupees One Thousand One Hundreds Ninety One and Seventy Six Paise Only		
399	Accomplishing the task of Mason (Skilled) related works like laying new or repairing of existing buildings and structures including masonry, PCC / RCC works, plastering, pointing, finishings, floorings, leakages repairing and all other types of complaints received from residents and offices at R.R. Site colonies with all required tools & tackles by engaging the minimum required mason as specified in conditions of contract, complete on all working days on daily basis.	1 Task per		1209.752		0
				Rupees One Thousand Two Hundreds Nine and Seventy Five Paise Only		
400	Accomplishing the task of Plumbing works (Skilled) like making new or repairing of existing water supply lines, sanitary fittings and fixtures, water outlets, leakages and all other types of complaints received from residents and offices at R.R. Site colonies with all required tools & tackles by engaging the minimum required plumbers as specified in conditions of contract & as directed by Engineer-In-Charge complete on all working days on daily basis.	1 Task per		1209.752		0
				Rupees One Thousand Two Hundreds Nine and Seventy Five Paise Only		
401	Accomplishing the task of Store-keeping works in (Semi Skilled) various Civil Engg., construction / maintenance materials, recording book-keeping, ledgers as specified in conditions of contract, complete on all working days on daily basis.	1 Task per		1006.2194		0
				Rupees One Thousand Six and Twenty One Paise Only		
402	Accomplishing the task of Allotment works (Skilled) in various Houses, New community centre, SPH, Recreation club etc., recording occupation / vacation report, night latch records, WC records etc. as specified in conditions of contract, complete on all working days on daily basis.	1 Task per		1191.7692		0
				Rupees One Thousand One Hundreds Ninety One and Seventy Six Paise Only		
403	Accomplishing the task of Helper for Allotment works (Semi-Skilled) in various Houses, New community centre, SPH, Recreation club etc., recording occupation / vacation report, night latch records, WC records etc. as specified in conditions of contract, complete on all working days on daily basis.	1 Task per		1006.2194		0
				Rupees One Thousand Six and Twenty One Paise Only		

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Amount in ₹
		Rate in Words				
404	Providing & fixing mineral glass wool based acoustic false ceiling tiles Armstrong or other similar approved make having NRC of 0.90 of size 595mm x 595mm in true horizontal level, suspended on inter locking metal grid of hot dipped galvanized steel sections (galvanized @ 120 grams/ sqm, both side inclusive) consisting of main "T" runner with suitably spaced joints to get required length and of size 24x38 mm made from 0.30 mm thick (minimum) sheet, spaced at 1200 mm center to center and cross "T" of size 24x25 mm made of 0.30 mm thick (minimum) sheet, 1200 mm long spaced between main "T" at 600 mm center to center to form a grid of 1200x600 mm and secondary cross "T" of length 600 mm and size 24x25 mm made of 0.30 mm thick (minimum) sheet to be interlocked at middle of the 1200x600 mm panel to form grids of 600x600 mm and wall angle of size 24x24x0.3 mm and laying false ceiling tiles of approved texture in the grid including, required cutting/making, opening for services like diffusers, grills, light fittings, fixtures, smoke detectors etc. Main "T" runners to be suspended from ceiling using GI slotted cleats of size 27 x 37 x 25 x1.6 mm fixed to ceiling with 12.5 mm dia and 50 mm long dash fasteners, 4 mm GI adjustable rods with galvanised butterfly level clips of size 85 x 30 x 0.8 mm spaced at 1200 mm center to center along main T, bottom exposed width of 24 mm of all Tsections shall be pre-painted with polyester paint, all complete for all heights as per specifications, drawings and as directed by Engineer-in-charge.	SqM		1879.2026		0
		Rupees One Thousand Eight Hundreds Seventy Nine and Twenty Paise Only				
405	Providing & replacing mineral glass wool based acoustic false ceiling tiles Armstrong or other similar approved make having NRC of 0.90 of size 595mm x 595mm in true horizontal level complete for all heights as per specifications, drawings and as directed by Engineer-in-charge.	SqM		1465.5982		0
		Rupees One Thousand Four Hundreds Sixty Five and Fifty Nine Paise Only				
406	Providing & Applying of Two Component Polysulphide base Sealing compound GUN GRADE for vertical surface as per BIS-12118, in 4 kg (Four) standard pack as per specifications and direction of Engineer in charge.	Kg		468.3702		0
		Rupees Four Hundreds Sixty Eight and Thirty Seven Paise Only				
407	Providing and fixing Heat Resistant Terrace Tiles (300 mm x 300 mm x 20 mm) with SRI (solar refractive index) > 78, solar reflection > 0.70 and initial emittance > 0.75 on waterproof and sloped surface of terrace, laid on 20 mm thick cement sand mortar in the ratio of 1:4 (1 cement : 4 coarse sand) and grouting the joints with mix of white cement & marble powder in ratio of 1:1, including rubbing and polishing of the surface upto 3 cuts complete, including providing skirting upto 150 mm height along the parapet walls in the same manner.	SqM		1409.1976		0
		Rupees One Thousand Four Hundreds Nine and Nineteen Paise Only				
408	Providing and fixing Stainless Steel A ISI 304 (18/8) kitchen sink with drain board - 510x1040 mm bowl depth 200 mm as per IS:13983 with C.I. brackets and stainless steel plug 40 mm, including painting of fittings and brackets, cutting and making good the walls wherever required :	Each		6071.6472		0
		Rupees Six Thousand Seventy One and Sixty Four Paise Only				

Note: All Item Rates are considered to be in Indian Rupees unless otherwise explicitly specified and in which case shall be always converted appropriately to arrive at the amount in Indian Rupees.

Work Order Total	₹ 4,45,89,331.00
Overall Rebate (%)	0
Work Order Value After Overall Rebate in Figure	₹ 4,45,89,331.00
Work Order Value After Overall Rebate in Words	Rupees Four Crore Forty Five Lakh Eighty Nine Thousand Three Hundreds Thirty One Only

Signature Not Verified

Digitally signed by NAUNIHAL SINGH MEENA
Date: 2026.07.21 10:01:27 IST
Location: eProcurement System for Central PSUs